


AUGUST 1986

VOL. 4, No. 8 \$3.95

FOR IBM PERSONAL COMPUTER USERS

TECH JOURNAL




OUT FROM THE SHADOW OF IBM
Compatibility and Performance on 286 Machines

COMPAQ DESKPRO 286

NINE-TRACK TAPE SYSTEMS

ANIMATION WITH SPRITES





Turbo GameWorks™

Also recently released, Turbo GameWorks is what you think it is: "Games" and "Works." Games you can play right away (like Chess, Bridge and Go-Moku), plus the Works—which is how computer games work. All the secrets and

strategies of game theory are there for you to learn. You can play the games "as is" or modify them any which way you want. Source code is included to let you do that, and whether you want to write your own games or simply play the off-the-shelf games, Turbo GameWorks will give hours of diversion, education, and intrigue. George Koltanowski, Dean of American Chess, and former President, United States Chess Federation, reacted to Turbo GameWorks like this, "With Turbo GameWorks, you're on your way to becoming a master chess player," and Kit Woolsey, writer, author, and twice Champion of the Blue Ribbon Pairs, wrote, "Now play the world's most popular card game—Bridge... even program your own bidding or scoring conventions." Suggested retail: \$69.95.



Turbo Graphix Toolbox™

It includes a library of graphics routines for Turbo Pascal programs. Lets even beginning programmers create high-resolution graphics with an IBM, Hercules,™ or compatible graphics adapter. Our Turbo Graphix Toolbox includes all the tools you'll ever need for complex business graphics, easy windowing, and storing screen images to memory. It comes complete with source code, ready to compile. Suggested retail: \$69.95.



Turbo Database Toolbox™

A perfect complement to Turbo Pascal, because it contains a complete library of Pascal procedures that allows you to search and sort data and build powerful database applications. Having Turbo Database Toolbox means you don't have to reinvent the wheel each time you write a Turbo Pascal program. It comes with source code for a free sample database—right on disk. The database can be searched by keywords or numbers. Update, add, or delete records as needed. Just compile it and it's ready to go to work for you. Suggested retail: \$69.95.



Technical Specifications:

TURBO PASCAL 3.0 Minimum memory: 128K; includes 8087 and BCD features for 16-bit MS-DOS and CP/M-86 systems. CP/M-80 version minimum memory: 48K; 8087 and BCD features not available

TURBO DATABASE TOOLBOX Minimum memory: 128K. CP/M-80 minimum memory: 48K. Requires Turbo Pascal 2.0 or later.

TURBO GRAPHIX TOOLBOX™ Minimum memory: 192K. Requires PC/MS-DOS 2.0 or later, Turbo Pascal 3.0, and IBM CGA, Hercules Monochrome Card or equivalent.

TURBO TUTOR 2.0 Minimum memory: 192K. CP/M-80 version minimum memory 48K. Requires PC/MS-DOS 2.0 or later and Turbo Pascal 3.0.

TURBO EDITOR TOOLBOX™ Minimum memory: 192K. Requires PC/MS-DOS 2.0 or later and Turbo Pascal 3.0.

TURBO GAMEWORKS™ Minimum memory: 192K. Requires PC/MS-DOS 2.0 or later and Turbo Pascal 3.0.

TURBO PROLOG™ Minimum memory: 384K.

REFLEX: THE ANALYST™ Minimum memory: 384K. Requires IBM CGA, Hercules Monochrome Card or equivalent. Works with Intel's AboveBoard-PC and -AT; AST's RAMPAGE! and RAMPAGE! AT; Quadram's Liberty-PC and -AT; Tecmar's 640 Plus; IBM's EGA and 3270/PC; AT&T's 6300 and many others.

REFLEX WORKSHOP™ Minimum memory: 384K. Requires Reflex: The Analyst. Two disk drives or hard disk recommended.

TURBO LIGHTNING™ Minimum memory: 256K. Two disk drives required. Hard disk recommended.

LIGHTNING WORD WIZARD™ Minimum memory: 256K. Requires Turbo Lightning. Turbo Pascal 3.0 required to edit source code.

SIDEKICK™ Minimum memory: 128K.

TRAVELING SIDEKICK™ Minimum memory: 256K.

SUPERKEY™ Minimum memory: 128K.

*For IBM PC, AT, XT, PCjr and true compatibles only, running PC/MS-DOS 2.0 or later.




Recognition for Borland International has come from business, trade, and media, and includes both product awards and awards for technical excellence and marketing. Borland was named "Company of the Year" by PC Magazine; Sidekick, the #1 best seller for the IBM PC, was named "Product of the Year" by InfoWorld; Turbo Pascal was selected one of PC Week's Top 10 Products for 1984; SuperKey won one of PC Magazine's "Best of 1985" awards; Reflex, The Analyst was recognized in the "Software Products of the Year" awards by InfoWorld; and Reflex and Sidekick were both nominated for British Micro Awards in 1986.



TURBO PASCAL™

©Copyright 1983. Licensed-Material-Program property of BORLAND International, Inc., 4585 Scotts Valley Drive, Scotts Valley, CA 95066. Unauthorized use, duplication or distribution is strictly prohibited by Federal Law.





We frequently surprise people with inventive, imaginative software, and people frequently surprise us with the way they use it.

For example, you'll read on this page how Michael J. Watkins of the Petroleum Technology Center in Houston, Texas,

used Turbo Pascal® (and Turbo Graphix Toolbox™ and Turbo Tutor®) to cut down the tedium and time in creating Circular Performance Profile Charts (CPPCs).

We didn't know they existed, but you learn something new every day!

Applications like CPPCs might not fit your exact needs, but at the same time they might stimulate fresh ideas in your mind about how you can put Turbo Pascal and the Turbo Pascal family to work for you.

And thank you for your interest in and support for Borland International.

PKahn

Philippe Kahn,
President, Borland International

INSIDE STORIES!

- Turbo Pascal 3.0, already described by *PC Magazine* as "Language deal of the century," is now an even better deal than that, because we've included the most popular options (BCD reals and 8087 support). What used to cost \$124.95 is now only \$99.95!
- Completely new Turbo Tutor 2.0 now available. New software. New manual. New split screens. New quizzes. Only \$39.95. Upgrades available under Borland's "Almost-Free" upgrade plan. Details inside.

LATE NEWS!

- June/July Special Artificial Intelligence Issue of *The Micro Technical Journal* says, "Turbo Prolog looks like it's going to be a winner, for both the beginner and professional programmer."

Turbo Pascal deliberately programmed to go around in circles


Circular charts (or CPPCs) are used by Michael J. Watkins of the Petroleum Technology Center in Houston, Texas, to plot a single performance property for a large number of elastomers, which have elastic, rubber-like properties.

Mr. Watkins wrote us saying, "Because CPPCs condense a lot of data in one graphic, they can be very tedious and time-consuming to draw."


What he did to solve those problems was to write a Turbo Pascal program for IBM® personal computers to "generate these charts quickly and easily."

He used Turbo Pascal "because it has a companion set of very powerful graphics programs (Turbo Graphix Toolbox) which greatly simplifies the required programming."

Turbo Pascal is not a difficult language to use and can be easily learned by persons who can program in FORTRAN or BASIC. An excellent tutorial (Turbo Tutor) is available for the novice or experienced programmer. The Turbo Pascal products are also very moderately priced."



*"The computer is no better than its program."
Elting Morison, author of "Men, Machines and Modern Times"*






COMPLETELY
NEW VERSION!

Turbo Tutor® 2.0

Just released (July '86), the new Turbo Tutor can take you from "What's a computer?" on through to complex data structures, assembly languages, trees, tips on writing long programs in Turbo Pascal, and a

high level of expertise. Source code for everything is included. New split screens allow you to put source text in the bottom half of the screen and run the examples in the top half. There are quizzes that ask you, show you, tell you, teach you. You get a 450-page manual—which is not as daunting as it sounds, because unlike many software manuals, it was not written by orangutans. (With our all "almost-free" upgrade, you can upgrade to Turbo Tutor 2.0 by sending us your master diskettes, proof of purchase, and \$10.00, which covers shipping and handling.) Suggested retail: \$39.95.



Turbo Editor Toolbox™

Recently released, we called our new Turbo Editor Toolbox a "construction set to write your own word processor." Peter Feldmann of PC Magazine covered it pretty well with, "A 'write your own word processor'

program for intermediate level programmers, with lots of help in the form of prewritten procedures covering everything from word wrap to pull-down windows."

Source code is included, and we also include MicroStar, a full-blown text editor with pull-down menus and windowing. It interfaces directly with Turbo Lightning to let you spell-check your MicroStar files. Jerry Pournelle of BYTE magazine said, "The new Turbo Editor Toolbox is the Turbo Pascal source code to just about anything you ever wanted a PC-compatible text editor to do." Suggested retail: \$69.95.



NEW SPECIAL!

Turbo Pascal® 3.0

"For the IBM PC, the benchmark Pascal compiler is undoubtedly Borland International's Turbo Pascal," says Gary Ray of PC Week. We and more than 500,000 other people around the world think Mr. Ray got that right.

Since launch, Turbo Pascal has become the *de facto* worldwide standard in high-speed Pascal compilers. Described by Jeff Duntemann of PC Magazine as the "Language deal of the century," Turbo Pascal is now an even better deal than that—because we've included the most popular options (BCD reals and 8087 support). What used to cost \$124.95 is now only \$99.95! You now get a lot more for a lot less: the compiler, a completely integrated programming environment, and BCD reals and 8087 support—all for a suggested retail of only \$99.95.



Borland's Business Productivity Programs:

Reflex: The Analyst™ Analytical database manager. Provides complete new look at data normally hidden by programs like 1-2-3* and dBASE.* Best report generator for 1-2-3.

NEW! Reflex Workshop™ Important new addition to Reflex: The Analyst. Gives you 22 different templates to run your business right.

SideKick™ Complete RAM-resident desktop management includes notepad, dialer, calculator and more.

Traveling SideKick™ Electronic version of business/personal diaries, daytime organizers; works with your SideKick files; important professional tool.



SuperKey™ Keyboard enhancer. Simple macros turn 1000 keystrokes into 1. Also encrypts your files to keep confidential files confidential.

Borland's Electronic Reference Programs:

Turbo Lightning™ Works with all your programs and checks your spelling while you type! Includes 80,000-word Random House* Concise Dictionary and 50,000-word Random House Thesaurus. Forerunner of Turbo Lightning Library.


Lightning Word Wizard™ Includes ingenious crossword solver and six other word challenges. If you're into programming, Lightning Word Wizard is also a development toolbox and the technical reference manual for Turbo Lightning.

All Borland products are registered trademarks or trademarks of Borland International, Inc. or Borland/Analytica, Inc. 1-2-3 is a registered trademark of Lotus Development Corp. dBASE is a registered trademark of Ashton-Tate. Random House is a registered trademark of Random House, Inc. Hercules is a trademark of Hercules Computer Tech. IBM, AT, XT, and PCjr are registered trademarks of International Business Machines Corp. Copyright 1986 Borland International BI-1067



Borland's new Turbo Prolog is the powerful, completely natural introduction to Artificial Intelligence

Our new Turbo Prolog, the natural language of **Artificial Intelligence**, brings supercomputer power to your IBM® PC and introduces you step-by-step to the fascinating new world of **Artificial Intelligence**. And does all this for an astounding \$99.95.




Darryl Rubin,
AI Expert

If you think that this is amazing, you just need to remember that Turbo Prolog is a 5th-generation language—and the kind of language that 21st century computers will use routinely. In fact, you can compare Turbo Prolog to

So don't delay—don't waste a second—get Turbo Prolog now. \$99.95 is an amazingly small price to pay to become an immediate authority—an instant expert on artificial intelligence! The 21st century is only one phone call away.



If lightning still scares you, you're using the wrong file manager.



Be sure. Btrieve.[®]

Lightning may strike. But it doesn't have to destroy your database.

Btrieve[®] file management offers automatic file recovery after a system crash. So accidents and power failures don't turn into database disasters. Your Btrieve-based applications will come up when the lights come back on.

Fast. Btrieve is lightning fast, too. Its b-tree file structure automatically balances—you never waste time reorganizing the index. And Btrieve is written in Assembly language especially for the IBM PC. The result: electrifying speed on file maintenance routines. Applications that run fast. Users who don't waste time waiting.

The standard for networking. When your application requires multi-user file sharing, Btrieve/N (network version) sets the standard for the industry's most popular LANs: IBM's PC Network, Netware, PC Net and EtherSeries. And now Btrieve sets the standard for multi-user systems: XENIX, Multi-

Link Advanced and others. Btrieve/N offers **safe** network file management that coordinates simultaneous updates and protects against lost data.

Fully-relational data management. Using SoftCraft's entire family of products gives you a complete, fully-relational database management system. Rtrieve[™] adds report writing capabilities for generating the reports you need. Xtrieve[™] speeds users through database queries with interactive, on-screen menus—no command language or special syntax.

For professional programmers. Btrieve is the fast, reliable answer for all your application development. In any development language—BASIC, Pascal, COBOL, C, FORTRAN and APL. With multikey access to records. Unlimited records per file. Duplicate, modifiable, and segmented keys.

With Btrieve, you can develop better applications faster. And know they'll be safe if lightning strikes.

NO ROYALTIES

Suggested retail prices: Btrieve, \$245; Btrieve/N, \$595; Xtrieve, \$245; Xtrieve/N, \$595; Rtrieve, \$145; Rtrieve/N, \$345. Requires PC-DOS or MS-DOS 1.X, 2.X, or 3.X.

Btrieve is a registered trademark and Xtrieve and Rtrieve are trademarks of SoftCraft Inc.


SC
SoftCraft Inc.

P.O. Box 9802 #917
Austin, Texas 78766
(512) 346-8380 Telex 358 200




Compaq Deskpro 286

80



Nine-Track Tape Systems

94



Smooth Curves

110

OUT FROM THE SHADOW OF IBM / STEVEN ARMBRUST, TED FORGERON, and PAUL PIERCE

IBM is casting a smaller shadow in the 80286 market as more and more companies offer alternatives to the PC/AT. With this issue, *PC Tech Journal* begins its series evaluating these AT compatibles. The introductory article offers a detailed explanation of the methods and criteria that will be used to judge each machine. The critical items: compatibility and performance.

52

Compatibility and Performance: COMPAQ DESKPRO 286 / STEVEN ARMBRUST and TED FORGERON

The first entry in our series on PC/AT compatibles evaluates Compaq's bid in the 286 market and finds that the company lives up to its reputation for overall quality and IBM compatibility. The Deskpro 286 is intended not as a low-cost substitute for the AT, but as a competitive alternative with a few extra features. Compaq's Portable II also meets 286 expectations.

80

NINE-TRACK TAPE SYSTEMS / ROGER ADDELSON

Although nine-track tapes may seem to be from another time and place when considered in the PC environment, a time-tested set of standards is the key to their longevity. Eight tape subsystems are evaluated here, each of which offers consistent performance, control over data storage and transfer, and a strong link between PCs and bigger computers.

94

SMOOTH CURVES / MICHAEL A. COVINGTON

The computer equivalent of a spline is presented in the form of a Pascal program to help users draw curves on the PC screen without ragged edges, a classic problem in computer graphics. Although written for the IBM Color Graphics Adapter, the program can be modified for the Enhanced Graphics Adapter and can be easily translated into other languages.

110

SOFTWARE SPRITES / MICHAEL ABRASH and DAN ILLOWSKY

The few, small flickering objects that pass for animation on the PC screen are the result of the PC's lack of appropriate hardware. But software emulation of hardware sprite animation capabilities is possible, and with some clever programming techniques, even the PC can be made to approach the quality of arcade game machines.

125

9 DIRECTIONS

Long Live the 286!

15 LETTERS

29 PRODUCT OF THE MONTH

PC Scheme

30 TECH RELEASES

47 TECH NOTEBOOK

Using ROM Characters

159 PROGRAMMING PRACTICES

Sixteen-Color Graphics

175 PRODUCT WATCH

*QUICKCODE for 1-2-3
Let's C
GENSCREEN*

183 BOOK REVIEWS

An Elegant Scheme

185 LEGAL BRIEF

Taxing Software

187 MAIL ORDER

197 TECH MART

199 TECH BOOK

206 CALENDAR

207 READER SERVICE CARD

PRODUCTIVITY TOOLS

From Opt-Tech Data Processing

NEW
Version

Opt-Tech Sort™

NEW
Version

ALL NEW Version 3.0 features even faster sorting, record selection, output record reformatting, dBASE III files, comma delimited fields, and much more. This high performance sort/merge/record selection utility can be used as a stand-alone program or called as a subroutine from most languages.

Supports unlimited filesizes, multiple input files and fixed or variable length records. Many special file types are supported including Btrieve and dBASE. Up to nine sort control fields (ascending or descending), all common data types supported. Output files can be combinations of full records, keys or pointers, subsets of the input file fields, and literal values.

Written in assembly language for **high performance**. Example: 4,000 128 byte records sorted to give key and pointer in 30 seconds. **\$149.**

On-Line Help™

A comprehensive utility for adding help windows to your programs. It provides efficient utilities and routines for interfacing your programs with the help system routines and help message libraries.

Help windows are displayed in a fraction of a second. You have total control over the contents of the window, its size and its position on the screen, including the display and border colors.

On-Line Help can be interfaced with interpreted Basic and all popular compilers. **\$149.**

Scroll & Recall™

Allows you to conveniently scroll back through data that has gone off the top of your display screen. Up to 27 screens of data can be recalled or written to a disk file (great for documenting systems operations).

Allows you to easily recall and edit your previously entered DOS commands and data lines without re-typing.

Scroll & Recall is very easy to use. It's a resident utility that's always there when you need it! **\$69.**

All programs IBM PC/XT/AT & MS-DOS compatible.

Visa, M/C, AMEX, Check, Money Order, COD or Purchase Orders accepted.

Quantity and Dealer Discounts Available

To order or to receive additional information write or call:

Opt-Tech Data Processing

P.O. Box 678 - Zephyr Cove, NV 89448
(702) 588-3737

TECH JOURNAL®

VOL. 4, NO. 8

PUBLISHER: Newton Barrett

EDITOR: Will Fastie

EDITORIAL

MANAGING EDITOR: Marjory Spraycar

EXECUTIVE EDITOR: Julie Anderson

SENIOR TECHNICAL EDITOR: Jim Shields

TECHNICAL EDITORS: Jeff Duntemann, Caroline Halliday

ASSOCIATE TECHNICAL EDITOR: Dan Beale

SENIOR COPY EDITOR: Susan Holly

COPY EDITOR: Gail Shaffer

PROOFREADERS: Kathleen Peddicord, Elizabeth Wardlaw

NEW PRODUCTS EDITOR: Carole Autenzio

ADMINISTRATIVE ASSISTANT: Diana Carey

CONSULTING EDITORS: Thomas V. Hoffmann, Richard M. Foard

CONTRIBUTING EDITORS: Steven Armbrust, Michael Covington, Ted Forgeron, Augie Hansen, Ted Mirecki, Max Stul Oppenheimer

ART & PRODUCTION

ART DIRECTOR: Ina Saltz

ASSOCIATE ART DIRECTOR: Sharon Reuter

ASSISTANT ART DIRECTOR: Monique Cubicciotti

ART SECRETARY: Sabrina Reynolds

ADVERTISING PRODUCTION MANAGER: Lisa Franey Ducey

EDITORIAL PRODUCTION COORDINATOR: James Olsson

ADVERTISING SALES

ADVERTISING DIRECTOR: Rita Burke

MARKETING DIRECTOR: Gayl Sorota

MARKETING COORDINATOR: Julie Henderson

ADVERTISING COORDINATOR: Michele Fischetti

DISTRICT MANAGERS: Rosemarie Caruso, Jan Schultz—East Coast; Pat Toobey—Mid-Atlantic; Arlene Braithwaite—Midwest; Ted Bahr, Bill Busb, Phyllis Egan—West Coast

ACCOUNT REPRESENTATIVES: Jane Anderson—East Coast; Pam Sigal, Jane Anderson—West Coast

CIRCULATION

CIRCULATION MANAGER: Charles Mast

CIRCULATION SALES DEVELOPMENT: Daniel Rosensweig

MEDIA MANAGER: Melinda Kendall

ZIFF-DAVIS PUBLISHING COMPANY, a division of Ziff Communications Company

PRESIDENT: Kenneth H. Koppel

SENIOR VICE PRESIDENT, Marketing: Paul Chook

VICE PRESIDENT, Operations: Baird Davis

VICE PRESIDENT, Controller: John Vlachos

VICE PRESIDENT, Creative Services: Herbert Stern

VICE PRESIDENT, Circulation: Alicia Marie Ivans

VICE PRESIDENT, Circulation Services: James Ramaley

VICE PRESIDENT, Marketing Services: Ann Pollak Adelman

VICE PRESIDENT, Development: Seth Alpert

VICE PRESIDENT: Hugh Tietjen

BUSINESS MANAGER: Gary A. Gustafson

PRODUCTION DIRECTOR: Walter J. Terlecki

ZIFF COMMUNICATIONS COMPANY

PRESIDENT: Philip B. Korsant; **EXECUTIVE VICE PRESIDENT:** James D. Dunning, Jr.;

SENIOR VICE PRESIDENTS: Philip Sine, Kenneth H. Koppel; **VICE PRESIDENTS:** Laurence Usdin, William L. Phillips, J. Malcolm Morris, Steven C. Feinman; **TREASURER:** Selwyn Taubman; **SECRETARY:** Bertram A. Abrams

EDITORIAL OFFICE

PC TECH JOURNAL, The World Trade Center, Suite 211, Baltimore, MD 21202.

301/576-0770. FAX (group 3): 301/576-9603. MCI Mail: PCTECH. PCTECHline:

301/576-PCTJ (7285). Telex: 6502565932 MCI.

ADVERTISING OFFICES

(East Coast/Midwest) One Park Ave., New York, NY 10016. 212/503-5185.

(West Coast) 3460 Wilshire Blvd., Los Angeles, CA 90010. 213/387-2100;

11 Davis Drive, Belmont, CA 94002. 415/598-2290.


SUBSCRIPTION INQUIRIES

PC TECH JOURNAL, P.O. Box 2968, Boulder, CO 80321. Subscription service:


800/525-0643, 303/447-9330. Back issues: send \$7/copy (\$8 outside U.S.) to Ziff-Davis Publishing, One Park Ave., 4th floor, New York, NY 10016.

PC TECH JOURNAL (ISSN 0738-0194) is published monthly, \$29.97 for one year, \$52.97 for two years, \$69.97 for three years. Additional postage \$6 for Canada & Foreign by Ziff-Davis Publishing Company, a division of Ziff Communications Company, One Park Avenue, New York, NY 10016. Second-Class Postage paid at New York, NY and at additional mailing offices. POSTMASTER: Send address changes or subscription inquiries to P.O. Box 2968, Boulder, CO 80321.

PC TECH JOURNAL is an independent journal, not affiliated in any way with International Business Machines Corporation. IBM is a registered trademark of International Business Machines Corp. Entire contents Copyright © 1986 Ziff-Davis Publishing Company, a division of Ziff Communications Company. All rights reserved; reproduction in whole or in part without permission is prohibited. Direct written requests to Jean Lamensdorf, Licensing Manager, Reprints/Rights & Permissions, One Park Avenue, New York, NY 10016.



Save On New Model of Periscope



"A marvelous debugging tool..." says Peter Norton.

SUMMER SALE.

You don't have to spend thousands, or even hundreds, of dollars to buy a high-performance debugger. Through August 31, the new software-only Periscope II-X is yours for only \$95! Periscope II, normally \$145, is only \$125!

NEW MODEL.

Periscope I includes both a break-out switch for "spontaneous" debugging and a RAM board to protect the debugger from programs that overwrite memory. Periscope II includes a break-out switch that doesn't require an extra slot to install. And the new Periscope II-X is Periscope II without the break-out switch. So you can now get Periscope with no hardware at all!

NEW RELEASE.

The new version 2.1 enhances all models with many of the features users have requested. Call for details.

CHECK OUT THE REVIEWS.

- ✓ *"Periscope strikes a balance of power and features that will please serious PC programmers."* — Jeff Dunte-mann, PRODUCT OF THE MONTH, *PC Tech Journal*, 1/86
- ✓ *"This symbolic debugger, with its breakout button and powerful command options, stands unrivaled for its flexibility . . . Periscope's diverse features, affordable price, and portability place it in a class by itself."* — Ward Christensen, "Breaking out with Periscope," *PC Tech Journal*, 3/86
- ✓ *"Periscope represents the finest software debugger available in its class."* — Andrew Fried, *Computer Shopper*, 4/86

Other reviews have appeared in *Computer Language* (3/86), the Boston Computer Society's *PC Report* (1&2/85), and *Programmer's Journal* (Vol. 3, No. 1).

I'M CONVINCED PERISCOPE IS FOR ME!

Please send me the following:

Periscope II-X _____ @ \$95* _____

Periscope II with
Switch _____ @ \$125* _____

Periscope I with Board
& Switch _____ @ \$295. _____

Add Shipping Cost (see below) _____

Total Order Amount _____

Shipping-\$3 UPS; \$5 COD; \$8 Canada; \$24 Foreign

We accept qualified PO's in the U.S.

*Prices good through August 31, 1986

Ship to:

Name _____

Company _____

Address _____

City/State/Zip _____

Telephone _____

Payment: ☐ Check enclosed ☐ COD ☐ MC ☐ Visa

Card No. _____

Expires _____

Signature _____

PERISCOPE REQUIRES an IBM PC, XT, AT, Compaq, or other close compatible; 128K RAM; DOS 2.0 or later; one disk drive; and an 80-column monitor.

Take advantage of the low sale prices while they last . . . Order your Periscope today! To order, clip the coupon, or call TOLL-FREE



800/722-7006




30-Day Money-Back Guarantee

Get Your Programs Up and Running;


UP PERISCOPE!

Data Base Decisions
14 Bonnie Lane
Atlanta, GA 30328
404/256-3860

CIRCLE NO. 215 ON READER SERVICE CARD



EGA Mode



Plantronics Mode

Finally, An EGA Card Responds To You

Introducing The Paradise AutoSwitch™ EGA Card.

You've decided you want an EGA Video Card because it offers the best quality text with high resolution color graphics. The problem is that older versions of popular software, like Lotus 1A, (and some current versions too) won't work with the EGA standard. That's a problem because in the course of your workday you'll need to use software written for different video modes.

Paradise has the answer. The Paradise AutoSwitch

EGA works with every popular PC video mode. And is smart enough to switch to the right mode every time you change programs. Automatically.


AutoSwitch. Only Paradise has it.

The Paradise AutoSwitch EGA changes video modes automatically to work with your software. No Mode commands. No special software to run. On RGB monitors it "autoswitches" between EGA, CGA (IBM Color Graphics) and Plantronics modes; on monochrome


monitors between EGA, MDA (IBM Mono Text) and Hercules modes. The Paradise AutoSwitch EGA runs any PC software you want. Immediately. Automatically. That's something ordinary EGA Cards can't do.

Runs all EGA, CGA, MDA and Hercules Software with true hardware level compatibility.

True hardware compatibility makes the Paradise AutoSwitch EGA Card different from other EGA Cards. No other EGA Card offers the



CGA Mode



Hercules Mode

And That Automatically Runs in Every Mode.

The 6845 CRT controller included on the IBM Monochrome, IBM Color and Hercules Cards. The Paradise-designed PEGA video controller chip has the equivalent of a 6845 inside. That means when the Paradise AutoSwitch EGA runs EGA software, it's an EGA card; when it runs IBM Color Graphics (CGA) software, it's a CGA card; when it runs Hercules software, it's a Hercules card. No "batch files," special software or complicated installation. No incompatibility hassles. EGA with true 6845 hardware compatibility.


The Simpler the Better.

Paradise's exclusive AutoSwitch feature and true 6845 hardware compatibility make using the Paradise AutoSwitch EGA simple and hassle free. The Paradise-designed single chip EGA video controller makes possible all this functionality and intelligence on a short card. In fact, even the users manual is short. Only 24 pages.

The Paradise AutoSwitch EGA Card. Just what you would expect from the innovators in Video Technology.

PARADISE
SYSTEMS, INC.

The Paradise AutoSwitch EGA Card



CIRCLE NO. 137 ON READER SERVICE CARD

For more information call 800-527-7977 Ext. 356, toll free. From California, 800-822-2020 Ext. 356. Or stop by your favorite computer store.

ATRON BUGBUSTERS GREASE BORLAND LIGHTNING

"If I were starting a software company again, from scratch, Atron's AT PROBE™ would be among my very first investments. Without Atron's hardware-assisted, software debugging technology, the flash of Turbo Lightning™ would be a light-year away."

Philippe Kahn, President, Borland

HOW BORLAND DOES SO MUCH, SO WELL, SO FAST

We asked Borland International president Philippe Kahn to share his secrets for rapidly taking a good idea and turning it into rock-solid reality. How does the Borland team do so much, so well, so fast?

He begins, "I remember when Atron used the June 24, 1985 *Wall Street Journal* chart of top-selling software in an ad." [Note: At that time, seven of the top ten software packages were created by Atron customers; it's now now nine out of ten.] "SideKick was number four, and I let Atron quote me in saying that there wouldn't have been a SideKick without Atron's hardware-assisted debuggers.

"You might say lightning has literally struck again. Turbo Lightning made number four on

SoftSel's Hotlist within weeks of its introduction! And again, I say we couldn't have done it without Atron debugging technology.

"Cleverly written code is, by definition tight, recursive, and terribly complex," he continues. "Without the ability to externally track the execution of this code, competent debugging becomes very nearly impossible."

Concludes Philippe, "And after Turbo Lightning was solid and reliable, Atron tuning software turned our Probes into performance analyzers. How do you think we greased our lightning?"

Philippe, along with a couple million or so of your satisfied customers, we say congratulations on yet another best-selling product. We can't wait to see what awesomely useful technology will come shooting out of Borland International next.

Copyright © 1985 by Atron Corp. PC PROBE™ and AT PROBE™ Atron. SideKick™ and Turbo Lightning™ Borland International, Inc., Adv. by TRBA, 408/258-2708.

HOW BUGBUSTERS KEEP YOU FROM GETTING SLIMED

The AT PROBE is a circuit board that plugs into your PC/AT. It has an umbilical which plugs into the 80287 socket and monitors all 80286 activity.

Since AT PROBE can trace program execution in real time, and display the last 2048 memory cycles in symbolic or source-code form, you can easily answer the questions: "How did I get here?" and "What are those silly interrupts doing?"

It can solve *spooky* debugging problems. Like finding where your program overwrites memory or I/O - impossible with software debuggers.

You can even do source-level debugging in your favorite language, like C, Pascal or assembler. And after your application is debugged, the AT PROBE's performance measurement software can isolate performance bottlenecks.

Finally, the AT PROBE has its own 1-MByte of memory. Hidden and write-protected. How else could you develop that really large program, where the symbol table would otherwise take up most of memory.

LOOK AT IT THIS WAY.

History shows that non-Atron customers don't stand a very good chance of making the Top Ten list. Lightning *really does* have a way of striking twice!

The PC PROBE™ is \$1595 and the AT PROBE is \$2495. So call Atron today. You can be busting some really scary bugs tomorrow. And maybe, just like Borland, you can also bust some records.

atron
THE DEBUGGER COMPANY

20665 Fourth Street • Saratoga, CA 95070 • 408/741-5900



Long Live the 286!

We wish the 386 would go away, at least for a while.

With this issue *PC Tech Journal* breaks from a three-year editorial policy. Until now we have been "true blue" in that we have limited our coverage of desktop computers to those manufactured by IBM. Because IBM was the majority shareholder in the market for 8088-based machines, a standard emerged that allowed *PC Tech Journal* to disperse technical information about IBM products that was perfectly usable by developers for end users of other 8086-family desktops.

IBM still dominates the market with its PC and XT models, but times have changed. In the process of bringing a new, 80286-based machine to the market and establishing yet another standard, IBM stumbled. Within three months the market responded with 286 machines of higher performance, and the race was on.

IBM still is the majority shareholder in the AT market, but it has a much smaller share than it had in the PC arena. While most estimates credit IBM with 80 to 85 percent of 8088-based PC sales, its AT share is judged to run from 65 percent to an incredible 50 percent. To pour gasoline on an already substantial fire, the AT competition usually has something significant to offer over the IBM product; this was less often the case with the PC.

The market is one consideration. *PC Tech Journal's* readers are another, and we wanted to know what they were up to in this new market. We took advantage of the extensive research done by our advertising department and commissioned a study of our own. The results, so far, are clear.

First, our audience is moving to 286-based machines much more rapidly than the market at large. This comes as no surprise. Those who are developing software or using desktops in technical environments always want and need the best performance per dollar spent. AT-class machines deliver not only per-




ILLUSTRATION • MACIEK ALBRECHT

formance but also great opportunity for expansion, thus stretching the investment well into the future.

Second, IBM equipment still is preferred by our readers, but just barely—50.7 percent of your companies are planning to buy IBM and of those, 58.3 percent intend to buy ATs. Another not-unexpected result: Compaq is a hearty number two with its 286 machines, and that does not even include the Portable II, which was just becoming available at the time our research was conducted.

The study indicates one more factor that is not surprising for our audience but different from the world at large. When asked which brands of AT compatibles they are considering, our readers replied with a long list, identifying almost all of the companies in the market. The less technically inclined buyer is likely to know only one or two other brands. This means that our audience, besides being more knowledgeable, is willing to exploit the advantages of alternative solutions even if it means taking a risk. Willingness to take the risk is also evidenced by the response to our question about where equipment would be purchased: an astonishing 40 percent said mail order.

All of this leads up to our decision to cover non-IBM computers in these pages, under the aegis of compatibility

and performance. Our audience is certainly clear on these two points. High performance is a real draw, but not at the expense of a machine that is markedly different from the AT.

So we begin with the superb work of contributing editors Steven Armbrust and Ted Forgeron. As is usual for *PC Tech Journal*, the introductory article (see p. 52, this issue) in our series consists of a description of the methodology that will be used to evaluate each system. Armbrust and Forgeron, along with Paul Pierce, have devised a suite of programs that examines the machine's degree of compliance with the IBM specification and analyzes its performance. Bob Smith's excellent CPUID.ASM program (see "Chips in Transition," April 1986, p. 56, or call PCTECHline) was used as a starting point. The performance programs are noteworthy because they report more information than is normally considered when evaluating speed; using these programs, Armbrust and Forgeron determined that the Compaq Deskpro 286 ran its memory at 6 MHz even though the 286 was running at 8 MHz.

Appropriately, the first review in which these criteria are applied reports on the Compaq 286 machines (see p. 80, this issue). Forthcoming articles will review the HP Vectra, the TeleVideo

Tele-CAT 286, the PC's Limited 286 series, the new ITT machine, and others. With luck we will have several of these alternatives around our offices for continuing study.

386: SOONER OR LATER?

The efforts of the industry to establish standards for the construction of 386-based computers are commendable. Although IBM could ruin such attempts by announcing its own open architecture, serious work by third parties can only be beneficial. If the 386 market gets off to a good start before IBM gets into the act, IBM will have to answer for any design that strays too far from what its aftermarket (or is it beforemarket?) is prepared to support. If IBM gets in faster, perhaps the good work of outsiders will be recognized and integrated.

The 386 machines will be available soon, perhaps even by the time you read this. They will be expensive, because chips are in limited supply, but they will be interesting because the 386 has a far better memory management scheme and better support for serious operating systems than does the 286. The extent to which they will influence the desktop market in the next year is unclear; my guess is that at least 18 months will pass before the 386 desktop is available in large enough quantities to spur a serious market.

In the meantime, we are not exploiting the full potential of the 286. It is now abundantly clear that the 286 is really two chips in one: an 8086 and an 80286. In the context of DOS, it does not seem feasible to have an operating system that can run in both real and protected modes at the same time. It is possible, however, to have an operating system that runs in protected mode and allows 640KB applications to run if they obey a few rules and keep their hands off the hardware. That means there has to be a decision point at which a user is willing to shift from one architecture to the other. The advantage of the 80286 is that both architectures are present in the same machine, so no hardware purchases (outside of more memory) are required. What is necessary—and what is not available at the moment—is a DOS-compatible operating system that allows the transition.

The 386 offers improvements in architecture that enable an operating system to become more efficient at delivering services. The 286 offers only increased memory, with limited operating system support. These are the reasons I hear most often by those who es-

A NOTE ABOUT RESEARCH

Most magazines conduct regular research within their audiences. The reasons are varied, but include analysis of advertising, editorial satisfaction, future editorial directions, and general market analysis. Many of you have been called or asked to return a questionnaire. From several of your comments, I know some of you believe that our motives are selfish, designed solely to sell advertising.

We do have to sell advertising to bring you this product every month. Our advertisers need the information our research gathers not only to decide about media purchases but also to support their own market conclusions. We make no secret of that. However, you might not realize some other aspects about our research.

First, all research reports are used by the editorial staff. We contrib-

ute to almost every survey during its development to be sure it generates information helpful to us. The results are extremely valuable to us in assessing your interests and needs and the state of the market. Second, some surveys are done purely for editorial reasons and have nothing to do with selling ads. Because of the way surveys are constructed, it may be difficult to sense this as you respond. Finally, not all the surveys identify *PC Tech Journal* as the source. For reasons of statistical validity, it is sometimes necessary to conceal our identity.

I know your time is valuable. All of us appreciate your help with our research, your time permitting. What we try to offer in return is an improved *PC Tech Journal*, a magazine that better serves your needs.

—WF

pouse the 386 solution. Therefore, they say, ignore the 286 and migrate now.

I disagree. Most users have three simple areas in which they desire greater performance and capacity. The first is raw processor power. There is little doubt that the 386 delivers more processing power than the 6-MHz AT; even 8-MHz systems appear sluggish by comparison. However, 10- and 12-MHz 286 systems are available today that offer speeds closer to that of the 16-MHz 386. When the 20-MHz version of the 386 becomes economically attainable, the 286 will become less desirable—but for now it is acceptable.

The second area is main memory, both for executing large programs and keeping large amounts of data resident. The 386 dramatically improves the memory situation over the 286 with its better memory management unit, but most users should be able to work effectively in the 286's 16MB for the next two to three years.

The third area is disk performance. The problem with most IBM systems and their clones is that faster disks chew up more direct memory access time and thus reduce the cycles available for CPU operation. This problem is inherent in the design of the disk controller and main memory, not the processor itself. When main memory is dual-ported, with the I/O bus on one side and the CPU on the other, then real improvement will be possible.

A possible fourth concern of performance buffs is the speed of graphical

operations. To date, the IBM standard architecture has promoted solutions in which the processor did all the work; as the resolution and color capability of these subsystems rises, so does the number of CPU cycles necessary to service them. The 386 offers no significant improvement over the 286 for supporting graphical operations. Clock rate improvements do help, but the number of bits that must be moved is rising faster than the performance of the base processor. The only real solution is a graphics adapter board with its own processor (such as Intel's 82786 or TI's 34010). That seems a likely direction for growth, and it is applicable to any processor, even the now lowly 8088.

As far as I am concerned, that adds up to a lot of life left in the 80286 machines—the ones that are especially attracting the attention of the *PC Tech Journal* audience and that we will all have bought so many of by the time a viable, cost-effective 386 machine is available. What we need are some new and improved hardware subsystems and, especially, a protected mode version of DOS to exploit the in-place memory capability.

This is an election year. Let's vote NO for a 386 until our investment in 286 machines has been returned, or until they have been fully depreciated, whichever comes first. And let's vote YES for expansion to the outer limits of 286 functionality.

Please drop me a postcard with your vote on it.



“One of the
primary reasons the
Computer Press Association
was formed was to promote
high standards of writing
in computer journalism.
It's time to reward those
who do it best.”

Hal Glatzer
Vice President
Computer Press Association

Computer Press
Awards
1985

Best Computer Magazine

PC Tech Journal


 **CITIZEN**

Computer Press
Association 

Best Computer Magazine

JUNE 1986 VOL. 4, No. 6 \$3.95
FOR IBM PERSONAL COMPUTER USERS

TECH PC JOURNAL




SIX NEW SHAPES OF BASIC
Building on BASIC

INSTANT SCREENS

DATA MANAGER: KNOWLEDGEMAN/2

IRMX FOR THE PC



We are proud and honored to have been selected as the "Best Computer Magazine" by the Computer Press Association in its first annual awards.

At the awards ceremony, it was said that "PC TECH JOURNAL has substance, style and clear writing combined with superior information, value and contemporary graphics."

Indeed, it would be difficult for us to express more succinctly the standards we set for ourselves in publishing PC TECH JOURNAL. And we accept with appreciation the fact that our professional colleagues have recognized our achievement.

By concentrating on the rapidly growing need for information about PC systems, PC TECH JOURNAL has created a unique publication for PC systems experts, the key segment of an extremely sophisticated market.

This award as the "Best Computer Magazine" commits us even more toward the development of PC TECH JOURNAL as the information source for those dedicated systems professionals whose vision and industry are fast making the personal computer the most important business tool ever invented.

Now You Know Why **BRIEF** is **BEST**

"BRIEF is simple to learn and use and extremely sophisticated."

PC Magazine, July 1986

The Program Editor with the **BEST** Features

Since its introduction, BRIEF has been sweeping programmers off their feet. Why?

Because BRIEF offers the features **MOST ASKED FOR** by professional programmers. In fact, BRIEF has just about every feature you've ever seen or imagined, including the ability to configure windows, keyboard assignments, and commands to **YOUR** preference. One reviewer (David Irwin, DATA BASED ADVISOR) put it most aptly, "(BRIEF)... is quite simply the best code editor I have seen."

Solution Systems™

COMPILER SUPPORT

No matter what compiler you have, it will run inside BRIEF. If errors occur during compilation, the supplied macros place your cursor on the line with the first problem and display the compiler's message. After you make your corrections, you skip to the next error with one keystroke. BRIEF automatically moves your cursor to the right place, even if you've added or deleted lines.

BRIEF is preconfigured (using the built-in macro language) for the Microsoft Macro Assembler v 4.0, and the Microsoft, Computer Innovations, Lattice, and Wizard C compilers. If you use another product, you can modify the macros to support it.

Every Feature You Can Imagine

Compare these features with your editor (or any other for that matter).

- FAST
- Full UNDO (N Times)
- Edit Multiple Large Files
- Compiler-specific support, like auto indent, syntax check, compile within BRIEF, and template editing
- Exit to DOS inside BRIEF
- Uses all Available Memory
- Tutorial
- Repeat Keystroke Sequences
- 15 Minute Learning Time
- Windows (Tiled and Pop-up)
- Unlimited File Size –(even 2 Meg!)
- Reconfigurable Keyboard
- Context Sensitive Help
- Search for "regular expressions"
- Mnemonic Key Assignments
- Horizontal Scrolling
- Comprehensive Error Recovery
- A Complete Compiled Programmable and Readable Macro Language
- EGA and Large Display Support
- Adjustable line length up to 512

Program Editing **YOUR** Way

A typical program editor requires you to adjust your style of programming to its particular requirements – NOT SO WITH BRIEF. You can easily customize BRIEF to your way of doing things, making it a natural extension of your mind. For example, you can create ANY command and assign it to ANY key – even basic function keys such as cursor-control keys or the return key.

The Experts Agree

Reviewers at BYTE, INFOWORLD, DATA BASED ADVISOR, and DR. DOBB'S JOURNAL all came to the same conclusion – **BRIEF IS BEST!**

Further, of 20 top industry experts who were given BRIEF to test, 15 were so impressed they scrapped their existing editors!

NOT COPY PROTECTED

MONEY-BACK GUARANTEE

Try BRIEF (\$195) for 30 days – If not satisfied get a full refund.

TO ORDER CALL (800-821-2492)

SOLUTION SYSTEMS, 335-P WASHINGTON ST., NORWELL, MA 02061, 617-659-1571

BRIEF is a trademark of UnderWare



INTELLIGENT COMMENTS

Thank you for the excellent review of Q-PRO 4 by Chris Christian ("A Data Manager for Intelligent Screen Forms," January 1986, p. 126). We appreciate the work reflected in the depth and accuracy of the review. We, along with all manufacturers, have convinced ourselves that our products have only good points. Nonetheless, in all key areas, we agree with your analysis of the good and bad points of the product.

The reviewer made the astute observation that Q-PRO 4's file handler, although suitable for an eight-bit environment, was not fast enough for large files under DOS. The review also mentioned that a new file handler was to be available soon. Indeed, the new B+ tree file handler was released in February 1986. It has proven to increase the product's file-handling speed in most cases by an order of magnitude.

Again, our organization's sincere appreciation to Mr. Christian and the staff for a job well done.

Robert W. Roth
President
Q-N-E International

STATISTICAL STATIC

I am generally pleased to see articles on statistics in computer magazines because the personal computer is an ideal environment for interactive statistical analysis. That is assuming, of course, the user has the appropriate software available and sufficient training in statistics to use it correctly.

I was, therefore, distressed to see the substantial errors included in the article "Statistical Correlation" by Thomas Madron in the April 1986 issue of *PC Tech Journal* (p. 126). I point out the following examples.

The caption to figure 1 states, "The correlation coefficient is the slope of the 'best fit' straight line through these points." In fact, the correlation coefficient equals the slope of the line times

the ratio of the standard deviations of the two variables.

On page 128 is the statement, "A coefficient of ± 1.0 implies a completely causal relation between two variables..." Of course, a unit correlation implies only that two variables are perfectly associated and says nothing about causal relationships. This is an extremely significant distinction.

The discussion of the effect of missing data on page 130 is obscure. For example, the statement "a correlation coefficient based on these two variables can have a somewhat different meaning than if all respondents had answered both questions" is meaningless since the correlation is computed on the sample of observations with data present on both variables.

The description provided for figure 5 is incorrect and incomplete. The title "Sample Correlation Matrix" is wrong—figure 5 is a contingency table display of the frequencies of occurrence of the responses to the two questions. While the rows and columns of figure 5 are never described, the text implies that 3 represents missing data and the valid responses are 1 and 2. In that case, Pearson's product-moment correlation is entirely inappropriate to describe the association between two dichotomous variables.

On page 130, the statement "CORL.FOR is a linear analysis, finding a linear least-squares fit and performing a linear transformation to normalize data around 0" is incorrect—neither correlation nor regression normalizes the data about anything. To normalize the data around 0, the user could subtract the mean and divide by the standard deviation to transform each observation to a standard normal deviate.

On page 140 (within listing 3, STAT.FOR) is the comment "Programs that calculate significance tests usually need an estimate of the number of observations. Subsequent programs use

the *lowest* number of observations taken from the lower diagonal matrix as a conservative estimate since any significance tests based on a data matrix with missing data are suspect." Nonsense. In the first place, one does not estimate the number of observations since one can count them exactly. What the author probably meant to say was that in making multivariate tests of an hypothesis with missing data, some adjustments may be required to the degrees of freedom for the particular test. However, univariate tests of significance on individual correlations with different numbers of observations are entirely appropriate and valid.

In addition, while I have not examined the listings in detail, I strongly recommend that readers not use these programs until they have been validated on some multivariate data sets for which the results are known. My concern is based on the absence of a discussion of the substantial numerical problems involved in multivariate statistical computing. The author even failed to take the precaution of performing the operations on sums and sums of squares in double precision. The potentially disastrous results due to accumulating round-off errors in single precision (REAL*4 type on page 140) should not be underestimated.

If you expect your magazine to have any credibility at all in the statistical community, you must take stronger action to ensure that your editorial process keeps such erroneous information from your readers.

David N. Ikle, Ph.D.
Denver, CO

It is gratifying to see interest in statistical applications such as Thomas Madron's article "Statistical Correlation." Unfortunately the choice of algorithm used to compute the correlations (formula c on page 129) is not very accurate when applied to large numbers

and/or large amounts of data. Several alternative algorithms have the desirable property of requiring only one pass through the data without incorporating a final subtraction of very large numbers where much precision is lost. One such algorithm is described below.

Suppose I were intercorrelating K variables based on data from N observations, and X_{ij} is the value on variable j from observation i . First, initialize the variable sums

$$m_1^{(0)} \dots m_K^{(0)}$$

to 0 and the lower triangular matrix

$$v_{ii'}^{(0)} \text{ for } i = 1 \dots K, i' = 1 \dots i$$

to 0. Now, at each step, as $j = 1$ to N ranging over the N observations, I would accumulate the following:

$$m_i^{(j)} = m_i^{(j-1)} + X_{ij} \text{ for } i = 1 \dots K$$

in addition to

$$v_{ii'}^{(j)} = v_{ii'}^{(j-1)} + \frac{(jX_{ij} - m_i^{(j-1)})(jX_{i'j} - m_{i'}^{(j-1)})}{j(j-1)}$$

for $i = 1 \dots K$ and $i' = 1 \dots i$

The second step shown above is

skipped over when $j = 1$. After j reaches N , the mean for variable i is

$$m_i^{(N)}/N$$

the standard deviation is

$$\sqrt{\frac{v_{ii}^{(N)}}{N-1}}$$

and the correlation of the two variables i and i' is as follows:

$$r_{ii'} = \frac{v_{ii'}^{(N)}}{\sqrt{v_{ii}^{(N)} v_{i'i}^{(N)}}}$$

One other small error (which does not affect the correlations) is the use of N rather than $N - 1$ in the denominator when calculating the standard deviation (p. 132). N is correct when calculating the standard deviation over an entire population. When analyzing a sample from the population (as in almost all applications), the use of N underestimates the population value.

Alan Bostrom, Ph.D.

President

Crunch Software Corporation

Some of the comments by both Mr. Ikke and Mr. Bostrom are correct and well-

taken. Mr. Bostrom particularly made several thoughtful points that should be considered when doing statistical programming. Unfortunately, several of the problems that were identified by Mr. Ikke crept into the article during the editorial process. The points on which he is clearly correct—his comments about unit correlation, figure 5, and CORL.FOR—were editorial glitches.

Of more substance are the comments by Mr. Bostrom when he observes that the choice of algorithm can affect the numerical accuracy of the calculations. An example of this can be found by compiling the correlation program in single precision without an 8087 math coprocessor, then running it with data that are ill conditioned, such as the so-called Wampler data set, part of which is reproduced as follows:

```
200000 1.00001 0.99999
600000 2.00001 1.99999
400000 1.99999 2.00001
400000 0.99999 1.00001
```

The resulting calculation will generate a -4.0 correlation between variables 1 and 3—clearly a ridiculous result (the correct answer is 1.0).

FOR C
AND UNIX

WINDOWS FOR DATA™

MS WINDOWS
COMPATIBILITY

DATA ENTRY WINDOWS MENUS HELP

Windows for Data does the hard jobs that others can't — we **guarantee** it. Makes standard display and entry tasks easy. Reliable. Compact. Portable.

DATA ENTRY: The most complete and flexible data entry system on the market. Pop-up data-entry windows; field types for all C data types, plus decimals, dates, and times; auto conversion to and from strings for all field types; system and user-supplied validation functions; range-checking; scrollable context-sensitive help; required and must-fill fields; programmer-definable edit keys, field types, and field masks. Read field by field or auto-read all fields. Branch and nest window forms. **Virtually every capability of WFD can be modified to meet special needs.**

WINDOWS: WFD is built upon and includes **Windows for C**, the windowing system rated #1 in PC Tech Journal (William Hunt, July 1985). WFC now has more features than ever, including automatic full compatibility with Microsoft Windows and TopView.

UNPRECEDENTED FLEXIBILITY



As many possibilities as Vermont in June.

MENUS: Build multi-level menus in the format of Lotus 1-2-3, Macintosh, or a style of your own choosing.

HELP: Build context-sensitive or menu-driven help systems. Display text in pop-up, scrollable windows.

UNIX, DOS, OR BOTH

WFC and WFD provide source code compatibility between PC DOS and UNIX.

OUR CHALLENGE AND GUARANTEE

If you have an application where no other tool can do the job, try **Windows for Data**. If it doesn't help you solve your problem, RETURN FOR A FULL REFUND. YOU MUST BE SATISFIED.

WINDOWS FOR DATA WINDOWS FOR C

PC DOS*	\$295	\$195
XENIX-286	\$595	\$395
UNIX	CALL	CALL

Call for **FREE Demo diskette**.

*All popular C compilers; no royalties.



**Vermont
Creative
Software**

21 Elm Ave.
Richford, VT 05476
802-848-7738,
ext. 21.

MasterCard & Visa Accepted. Shipping \$3.50
VT residents add 4% tax.

Mark Williams

Now the biggest name
in C compilers comes in a size
everybody can afford.

Let's C.™

\$75

Introducing Mark Williams' \$75 C compiler. Want to explore C programming for the first time? Or just on your own time? Now you can do it in a big way without spending that way. With Let's C.

This is no little beginner's model. Let's C is a powerful programming tool, packed with all the essentials of the famous Mark Williams C Programming System. The one chosen by Intel, DEC, Wang and thousands of professional programmers. The one that wins the benchmarks and the reviewers' praise:

Mark Williams Let's C

- For the IBM-PC and MS-DOS
- Fast compact code plus register variables
- Full Kernighan & Ritchie C and extensions
- Full UNIX™ compatibility and complete libraries
- Small memory model
- Many powerful utilities including linker, assembler, archiver, cc one-step compiling, egrep, pr, tail, wc
- MicroEMACS full screen editor with source
- Supported by dozens of third party libraries
- Upgradeable to C Programming System for large scale applications development

Let's C Benchmark Done on an IBM-PC/XT, no 8087.
Program: Floating Point from BYTE, August, 1983.

Exec Time in Seconds

Let's C	134.20
MS 3.0	347.45

"(This compiler) has the most professional feel of any package we tested..."—BYTE
"Of all the compilers reviewed, (it) would be my first choice for product development."—David W. Smith, PC WORLD

And now for more big news. Get our revolutionary csd C Source

Debugger for just \$75, too. You can breeze through debugging at the C source level ignoring clunky assembler code.

Affordable, powerful, debuggable. Mark Williams Let's C is the big name C compiler at a price you can handle. Get your hands on it now.

Use this coupon or charge by calling toll-free:
1-800-MWC-1700. In Ill. call 312-472-6659.

ORDER NOW! 60-DAY MONEY BACK GUARANTEE!

Mark Williams Let's C

Please send me:

_____ copies of Let's C and _____ copies of csd (C Source Debugger) at \$75 each. (Ill. residents add 7% sales tax.)

☐ Check ☐ Money Order ☐ Visa, MasterCard or American Express

Name _____

Address _____

City _____ State _____ Zip _____

Card # _____ Exp. Date _____

Signature _____ TJ0886



**Mark
Williams
Company**

1430 West Wrightwood
Chicago, Illinois 60614

At last! - Fast, On-screen FLOWCHARTS

And Organization Charts

Finally! An on-screen flowchart processor that knows about flowcharts and organization charts - not just another "screen draw" program that makes you do most of the work.

Interactive EasyFlow is a powerful full-screen graphics program dedicated to flowcharts and organization charts. With this program you can quickly compose charts on the screen. More important, you can easily modify charts so they are always up to date.


Features: • Text is automatically centered, character by character, within shapes as you type it • Text formatting controls allow you to over-ride the automatic formatting where desired • Lines are created by specifying the starting and ending points - the program automatically generates the route • Powerful editing facilities allow shapes and even entire rows and columns of shapes to be inserted or deleted; lines are automatically re-routed as necessary • Large chart size (up to 16 shapes wide by 16 shapes high) allows very large flowcharts and organization charts to be handled with ease • Charts can be larger than the screen - the window into the chart scrolls both horizontally and vertically as necessary • Flexible printer interface allows it to work with all

printers, not just dot matrix printers. Wide charts can be printed in strips Also works with Hewlett-Packard 7475A (and compatible) plotters • Twenty standard flowcharting shapes included • Common shapes supplied in three sizes • Extensive manual (125 pages) includes many examples • Context sensitive "help" facility provides immediate assistance at any time • Any number of titles can be placed on a chart • Commentary text blocks can be placed anywhere in the chart • Fast: written in 8088 assembler • Plus many more features than we can mention here.

Requires at least 256K memory, DOS-2 or higher and an IBM or Hercules compatible graphics card.

Order direct for only **\$149.95** + \$2.00 S&H (USA/Canada), \$10.00 (foreign). Payment by MO, check, VISA, COD or Company PO. Rush orders accepted (\$15.00 S&H; USA/Canada only). Rush orders received by noon will be delivered the next business day (to most locations).

The sample screen display shown below is typical of what you see while editing a chart. Other screen displays are provided for entering titles, changing options, getting "help" and so on.



HavenTree Software Limited
P.O. Box 1093-N
Thousand Island Park, NY 13692
(613) 544-6035 ext 48

CIRCLE NO. 113 ON READER SERVICE CARD

LETTERS

A change in algorithm cannot, by itself, correct problems generated by very problematic data. That may be accomplished in two ways: through the use of double precision or by the use of an 8087 coprocessor (or both). An executable file containing the compiled correlation program—compiled to take advantage of the 8087—is available on PCTECHline. As a side note, I would suggest that serious statistical or other mathematical programming on a microcomputer must assume the availability of an 8087. With the 8087, program CORL produces results for the Wampler data that are essentially the same as major mainframe statistical packages, such as SAS. A combination of an 8087 and double precision may be required just to read and write the data properly. You should be aware, however, that most real data are not so ill conditioned as the Wampler data.

Mr. Bostrom also notes that I calculated the standard deviation for a population rather than a sample. Very true. Users may wish to change the formula for calculating the standard deviation in subroutine CORR (p. 140). Within that subroutine, the following set of lines appears:

```
DO 80 I = 1,NV
  FMEAN(I) = FMEAN(I)/ T
  STD(I) = SQRT(R(I,1)/ T-FMEAN(I)**2)
80 CONTINUE
```

The line that begins with STD(I) = is changed so that the loop becomes:

```
DO 80 I = 1,NV
  STD(I) = SQRT((R(I,1)-FMEAN(I)**2)/T)
  Z/(T-1.0))
  FMEAN(I) = FMEAN(I)/ T
80 CONTINUE
```

This is one among several algorithms that will accomplish the desired results.

With the foregoing comments said, I will address the remaining criticisms from Mr. Ikle. On the first point, Mr. Ikle is only partially correct. It is true that one way to define the correlation coefficient is as he states it. If however, correlation coefficient is defined in terms of "standard" scores (or standard normal deviates)—where both variables have been transformed to have a mean of 0 and a standard deviation of 1—and where the slope of the regression is based on standard scores, then the definition as given is correct.

Another common definition is that the correlation coefficient is the ratio of the covariation to the square root of the

FOUR STARS



Paradox® is the only relational database ever to earn this honor from Software Digest.

In all, 15 relational databases were tested. And when the results were tabulated, Paradox was the only one to win high ratings in every category. From ease of learning through ease of use, error handling, performance and versatility.

So not only was it Software Digest's number one relational database, it's now the only one ever to earn their coveted four-star rating. And if you think that's

good, see our new version, Paradox 1.1. For the name of the Ansa dealer nearest you, call 800-547-3000, Dept. 154; in Oregon, 503-684-3001.



PARADOX

Relational Database by Ansa Software

Software Digest Rating		Overall Evaluation	Program Name	Version Tested	Version Tested					Ease of Learning	Error Handling	Performance	Versatility	Memory Required	Price
★★★★★	8.1														
★★★★★	8.1	Paradox	1.0	■	■	■	■	■	512K	\$695	✓				
★★★★	7.8	R:base 5000	1.01	■	■	■	■	■	320K	\$700	✓				
★★★★	7.3	The Smart Data Manager	2.00	■	■	■	■	■	256K	\$495	✓				
★★★★	7.1	dBase III Plus	1.0	■	■	■	■	■	256K	\$695	✓				
★★★★	7.0	PractiBase	1.14	■	■	■	■	■	256K	\$70	✓				
★★★★	7.0	Dataease	Pre. 2.5	■	■	■	■	■	384K	\$600	✓				
★★★	6.9	Power-base	2.10	■	■	■	■	■	320K	\$349	✓				

Software
Digest

RATINGS NEWSLETTER

Test results reprinted from cover of Software Digest March 1986.

Software Digest is a registered trademark of Software Digest, Inc., Philadelphia, Pa.

■ 7.0-9.9 ■ 5.0-6.9 ■ under 5.0

Paradox is a registered trademark of Ansa Software.

CIRCLE NO. 198 ON READER SERVICE CARD

MS-DOS 3.1 ON THE STD BUS: INDUSTRIAL QUALITY AND COMMERCIAL CONVENIENCE FROM PRO-LOG.



Your control system has a lot riding on it. A million-dollar production facility. Life-giving medical equipment. Tomorrow's daily newspaper. It needs to work. . . and keep on working.

Whatever your application, you can benefit from Pro-Log's STD-DOS: The convenience and familiarity of IBM PC/AT® software and operating standards, but in rugged, industrial-quality hardware. It works . . . and keeps on working.

INDUSTRIAL QUALITY:

Operates 0° to 65°C for more than 10 years with an average MTBF of more than 20 years per card. Backed by Pro-Log's 5-year parts and labor warranty.

COMMERCIAL CONVENIENCE:

Microsoft's® MS-DOS 3.1 is a software bus for connecting libraries, languages, editors, and application programs.

The STD BUS is an industry standard hardware bus for connecting memory, I/O, and peripheral functions.

The IBM PC/AT or clone is your development tool.

STD-DOS FEATURES: WITH 2 CARDS

- 8088 CPU, 5 MHz
- Time-of-day clock
- MS-DOS 3.1 in ROM disk
- 128K-byte user ROM disk
- 16K-byte user RAM disk
- 112K bytes system RAM
- RS-232-C, RS-422/485 ports
- I/O expandable to 24 STD BUS card slots
- Memory expandable to 640K bytes
- Under \$1200

NEW SOFTWARE! . . . STD-LIB 1.1: a fully documented disc-resident library of driver software that supports Analog and Digital STD BUS cards for "C", BASIC, and Assembly language programs.

For information on STD-DOS products, local seminars, or a personal demonstration, CALL or WRITE TODAY.



Circle Reader Service No. 252 for Literature, No. 253 for Direct Factory Contact
2560 Garden Road, Monterey, CA 93940 (408) 372-4593, Outside
CA: (800) 538-9570, TLX: 171879; Australia (3) 836-3533; Canada
(416) 625-7752; England (0276) 26517; France (1) 3956-8142;
Germany (07131) 50030; Italy (2) 498-8031; Switzerland (01) 62 44 44.

©Microsoft and MS-DOS are registered trademarks of Microsoft Corporation
©IBM is a registered trademark of International Business Machines Corporation
©1986 ADGROUP International PL052

product of the variation in X and the variation in Y. This is the definition Mr. Bostrom used in his suggestion for an alternative computational algorithm. The point is that several definitions exist for the correlation coefficient that ultimately can be shown to be algebraically equivalent, although not necessarily equivalent in computational precision.

Mr. Ikle's comments on the consequences of missing data result primarily from a difference of opinion on how extensively an issue can be discussed in a short article. My statement is not meaningless. Missing data results in restricting the range of values (variation) on one or both variables. The consequence of this is that the maximum value of the correlation coefficient may not be 1.0. In a correlation matrix, therefore, where the total number of observations may vary from one correlation coefficient to another, they may have varying maximum values. When the sample size is large and the number of missing values is small, these differences are inconsequential. In other words, sampling over a small and restricted range for one variable has the effect of decreasing the value of r . I do not think a complete explanation of the implications of missing data was within the scope of the article.

Concerning comments that appear in listings, they are placed in the code simply to provide a warning, not as a full explanation of the problems of calculating significance tests. Mr. Ikle is obviously correct in his comments on univariate tests of significance, but the fact is that virtually all tests of significance are sensitive to sample size and in multivariate statistical tests, varying sample sizes for difference correlations in the matrix will present problems of interpretation. A rigorous approach would be to restrict tests of significance only to situations in which all data were present or to calculate statistics only on complete data matrices.


Dealing with statistics in a short article is difficult at best. It is not possible to discuss every pitfall—that is the task of statistics text books or more scholarly articles. Perhaps some of these issues can be dealt with in future articles.

—Thomas Madron

WILL THE REAL BUG...

Your article "Taking Command in Turbo Pascal" (Programming Practices, David D. Steiner, March 1986, p. 161) has an interesting bug. The author attempts to work around a bug in DOS 2.0, but fails. The bug is that after a

Using SoftScreen™/HELP we built this sample help system in under 2 hours without programming...



Imagine what you can do!

Introducing SoftScreen/HELP, the most complete system available for creating professional context-sensitive on-line help systems for all your applications.

Finally there is a tool that allows any creative person to build complete on-line help systems. With SoftScreen/HELP, screens that would take days to design, build and modify can now be done in hours.

SoftScreen/HELP features...

- **Screen Processor**—A complete WYSIWYG screen editor that gives you full control of your video display with features like line drawing, special characters and logical video attributes.
- **Screen Linker**—Creates a help file optimized for execution speed and efficient memory use.
- **Runtime Manager**—Simplifies the interface between the help system and your application.

SoftScreen/HELP is not a program generator. It creates a highly compressed, fully indexed data file which is accessed through our Runtime Manager. SoftScreen/HELP will not interfere with other software tools you use to build your applications.

SoftScreen/HELP runs on the IBM-PC™ and true compatibles with MS-DOS™ 2.0 or higher. It requires 256K memory and supports Monochrome and Color/Graphics Adapters in text mode. A hard disk is recommended. SoftScreen/HELP supports most programming languages. Call for the latest information.

SoftScreen/HELP costs \$195 and comes with a 30-day money back offer. Telephone support is provided from 8 a.m. to 8 p.m., Eastern time, Monday through Friday. Not copy protected and no royalties. Source code and UNIX™ versions are available.

To order or for more information:
call (609) 424-0140.

Visa and MasterCard accepted
(NJ residents add 6% sales tax).
To order by mail, send check to:

Dialectic Systems, Inc.

1930 E. Marlton Pike
Cherry Hill, NJ 08003-2148

IBM-PC, Monochrome and Color/Graphics Adapters are trademarks of International Business Machines Corporation. Unix is a trademark of AT&T Bell Laboratories, Inc. MS-DOS is a trademark of Microsoft Corporation.



ATTENTION C-TREE* USERS!

The Portable Application Support System provides on-line query, screen I/O, report generation, and form generation with **no sacrifice in portability!**

- Query system allows end user on-line data inquiry and ad-hoc report generation
- Source code
- Menu and data inquiry utilities
- No royalties on application programs or on executable versions of the Query System
- Uses C-tree* portability conventions
- Complete windowing capability in a portable system. Configuration files included for IBM PC, MS-DOS generic(ANSI), and Xenix systems
- Multiple window Screen I/O system
- Single/multiple line report generator
- Page oriented form generator with automatic pagination of variable length documents
- Other source code programs available. Call for information.

\$395.00

VISA/Master Charge accepted

(718) 229-4540

**KURTZBERG
COMPUTER SYSTEMS**

*C-tree is a trademark of FairCom

CIRCLE NO. 148 ON READER SERVICE CARD

**MS-DOS, UNIX, APPLE MAC, CP/M,
NETWORKS and MORE.
ONE c-tree ISAM DOES THEM ALL!**

The creator of Access Manager™ brings you the most powerful C source code, B+ Tree file handler: **c-tree™**

- multi-key ISAM and low-level B+ Tree routines
- complete C source code written to K&R standards
- single-user, network and multi-tasking capabilities
- fixed and variable record length data files
- virtually opened files accommodate limited file descriptors
- no royalties on application programs

\$395 COMPLETE

Specify diskette format:

- 5¼" MS-DOS
- 8" CP/M
- 3½" Mac
- 8" RT-II



For VISA, MC and COD orders
call (314) 445-6833

FairCom

2606 Johnson Drive
Columbia, MO 65203

© 1985 FairCom

The following are trademarks: c-tree and the circular disk logo—FairCom; MS—Microsoft Inc.; CP/M and Access Manager—Digital Research Inc.; Unix—AT&T; Apple—Apple Computer Co.

CIRCLE NO. 119 ON READER SERVICE CARD

LETTERS

DOS EXEC function call (4BH), the stack pointer registers SS and SP are destroyed. The only registers that can be counted on after returning from an EXEC call are CS and IP. Therefore it is necessary to save SS and SP in CS-relative storage before calling EXEC.

Because the EXEC-calling routine, DOS4BH.ASM, is written as a Turbo Pascal external routine, it cannot be assumed to be at any fixed origin within the code segment. A trick is needed to access CS-relative storage. A NEAR CALL is made to the immediately following instruction. POPping BX retrieves the address from which the call was made, giving the program an offset that can be used to locate CS-relative data. However, if the DOS bug has occurred, that CALL instruction pushes a word of data onto a stack that is not valid. This destroys two bytes of data *somewhere* in memory. Where, is anyone's guess. Thus, the obvious DOS bug has been exchanged for a far more subtle and hard-to-find bug in the calling routine.

I suspect that DOS4BH.ASM and the rest of the routines in the article were tested only under DOS versions 2.1 and later. Because the DOS bug is not present in those versions, the mistaken work-around will cause no problems: the stack is valid when the CALL is made, and no damage is done.

It would seem that EXEC cannot be called reliably from Turbo Pascal. But that is not so. The solution is to write the EXEC-calling routine as an in-line statement instead of an external. Turbo Pascal will generate the address of a typed constant (CS-relative initialized variable) into an in-line statement. That address is correct as is; it requires no tricks to properly locate the data. Therefore, no stack manipulations are required during the critical period while the stack is invalid, and the routine will work on DOS versions 2.0 to 3.1.

Bela Lubkin
Santa Cruz, CA

I read with interest David D. Steiner's article "Taking Command in Turbo Pascal" and also Bela Lubkin's letter (over CompuServe) pointing out the bug in DOS4BH.ASM, included with the article. While I agree with Mr. Lubkin that in-line code is preferable to an external routine when invoking EXEC from a Turbo Pascal program, DOS4BH.ASM can be modified to correct the bug. Replace the four MOV instructions that save SS and SP with the following two:

```
MOV CS:LOADSS+1[BX],SS
MOV CS:LOADSP+1[BX],SP
```


“Turbo Pascal...
is a very good system.
But don't make
the mistake of trying to
use it for large programs.”

*Niklaus Wirth
as reported in Micro Cornucopia
August-September 1985*



LOGITECH
MODULA-2/86

Is LISP Right for Your Expert System?

Find Out — FREE

You can explore LISP by examining a complete sample problem. Call and we will send you a free source listing of "SELECTWP".* It prompts users for criteria and helps them choose which micro word processor to buy.

Look over the TransLISP syntax (COMMON LISP compatible). Your application will probably have similar characteristics.

Power & Flexibility

Do you get flexibility in PASCAL and C? Of course, but examine the listing of SELECTWP to see how much more power and flexibility you get. The LISP advantages:

- forward references make program flow fit the problem
- manipulate data structures of varying sizes
- create your own language to fit the problem domain
- avoid mundane, busy work required with traditional procedural languages
- powerful function and macro building facilities provide better data abstraction

*SELECTWP includes 512 lines of LISP code and 335 lines of comments.

Full refund if not satisfied in 30 days.



TransLISP gives You the Advantage

Using TransLISP for your expert system has several advantages over other AI tools. And you will see SELECTWP illustrate:

- * the ability to control how decisions are made
- * the freedom to assign weights and react to user choices
- * the complete control you have over how a problem is solved, and interaction with the user

Nothing to lose

Examine LISP carefully by studying a practical program free.

Or buy TransLISP risk free. SELECTWP is just 1 of over 20 sample programs in the complete TransLISP system. The other sample programs include: an adventure game, a program to read dBASE SDF files, "Job Counselor" and more. Use the modular tutorial, the complete 300+ function LISP interpreter, and the online help, to get started in LISP in only a few hours.

Develop programs of up to 12000 lines on a 640K system or use TransLISP on a floppy only, 256K RAM machine. MSDOS.

Call 800-821-2492 for SELECTWP FREE. Or order the complete TransLISP system risk free for only \$75.

**Solution
Systems**

335 Washington St., Norwell, MA 02061 (617) 659-1571

CIRCLE NO. 126 ON READER SERVICE CARD

Make your PC or AT into a COMMUNICATING WORKSTATION for only \$85

BUY NOW
Price will increase
to \$95 on 9/1/86

Use ZAP, the Communications System for Technical Users COMPLETE Communications for PROGRAMMING and ENGINEERING

EMULATION of graphics and smart terminals is combined with the ability to TRANSFER files reliably, CAPTURE interactive sessions, and transmit MESSAGES while also being able to swap between your mini or mainframe session and your PC application. SUSPEND a line to run a PC application. Reconfigure features to fit the communications parameters and keyboard requirements of the host computer software. Complete technical documentation helps you understand and fit ZAP to your style.

HIGHLIGHTS OF ZAP:

- Emulate TEKtronix 4010/14 and DEC VT 100, 102, 52 including variable rows and columns, windows, full graphics, and smooth scrolling.
- Reliable file transfer to/from any mainframes and PCs including KERMIT and XMODEM protocols plus you get a full copy of KERMIT. Transfer speeds ranging from 50 to 38,400 BAUD. Session control include printer dumps and save to disk.
- MACRO and Installation files ("scripts") controllable by you.
- EMACS, EDT and VI "Script" files are included. ZAP is also used with other popular software including graphics products like DISSPLA and SAS/GRAPH.
- CONFIGURABLE to communications, terminal features on the "other end"; 1, 2 stop bits; 5, 6, 7 or 8 data bits; parity of odd, even, none, mark and space; remap all keys including the numeric pad and standard keyboard, set any "virtual" screen size.
- Full PC/MSDOS access to run any command or program that will fit in your systems memory. ZAP takes less than 64K.
- 9 Comm ports are supported by ZAP. Plus full color in text and graphics make use of the IBM color, EGA cards, or Hercules Monochrome.

ONLY
\$85

**Solution
Systems**

335-P Washington St.
Norwell, Mass. 02061
617-659-1571
800-821-2492

Full refund if not satisfied during first 30 days.

CIRCLE NO. 129 ON READER SERVICE CARD

LETTERS

and replace the seven instructions from CALL RELO2 through MOV SP, DX, which restore SS and SP, with:

```
LOADSS: MOV SP,0
          MOV SS,SP
LOADSP: MOV SP,0
```

These changes store the values of SS and SP directly into the move immediate instructions that will restore SS and SP after the EXEC call. The values thus stored replace the dummy 0 values in the move immediate instructions above.

Self-modifying code is normally to be avoided in most situations.

Randy Forgaard
Watertown, MA

Mr. Lubkin's comments about the subtleties of executing subprocesses with DOS 2.0 compared to versions 3.x are substantially correct, although the bug he identifies may not need correcting.

He correctly notes that when DOS4BH regains control from the subprocess and uses a local CALL and POP to calculate a relocation factor, a word is PUSHed onto the stack before the Turbo Pascal stack is restored. If DOS 2.x is used, then this stack will not be the Turbo Pascal stack. Mr. Lubkin is incorrect that this can overwrite a word anywhere in memory, because the value of the SS:SP register pair following a DOS EXEC call is not random. Rather, it points to the region that DOS last used as a stack. Hence, it is improbable that harm will befall either a resident user application or the operating system.

I have modified DOS4BH to eliminate the "bug." Before the relocation factor is recalculated, the SS:SP pair is set to 0:03C2H, a word of memory that the IBM Technical Reference says is used by the "BASIC interpreter while BASIC is running." This assures that the word modified by the Call is unneeded. (DOS4B.ASM is on PCTECHline.)

Mr. Forgaard's solution is elegant, but self-modifying code should be avoided. Also, his changes will not assemble with Microsoft MASM 3.0. His first two MOVs produce "Illegal Item Size" messages. Replace them with:

```
MOV WORD PTR CS:LOADSS + 1[BX],SS
MOV WORD PTR CS:LOADSP + 1[BX],SP
```

—David D. Steiner

ERRATUM

In "Matching Regular Expressions" (Programming Practices, Jon Forrest, May 1986, p. 191), note that program listings 2 and 3 were transposed. PC Tech Journal regrets the error.



TAKE THE NEXT LOGICAL STEP

\$89 Price

- Separate Compilation
- Native Code Generation
- Large Memory Model Support
- Multitasking
- Powerful Debugging Tools
- Comprehensive Module Library
- Available for the PC and the VAX

Move up to LOGITECH MODULA-2/86. Whether you're a single programmer or part of a team, with LOGITECH MODULA-2/86 you'll decrease your overall development cycle and produce more reliable, more maintainable code. Build your program using our extensive library modules, your own modules or those from a growing list of available third-party software vendors. If you're a Turbo Pascal user you can even take your existing code along with you with the help of our new Translator!

NEW & IMPROVED!

Turbo Pascal to Modula-2 Translator

\$49

Now it's even easier for Turbo users to step up to Modula-2/86. Our improved Translator changes your Turbo source code into Modula-2/86 source, solving all the incompatibilities, and translating the function calls of Turbo into Modula-2/86 procedures. Implements the complete Turbo library!

LOGITECH MODULA-2/86

\$89

Complete with Editor, Run Time System, Linker, 8087 Software Emulation, Binary Coded Decimal (BCD) Module, Logitech's comprehensive library, Utility to generate standard .EXE files. AND more!

■ LOGITECH MODULA-2/86

with 8087 Support

\$129

■ LOGITECH MODULA 2/86 PLUS

\$189

For machines with 512K of RAM. Takes advantage of larger memory to increase compilation speed by 50%.

Turbo Pascal is a registered trademark of Borland International.



MODULA-2/86

RUN TIME DEBUGGER

\$69

(Source level!)

The ultimate professional's tool! Display source code, data, procedure call chain and raw memory. Set break points, assign values to variables, pinpoint bugs in your source.

UTILITIES PACKAGE

\$49

Features a post-mortem debugger (PMD). If your program crashes at run time the PMD freezes the situation so you can pinpoint, in the source, the cause of the error and the status of the data. Also includes a disassembler, cross reference utility and version that allows conditional compilation.

LIBRARY SOURCES

\$99

Source code for our major library modules is now available for customization or exemplification.

WINDOW PACKAGE

\$49

Now you can build true windowing into your Modula-2 code. Powerful, though only 15K in size. Features virtual screens, color support, overlapping windows and a variety of borders.

MAKE UTILITY

\$29

Automatically selects modules affected by code changes to minimize recompilation and relinking. Even figures out dependencies for you!

CROSS RUN TIME DEBUGGER

AND ROM PACKAGE

\$199

Now available at an introductory price!

NEW, improved Turbo Pascal to Modula-2 Translator!

Call for information about our VAX/VMS version, Site License, University Discounts, Dealer & Distributor pricing.

To place an order call our special toll free number:

800-231-7717

In California:

800-552-8885

YES

I want to move up to LOGITECH MODULA-2/86!

Here's the configuration I'd like:

- | | |
|---|--------------|
| <input type="checkbox"/> Logitech Modula-2/86 | \$89 |
| <input type="checkbox"/> with 8087 support | \$129 |
| <input type="checkbox"/> Plus Package | \$189 |
| <input type="checkbox"/> Turbo to Modula Translator | \$49 |
| <input type="checkbox"/> Run Time Debugger | \$69 |
| <input type="checkbox"/> Utilities Package | \$49 |
| <input type="checkbox"/> Library Sources | \$99 |
| <input type="checkbox"/> Window Package | \$49 |
| <input type="checkbox"/> Make Utility | \$29 |
| <input type="checkbox"/> ROM Package | \$199 |

Total Enclosed \$_____

☐ Visa ☐ Mastercard ☐ Check Enclosed

Card Number _____ Expiration Date _____

Signature _____

Name _____

Address _____

City, State _____

Zip _____ Phone _____



LOGITECH

Logitech, Inc.
805 Veterans Blvd.
Redwood City, CA 94063
Telephone 415-365-9852

For European pricing please contact:

Logitech SA
Box 32, CH-1143
Apples, Switzerland
Telephone 41-21-774545

A few good reasons

WORDPERFECT

WORDPERFECT CORPORATION

DBASE III PLUS

ASHTON-TATE

EASY BUSINESS SYSTEM PLUS SERIES

COMPUTER ASSOCIATES MICRO

PRODUCTS DIVISION (SORCIM/IUS)

MICROSOFT WORD

MICROSOFT CORP.

OPEN SYSTEMS ACCOUNTING

SOFTWARE

OPEN SYSTEMS, INC.

HARDISK ACCOUNTING SERIES

GREAT PLAINS SOFTWARE

R:BASE 5000

MICRORIM

NETWORK REVELATION

COSMOS

WORDSTAR 2000

MICROPRO INTERNATIONAL

MULTIMATE ADVANTAGE

MULTIMATE INTERNATIONAL CORP.

DATAFLEX

DATAACCESS CORP.

MULTIMATE PROFESSIONAL WORD

PROCESSOR

MULTIMATE INTERNATIONAL CORP.

MDBS III

MICRO DATA BASE

SYSTEMS, INC.

KNOWLEDGEMAN

MICRO DATA BASE

SYSTEMS, INC.

SOLOMON III

TLB

MBA ACCOUNTING SOFTWARE

MICRO BUSINESS APPLICATIONS

EXCALIBUR PLUS SERIES

ARMOR SYSTEMS INCORPORATED

INFORMIX-SQL

RELATIONAL DATABASE SYSTEMS

SAMNA WORD III

SAMNA

CYMA GENERAL BUSINESS

CYMA/MCGRAW HILL

ACCOUNTING SOFTWARE

LIBRA PROGRAMMING

DBMAN-NET

VERSASOFT CORPORATION

SAMNA+

SAMNA

FASTRAK

CORE SOFTWARE, INC.

ZIM

ZANTHE

LAN: DATASTORE

SOFTWARE CONNECTIONS

INFORMA

UNLIMITED PROCESSING, INC.

INTEGRATED ACCOUNTING

SOFTWARE

PROMARK LTD.

TEAM-UP

UNLIMITED PROCESSING, INC.

B.O.S.S.

AMERICAN PLANNING CORP.

METAFILE

METAFILE INFORMATION

SYSTEMS, INC.

OFFICE WRITER

OFFICE SOLUTIONS

Q-PRO 4

QNE

THE BIG 8 ACCOUNTING

MODTECH

GOLDDATABASE

GOLDDATA COMPUTER

SERVICES, INC.

THE SENSIBLE SOLUTION

O'HANLON COMPUTER SYSTEMS

MICRO-ADAPT

DATA FINANCIAL SYSTEMS

EXCALIBUR SERIES

ARMOR SYSTEMS

BBX-BUSINESS BASIC EXTENDED

BASIS INCORPORATED

CLEO 3270 BSC CLUSTER

CLEO SOFTWARE

HIGGINS ADMINISTRATIVE

SOFTWARE

CONETIC SYSTEMS INCORPORATED

NETWORK COURIER

CONSUMERS SOFTWARE, INC.

HARDISK ACCOUNTING SERIES

GREAT PLAINS SOFTWARE

TOPVIEW

IBM

SMART SOFTWARE SYSTEM

INNOVATIVE SOFTWARE CORP.

MBP COBOL

MBP SOFTWARE AND SYSTEMS

WORDSTAR 2000 PLUS

MICROPRO INTERNATIONAL

CC-MAIL

PPC/SYSTEMS

ACCOUNTS PAYABLE

REALWORLD CORP.

GENERAL LEDGER

REALWORLD CORP.

JOB COST

REALWORLD CORP.

INVENTORY CONTROL

REALWORLD CORP.

RM/COBOL

RYAN-MCFARLAND CORPORATION

BTRIEVE/N

SOFTCRAFT, INC.

OPEN ACCESS 2

SOFTWARE PRODUCTS

INTERNATIONAL, INC.

DBIII COMPILER

WORDTECH SYSTEMS, INC.

MARKET MANAGEMENT SYSTEM

ABACUS

PRISMA PRODUCTION

ABC SYSTEMS AG

C-MAIL/C-MERGE

ACCESS DYNAMICS, INC.

CENTRAL SERVICES MGMT

SOLUTION

ADVANCED HEALTHCARE

SYSTEMS, INC.

HOT PRINT

ADVANCED PC SOLUTIONS

MARCON II

AIRS, INC.

AMBER

AMBER SOFTWARE CORPORATION

P.O. WRITER

AMERICAN TECH, INC.

COLLECT

ANOTHER DIRECTION DATA

HPMS

ANOTHER DIRECTION DATA

H.I.S.

ANOTHER DIRECTION DATA

RAISE

ANOTHER DIRECTION DATA

PHYSICIANS BILLING

ANOTHER DIRECTION DATA

CUMS

ANOTHER DIRECTION DATA

PROJECT WORKBENCH

APPLIED BUSINESS TECHNOLOGY

TELECONFERENCING

APPLIED COMPUTER RESOURCE

SERVICES

JOB TRACKING

APPLIED COMPUTER RESOURCE

SERVICES

TEN-IN-ONE

ARMOR SYSTEMS

MAINSTREET MERCHANDISER

ARMOR SYSTEMS

DONOR TRACKING SYSTEM

ARMSTRONG BUSINESS

COMPUTERS

DENTALIS SYSTEM VI

ARTICULATE PUBLICATIONS, INC.

MEDCALIS SYSTEM VI

ARTICULATE PUBLICATIONS, INC.

PM/TURBO

ASPEN COMPUTER SYSTEMS, INC.

DEX

ATLANTA TECHNOLOGIES

CALL-CONTROL

ATLAS SYSTEMS

SERVICE MASTER

AVNET COMPUTER TECHNOLOGY

AUTOMATED PROOF CORRECTION

SYSTEM

BACKROOM SYSTEMS GROUP

RESEARCH & ADJUSTMENT

CONTROL

BACKROOM SYSTEMS GROUP

LARGE ITEMS MONITORING SYSTEM

BACKROOM SYSTEMS GROUP

RETURN ITEMS CONTROL SYSTEM

BACKROOM SYSTEMS GROUP

AUCTIONEER 3 & LISTRIEVE

BAROQUE SOFTWARE SYSTEMS

TRACTOR & IMPLEMENT DEALERS

ACCOUNTING

BASIC SOFTWARE SYSTEMS

PC NETWORKING PRODUCTS

BRAEGEN CORP.

NETUTILS

BRITISH RAILWAYS BOARD

TIME ANALYSIS AND BILLING

BUSINESS APPLICATIONS

SOFTWARE, INC.

CLIENT ACCOUNTING/GL

BUSINESS APPLICATIONS

SOFTWARE, INC.

THE OFFICER

BUSINESS SYSTEMS RESOURCES

PM/TURBO

CALDWELL COMPUTER ENTERPRISES

CHARTERHOUSE ACCOUNTING

SYSTEMS

CHARTERHOUSE SOFTWARE CORP.

CHARTER ACCOUNTING SYSTEMS

CHARTERHOUSE SOFTWARE CORP.

CB86 TO NOVELL INTERFACE

CHECKPOINT SYSTEMS

VIDWARE

CHECKPOINT SYSTEMS

AUTOBOOK

CISCO, INC.

WHEELS

CISCO, INC.

CITATIONS

CISCO, INC.

TIES

CISCO, INC.

CAD

CISCO, INC.

IMIS

CISCO, INC.

CASS

CISCO, INC.

POSSE

CISCO, INC.

ELECTRONIC PEGBOARD

COLONIAL VALLEY

SOFTWARE, INC.

NOVELLIB & NOVELLIB-L

COMMUNICATION HORIZONS

PIER

COMPTON, INC.

EARTHWK

COMPTON, INC.

BEAMS

COMPTON, INC.

CTCGO

COMPTON, INC.

STABY

COMPTON, INC.

PGELEV

COMPTON, INC.

STRAN

COMPTON, INC.

CADLINK

COMPTON, INC.

POLICY EXPRESS

COMPARE DATA CORPORATION

COMPUNews CLASSIFIED AD

MANAGEMENT

COMPUNews, INC.

SCRIPMASTER/PC

COMPUTER, INC.

THE PROGRAM MANAGER

COMPUTERIZED BUSINESS

SOLUTIONS

HERITAGE LIVESTOCK AUCTION

COMPUTERIZED SERVICE AND

DESIGN

MENU SYSTEM

COTTAGE INDUSTRIES, INC.

4GL

CRAIGMORE HOUSE, LTD.

CYBERGRAM WIDE AREA MAIL

CYBERTEK COMPUTER

PRODUCTS, INC.

MICRO INFORMATION MANAGER

CYBERTEK COMPUTER

PRODUCTS, INC.

CYBERSCRIBE V

CYBERTEK COMPUTER

PRODUCTS, INC.

AUTOSERV

CYLLON SYSTEMS

INTERNATIONAL, LTD.

MAILING LIST

DATABASE GROUP

PROF TIME MANAGER AND BILLING

MONITOR SYSTEMS GROUP
 INFOSEV FOOD SERVICE
 MANAGEMENT SYSTEM
COMEAGAIN
 INTERNATIONAL EXPERT
 SYSTEMS, INC.
NETWORK MANAGEMENT
REPORT UTILITY
 J.A. LOMAX AND ASSOCIATES
RETAIL FINANCIAL MGMT SYSTEM
 JAHLL DATA SYSTEMS
POWER PAYROLL
 JCA SYSTEMS
CLASS
 KLEIN & KLEIN
OMICROM MEDICAL MGMT SYSTEM
 LEDON
THE ASSISTANT
 LIBRARY AUTOMATION
 PRODUCTS, INC.
LOGGMATE
 LODGISTIX
MACOLA FINANCIAL SOFTWARE
 MACOLA, INC.
HR-1
 MAINFRAME MICROS
HR-APPLICANT TRACK
 MAINFRAME MICROS
RETAIL MANAGEMENT SYSTEM
 MANAGEMENT INFORMATION
 SOLUTION, INC.
MEGASOURCE HOSPITAL
PHARMACY
 MEGASOURCE, INC.
ACCOUNTMASTER/
DISTRIMASTER
 METAPLUS INTERNATIONAL
INTERNATIONAL BANKINGS
PRODUCT
 MICRO BANKING
 AUTOMATION, INC.
MORTGAGE TRACKING SYSTEM
 MICRO VENTURES, INC.
MULTISOFT
 MULTISOFT
NGC ACCOUNTING
 NGC COMPUTER SYSTEMS
N.E.T. UTILITIES
 NETWORK ENHANCEMENTS TOOLS
SIMCOM HOTEL MGMT SYSTEM
 NEW SYSTEMS, INC.
GLAS PAC I
 PACIFIC COMPUTER &
 INFORMATION
NETWORKED MCBA ACCOUNTING
 PACIFIC DATAWARE
PRACTICE MANAGER
 PACIFIC MEDSOFT, INC.
NETWORK ASSISTANT
 PACIFIC SOFTWARE
TRUST ACCOUNTING
 PENTABS
DEFINED BENEFIT
 PENTABS
PENSION SELECTOR SYSTEM
 PENTABS
401(K)/DEFINED CONTRIBUTION
 PENTABS
TIME & CHARGES SYSTEM
 PENTABS
DATA MANAGEMENT SYSTEM
 PENTABS
WORD MANAGEMENT SYSTEM
 PENTABS
THE PENSION SALES CREATOR
 PENTABS
PLAN DOCUMENT SYSTEM
 PENTABS
THE CLIENT MANAGEMENT SYSTEM
 PENTABS
401(K)/THRIFT OPTION
 PENTABS
PARS
 PHYSICIANS RESOURCE
 MANAGER-MO
EMS/PC
 PROTOTYPE, INC.
MATCH MAKER+
 QBIT COMPUTER SOLUTIONS
UPSTART
 RAM SOFTWARE LIMITED
SYNERGY
 RAM SOFTWARE LIMITED
FINANCIAL MANAGEMENT SYSTEM
 RCP CONSULTING, LTD.
LAN-MAIL MONITOR
 SOFTWARE CONNECTIONS
LAN:DACORE
 SOFTWARE CONNECTIONS
REAL WORLD
 SOFTWARE SERVICES, INC.

DIRECT MAIL II
 SOFTWARE SYNERGY GROUP
TABS III-M
 SOFTWARE TECHNOLOGY, INC.
GENERAL LEDGER SYSTEM
 SOFTWARE TECHNOLOGY, INC.
CRITICAL DATE SYSTEM
 SOFTWARE TECHNOLOGY, INC.
TRUST ACCOUNTING SYSTEM
 SOFTWARE TECHNOLOGY, INC.
EASE
 STANHOPE ASSOCIATES, INC.
M.A.S. 90
 STATE OF THE ART, INC.
SUMMIT BROADCAST SYSTEM
 SUMMIT SOFTWARE
 SYSTEMS, INC.
SUNDB6A
 SUNBELT COMPUTER SYSTEMS
SUNDB86M
 SUNBELT COMPUTER SYSTEMS
MUNIS
 THE COMPUTER CENTER
TENANTRAC
 TIMBERLINE SOFTWARE
 CORPORATION
AEPEX
 TIMBERLINE SOFTWARE
 CORPORATION
MEDALLION/SPECIALTY
 TIMBERLINE SOFTWARE
 CORPORATION
MEDALLION/BUILDER
 TIMBERLINE SOFTWARE
 CORPORATION

MEDALLION/GENERAL
 TIMBERLINE SOFTWARE
 CORPORATION
MEDALLION COLLECTION
ACCOUNTING
 TIMBERLINE SOFTWARE
 CORPORATION
IMPULSE
 TOM FAIREY COMPANY
TRACLINE
 TRACLINE SOFTWARE, INC.
CUST. APPL: FINAN, MANU, DISTR
 TRACY ASSOCIATES, INC.
KINDERGARTEN THRU 12TH
COURSEWARE
 WASATCH EDUCATION SYSTEMS
WORKERS' COMPENSATION
CASE MGMT SYSTEM
 WEISENBERGER AND ASSOCIATES
WELBER RM. & EVENT SCHEDULING
 WELBER COMPANY
BUSINESS ACCOUNTING SYSTEM
 WESTCON ASSOCIATES, INC.
OCS OFFICE CONTROL SYSTEM
 WIBBEN CONSULTING & SYSTEM
LASER BEAM
 WORDNET
DBXL
 WORDTECH SYSTEMS, INC.
INFORMAL COMPLETE TRACKING
 SYSTEM
 WUTC
RAILROAD INVENTORY
 WUTC
PRODUCE BROKERAGE SYSTEM
 ZADEK, INCORPORATED

PAYROLL
 REALWORLD CORP.
ORDER ENTRY/BILLING
 REALWORLD CORP.
SALES ANALYSIS
 REALWORLD CORP.
ACCOUNTS RECEIVABLE
 REALWORLD CORP.
MBSI ACCOUNTING
 REALWORLD CORP.
RED RIVER FUEL PACKAGE
 RED RIVER SOFTWARE
ESQL/C
 RELATIONAL DATABASE
 SYSTEMS, INC.
C-ISAM
 RELATIONAL DATABASE
 SYSTEMS, INC.
ROBEC SIMPLIFIED BUSINESS
SYSTEM
 ROBEC, INC.
UBS-2 UTILITIES BILLING SYSTEM
 ROBITRON SOFTWARE RESEARCH
IPC-1 INVENTORY PRODUCTION
 ROBITRON SOFTWARE RESEARCH
GLS-1 GENERAL LEDGER SYSTEM
 ROBITRON SOFTWARE RESEARCH
FBS-1 FREIGHT BROKERAGE SYSTEM
 ROBITRON SOFTWARE RESEARCH
ATS-1 AUTO TIRE STORE
MANAGEMENT
 ROBITRON SOFTWARE RESEARCH
APS-2 AUTO PARTS MANAGEMENT
SYSTEM
 ROBITRON SOFTWARE RESEARCH
 AND MANY MORE...

for using NetWare.®

There are currently over 3,000 NetWare-compatible multiuser applications available. With more being introduced every day. No other local area network operating system can say the same. And that's reason enough for the 300,000 NetWare users throughout the world.

See for yourself.

Send for a copy of the new "NetWare-Compatible Software Directory" today. In it you'll find a comprehensive listing and descriptions of the thousands of applications available for NetWare-supported LANs.

Price: \$50.

Yes, please send me _____ copy(ies) of the Software Directory at \$50 each. I'm enclosing a check, or charge my VISA or MasterCard (circle one).
 Credit card # _____ Expiration Date _____

Signature _____

Name _____

Title _____

Company _____

Address _____

City _____ State _____

Zip _____ Phone () _____

Return to:
"Software Directory"
 Novell, Inc.
 748 North 1340 West
 Orem, Utah 84057



NOVELL

News about the Microsoft Language Family

Improved Microsoft® C Compiler Version 4.00 Is Now Available

ANSI compatibility: Microsoft C Compiler Version 4.0 provides increased support for the developing ANSI standard. **Library support:** Over 30 new library functions have been added, including UNIX™ System V functions `vprintf`, `vscanf`, and `setvbuf`. **More memory models:** Compact and huge memory models have been added for increased versatility, bringing the number of supported memory models to five. **Optimizations:** Elimination of common sub-expressions joins our list of optimizations to make your generated code tighter than ever before. **Source code:** Full start-up and exit source code is provided. In addition to these new features, Microsoft C Compiler Version 4.0 allows you to compile and optimize larger programs, get mixed source and disassembly listings, control floating-point math better, and use improved overlay capabilities. And **MAKE**, the program maintenance utility, helps ensure up-to-date program components by automatically recompiling and relinking to keep up with your source code changes.

The New CodeView™ Source Debug Utility Is Bundled with Microsoft C. All the power of SYMDEB plus full windowing orientation make CodeView the debugger you will want to grow into. See source code and disassembly interspersed. Use drop-down menus, multiple windows, independent graphics screen swapping, and a read-only source code editor to navigate through your code and locate logic errors more quickly than ever before. Exercise your code with the dynamic C expression evaluator instead of recompiling multiple test cases. Set conditional breakpoints. See registers and variables (even locals) change as you watch an animated trace program execution. Special offer for CodeView demo: Words can't say it all here, but our freely copyable demo disk is available for only \$5. Take a test drive!

New Microsoft QuickBASIC Version 2.00 Makes Programming in BASIC Easier and Faster

Microsoft QuickBASIC has undergone a major transformation in its new Version 2.0 release. We think that it will change the way you program in BASIC. The Microsoft QuickBASIC programming environment features an integrated editor, compiler, and runtime.

The editor uses a Microsoft Windows-like interface for full screen editing with pull-down menus. The editor supports the Microsoft Mouse and the IBM® 43-line Enhanced Graphics Adapter. The faster compiler can be invoked directly from the editor, compiling Microsoft QuickBASIC programs directly into memory and bypassing the link step. If no errors are detected the program can start executing immediately. Both compilation errors and runtime errors will restart the editor and place the cursor on the troublesome line.

Debugging compiled programs is easier with Microsoft QuickBASIC 2.0. The TRON statement enables the new source display animated trace and step modes. The tracing features can be toggled on and off using the function keys.

Large BASIC program development is supported by an additional new method of separate compilation. User libraries of BASIC and assembly language routines can be loaded into the in-memory compilation and execution environment. Microsoft QuickBASIC 2.0 also supports stand-alone application development.

New Microsoft QuickBASIC language features include block IF/THEN/ELSE, Enhanced Graphics Adapter support including the new 640 by 350 graphics modes, and dynamic arrays that can now use all of available user memory.


For more information on the products and features discussed in the newsletter,
write to: Microsoft Languages Newsletter
16011 NE 36th Way, Box 97017, Redmond, WA 98073-9717
Or phone:
(800) 426-9400. In Washington State and Alaska,
call (206) 882-8088. In Canada, call (416) 673-7638.

Latest DOS Versions:

Microsoft C Compiler	4.00
Microsoft COBOL	2.10
Microsoft FORTRAN	3.31
Microsoft Macro Assembler	4.00
Microsoft Pascal	3.31
Microsoft QuickBASIC	2.00

Microsoft is a registered trademark and CodeView is a trademark of Microsoft Corporation. UNIX is a trademark of AT&T Bell Laboratories. IBM is a registered trademark of International Business Machines Corporation.

Look for the Microsoft Languages Newsletter every month in this publication.



PC Scheme

This fast LISP compiler runs on the base IBM PC hardware, yet meets professional programming standards.

Implementors of the LISP language have had a tacit agreement that the IBM PC hardware is not powerful enough to drive LISP software. And no wonder—the emerging standard for LISP, Common LISP, requires 10 times as much memory as a 640KB machine can provide. Memory and speed considerations relegate the PC and PC/XT to the lesser roles of training vehicles and target machines—or do they?

An examination of IBM PC LISP implementations confirms this dim view of what can be done on the PC. None is a complete implementation of a standard dialect; some are mere training tools; and one delivers, in the words of an author, “conceptual tinker toys for adults.” Implementors provide some Common LISP functions, but fundamental differences between dialects prevent portability. Other factors mitigate against serious LISP development; designers have paid little attention to support environments or debugging. Most products are interpreters, so they are quite slow. (An exception is Golden Common LISP 286 Developer, a fast \$1,195 compiler for PC/ATs with extended memory. For more information on Gold Hill’s implementations, see “Creating a Standard LISP,” Mark Bridger and John Frampton, December 1985, p. 98.)

Texas Instruments challenges conventional wisdom with PC Scheme, a full LISP development system tailored to the PC and compatibles. PC Scheme is complete, well-designed, and inexpensive at \$95. For these reasons, *PC Tech Journal* has named PC Scheme Product of the Month for August.

Creating a full LISP system on a PC is a marvel somewhat akin to building a sailing ship in a bottle, so every step of PC Scheme’s design was carefully focused on the task. Texas Instruments took the extra step of molding the language as well as the implementation to the microcomputer environment. PC Scheme is actually two products in one:

the implementation and a language (called TI Scheme).

The TI Scheme language is different without being nonstandard. Scheme is a LISP dialect used for teaching at the college level. It was designed expressly for personal computers at MIT in 1975 and standardized in 1985. A number of books and papers have been published on Scheme, most notably, *The Structure and Interpretation of Computer Programs*, (see “An Elegant Scheme,” Book Reviews, this issue, p. 183). TI Scheme was designed to run the examples in this book unmodified, a significant concession to the novice seeking to master this complicated language.

Block structure and simple syntax make Scheme the most elegant dialect in the LISP family. While respecting the language, TI Scheme’s designers did not lose sight of the practical realities of programming. TI Scheme is a vast extension of the Scheme standard, which includes character and string handling, structures (similar to Pascal records), arrays, vectors, windows, graphics and interfaces to C and assembly language. The Scheme command SET! has the same generic replacement capabilities as Common LISP’s SETF. The TI Scheme reference manual contains a description and example for each of the more than 400 functions.

The PC Scheme implementation is as tightly designed as the TI Scheme language specification. An incremental compiler processes all source code into virtual machine code, which is smaller but slower than native code. Slow or not, PC Scheme achieved the best overall times of any IBM PC LISP implementation on a function-calling and CON-
SING benchmark (TAK and DERIV in *Performance and Evaluation of LISP Systems*, MIT Press, 1986).

Attention to detail marks the PC Scheme implementation as much as its high speed. Such attention is especially important in LISP implementations

because parenthesis-laden LISP code is not easy to read. PC Scheme’s EMACS-style editor (the standard syntax-sensitive LISP editor) is spare but fast, providing a quick edit/compile cycle. Extras, such as session transcript, fast-loading files, and shell-to-DOS, are abundant. PC Scheme’s smooth and bug-free operation contrasts markedly with other PC LISP implementations.


PC Scheme takes a unique and laudable approach to error handling. The TI Scheme language includes 22 error handling functions in addition to the normal TRACE command, providing all sorts of low-level hooks, breakpoints, and diagnostic print-outs. In addition, PC Scheme has another facility for debugging. While most LISP systems spawn error levels during interactive sessions, PC Scheme uses a single error level. When an error is encountered, the runtime debugger displays a command menu. The debugger displays the current lexical and dynamic state of the LISP system and allows the user to step through the system’s nested blocks and environments. Scheme objects can be listed or modified from the debugger.

Texas Instruments has succeeded in an endeavor that most LISP vendors have not even tried. The PC Scheme environment is a complete LISP system that runs a standard dialect on the base PC hardware. Space limitations were considered during every phase of TI Scheme design and PC Scheme construction, resulting in a tool that is not a toy, not a compromise, but a complete LISP implementation for the professional programmer.




PC Scheme: \$95
Texas Instruments, Inc.
Data Systems Group
P.O. Box 2909
M/S 2244
Austin, TX 78769-2909
800/527-3500
CIRCLE 343 ON READER SERVICE CARD

Hardware, software, and other developments for the IBM PC family



ShareData by Extended Systems



Intel's Above Board PS/AT

FROM IBM

IBM Corporation has announced that the National Service Division (NSD) now can remove or disconnect a non-IBM machine and/or non-IBM feature that is diagnosed as causing system or machine failure. Further, the NSD can replace the non-IBM machine or non-IBM feature with a similar non-IBM machine or non-IBM feature supplied by the customer. **Service support for non-IBM PC products** does not cover non-IBM machines or non-IBM features for which IBM offers maintenance agreement service. Service support for non-IBM products is available under an amendment to the IBM maintenance agreement. Annual charge of \$30 per system unit (this is in addition to the maintenance agreement charge for the IBM PC system unit).

IBM BOOKS is a new department of the company that will publish books for business and computer professionals. The books will be sold in bookstores and other retail outlets; they will be written by IBM authors and other experts in the field of information processing. Distribution will be handled by Random House, Inc. (New York) to stores in the United States and Canada. Six titles are planned for publication this fall, covering topics such as portable computing, networking, business graphics, word processing, maintenance, and a dictionary of computer terms. IBM plans to publish about 20 books a year.

CAEDS for the **RT/PC** provides users with engineering capability for solid geometric modeling and finite element modeling. Using the data-transfer facilities of the PC 3278/79 Emulation Adapter and RT 3278/79 emulation, data can be passed among CAEDS products on an IBM host and CAEDS for the RT/PC on an RT. Data also can be passed between CAEDS for the RT and other IBM CAD/CAM products running on an IBM host.

CAEDS base for the RT, \$1,655; CAEDS object modeler for the RT, \$6,060; CAEDS system modeler for the RT, \$8,230; CAEDS graphics finite element modeler for the RT, \$8,940.

IBM Corporation, 900 King Street, Rye Brook, NY 10573; Contact the local IBM dealer, 800/426-2468

CIRCLE 301 ON READER SERVICE CARD

HARDWARE

The **82786 graphics coprocessor** from **Intel Corporation** can manipulate windows in hardware 100 times faster than traditional software approaches. This high-performance, single IC supports two independent, on-chip processors for manipulating graphics and text while executing multiple windows. The 82786 operates independently of the host CPU; it is designed to work with all Intel microprocessors and requires minimal support circuitry for most system configurations. It uses the same advanced CHMOS-III process as the 80386 microprocessor. The 82786 coprocessor has 130,000 transistors, combines high performance and low power consumption, operates at less than 1 watt, and supports as many as 32 dynamic RAMs in its dedicated graphics memory. Less than \$100 in quantities of 1,000.

Intel Corporation, Literature Department, W-300, 3065 Bowers Avenue, Santa Clara, CA 95051; 800/548-4725

CIRCLE 306 ON READER SERVICE CARD

Intel also has announced a combination expanded memory and multifunction board for the PC/AT. The **Above Board PS/AT** has a serial port, a parallel port, several standard software utilities, and up to 1.5MB of memory. With the Above Board piggyback option, memory can be boosted to 3.5MB. Above Board PS/AT memory can be divided, and used to fill in conventional memory (up to 640KB), as expanded

memory consistent with the Lotus/Intel/Microsoft expanded memory specification, or as extended memory. 128KB version, \$595; 512KB version, \$695; Above Board/AT piggyback memory, \$295 for a 128KB configuration.


A new 8-MHz version of the 80287 math coprocessor also has been introduced. The **80287-8** can boost numeric processing speeds of many Intel 80286-based accelerator boards. \$410.
Intel Corporation, 5200 N.E. Elam Young Parkway, Hillsboro, OR 97124-6497; 800/538-3373; in Canada, 800/235-0444

CIRCLE 307 ON READER SERVICE CARD

The first of the new **ShareData** family of products designed to simplify data sharing has been announced by **Extended Systems**. These products allow up to four PCs to share concurrently as much data as they wish on one external 20MB hard-disk drive. Data security includes volume access protection and user access control. User log-on identification with or without password protection is available. An internal self-test diagnostic is activated each time ShareData is powered on and byte-by-byte error checking is provided for the interfaces between the computer and ShareData. The product can use RS-232 or RS-422 communication. The hard disk included with the ShareData package has a formatted capacity of 21MB with an average access time of 65 milliseconds. Nonrecoverable read errors are 1 per 10^{12} bits read. Other products offer sharing capability for printers (ShareSpool) and plotters (SharePlot). ShareData (ESI-3772) package, \$1,995; high-performance ShareData (ESI-37729) package with four RS-422 interface cards, \$2,395; RS-422 interface cards, \$150 each, \$545 for a bundle of four.

Extended Systems, P.O. Box 4937, 6062 Morris Hill Lane, Boise, ID 83711; 208/322-7163

CIRCLE 313 ON READER SERVICE CARD



PCI ControlLOGraph from Burr-Brown



By Omnitel, Inc.

Sigma Designs, Inc. has announced **FasTrak**, a portable, stand-alone streaming tape backup unit that allows both image and file-by-file backup and restore of data stored on PC hard disks.

Two models are available. The **FTK-0020** has a built-in, half-height 5¼-inch tape drive that accepts one-eighth-inch cassettes with a storage capacity of 20MB or 27MB. The **FTK-0060** includes a half-height 5¼-inch tape drive, but it will use one-fourth-inch tape cartridges capable of storing 60MB of data. Both packages include Sigma's QIC 36 tape controller board, tape utility software, one tape cassette, and shielded cable. FTK-0020, \$995; FTK-0060, \$1,395.

Sigma Designs, Inc., 2023 O'Toole Avenue, San Jose, CA 95131; 408/435-1480

CIRCLE 302 ON READER SERVICE CARD

The **DNA Gateway** from **Network Development Corporation** is a 3270 communications link emulating a remote 3274 communications cluster controller. Standard DNA Gateway features include support for 32 concurrent SNA sessions, realtime multitasking execution, IBM 3274 model 51C/61C remote communications controller emulation, IBM 3178/3278 model 2 and 3178/3279-base two-and four-color support display emulation, IBM 3287 printer emulation, and the SNA Soberly Protocol Analyzer. 8-session configuration, \$3,995; 16-session, \$4,995; 32-session, \$5,995.

Network Development Corporation, 81 Great Valley Parkway, Suite 700, Malvern, PA 19355; 215/296-7420

CIRCLE 304 ON READER SERVICE CARD

Omnipak is a single-board multifunction card integrated with a 1200/300-bps modem for use with the PC, PC/XT, PC/AT, and compatibles. Introduced by **Omnitel, Inc.**, the board features a Hayes-compatible modem that can be upgraded to 2400 bps, with 384KB of memory, both parallel and serial ports, a game port, and a clock/calendar with

battery backup. Omnipak comes bundled with communications and utilities software. The modem included offers COM 1 through 4 addressability as well as call-progress reporting. \$499.

Omnitel, Inc., 5415 Randall Place, Fremont, CA 94538; 415/490-2202

CIRCLE 310 ON READER SERVICE CARD

The **CMS** family of SCSI-compatible mass storage peripherals for the PC is available in internal or external configurations. Each subsystem consists of 20MB combination hard-disk and tape-backup peripherals, embedded VLSI controllers, and an SCSI host adapter. The external configuration, called the **SCSI Power Twin 20:20**, is packaged in a cabinet that fits alongside the CPU. A half-size PC host adapter card that



SCSI-compatible mass storage peripheral family from CMS

allows the PC to communicate with the SCSI peripheral bus is included; it can support both the disk and the tape drives in the Power Twin 20:20, as well as up to five other SCSI peripheral devices. The internal configuration includes a one-fourth-inch tape backup unit that can replace an internal floppy-disk drive and CMS's 20MB SCSI Drive Plus expansion card, which includes the half-card host and a 3½-inch disk drive. External configuration, \$1,950; internal, \$1,660; internal tape drive and host adapter card, \$910; Drive Plus, \$990.

CMS, 401-B W. Dyer Road, Santa Ana, CA 92707; 714/549-9111

CIRCLE 308 ON READER SERVICE CARD

The **PCI ControlLOGraph System** from **Burr-Brown** is a fully integrated system of hardware and software for data logging, graphics display, alarm annunciation, and digital control. Data input choices include 21 analog signals, 24 digital bits, and 3 frequency/event counting channels. Four ranges of input voltage as well as J, K, or T thermocouples can be selected via menu. Analog, digital, and frequency/event data all are acquired on each data acquisition scan performed by the ControlLOGraph. The data can be displayed in realtime, as they are being stored on disk. The system's software can restart itself in the event of a power failure; after power is restored, ControlLOGraph automatically reboots the computer. Hardware/software system, \$2,750; software, \$795.

Burr-Brown, International Airport Industrial Park, 6730 S. Tucson Blvd., P.O. Box 11400, Tucson, AZ 85734; 602/746-1111


CIRCLE 309 ON READER SERVICE CARD

The **QMS-PS 800** from **Quality Micro Systems** combines the technology of a laser printer with that of the PostScript typesetting language from Adobe Systems, Inc. This printer (which prints eight pages per minute) enables the user to include text, line art, halftones, textures, grayscale, patterns, and images in any size with a resolution of 90,000 dots per square inch. \$5,895.

Quality Micro Systems, P.O. Box 81250, Mobile, AL 36689; 205/633-4300

CIRCLE 318 ON READER SERVICE CARD

Through a joint OEM agreement, **Computer Identics Corporation** will handle the national distribution of **Micro Peripherals, Inc.**'s two bar code printers. The **Printstar 200** and the **Printstar 345** (the numbers refer to the length of the printable line in millimeters) produce optically scannable output in the form of bar codes, as well as machine-readable OCR-A. The two



Tseng Labs' EVA (Enhanced Video Adapter)



T4 Color Graphics Controller by Microfield Graphics

printers are enhanced versions of the MPI BarMate 9 and BarMate 15. All BarMate printers have Code 39, Code 128, and Rationalized Codabar symbologies suitable for LOGMARS, AIAG, and HIBC as standard. The programs for the bar code and OCR-A symbologies are resident in the PROMs of the printers and produce the symbologies independent of special software. In IBM-compatible mode, these printers handle all printing requirements of a PC. Friction and tractor feed allow for many types of paper, including labels and continuous form. Printstar 200, AI-66501-1, \$1,395; Printstar 345, AI-66502-1, \$1,995; AI-66502-2 (with RS-232 interface), \$2,105.

Computer Identics Corporation, 5 Shawmut Road, Canton, MA 02021; 617/821-0830

CIRCLE 311 ON READER SERVICE CARD
Micro Peripherals, Inc., 4415 S. 500 West, Salt Lake City, UT 84123; 801/263-6000

CIRCLE 312 ON READER SERVICE CARD

ITT Information Systems has announced the **ITT XTRA XL**, a high-performance, 80286-based microcomputer that runs DOS and XENIX. The system features 8-MHz frequency, zero-wait-state memory, dynamic disk I/O caching, an average hard disk access time of 28 milliseconds, and an optional 80287 coprocessor. An 8-MHz 80186-based communications coprocessor offers speed in multiuser configurations. The ITT XTRA XL can be used as a LAN server (models I and II) or as a multiuser system (models III and IV). All models include a battery-backed realtime clock, an audio speaker, two serial ports and one parallel port on the motherboard, six PC/AT-compatible expansion slots, and three PC/XT-compatible expansion slots. Prices begin at \$5,299.

ITT Information Systems, 2350 Qume Drive, San Jose, CA 95131; 408/945-8950

CIRCLE 305 ON READER SERVICE CARD

From **Tseng Laboratories, Inc.** comes **EVA**, an IBM EGA-compatible enhanced video adapter that is equipped with a parallel port. It uses the proprietary ET2000 VLSI Graphics Chip Set designed by Tseng Labs and is intended as a superset of the EGA. Features of EVA include a hardware zoom, a viewport/zoom window, a turbo graphics engine, a 132-column screen, and light pen pixel manipulation. EVA drives monochrome, color, and enhanced color displays and offers 256KB of display memory, 16 user-selectable colors from a color palette of 64, a split screen, smooth scrolling and pixel panning, a soft downloadable font capability, and an 80-by-25/43 text display. \$525.

Optional hardware compatibility for the Hercules, CGA, and monochrome adapters (beyond the BIOS level compatibility standard with EVA) is achieved with the optional Compatibility Module II daughterboard. \$50.

Tseng Laboratories, Inc., 205 Pheasant Run, Newtown, PA 18940; 215/968-0502

CIRCLE 320 ON READER SERVICE CARD

Microfield Graphics, Inc. has announced the **T4 Color Graphics Controller** for the RT. The T4 is a 1,024-by-800, four-plane color controller that uses a VLSI-based bit-slice processor to provide high-speed, high-resolution graphics. It is supported by an ANSI CGI interface permitting its use on either the RT's RISC processor or its optional DOS coprocessor. The CGI interface permits applications to access the line drawing, polygon and text manipulations, and window-management microcode of the T4 directly from C subroutines, while incurring minimal overhead on the RISC or DOS processors. \$3,200; RT support software, \$150.

Microfield Graphics, Inc., 8285 S.W. Nimbus Avenue, Suite 161, Beaverton, OR 97005; 503/626-9393

CIRCLE 317 ON READER SERVICE CARD

The **GhostWriter** is a new multiformat software copier product from **Magnetic Designs** that allows automatic duplication of all common brands (formats) of diskette software. It includes a plug-in card for the IBM PC and the SmartCopy software package, which allows even first-time users to duplicate and validate software easily. Key features include automatic analysis and duplication of diskettes, the ability to duplicate as many as 80 IBM PC or 163 Commodore diskettes per hour with an optional diskette autoloader (eliminates reloading), the ability to store multiple software masters on the system hard disk, support of direct connection to floppy-disk drives, and variable bit-cell timing with precompensation. Optional extensive analysis tools are available. \$1,995. *Magnetic Designs, 643 Bair Island Road, Redwood City, CA 94063; 415/363-1141*

CIRCLE 315 ON READER SERVICE CARD

A high-speed, high-capacity optical disk system for users of IBM PC-based CAD/CAM systems has been introduced by **N/Hance Systems**. The **N/Hance 525** system provides 230MB of formatted storage and includes the optical disk drive, a 5¼-inch disk, an IBM PC short-board controller, and device driver software. The N/Hance 525 is a WORM (write-once-read-many-times) system that allows users to write data to the disk, store them in a secure, unalterable form, and read them quickly when needed. The system has a transfer rate of 2.5 Mbps, a track-to-track access time of less than 1 millisecond, and an average access time comparable to that of a Winchester disk. \$3,495. Also available is a text database management system that allows users to search the database by keyword or phrase, priced at \$1,000. *N/Hance Systems, 908R Providence Highway, Dedham, MA 02026; 617/461-1970*

CIRCLE 316 ON READER SERVICE CARD

READ ONLY



A review of the IBM Personal Computer Family. Vol. 3, No. 1

Welcome To Read Only.

Here's great news for IBM PC users. IBM has expanded its already expansive PC product line to bring even more power and flexibility to your desktop.

In this issue alone you'll be reading about new enhancements to the IBM PC/XT, the IBM Personal Computer AT®, the IBM PC Keyboard, the IBM Proprinter, the Mainframe Communications Assistant, and more.

And, as if that weren't enough, IBM has also found time to expand your computing horizons even more by introducing exciting new PC products. This issue of *Read Only* will tell you about the new IBM PC

Convertible, new 3.5" diskettes, the new IBM PC 3.5" External Diskette Drive, and two new accounting software packages.



HARDWARE NEWS

The Right Touch.


To make it easier than ever to work at an IBM PC/XT or Personal Computer AT, IBM has introduced the new IBM Enhanced Personal Computer Keyboard (shown below).

IBM redesigned its classic keyboard to better meet the needs of PC users, office system users, as well as users who communicate with larger computers.

To accomplish this, IBM included separate cursor and screen control keys, making it easier for users to dedicate the numeric keypad to numeric input when working with number-intense applications. Plus, the keypad can still be used for cursor and screen control when not in the num/lock mode.

IBM also increased the number of function keys from ten to twelve, arranged across the top of the keyboard. This gives users two additional keys for increased automatic operation.

All to enhance the productivity of those who work with words, numbers or a host of other applications.



The IBM Enhanced PC Keyboard to help you be more productive, faster.

Small Wonder.

Proof positive that good things come in small packages is the new 3.5-inch diskette.

And that's big news for anyone who uses an appropriately configured IBM PC, PC/XT, Personal Computer AT and the new IBM PC Convertible.

Durable 3.5" diskettes, allow you to carry over 350 standard typed pages (720KB) in your shirt pocket. That's twice as much information as on a 5.25" (360KB) diskette, in a much more rugged, portable form.




The new 3.5" diskette stores up to twice as much (720 KB) as a 5.25" (360KB) diskette.

Now IBM PC users have the option of using programs and data in either size, and the flexibility to work with other members of the IBM PC family using 3.5" diskettes.

Translation Services.

The new IBM Personal Computer 3.5" External Diskette Drive provides a vital bridge between your IBM PC and 3.5" technology. This compact unit makes it easy for you to share information between computers using 3.5" diskettes and 5.25" diskettes.



The IBM PC 3.5" External Diskette Drive provides a cost-effective bridge between 3.5" and 5.25" technology.



The new IBM PC Convertible is a

The IBM Personal Computer 3.5" External Diskette Drive comes in two models, one for the IBM Personal Computer AT and one for the IBM PC, PC/XT or IBM PC Convertible.

Information and applications can be shared* between 3.5" diskette drive machines and an IBM PC running DOS 3.2 with the IBM Personal Computer 3.5" External Diskette Drive attached.

Transferring files and programs between 3.5" and 5.25" diskettes is as easy as making a backup copy of a diskette. So, you can very quickly have a "database to go" for your IBM PC Convertible. Or, a week's worth of sales call information in a ready-to-use form for your secretary when you return.

Print Evolution.

The new IBM Proprinter XL is especially designed to make life easier for those who work with accounting applications. Its wide carriage design and switchable printing speeds of up to 200cps are perfectly suited for spreadsheet applications.

The IBM Proprinter XL also features an easy-to-use front operator panel that lets you choose from the XL's extensive menu of features, even if you have little or no programming skills.

Plus, the new Proprinter XL offers a long list of standard, labor-saving features to make many printing jobs easier: easy printing of single sheets and envelopes without removing your continuous forms paper, power-assisted paper

loading, all-points-addressable graphics capabilities, near-letter-quality printing (40cps), and emphasized text printing (100cps). Plus, you can set the printer in double high, double wide or emphasized print through the operator panel or through software.

Power To Go.

The new IBM PC Convertible can play two powerful roles in any businessperson's life.

In the office, with an optional IBM PC monochrome or color display and adapter, the PC Convertible fills the bill as a space-saving desktop PC.

But when you're ready to hit the road or runway, just attach the high quality, 80-column x 25-line detachable LCD display, and the PC Convertible is ready to travel, too.

Weighing in at a scant 12 pounds, the IBM PC Convertible delivers full-size PC performance in a portable computer with heavyweight features including:

A full-function keyboard with full-size keys and the same center-to-center key spacing as a standard IBM PC keyboard.

A fast, very efficient 80C88 microprocessor with up to 10 hours of non-stop computing power between battery recharges (with average use).

Up to 512KB of user storage (through 128KB expansion cards from a standard 256KB).

Dual 3.5" diskette drives supporting 720KB capacity 3.5" diskettes.

Additional IBM PC Convertible features help ensure that work done on the road doesn't get lost in transit.



...ver PC that works wherever you do.



These optional features include:

An internal modem feature to let you communicate with other computers simply by plugging the PC Convertible into any standard modular phone outlet.

The IBM PC Convertible Printer for system battery powered, near-letter-quality printing anywhere.

Plus, the IBM PC Convertible can come with a helpful set of programs to get you up and running on the road to enhanced productivity. Fast.

Planned For Growth.

It's a classic case of a very good thing that just keeps getting better.

IBM has now introduced the enhanced PC/XT product family: increased flexibility in storage, memory and option configuration for maximum productivity today, and



The new IBM PC/XT—enhanced power and flexibility for today. And tomorrow.

plenty of room to expand as your business does.

The XT is now available with a 20-megabyte hard file that can store up to 10,000 pages of information. There's also an easy, low cost way to increase memory to a full 640KB on the system board without tying up valuable expansion slots. And the XT now has 3.5" diskette capability, utilizing the new IBM Personal Computer 3.5" External Diskette Drive.

Plus, full IBM PC compatibility means that no matter which XT model you choose, you can benefit from the extensive IBM Personal Computer software library.

The new IBM PC/XTs, because one size should not have to fit all.

Power Play.

If you thought you'd seen all the IBM Personal Computer AT has to offer, think again. Twice.

IBM has increased processor speed in two new models of the IBM Personal Computer AT by an impressive 33% (from 6mhz to 8mhz). So, they're sure to become your fast friends if you work with large spreadsheets and volumes of data.

The new models offer a standard 30MB hard file and the option to add an additional 20MB or 30MB hard file. That's a grand total of 60MB, or approximately 30,000 pages of words and numbers.

These two newcomers are born communicators: Sharing files with other PCs from a variety of popular software programs. Working as a server for data storage and file processing in an IBM PC LAN running

the IBM PC Local Area Network program. Utilizing IBM TopView™ and one of the IBM PC 3270 Emulation Programs to access mainframe information and to execute PC DOS and mainframe applications concurrently.

And the best news of all is that you can get all this increased power without an increased price.



20MB

30MB

Now the IBM Personal Computer AT offers a choice of hard files to meet your storage needs.




WHAT'S THE PROGRAM

Meet Your New Assistant.

Keeping the books for a small business is a very big job. So, IBM thought you could use a friendly, versatile, highly skilled assistant. The new IBM Accounting Assistant Series.

This complete series of automated bookkeeping application programs for small to medium size businesses can help cut any job down to size. And, its modular design means that you can start out with just the programs you need today, then expand your series as your business grows.

The IBM Accounting Assistant Series includes six individual editions: General Accounting, Accounts Payable, Accounts Receivable and Billing, Payroll, Inventory



The IBM Accounting Assistant Series. Big help for small to medium size businesses.

Control and Purchasing, and Job Cost bidding software.

Plus, thanks to the IBM Accounting Assistant Series' user-friendly attributes and easy-to-follow instructions, you can start profiting from your system from day one.

High-Powered Advice.

Perhaps your business has progressed past the need for basic accounting software. Then you should consider getting powerful, sophisticated help: the IBM Business Advisor.

IBM Business Advisor PC accounting software takes integrated software to a new level of sophistication and ease-of-use.

Business Advisor's seamless architecture allows functions from each of its modules to play together. Passage back and forth among the General Accounting, Accounts Payable, Accounts Receivable, Payroll, Inventory Control, Order Entry and other applications is intuitive. Menus guide you easily from one task to another.

And when you make a change anywhere, consider it made everywhere it applies. Automatically, through Business Advisor's real-time posting feature.

This Business Advisor speaks your language, too. It uses business language instead of accounting language, and has over 80 easily customized financial report formats built in. And you don't have to keep this all to yourself, because in an IBM LAN

different people at different PCs can work on the same file at the same time.

And you always go further when everyone is working together.




"NEWS" BRIEFS

The 3270 Emulation Programs, Entry Level, Version 2 and Version 3, give you an easy and inexpensive way to attach your IBM PC to your host computer.

Working at your IBM PC, stand-alone or in an IBM LAN, you can now utilize the local power and user-friendly attributes of your PC for DOS applications, plus have access to the vast memory, number-crunching capacities and other productivity-enhancing capabilities of your host computer.

The Entry Level product offers up to 40% faster file transfer between your



IBM PC 3270 Emulation Products can put your IBM PC or IBM LAN in touch with the big time.

PC and host computer. A "Hot Key" for easy switching between host and PC applications. Keyboard remapping so you can always work in a familiar keyboard format. And much more.

Versions 2 and 3 can provide an economical gateway which lets you

share the wealth of host knowledge with the members of your IBM PC Network or Token-Ring Network.

Versions 2 and 3 support the new PC DOS 3.2, 3.5" media, the IBM Local Area Network program 1.10, a host of printers and the TopView 1.1 interface, for multitasking and windowing capabilities.

All of which adds up to added productivity for you and everyone on your IBM Local Area Network or token ring.

To find out more about the entire family of 3270 PC Emulation Programs, as well as a wide range of other IBM connectivity hardware and software, watch for the next *Read Only*.

Mainframe Communications Assistant enhancements include 3.5" media support and increased IBM PC family communications capabilities.

The IBM PC Voice Communications Option speaks for itself. This multifunction adapter card can allow your IBM PC to recognize and respond to voice commands, speak text that appears on the screen, initiate and receive/record/playback phone calls, provide remote, tone push button phone access to your PC (and host), and transmit voice and data simultaneously.




For more information on any of the Personal Computer products discussed in this issue of *Read Only*, see your Authorized IBM Personal Computer Dealer. Or, call 800-447-4700. In Alaska call 800-447-0890.


IBM and Personal Computer AT are registered trademarks of International Business Machines Corporation. PC/XT and TopView are trademarks of International Business Machines Corporation.

*Before copying any software product, be sure to read, understand and comply with the specific software license agreement and installation instructions for that product.

© 1986 International Business Machines Corporation. Little Tramp character licensed by Bubbles Inc., S.A.



Attachmate's 3270 Host Graphics program



JetReader Plus by Datacopy Corporation

A high-performance scanning system that provides OCR (optical character recognition) and image processing capabilities has been announced by **Datacopy Corporation**. The **JetReader** is a compact, lightweight image scanner with high resolution and an automatic paper feed. It comes with an interface to the IBM family of PCs as well as Datacopy's OCR and OCR Plus software and Word Image Processing System software. JetReader accepts a stack of as many as 10 sheets of legal-size paper for automatic feeding, and transfers them to an output tray in proper order after scanning. The image scanning is based on charge-coupled-device technology and provides selectable resolutions of 300 or 200 dots per inch (dpi). Scan times are approximately 43 seconds at 300 dpi and 28 seconds at 200 dpi. For OCR, the conversion time depends on the quality of both the original document and the computer in use; full page conversions typically take less than a minute for scanning and translation. Also available from Datacopy is another scanner, the **JetReader Plus**, which includes OCR Plus software for user training to recognize unknown type styles. JetReader, \$2,950; JetReader Plus \$3,250. **Datacopy Corporation**, 1215 Terra Bella Avenue, Mountain View, CA 94043-1834; 415/965-7900

CIRCLE 314 ON READER SERVICE CARD

The **NMS R8000A** is a controller from **National Memory Systems** designed for high-performance, high-capacity disk/tape memory systems. This controller offers support for two SMD drives along with up to 4 SCSI interface devices on a single board for PC/ATs and RTs supporting UNIX and DOS applications. The board features switch-selectable DMA channels and port address to make installation in networks, varied CPUs, or large systems environments conflict-free. The R8000A is compatible with all major networks; it can simulta-

neously support the NMS PC.25, a one-fourth-inch cartridge tape system, and the NMS 007 (a 1,000MB laser optical cartridge disk that uses 12-inch media). \$895 in OEM quantities.

National Memory Systems, 355 Earhart Way, Livermore, CA 94550; 415/443-1669

CIRCLE 303 ON READER SERVICE CARD

SOFTWARE

The **3270 Host Graphics Program** from **Attachmate Corporation** is a software package that lets users access host-generated color graphics. The product uses Attachmate's IBM IRMA-compatible 3-N-1 Coax Adapter and 3270-PC emulation program to manage four concurrent host sessions. Any combination of 3270 text or graphics sessions as well as a PC application can be active simultaneously. Attachmate uses the PC's all-points-addressable graphics and a unique algorithm to match host graphics screens to the resolution of the CGA or EGA on the PC. Thus, it can display full 3270 graphics screens without special adapters. Host graphics screens can be saved to disk, then edited locally using programs such as Z-Soft's PC Paintbrush. Output from the 3270 Host Graphics Program also can be routed directly to a PC printer, including IBM's 3852 Color Jetprinter. \$595; 3-N-1 Coax Adapter, \$1,195.

Attachmate Corporation, 3241 118th SE, Bellevue, WA 98005; 206/644-4010

CIRCLE 324 ON READER SERVICE CARD


Release 3.0 of **BABY/36** is now available from **California Software Products, Inc.** BABY/36 lets a PC user develop, edit, compile, and execute new and existing RPG II programs; release 3.0 includes enhancements in step with version 3.0 of IBM's System Support Procedures for the System/36. REDE, READP, and *LIKEDEFN operation codes have been

added. Noncontiguous index keys are now supported in the RPG compiler and BLDINDEX operation code. Maximum key length is increased to 63 bytes. MOVEA has been enhanced to allow numeric fields, and EVALUATE has been enhanced to support multiplication and division. Other features have been added for creating and maintaining libraries, printing data files, and editing and compiling programs and screens in an on-line environment. Prices range from \$700 for the runtime version to \$3,500 for a software development system.

California Software Products, Inc., 525 N. Cabrillo Park Drive, Santa Ana, CA 92701; 714/973-0440

CIRCLE 335 ON READER SERVICE CARD

A full-function statistical package for the PC, PC/XT, and PC/AT has been released by **SAS Institute Inc.** The **SAS/STAT** software performs both simple and complex analyses. The package includes interactive procedures for regression analysis, analysis of variance, common factor and component analyses, discriminant analyses, and scoring. To use SAS/




SAS/STAT screen

STAT, sites first need PC-based SAS software, which includes tools for data management, descriptive statistical analysis, and report writing. First-year license for corporate customers with up to 50 workstations, \$2,000.

SAS Institute Inc., P. O. Box 8000, SAS Circle, Cary, NC 27511-8000; 919/467-8000

CIRCLE 325 ON READER SERVICE CARD



Ada compiler for the PC/AT by Alslys

From **Visionics Corporation** comes **EE Designer**, a CAE/CAD integrated software package for electronic circuit design, layout, and fabrication applications. EE Designer consists of three integrated programs for schematic design, circuit simulation, and printed circuit board layout. It provides for automatic packaging of the engineer's design schematic into functional blocks that can be added to the system library of components consisting of standard TTL parts. Features of the package's schematic design module include auto-placement and back-annotation. The circuit simulation package includes a library of 150 common TTL and CMOS devices, including gates, flip-flops, counters, buffers, decoders, and RAMs. The user can expand the library by creating and adding unique shapes and components. The printed circuit board layout module of the package provides all functions necessary to design a printed circuit board as well as to produce artwork masters for fabrication, pen plotter, and photo plotter outputs. \$975.

Visionics Corporation, 1284 Geneva Drive, Sunnyvale, CA 94089; 408/745-1551

CIRCLE 323 ON READER SERVICE CARD

Smalltalk-AT is the complete Smalltalk-80 version 2 for the PC/AT. Smalltalk-80 is an object-oriented programming environment previously available only on large, dedicated machines. Released by **Softsmarts, Inc.**, Smalltalk-AT includes the Xerox Smalltalk-80 source code, the Xerox image, and Softsmarts' ST-80 virtual machine, which is a true multiprocessing system. Smalltalk-AT features bit-mapped graphics, a window-based interface, all of the Smalltalk-80 version 2 classes, system browsers, a compiler, a profiler, and an interactive debugger that supports realtime debugging. \$995.

Softsmarts, Inc., 4 Skyline Drive, Woodside, CA 94062; 415/327-8100

CIRCLE 339 ON READER SERVICE CARD

Alslys, Inc. has announced that its **Ada compiler** for the PC/AT has been validated through the Ada Validation Facility of the Ada Joint Program Office of the United States Department of Defense. A key feature of the Alslys Ada compiler is its use of protected (virtual) mode to overcome the 640KB limitation that is imposed by DOS. This permits access to extended memory up to 16MB and the accommodation of serious Ada programs on a PC. The compiler is bundled with a 4MB memory board. \$2,995.

Alslys, Inc., 1432 Main Street, Waltham, MA 02154; 617/890-0030

CIRCLE 337 ON READER SERVICE CARD

Tominy, Inc. has announced **MACH 1 Professional Application Developer (PAD)**, a single-user system generation facility that provides comprehensive applications development facilities for software practitioners. Product components include a relational/network/hierarchical DBMS, a fourth-generation programming language called LOGIC, a powerful applications program generator, an automatic screen editor, an efficient report generator, comprehensive system utilities, and flexible query. \$199.95.

Tominy, Inc., 4221 Malsbary Road, Cincinnati, OH 45242; 800/543-8628; in Ohio, 800/445-1737

CIRCLE 338 ON READER SERVICE CARD

Three new products have been added to **LOGITECH, Inc.**'s family of Modula-2/86 development tools. A Turbo Pascal-to-Modula-2 translator called the **Turbo Translator** reads an existing Turbo Pascal program and generates a Modula-2 translation. It comes bundled with several new Modula-2 library modules, including screen-handling, graphics, and file-handling modules, which have been adapted to correspond directly to Turbo Pascal functions. \$49.95.

The **Make Utility** runs through a program after changes have been made to the source file and selects modules

affected by the changes. The utility generates a batch file containing a list of the compilation required to correct the system, providing the user with a map of all the files it has analyzed, as well as a list of which files need to be recompiled and why. It identifies new dependencies and gives a cross reference of exported/imported identifiers. \$29.

A third new tool is the **Windowing Package**, which enables users to build windowing into their Modula-2 code. The package features virtual screens, color support, and overlapping windows with a variety of borders. It uses only 15KB of code. \$49.

LOGITECH, Inc., 805 Veterans Blvd., Redwood City, CA 94063; 415/365-9852



CIRCLE 332 ON READER SERVICE CARD

TPORT-05, a systems-level program that enables the porting of mainframe- and minicomputer-based graphics software to the PC has been announced by **Grafpoint**. The new package resides under DOS as a device driver, allowing PC applications programs to use Tektronix 4105 graphics commands. The package processes Tektronix-like commands and escape sequences, thereby eliminating the need to rewrite software to conform to the virtual device interface standard for the PC. \$495.

Also from Grafpoint comes **TNET-05**, a high-performance Tektronix 4105 emulation package running on PCs configured in a LAN. TNET-05, a device driver that processes Tektronix 4105 commands under DOS, gives network users the display and processing capabilities of a Tektronix graphics terminal on a PC. The package includes software that connects with communications software packages from Bridge Communications (EtherTerm) and Network Research Corporation (Fusion). \$495.

Grafpoint, 4340 Stevens Creek Blvd., San Jose, CA 95129-1102; 408/249-7951

CIRCLE 328 ON READER SERVICE CARD



TALL TREE SYSTEMS. A Technological Innovator. Always a Step Ahead!

For true industry leadership, look no further than Tall Tree Systems.

We have a history of being first.

We were the first to introduce bankswitching. The first with two megabyte memory boards. The first with I/O modularity in a single slot. The first with 8 MHz speed capabilities. The only maker of single

command EMS boards.

The first with a laser printer solution — JLASER — that allows you to do full-page graphics and multiple type fonts on any Canon® or Ricoh® laser engine.

Now, we're first again with memory expansion for the IBM® RT.

Innovation is our tradition. Our trademark is superior technology at the lowest possible price.




TALL TREE SYSTEMS

1120 San Antonio Road • Palo Alto, CA 94303 • (415) 964-1980

CIRCLE NO. 197 ON READER SERVICE CARD

©1986 by Tall Tree Systems. All rights reserved. IBM, RT are registered trademarks of International Business Machines Corp. Canon and Ricoh are registered trademarks of Canon Corp. and Ricoh Corp., respectively.



PASCMAN screen



By Wiley Professional Software

NETWORK-OS is a 16-bit, NetBIOS-compatible network operating system that supports DOS 3.1 or later, all major network topologies, and Novell file and record locking. Introduced by **CBIS, Inc.**, **NETWORK-OS** is menu driven and employs a unique visual network shell (VNS) user interface. Commands are presented on hierarchical, pull-down screens. LAN resources are addressed by user-defined object names and mapped by mouse or keyboard. Four users per PC/XT or 16 per PC/AT are supported. When more workstations are required, multiple file servers may be employed.

In addition, **CBIS** announced a new open-bus twisted-pair wire interface able to transmit data at 2.5Mbps. This is three times faster than the existing RS-422 interface (which runs at 800Kbps). **NETWORK-OS**, \$995; interface boards, RS-422, \$295; twisted-pair, \$395. **CBIS, Inc.**, 2323 Chesire Bridge Road, Atlanta, GA 30324; 404/634-3079

CIRCLE 330 ON READER SERVICE CARD

An advanced software tool called **CUBIT** has been announced by **SoftLogic Solutions, Inc.** This utility enables users to reduce the number of bytes required to store a file. **CUBIT**, comprised of four programs, is designed to compress and decompress data files. **CUBIT**'s internal dictionary performs a look-up operation on each word in a test file to determine if the word is included in the dictionary. If it is, the word is reduced to one or two bytes of encoded data. For words that are not in the dictionary, **CUBIT** uses two additional techniques. One assigns new, shorter codes to the words, the other analyzes the frequency of character strings in the data. All programming is transparent and automatic. **CUBIT** also compresses binary files by adapting its algorithm. \$49.95. **SoftLogic Solutions, Inc.**, 530 Chestnut Street, Manchester, NH 03101; 603/627-9900

CIRCLE 329 ON READER SERVICE CARD

A programming tool for users of the IBM data acquisition and control adapter has been introduced by **Wiley Professional Software**. Called **LabSoft**, this program, which was originally developed by Cyborg Corporation for use with its ISAAC series of computer-based data acquisition and control systems, can be used to acquire, manipulate, and analyze real-world data. **LabSoft** is available in three versions—FORTRAN, BASIC, and C—to provide complete language compatibility; it features more than 40 programming tools/commands. FORTRAN or BASIC version, \$350; C supplement, \$75.

Wiley Professional Software, 605 Third Avenue, New York, NY 10158; 212/850-6788

CIRCLE 342 ON READER SERVICE CARD

Financial Software Systems, Inc. has released **PASCMAN** (Pascal Screen Management System) for use with Borland International's Turbo Pascal. With **PASCMAN**, a programmer can design colorful computer screen displays quickly. Using **PASCMAN**'s full-screen editor, the user can set up screens identifying input and output fields. The editor handles all screen design, including colors, graphic characters, and an easy box drawing facility. Help screens and pop-up windows for every variable field on a screen can be created. \$29.95. **Financial Software Systems, Inc.**, 3125 Woodlark, Fort Worth, TX 76123; 817/294-3651

CIRCLE 340 ON READER SERVICE CARD

A software library of initialization and driver routines that allows applications programs written in BASIC, C, or assembly language to link easily to STD bus I/O cards is now available from **Pro-Log Corporation**. Designated **STD LIB 1.1**, the library supports Pro-Log's STD DOS system, which is MS-DOS 3.1 merged with the industrial quality hardware of Pro-Log's STD bus. **STD LIB 1.1**,

based on the Microsoft Library Manager and Linker, consists of modules written in assembly language for high-speed execution and efficient use of memory. Release 1.1 supports the Pro-Log 7312-1/7314A-1 dual and quad RS-232 communications controller card, the Pro-Log 7507/7508 general purpose I/O card, the Pro-Log 7303 keyboard display card, and the Analog Devices RTI-1225 analog I/O card. The library specifications allow the user to add modules for I/O cards not currently supported. \$295.

Pro-Log Corporation, 2560 Garden Road, Monterey, CA 93940; 408/372-4593


CIRCLE 333 ON READER SERVICE CARD

A language-independent, PC-based screen management system and software development environment has been introduced by **Master Computer Systems, Inc.** Aimed at professional developers of interactive transaction processing systems for DOS environments, **FORMIX version 2** automates 45 additional screen functions in a panel-oriented environment and provides full keyboard and system-control configuration. It features a memory-resident executive to manage all screen processing on behalf of the application program and a menu-driven environment on PC workstations to reduce development time. The objectives of **FORMIX** are to reduce program development cost, to optimize application screen performance, and to provide a flexible end-user interface. The **FORMIX Executive** (which also runs under **TopView**) executes 57 screen management functions. \$695. **Master Computer Systems, Inc.**, 9531 W. 78th Street, Eden Prairie, MN 55344; 612/944-5220

CIRCLE 341 ON READER SERVICE CARD



The material that appears in Tech Releases is based on vendor-supplied information. These products have not been reviewed by the PC Tech Journal editorial staff.



Hercules compatible graphics:
720x348.

Plantronics compatible graphics:
640x200x4 colors.

Introducing The Paradise Hi-Res Graphics Card.TM Two Upgrades For The Price Of One.

Now you can have much higher resolution than your current video card gives you. Without buying new software. Or an expensive monitor.

All you need is the new Paradise Hi-Res Graphics Card.

It gives you the highest resolution possible on a standard monitor. With monochrome displays, you get Hercules compatible 720x348 graphics. With RGB and composite displays, you get Plantronics compatible graphics: 16 colors in 320x200, and 4 colors in 640x200. That's two upgrades for the price of one.

And no matter which monitor

you choose, the Paradise Hi-Res Graphics Card gives you full compatibility with standard video modes.

Better yet, you can use your existing software to its best advantage. Because Hercules and Plantronics graphics are widely supported by packages like Lotus 1-2-3, Symphony, Framework, and lots more.

And Paradise gives you all this, plus a parallel port. On one short card.


If you'd like to know more, we'll send you full information. Including a free Hi-Res software compatibility guide. Just call (800) 527-7977, Ext. 338, toll-free. From California,

(800) 822-2020, Ext. 338. Or check it out at the best PC dealers.

PARADISE

S Y S T E M S , I N C

The Paradise Hi-Res Graphics Card



Trademarks: Paradise, Hi-Res Graphics Card-Paradise Systems Inc.; Lotus 1-2-3, Symphony-Lotus Development Corporation; Symphony, Framework-Ashton-Tate, Inc. Registered trademark IBM-International Business Machines Corp.

CIRCLE NO. 230 ON READER SERVICE CARD

The fastest C

Your search for execution speed is over. The new Microsoft® C Compiler Version 4.0 is here. With blazing performance. We've added common sub-expression elimination to our optimizer that produces code that rips through the benchmarks faster than ever before.

"... the Microsoft performance in the benchmarks for program execution is the best of the lot overall."
— William Hunt, *PC Tech Journal*, January, 1986*

But speed isn't the only edge you get with Microsoft C. Other advantages include a variety of memory models like our new HUGE model that breaks the 64K limit on single data items. Plus our NEAR, FAR and HUGE pointers, which provide you greater flexibility. All this allows you to fine tune your program to be as small and fast as possible.

"Excellent execution times, the fastest register sieve, and the best documentation in this review ... Microsoft Corporation has produced a tremendously useful compiler." — Christopher Skelly, *Computer Languages*, February, 1986.

No more debugging hassles. Introducing CodeView. Free.

Now, for a limited time, we'll give you an unprecedented programming tool when you buy Microsoft C, free. New Microsoft CodeView™ offers the most powerful tool yet in



the war on C bugs. Forget the hex dumps. Now you can view and work with programs at any level you want. Use the program source, the disassembled object code, or

Microsoft C Compiler Version 4.00

Microsoft C Compiler

- Produces fast executables and optimized code including elimination of common sub-expressions. NEW!
- Implements register variables.
- Small, Medium and Large Memory model libraries.
- Compact and HUGE memory model libraries. NEW!
- Can mix models with NEAR, FAR and the new HUGE pointers.
- Transport source and object code between MS-DOS® and XENIX® operating systems.
- Library routines implement most of UNIX™ System V C library.
- Start-up source code to help create ROMable code. NEW!
- Full proposed ANSI C library support (except clock). NEW!
- Large number of third party support libraries available.
- Choose from three math libraries and generate in-line 8087/80287 instructions or floating point calls:
 - floating point emulator (utilizes 8087/80287 if installed).
 - 8087/80287 coprocessor support.
 - alternate math package — extra speed without an 8087/80287.
- Link your C routines with Microsoft FORTRAN (version 3.3 or higher), Microsoft Pascal (version 3.3 or higher) or Microsoft Macro Assembler.
- Microsoft Windows support and MS-DOS 3.1 networking support.
- Supports MS-DOS pathnames and input/output redirection.

Microsoft Program Maintenance Utility. NEW!

- Rebuilds your applications after your source files have changed.
- Supports macro definitions and inference rules.

Other Utilities

- Library Manager.
- Object Code Linker.
- EXE File Compression Utility.
- EXE File Header Utility.

C Benchmarks

	In seconds				
	Microsoft C 4.0	Lattice C 3.0	Computer Innovation C 2.3	Aztec C86 3.2	Wizard C 3.0
Sieve of Eratosthenes (register)	82.9	151.4	172.3	88.0	91.9
Copy Block	86.9	231.7	199.0	123.8	189.5

Run on an IBM PC XT with 512K memory

Microsoft CodeView

Window-oriented source-level debugger. NEW!

- Watch the values of your local and global variables and expressions as you debug.
- Set conditional breakpoints on variables, expressions or memory; trace and single step.
- Watch CPU registers and flags as you execute.
- Effectively uses up to four windows.
- Debug using your original source code, the resulting disassembly or both intermingled.
- Use drop-down menus to execute CodeView commands.
- Access the on-line help to lead you through CodeView's options and settings.
- Easily debug graphics-oriented programs since program output is kept separate from debugger output.
- Keyboard or optional mouse support.
- Enter in familiar SYMDEB or DEBUG commands.

you've ever seen.

```

File Search View Run Watch Options Calls Trace! Go!
math.c
0) island : 244
1) tiszero() : 1
2) 4034:0000 00 00 00 00 00 00 00 00 43 72 .....

3DB5:00EE B80200 MOV AX,0002
3DB5:00F1 E89402 CALL _chkstk (0308)
3DB5:00F4 56 PUSH SI
3DB5:00F5 8B7604 MOV SI,Word Ptr [BP+04]
13: t[0] = 1;
3DB5:00F8 C606441A01 MOV Byte Ptr [_t (1A44)],01
14: div(s); /* t[] = 1/s */
3DB5:00FD 56 PUSH s
3DB5:00FE E82601 CALL _div (0227)
3DB5:0101 83C402 ADD SP,+02
15: add();
3DB5:0104 E84D00 CALL _add (0154) ;BR0
16: island = 1;
3DB5:0107 C746FE0100 MOV Word Ptr [island],0001
17: do {

>da 33 0x29
4034:0021 Microsoft
>

```

both at the same time. Open a window to view CPU registers and flags. Watch local and global variables as well. All while your program is running.

CodeView gives you complete control. Trace execution a line at a time—using source or assembly code. Or set conditional breakpoints on variables, memory or expressions. CodeView supports the familiar SYMDEB command syntax, as you'd expect. Commands are also available through drop-down menus. Combine the new window-oriented interface with our on-line help and debugging has never been easier. Or quicker.

Take the \$5 CodeView tour.

You may find it hard to believe our debugger can do all we've claimed. So we're offering test drives. Five bucks will put you behind the wheel of a Microsoft C demo disk with CodeView. See for yourself how fast debugging can get.

For more information about the CodeView demo disk, the new Microsoft C Compiler, a list of third party library support or the name of your nearest Microsoft dealer, call (800) 426-9400. In Washington State and Alaska, (206) 882-8088. In Canada call (416) 673-7638.

Microsoft® C Compiler

The High Performance Software

Microsoft, MS-DOS and XENIX are registered trademarks and CodeView is a trademark of Microsoft Corporation. UNIX is a trademark of AT&T Bell Laboratories. IBM is a registered trademark of International Business Machines Corporation.

NEW DASH FOR YOU

Your old printer should look so good.

Introducing the ImagEnhancer™ PC add-on board. It enables ordinary monochrome or color dot matrix printers to produce high-quality, plotter-like graphics.

THE OUTPUT IS OUTSTANDING.


The ImagEnhancer is the perfect way to get presentation-quality graphs, charts and artwork from your old dot matrix printer.

What's more, it comes with a built-in 512K memory. So while your printer is printing one job, you can use your PC for another. Which will improve your productivity tremendously.

And of course, the ImagEnhancer works with the same computer products most everyone works with.

IBM® PCs, XTs, ATs or 100% compatibles

with graphics capability. Alps, Epson® or Epson-compatible monochrome or color dot matrix printers. And



The ImagEnhancer PC add-on board brings plotter-like output to dot matrix printers.

Houston Instrument (DM/PL) plotter-compatible software, including Lotus® 1-2-3®, Symphony®, PFS:Graph and Framework™, among others.

AND THE PRICE IS RIGHT.

At \$595,* the ImagEnhancer costs a fraction of what you'd pay for a new plotter. It's simple to install, too. And backed by a one-year warranty.

The ImagEnhancer is a product of Alps America, a U.S. subsidiary of Alps Electric Co., Ltd. of Japan, an International Fortune

REGIO

REVENUE (\$M)

\$500

400

300

200


100

0

Jan

Feb

Mar



500 company. Other Alps America products include a full line of high-quality printers.


For more information, print samples, or the name of the dealer/distributor nearest you, write to Alps America, 3553 North First Street, San Jose, CA 95134. Or call (800) 828-ALPS. In California, (800) 257-7872. In Canada, (800) 858-2577.

Better yet, send in this coupon along with your payment. And teach your old dot matrix some new tricks.

CIRCLE NO. 247 ON READER SERVICE CARD

R OLD DOT MATRIX.

NAL SALES FORECAST



This image was printed with an ordinary dot matrix printer and the ImagEnhancer PC add-on board.

SO ORDER TODAY.

Name: _____

Address: _____

City: _____

State: _____ Zip: _____

Phone: _____

Send _____ ImagEnhancer(s) at \$595 each*

*Add \$10.00 shipping and handling for each. California residents add 7% sales tax.
Offer available in U.S.A. only.

Method of payment (circle one):

Check Money Order **MASTERCARD** VISA

Card number: _____

Exp. date: _____

Signature: _____

Mail to: Alps America
3553 North First Street
San Jose, CA 95134
Or call (800) 828-ALPS
In California, (800) 257-7872

ALPS
AMERICA

THE PROGRAMMER'S SHOP™

31 Day
RISK-FREE TRIAL
on any product in this ad.

C Programmers: 7 Ways to Increase Productivity

Add Efficient MultiTasking to Your C Programs with Multi-C

Multi-C lets you create, manage, and communicate among tasks with little RAM and little processor overhead. Now you can handle multiple users, printers, communications, or just about anything else in a logical, well structured manner, without complex polling schemes or lockups in your programs.

Unlike an operating system toolkit, Multi-C is designed for ease of use in production programming, and Multi-C **cooperates** with your operating system, so functions are **reliable**. Existing and new programs can add Multi-C features without paying royalties. 40+ functions use 32,000 priority levels, handle interrupts, control flags, and messages and control queues.

Multi-C is lower in cost than other products of this type, and it's portable because it's written in C; use it for stand-alone systems. You can even make Multi-C the kernel of your own operating system!

Particularly good for applications in data acquisition, device control, communications, and to give the user control of application use, response, and keyboard productivity. Multi-C has all the functions you need for task scheduling, time scheduling, and inter-task communication.

Specify for use with MS C, Lattice 2.15 or 3.0, or C-86. Partial source.

Cytek MSDOS \$149

First Database Exclusively for C is also Royalty-Free. db_VISTA from RAIMA Corporation

— "If you are looking for a sophisticated C programmer's database, this is it." —

— Dave Schmitt, President, Lattice, Inc.
Designed exclusively for C, db_VISTA is a royalty-free programmer's DBMS. Take full advantage of C through ease of use, portability, and efficiency. You optimize for speed and efficient disk storage.

Multiple key records, fast B-tree indexing, virtual memory disk accessing. Tailor db_VISTA to your needs by using only those features you require. ASCII file transfer utilities make moving to db_VISTA a snap.

MSDOS, Unix, Xenix, Macintosh, Amiga. Single user Source \$459
Object \$179. Multiuser Source \$929. Object \$450

Even for Small Files: Convenient, Fast Access CBTREE — Only \$99

Why spend time writing file management code when you can use consistent, flexible, documented, professional functions? Even multiuser record locking and variable-length records are supported.

Add, delete, and update without needing to reindex. Store keys and record locations in B+ trees.

You can access any record or group of records by the value of a user specific key. Search your files from any point, forward or backward.

Full, balanced b-tree support includes use of multiple keys, unlimited number and length of keys.

Use this powerful ISAM, even if you've previously done without.

Learn how to write systems for managing large files by using CBTREE source as a guide. Modify it and transfer it to another operating environment without royalties.

MSDOS \$99

Full Screen Library Plus Fundamentals THE HAMMER LIBRARY

1-2-3 menus (even multilevel), data validation including range checking, field editing, and Full Screen input make this a thorough access library. Data entry routines let you move between fields before completing screen.

But you also get DOS and BIOS access, file handling, string functions, and data handling. Plus pattern matching calls and library handling utilities.

Full source, no royalties. Data entry routines for solid interface with user. Specify MS C, Lattice, CI-C86, Dmsmet, MW C.

MSDOS. A lot for only \$179

Looking for the right tool for the job? Reach for THE HAMMER.

Flexible Screen Development with SECURITY CHECKING and HELP SCREENS: ZVIEW Screen Library

Use this field-sensitive tool to develop data entry screens and windows and provide run-time flexibility. Security level settings restrict inquiry or update of fields; multiple screen help display is available at screen and field level. You can also customize ZVIEW's operation and make any field characteristic change during execution.

ZVIEW gives you full control of attributes, colors, boxes, protected fields, scrolling, and more. Load screens from memory for fast response. Field support includes alpha, numeric, or alphanumeric data types, case conversion, range checking, and field comparison, and ZVIEW provides automatic data conversion to and from ASCII screen format. For Microsoft C, Lattice 3.0, and Aztec 3.2e. Supports EGA, color, and monochrome displays.

PCDOS \$219

C DYNAMO! WINDOWING: Full C Source, No Royalties POWER WINDOWS AND C. FUNCTION LIBRARY

Power Windows covers all the bases; overlays, borders, 1-2-3 style or pop-up menus/help windows, zap instantly on/off screen, status lines, horizontal/vertical scrolling, color control or highlighting, word-wrap, files to windows, keyboard to windows. Powerful, easy to use, integrated error messages, thorough documentation. Supports IBM monochrome or color.

MSDOS. Only \$119

C Function Library - includes 325 fundamental functions with readable source and thorough documentation.

MSDOS. Only \$119

No matter what you have, you need these. Best value available. Highly recommended.

Fastest Interactive C Development on Earth: Instant C version 2.0

Instant C's NEW version 2.0 gives you immediate (2 secs.) compilation and execution of large (5,000+ line) programs, and the ability to link in external (commercial or your own) libraries in an interactive, Lattice 3.0 or Microsoft 3.0 compatible, interpreter-like environment with an integrated full screen editor and source level debugger.

You get full K&R standard C, fast (33 second sieve) execution speed, and debugging with source code animation, single-stepping, back-tracing, and unlimited conditional breakpoints.

Instant C now supports multiple screens and graphic devices, run-time checking of pointer and array references, and includes a new manual, expanded tutorial and reference section, and complete library source.

MSDOS \$399

Rational
Systems, Inc.

Call for a catalog, literature, advice and service you can trust

NEW HOURS

8:30 AM - 8:00 PM EST.

800-421-8006

THE PROGRAMMER'S SHOP™
128-P Rockland Street, Hanover, MA 02339
Mass: 800-442-8070 or 617-826-7531 5/86

"YOUR SERVICE IS FABULOUS!!! ... Your information packets are so enticing; I really want 10 of them ... Keep up the good work."


— Dana Bredemeyer
Bredemeyer Company

Using ROM Characters

Tic marks, plot titles, and y-axis titles can be labeled easily using the routines presented here.

Characters can be printed at any point in the 640-by-200 high-resolution graphics grid. A pattern table for the first 128 ASCII codes is found at location F000:FA6E in ROM. Each pattern consists of eight bytes representing the rows of dots that make up a character. In high-resolution graphics, the ROM BIOS displays characters by copying the appropriate bytes from the pattern table into video RAM.

The BASIC program called GLABEL.BAS (see listing 1) contains three subroutines that use this table for enhanced character displays. The first routine prints characters any-

where on the 640-by-200 high-resolution graphics grid and can be used for labeling tic marks. The second routine prints double-width characters similar to the ones that are possible with medium-resolution graphics. It can be used to label plot titles. The third routine prints characters rotated by 90 degrees and is useful for labeling y-axis titles. The main program offers a demonstration of the three routines. 

James Parsly is a systems analyst for the Tennessee Valley Authority. He has a B.S. degree in computer science and mathematics.

LISTING 1: GLABEL.BAS

```
10 SCREEN 2:KEY OFF:CLS
20 REM
30 REM DEMONSTRATE VERTICAL RESOLUTION
40 REM
50 X=0:FOR Y = 7 TO 20:LS=CHR$(Y+58):GOSUB 400
90 X=X+8
95 NEXT Y
100 REM
120 REM DEMONSTRATE HORIZONTAL RESOLUTION
130 REM
140 Y = 60:FOR X = 65 TO 75:LS=CHR$(X):GOSUB 400
170 Y = Y + 8
175 NEXT X
180 REM
200 REM DEMONSTRATE LARGE LETTERS
210 REM
220 Y=80:AS="BIG LETTERS"
230 FOR I = 1 TO LEN(AS)
250 X = 150+I*16:LS=MID$(AS,I,1)
260 GOSUB 690
280 NEXT I
290 REM
300 REM DEMONSTRATE 90 DEGREE ROTATION
310 REM
320 AS="90 DEGREE ROTATION":X = 400
330 FOR I = 1 TO LEN(AS)
350 Y = 200-I*8:LS=MID$(AS,I,1)
360 GOSUB 870
380 NEXT I
390 LOCATE 20,1:STOP
400 REM
410 REM SUBROUTINE PRINTS A LETTER LS WHOSE LOWER LEFT-HAND CORNER
420 REM WILL BE LOCATED AT (X,Y).
430 REM
440 IF ASC(AS) > 127 THEN RETURN
450 XX = X MOD 640:IF XX < 0 THEN XX = XX + 640 'MAKE 0 <= XX <= 639
460 REM
470 REM UNLESS (X MOD 8) = 0, PARTS OF THE LETTER WILL BE IN TWO
480 REM DIFFERENT COLUMNS.
490 REM
500 SHIFT = 2*(8-(XX MOD 8)) 'USED TO SHIFT BITS
510 LL = INT(XX/8) '1ST COLUMN
520 NN = (LL+1) MOD 80 '2ND COLUMN
530 FOR II=Y-7 TO Y 'ROW LOOP
540 YY = II MOD 200:IF YY < 0 THEN YY = YY + 200 'MAKE 0 <= YY <= 199
550 DEF SEG = &F000 'SEGMENT OF ROM
```

```
560 REM GET A BYTE REPRESENTING ONE OF THE EIGHT ROWS OF DOTS THAT
570 REM MAKE UP THE CHARACTER. SHIFT THE VALUE SO THAT THE BITS
590 REM THAT GO IN THE TWO COLUMNS ARE SEPARATED INTO SEPARATE BYTES
600 REM
610 KK = PEEK(&HFA6E+ASC(AS)*8+II-Y)*SHIFT
620 DEF SEG = &H8000 'SEGMENT FOR VIDEO
630 IF YY MOD 2 = 0 THEN DISP = 0 ELSE DISP = &H2000 'OFF. FR EVN/ODD ROWS
640 MM = INT(YY/2)*80 'OFFSET TO ROW
650 POKE DISP+MM+LL,PEEK(DISP+MM+LL) OR INT(KK/256) 'SET BITS IN 1ST COL
660 POKE DISP+MM+NN,PEEK(DISP+MM+NN) OR (KK-INT(KK/256)*256) '8 2ND COL
670 NEXT II
680 RETURN
690 REM SUBROUTINE PRINTS A DOUBLE-WIDTH CHARACTER LS WHOSE
710 REM LOWER LEFT-HAND CORNER IS (X,Y)
720 REM
730 IF ASC(AS) > 127 THEN RETURN
740 DEF SEG = &HFA6E 'SEGMENT OF ROM
750 FOR II = Y-7 TO Y 'ROW LOOP
760 XX = X MOD 640:IF XX < 0 THEN XX = XX + 640 'MAKE 0 <= XX <= 639
770 YY = II MOD 200:IF YY < 0 THEN YY = YY + 200 'MAKE 0 <= YY <= 199
780 KK = PEEK(&HFA6E+ASC(AS)*8+II-Y)*7 'GET PATTERN FOR A ROW
790 FOR LL=1 TO 8 'LOOK AT BITS IN THE PATTERN
800 NN = KK MOD 2 'GET LAST BIT
810 MM = XX+16*2*LL
820 IF NN < 0 THEN PSET(NN MOD 640,YY):PSET((NN+1) MOD 640,YY) '2 DOTS
830 KK = INT(KK/2) 'SHIFT BITS RIGHT
840 NEXT LL
850 NEXT II
860 RETURN
870 REM SUBROUTINE PRINTS A CHARACTER LS WHICH HAS BEEN ROTATED
890 REM 90 DEGREES AROUND ITS LOWER LEFT-HAND CORNER (X,Y).
900 REM
910 IF ASC(AS) > 127 THEN RETURN
920 DEF SEG = &HFA6E 'ROWS SEGMENT
930 FOR II = 1 TO 8 'ROW LOOP
940 KK = PEEK(&HFA6E+ASC(AS)*8+II-1) 'GET PATTERN FOR A ROW
950 FOR LL=1 TO 8 'COLUMN LOOP
960 MM = KK MOD 2 'GET LAST BIT
970 NN=(X-16*2*II-1) MOD 640:IF NN < 0 THEN NN=NN+640 'GET X COOR.
980 YY = (Y-8+LL) MOD 200:IF YY < 0 THEN YY = YY + 200 'GET Y COOR.
990 IF NN < 0 THEN PSET(NN,YY):PSET(NN+1,YY) 'MAKE TWO DOTS
1000 KK = INT(KK/2) 'SHIFT BITS RIGHT
1010 NEXT LL
1020 NEXT II
1030 RETURN
```


To Over 30,000 Installations, MultiLink® **MEANS** Multi-User.

At over 30,000 sites, as many as one-quarter of a million users tap into the power of MultiLink® Advanced everyday.

Since 1981, they've come to rely on our multi-tasking, multi-user system for compatibility with their favorite software, and the ability to share disks, files, printers, and programs in a *true* PC-DOS environment.

From the largest of the Fortune 500 to the smallest in small business, MultiLink® has provided a cost-effective multi-user solution that's available from no one else.

MultiLink® Means Cost-Effective Timesharing on a PC. MultiLink® Advanced utilizes the principle of timesharing by sharing a central PC's peripherals, files, and processor time among nine users. Up to eight inexpensive terminals can be connected to a single non-dedicated IBM PC, XT, AT or 100% compatible using standard RS-232 ports. Each terminal effectively emulates a PC having up to 512K RAM.

PC-Shadow™ Workstations, shown below, even have an AT look-alike, as well as work-alike, keyboard, display, and serial port. In addition, password-protected remote access via modem can be made with either dumb terminals or PCs running our terminal emulation software.

MultiLink® Means PC-DOS Compatibility with a Software-Driven System. Lotus 1-2-3, Symphony, WordStar, dBASE III, & Multimate are just a sampling of the wide variety of PC-DOS software that's fully compatible.

Our software-driven system is also IBM NETBIOS compatible, so programs that are written for IBM's Token Ring will run on our multi-user system, as well.

MultiLink® Means Multi-User to Leading Computer Publications. Whether you read *PC Magazine*, "MultiLink® Advanced delivers on...convenience, speed, and flexibility," or *InfoWorld*, "If you want a low-cost multiuser system with up to eight terminals, MultiLink® Advanced is worth a serious look," it becomes clear that MultiLink® Advanced is a formidable contender in the multi-user marketplace.

See What MultiLink® Can Mean to You. Learn, firsthand, how our multi-user system can benefit your company. Call The Software Link TODAY for complete information and the authorized dealer nearest you. MultiLink® Advanced is \$495 and comes with a money-back guarantee.

MultiLink® is a registered trademark of The Software Link, Inc. MultiLink® Advanced & PC-Shadow™ are trademarks of The Software Link, Inc. IBM PC, XT, AT, PC-DOS, Token Ring, & NETBIOS are trademarks of IBM Corp. WordStar, dBASE III, Multimate, Lotus 1-2-3 & Symphony are trademarks of MicroPro. Ashton-Tate, Multimate International, & Lotus Development Corp., respectively.

MultiLink® ADVANCED



THE SOFTWARE LINK, INC.


8601 Dunwoody Place, Suite 632, Atlanta, GA 30338 Telex 4996147 SWLINK

CALL: 404/998-0700

Dealer Inquiries Invited

THE SOFTWARE LINK, INC./CANADA
250 Cochrane Drive, Suite 12 Markham, Ontario L3R 6B7
CALL: 416/477-5480

CIRCLE NO. 196 ON READER SERVICE CARD



PROGRAMMER'S CONNECTION

There is a difference.



Please don't mistake us for our competition. We're Programmer's Connection, a leading independent dealer of quality programmer's development tools specifically for IBM Personal Computers. We're your best one-stop source for the professional PC/MS-DOS and XENIX programming tools you need.

Since we're an *independent* dealer, we'll look out for your best interest. Our courteous, knowledgeable, noncommissioned sales staff is always ready to assist you. If you aren't sure about your needs, you can talk to our experienced, professional technical staff for sound, unbiased advice. They can compare products, answer technical questions and send you detailed product information that's tailored to your needs.

Our product line consists of hundreds of high quality software development tools specifically for IBM Personal Computers and compatibles. We don't carry *everything* ever written for programmers — only those products that meet our very high standards for quality and value.

The products we carry are the latest version and they come with the same manufacturer's technical support as if buying direct. Unlike other dealers who participate in the software gray market, we're authorized to sell *every* product we carry.

We discount all software products — even special order items. We don't try to fool you by discounting some products and charging full list price for others. Every product in our price list is shown with its discounted *and* retail price. We want you to know exactly how much you'll save on *every* product.

Other dealers add extra rush charges for shipping via express services. We'll express your order to you with no special handling charges. We only charge you what the shipping carrier charges. And if you have your order shipped via standard UPS, *we'll* even pay for the shipping!

Most popular products are in stock and ready for immediate shipment. Maintaining an adequate inventory is part of our philosophy of fast, efficient service.

If we don't have a product in stock, we'll get it for you fast. Again — no extra charge. Some dealers charge your credit card at the time they take your order. This means you could be left waiting in vain for your order for weeks or months while they use your money interest free. *We never* charge your credit card until we actually ship your order.

Quite simply, the discount prices you see on the next two pages are all you pay. There are *no* hidden charges. We don't charge extra for standard UPS shipping, credit cards, COD orders, purchase orders or special handling (except orders outside the U.S. and Canada are charged \$5 for customs form preparation).

Our goal is customer satisfaction and that's why we offer 30 day no-risk return guarantees and 30 day evaluation periods on most of our products. Note that some items, especially those with source code, are restricted by the manufacturers from this guarantee. Please call for specific details.

As you can see, we're *not* like other dealers. Our customers keep coming back because we consistently provide high quality service and low discount prices.

So make the connection today and discover the difference for yourself. You'll be glad you did!

Call or write for our *FREE* comprehensive price guide.

US: 800-336-1166

CANADA: 800-225-1166

OHIO AND OVERSEAS: 216-877-3781

Customer Service: 216-877-1110

Hours: 8:30 AM to 8:00 PM Eastern Time.

 **programmer's
connection**

Turn the page for our latest advertised price list. ▷

CIRCLE NO. 175 ON READER SERVICE CARD



See previous page
for more information.

apl language

APL*PLUS/PC System by STSC	595	449
APL*PLUS/PC Tools Vol 1 by STSC	295	239
APL*PLUS/PC Tools Vol 2 by STSC	85	69
APL*PLUS Spreadsheet Manager by STSC	New	195
APL*PLUS/UNIX System For AT Xenix by STSC	995	795
Btrieve ISAM File Mgr with No Royalties by SoftCraft	250	195
Financial/Statistical Library by STSC	275	219
Pocket APL by STSC	95	79
QNAL Combination of APL with LISP by NIAL Systems	375	359
STATGRAPHICS Statistical Graphics System by STSC	795	619

arity products

Arity Expert System Development Package	New	295	279
Arity File Interchange Toolkit	New	50	48
Arity Prolog Compiler & Interpreter	New	795	739
Arity Prolog Interpreter	New	350	329
Arity SQL Development Package	New	295	279
Arity Screen Design Toolkit	New	50	48
Arity Standard Prolog	New	95	89

artificial intelligence

ExpertEDGE by Human Edge	795	659
Expertech Complete System by Intellware	475	389
EXSYS Expert System Development Software by EXSYS	395	339
First Class by Human Edge	New	500
GCLISP Golden Common LISP by Gold Hill	495	CALL
GCLISP 286 Developer LM Interpreter & LM Compiler	1190	CALL
Insight 1 AI Primer by Level Five Research	95	75
Insight 2+ by Level Five Research	New	485
Logic-Line Series All varieties by Thunderstone	New	CALL
Microsoft LISP Common LISP	250	189
PLA microProlog by Programming Logic Associates	250	219
with APES	450	399
PLA Professional microProlog by Programming Logic	395	349
with APES	695	599
QNAL Combines APL with LISP by NIAL Systems	375	359
Turbo Prolog Compiler by Borland International	100	79

assembly language

8088 Assembler w/Z-80 Translator by 2500 AD	100	89
ASMLIB Function Library by BC Associates	New	149 129
Cross Assemblers Over 25 Varieties from 2500 AD	CALL	CALL
Microsoft Macro Assembler with utilities	150	99
Turbo EDITASM Fast Assembler by Speedware	99	84
Visible Computer: 8088 by Software Masters	80	65

basic language

BASIC language		
BetterBASIC by Summit Software	200	165
8087 Math Support	99	85
Btrieve Interface	99	85
C Interface	<i>New</i>	CALL CALL
Run-time Module	250	225
Microsoft QuickBASIC Compiler	<i>New version</i>	99 79
Professional BASIC by Morgan Computing	99	79
8087 Math Support	50	47
True Basic	150	105
Run-time Module	<i>Special Price</i>	500 199

blaise products

Asynch Manager Specify for C or Pascal	175	136
C Tools Combination Package Both Items Below	175	149
C Tools	125	105
C Tools 2	100	84
Exec Program Chainer	95	79
Pascal Tools Combination Package Both Items Below	175	149
Pascal Tools	125	105
Pascal Tools 2	100	84
Turbo ASYNCH for Turbo Pascal	100	84
Turbo POWER TOOLS for Turbo Pascal	100	84
View Manager Specify for C or Pascal	275	209
with Source Code	295	239

borland products

REFLEX Data Base System	150	119
REFLEX Workshop	New 70	59
REFLEX and REFLEX Workshop Combination Package ...	New 200	159
Turbo DATABASE TOOLBOX	55	38
Turbo EDITOR TOOLBOX	70	54
Turbo GAMEWORKS TOOLBOX	70	54
Turbo GRAPHIX TOOLBOX	55	38
Turbo LIGHTNING	99	75
Turbo PASCAL	70	49
with 8087 or BCD	110	77
with 8087 and BCD	125	84
Turbo Prolog Compiler	100	79
Turbo TUTOR for Turbo PASCAL	35	28

c compilers

C-86 Optimizing Compiler	395	289
Datalight C Compiler <i>Small Memory Model</i>	60	49
Datalight Developer's Kit with <i>Large Memory Model</i>	99	79
DeSmet C Compiler with <i>Source Debugger</i>	159	145
Large Case Option	New	50
Eco-C <i>Complete Development System</i> by Ecosoft	125	89
Lattice C Compiler from Lattice	See Lattice Section	500
Let's C Compiler by Mark Williams	75	59
with csd <i>Source Level Debugger</i>	150	118
Microsoft C Compiler with <i>Source Debugger</i>	New version	CALL
MWC-86 by Mark Williams	495	299
Wizard C Compiler <i>Includes Lint</i> by Wizard Systems	450	369

c interpreters

C-terp by Gimpel Software <i>Specify compiler interface</i>	300	239
Instant C by Rational Systems <i>New version</i>	500	379
Introducing C by Computer Innovations	125	105
Run/C by Age of Reason	150	99
Run/C Professional by Age of Reason	250	184

c utilities

Also refer to Blaise, Computer Innovations, Lattice, Microsoft, Phoenix, Polytron, SoftCraft and Xenix System V sections.

APT Application Programmer's Toolkit by Shaw American	395	339
Basic C Library by C Source	175	135
C Essentials by Essential Software	100	85
C to dBase ISAM Manager by Computer Innovations	150	139
c-tree ISAM File Manager with source by FairCom	395	329
C Utility Library by Essential Software	185	139
C Windows by Syscom	100	85
C Wings by Syscom	50	45
CI Probe Source Level Debugger Limited Quantity Sale	225	159
CI RomPac for C-86 by Computer Innovations	195	149
dBx dBase to C Translator by Desktop AI New	350	329
dbVISTA Single-User DBMS by Raima	195	159
with Source Code	495	429
dbVISTA Multi-User DBMS by Raima	495	429
with Source Code	990	849
Entelekon Combo Package All 3 items below	200	175
C Function Library	130	115
C Windows	130	115
Superfonts for C	50	45
Essential Graphics No Royalties by Essential Software	250	219
Flash-up Windows by Software Bottling of NY	75	69
GraphiC Mono version 2.2 by Scientific Endeavors	280	219
GraphiC Color version 3.0 by Scientific Endeavors	350	299
The Greenleaf Functions by Greenleaf Software	185	135
Greenleaf Comm Library by Greenleaf Software	185	135
The HAMMER by OES Systems	195	175
MetaWINDOWS by Metagraphics	185	139
MetaWINDOWS/Plus by Metagraphics	235	199
Multi-Halo with Royalties by Media Cybernetics	300	219
On-line Help from Opt-Tech Data Processing	149	119
PANEL by Roundhill Library Source Also Available	295	229
PC Lint by Gimpel Software	139	109
Scientific Subroutine Library for C by Peerless	175	139
Vitamin C by Creative Programming	150	139
VC Screen Interactive Forms Designer	99	85
Zview with Free Updates by Data Mgmt Consultants	245	199

cobol language

Micro Focus COBOL Workbench	4000	3599	
Micro Focus Level II COBOL	Special Price	1500	CALL
COMATH	200	169	
FORMS-2	300	269	
Level II Animator	Special Price	900	CALL
Level II SOURCEWRITER	Special Price	2000	CALL
Micro Focus Level II COBOL For Novell NetWare	New	2000	1799
Micro Focus Micro/SPF	175	159	
Micro Focus Professional COBOL	3000	2395	
Multi-user Runtime for PC Network	New	500	449
Microsoft COBOL	See Microsoft Section		
OPT-Tech Sort Also Sorts Btrieve Files	149	119	
Realia COBOL	995	795	
RM/COBOL by Ryan-McFarland	950	675	
RM/COBOL 8X ANSI 85 COBOL by Ryan-McFarland	1250	995	

debuggers & profilers

Advanced Trace-86 with ASM Interpreter by Morgan	175	139
CI Probe Source Level Debugger	Limited Quantity Sale	225 159
Codesifter Execution Profiler by David Smith	New	119 99
Codesmith-86 Debugger by Visual Age		145 109
Periscope I w/Board & Switch by Data Base Decisions		295 249
Periscope II w/NMI Breakout Switch Only		145 115
Periscope II-X Software only	Special Price thru August	115 85
The PROFILER with Source Code by DWB associates		125 95

forth language

Forth language			
CFORTH Native Code Application Compiler by LMI	New	300	239
LMI Forth/83 Metacompiler Specify Target Processor	New	750	599
PC/Forth by Laboratory Microsystems		150	119
PC/Forth+ by Laboratory Microsystems		250	209
Advanced Color Graphics Support	New	100	79
Enhanced Graphics Support	New	200	159
Intel 8087 Support	New	100	79
Interactive Symbolic Debugger	New	100	79
Native Code Optimizer	New	200	159
PCTERM Modem Program for Smartmodem	New	100	79
Software Floating Point	New	100	79

fortran language

ACS Time Series by Alpha Computer Service	495	429
Btrieve ISAM File Manager	125	99
50 MORE: FORTRAN by Peerless Engineering	90	79
For-Winds by Alpha Computer Service	70	55
Fortlib-Plus by Alpha Computer Service	135	119
Grafmatic or Plotmatic by Microcompatibles	240	219
Grafmatic and Plotmatic by Microcompatibles	350	209
Microsoft Fortran	300	219
Multi-Halo with Royalties by Media Cybernetics	295	229
PANEL Screen Designer by Roundhill	595	395
RM/Fortran by Ryan-McFarland	175	139
Scientific Subroutine Library by Peerless	295	259
The Statistician by Alpha Computer Service	70	55
Strings & Things by Alpha Computer Service		

lattice products

Lattice C Compiler from Lattice	500	299
with Library Source Code	900	549
C Cross Reference Generator	50	39
with Source Code	200	159
C-Food Smorgasbord Function Library	150	99
with Source Code	300	195
C-Sprite Source Level Debugger	175	139
Curses Screen Manager	125	98
with Source Code	250	194
dBC dBase File Manager for C	250	194
with Source Code	500	388
LMK Make Facility	195	149
RPG II Compiler No Royalties	500	595
SecretDisk File Encryption Utility	60	49
SideTalk Resident Communications	120	95
Text Mgmt Utilities (GREF,DIFF,ED,WC,Extract,Build)	120	95
TopView Toolbasket Function Library	250	194
with Source Code	500	388
Z-80 C Cross Compiler	500	388
with Library Source Code	1000	789

microsoft products

Microsoft BASIC Interpreter for Xenix	350	279
Microsoft C Compiler with source debugger	CALL	CALL
Microsoft COBOL Compiler	700	495
for Xenix	995	795
Microsoft COBOL Tools with COBOL Source Debugger	350	209
for Xenix	450	359
Microsoft Fortran Compiler	350	209
for Xenix	495	389
Microsoft LISP Common LISP	250	189
Microsoft Macro Assembler with utilities	150	99
Microsoft Mouse Bus Version	175	149
Microsoft Mouse Serial Version	195	159
Microsoft muMath Includes muSIMP	300	195
Microsoft Pascal Compiler	300	195
for Xenix	495	389
Microsoft QuickBASIC Compiler	99	79
Microsoft Sort	195	149
Microsoft Windows	99	74
Microsoft Windows Developer's Kit	500	CALL

modula-2 language

MODULA-2/86 Compiler by Logitech	89	65
with 8087	129	105
with 512K	189	149
MODULA-2 Editor by Logitech	59	49
MODULA-2 Runtime Debugger by Logitech	69	59
MODULA-2 Source Package by Logitech	99	79
MODULA-2 Utilities Package by Logitech	49	45

other languages

CCS MUMPS Single-User version by MGlobal	60	55
CCS MUMPS Multi-User version by MGlobal	450	379
Janus/ADA C Pack by R&R Software	95	89
Janus/ADA D Pack by R&R Software	900	699
Methods Smalltalk by Digital	79	69
Smalltalk/V by Digital	99	89
SNOBOL4+ by Catspaw	95	84

other products

Dan Bricklin's Demo Program by Software Garden	75	65
FASTBACK Backup Utility by 5th Generation Systems	179	159
Interactive EASYFLOW by Haventree Software	150	129
SET:SCIL by System Engineering Tools	349	299
Source Print by Aldebaran Laboratories	139	119
SRMS Software Revision Mgmt System by Quilt Computing	125	109

phoenix products

Plantasy Pac (Pfinish,Plix+,Plink+,Pmaker,Pmate,Ptel)	1295	949
Pfinish Performance Analyzer	395	249
Pfix-86 Plus Symbolic Debugger	395	249
PforCe Comprehensive C Function Library	395	289
Plink-86 Overlay Linker	395	249
Plink-86 Plus Enhanced Overlay Linker	495	389
Pmate Macro Text Editor	225	149
Pre-C Lint Utility	395	249
Ptel Binary File Transfer Program	195	139

polytron products

Polytron C Beautifier	49	45
Polytron C Library I	99	79
Polytron PowerCom Communications	179	139
PolyLibrarian Library Manager	99	79
PolyLibrarian II Library Manager	149	119
PolyMake UNIX-like Make Facility	99	79
PolyOverlay Overlay Optimizer	99	79
PolyWindows Products All Varieties	CALL	CALL
PolyXREF Complete Cross Reference Utility	219	179
PolyXREF Support for one language only	129	109
PVCS Polytron Version Control System	395	329
PVMFM Polytron Virtual Memory File Manager	199	149

softcraft products

Btrieve ISAM File Manager with No Royalties	250	195
Xtrieve Query Utility for Btrieve	195	169
Btrieve Report Generator for Xtrieve	85	79
Btrieve/N for Networks	595	465
Xtrieve/N Query Utility for Btrieve/N	395	299
Btrieve/N Report Generator for Xtrieve/N	175	159

text editors

Brief from Solution Systems	195	CALL
Epsilon Multi-tasking Emacs-like editor by Lugu	195	165
FirstTime for Turbo by Spruce Technology	75	69
KEDIT Xedit-like editor by Mansfield Software Group	125	109
PC/VI by Custom Software Systems	149	129
SPF/PC by Command Technology Corp	195	165
Vedit by CompuView	150	115
Vedit Plus by CompuView	225	180
XTC Text Editor with source by Wendin	99	84

turbo pascal utilities

Also refer to Blaise, Borland and SoftCraft sections.

ALICE Turbo Pascal Interpreter by Software Channels	95	69
FirstTime for Turbo by Spruce Technology	75	69
Flash-up Windows by Software Bottling of NY	75	69
Multi-Halo with Royalties by Media Cybernetics	CALL	CALL
On-line Help from Opt-Tech Data Processing	149	119
Screen Sculptor by Software Bottling of NY	125	95
Turbo EXTENDER by TurboPower Software	85	69
Turbo Professional by Sunny Hill Software	70	49
TurboPower Utilities by TurboPower Software	95	84
TurboWINDOW by MetaGraphics	80	69

wendin products

Operating System Toolbox Build your own OS	99	84
PCUNIX Operating System	99	84
PCVMS Operating System Similar to VAX/VMS	99	84
XTC Text Editor with Pascal Source Code	99	84

xenix system v

Complete Xenix System by SCO All 3 items below	1295	1099
Xenix Development System	595	529
Xenix Operating System Specify XT or AT	595	529
Xenix Text Processing Package	195	179

xenix languages and utilities

APL*PLUS/UNIX System For AT Xenix by STSC	995	795
Btrieve ISAM File Manager by SoftCraft	595	465
c-tree ISAM File Manager with Source by FairCom	395	329
dBx dBase to C Translator w/source by Desktop AI	550	499
dbVISTA Single and Multi User versions by Raima	CALL	CALL
Informix by Relational Database Systems	995	839
Informix4GL by Relational Database Systems	CALL	CALL
InformixSQL by Relational Database Systems	995	839
Lyrix by SCO	595	489
Micro Focus Level II Compact COBOL For AT	1000	899
Forms-2	400	359
Level II ANIMATOR	600	539
Microsoft Languages	See Microsoft Section	
RM/COBOL by Ryan-McFarland	1250	995
RM/FORTRAN by Ryan-McFarland	750	599
SCO Professional Complete Lotus clone by SCO	795	695



Prices are subject to change without notice.

Ohio customers please add 5% state sales tax.



Hours: 8:30 AM to 8:00 PM EST, Monday through Friday.



U.S.

1-800-336-1166



CANADA

1-800-225-1166



OHIO AND OVERSEAS


1-216-877-3781

CUSTOMER SERVICE 216-877-1110

programmer's connection

136 SUNNYSIDE ST.
HARTVILLE, OHIO 44632





Out from the Shadow of IBM...

...emerges an assortment of AT compatibles, each claiming to be better than the original. PC Tech Journal launches its series evaluating these AT alternatives one by one.

STEVEN ARMBRUST, TED FORGERON, and PAUL PIERCE

With the introduction of the PC/AT in 1984, IBM set the standard for high-performance personal computing. Since that time, a multitude of imitators has come out from the shadow of IBM, each claiming some combination of features, price, or performance as an advantage over the original. Because of the aggressive marketing practices of the manufacturers of these computers, and because several major players (such as AT&T, Hewlett-Packard, Tandy, and Sperry) are offering their own machines, IBM has been left with a smaller share of the market for 80286-based computers than it might have anticipated.

As sales figures indicate, AT compatibles are tempting alternatives to the original IBM version. However, finding the right computer can be an arduous task demanding much time and effort.

To assist in sorting through the choices, *PC Tech Journal* begins with this issue a series of articles on AT-compatible computers. Each article will focus on a single machine, examining in detail the two items most critical in evaluating an AT compatible: compatibility and performance. Each computer will be compared to the original 6-MHz IBM AT and to the 8-MHz AT released in April. A review of the Compaq Deskpro 286 on page 80 starts the series.

In keeping with the spirit of *PC Tech Journal's* continuing database management series in which products are evaluated according to the same exhaustive guidelines, and to ensure that each of the compatibles is evaluated in a consistent, detailed fashion, *PC Tech Journal* has devised a set of criteria for judging the machines. In addition, we have developed a set of com-

patibility and performance tests that will be used to compare each computer with the IBM models.

Each article will conform to a template that will start out with a description of the computer's appearance and a listing of the type of equipment and options that are available with it. This section will contain a sidebar detailing the computer's vital statistics, including the base price, memory and disk-drive options, types of display adapters and monitors, number and kinds of expansion slots, and any extra features offered by the compatible that are not available with the IBM AT. These extra items—such as touch screens, tape drives, turbo switches, or any other feature that sets the machine apart—will be examined individually in the review.

The articles will look carefully at the standard features of the machine, such as the disk drives, display adapter, serial and parallel ports, and keyboard. It will report on unusual attributes of any item normally viewed as standard on an AT. Although all the computers will be tested with the manufacturers' standard hard disks, this section will mention whether any third-party disk controllers and hard disks have been certified for use with the computer.

Each review will venture inside the machine in question. The article will describe how easy (or how hard) it is to remove the cover of the system unit and install new boards or components. The power supply, disk drives, and memory will be discussed here.

Documentation provided with the computer will be reviewed and an overall evaluation made.

THE TESTS

At the heart of this series is a set of compatibility and performance tests. Two types of tests will be run. First, a selected set of commercial hardware and software products will be installed and run. The hardware includes an Intel Above Board AT, Microsoft bus and serial mouse, a Hayes Smartmodem 1200B, and an IBM Enhanced Graphics Adapter and monitor. The commercial software products chosen are Microsoft Windows 1.01 and Word 2.0 (to test a graphics-intensive environment and serial and parallel printer ports); Borland's SideKick 1.56A, SuperKey 1.11A, and Turbo Lightning 1.01A (to test memory-resident programs); Hayes's Smartcom II 2.1 (to test the communications interface); Living Video Text's Ready! 1.00D (to test the use of expanded memory as defined by the Lotus-Intel-Microsoft specification); and

the IBM AT Advanced Diagnostics 1.01 (for a general checkup).

The second type of test involves running programs designed for this series. To test compatibility, these programs provide information about the processor, BIOS, hard-disk drive, and keyboard. To measure performance, they determine the speed of the processor, hard-disk drive, and memory.

Table 1 lists the results of these tests when run on three different IBM computers: an original AT with a 20MB hard disk, the second version of the AT with a 30MB hard disk (and BIOS that limits the clock speed to 6 MHz), and the latest version of the AT with an official 8-MHz clock and a 30MB hard disk.

The two items considered the most critical in evaluating an AT compatible are compatibility and performance. Each computer will be compared to the 6- and 8-MHz IBM AT models.

In each of the upcoming articles, the same tests will be run on the AT-compatible computer and the results compared with those of the 8-MHz AT.

The source code for the tests is listed here in abbreviated form; the complete listings are on PCTECHline. *[The AT Evaluation Suite is copyright © 1986 by Ted Forgeron, Steven Armbrust, Paul Pierce, and PC Tech Journal. All rights reserved; the resale, other commercial use of the programs for profit, or publication of the programs is prohibited. Any internal or noncommercial use or display of the programs or their results requires permission from PC Tech Journal and full credit to PC Tech Journal and the authors.]* —WFJ

The tests are divided into five separate programs: ATBIOS, ATKEY, ATPERF, ATFLOAT, and ATDISK.

ATBIOS. Written in Turbo Pascal, the ATBIOS code is shown in listing 1. This test examines ROM locations of the BIOS to determine the date, machine ID, and copyright statement. This information determines which version of BIOS is present in the computer and who manufactured the BIOS, an important consideration for compatibility.

ATBIOS looks at the BIOS data area (a 256-byte area of RAM starting at address 400H that the BIOS uses for its variable data) to retrieve information such as the number of diskette drives installed, whether the 80287 math coprocessor is present, the initial and current video modes, the DMA flag, the number of serial and parallel ports, and the keyboard buffer (the last few characters typed at the keyboard). The test looks for this information at the locations used by the AT's BIOS. If the compatible computer's BIOS uses different locations to record the same items, the test will return useless information for those particular items.

Although the ATBIOS program was written specifically for AT-compatible computers, it will run on both PC- and AT-style machines and will display the machine type ("AT COMPATIBLE" or "NOT AT") based on the value of the BIOS machine ID field.

ATKEY. ATKEY is an assembly language program that tests the programmability of the keyboard. The AT contains an 8042 processor that defines the characteristics of the keyboard. This chip can be reprogrammed to redefine the keys or change the way the keyboard operates. By programming the 8042, ATKEY tests whether utility programs, such as those that speed up the typematic action, work on the compatible.

The source code of ATKEY is shown in listing 2. ATKEY sends a command to the 8042 keyboard processor and then attempts to set the keyboard's repeat count to 30 characters per second. If the computer does not have an 8042 controlling the keyboard, the test does not receive an acknowledgement from the original command. In such a case, ATKEY returns an error message.

The Microsoft assembler is used to produce ATKEY's object code. Assuming that ATKEY.ASM contains the assembly language source code, the following commands are used to assemble and link the program:

```
masm atkey;
link atkey;
```

Because ATKEY tests functions that are specific to the AT, this test will not run on PC- or XT-compatible computers. Once the ATKEY program has been run, the keyboard repeat count is left at 30 characters per second. The system should be rebooted if the user finds this setting undesirable.

ATPERF. The ATPERF tests determine the clock rates of both the CPU and the math coprocessor, measures the speed of memory accesses, and determines

TABLE 1: AT Compatibility and Performance Tests

	AT with 30MB disk (8-MHz)	AT with 30MB disk (6-MHz)	AT with 20MB disk (original)
ATBIOS			
ROM BIOS date	11/15/85	06/10/85	01/10/84
ATPERF			
Average RAM instruction fetch (μ s)	0.403 (100) ^a	0.569 (71)	0.555 (73)
Average RAM read time (μ s)			
BYTE	0.401 (100)	0.565 (71)	0.549 (73)
WORD	0.401 (100)	0.565 (71)	0.549 (73)
Average RAM write time (μ s)			
BYTE	0.401 (100)	0.566 (71)	0.549 (73)
WORD	0.401 (100)	0.565 (71)	0.549 (73)
Average ROM read time (μ s)			
BYTE	0.401 (100)	0.565 (71)	0.549 (73)
WORD	0.401 (100)	0.565 (71)	0.549 (73)
Average video write time (μ s) (CGA only)			
BYTE	1.208 (100)	2.143 (56)	2.141 (56)
WORD	2.415 (100)	3.822 (63)	3.831 (63)
Average EMM read time (μ s)			
BYTE	0.402 (100)	0.566 (71)	0.549 (73)
WORD	0.402 (100)	0.566 (71)	0.549 (73)
Average EMM write time (μ s)			
BYTE	0.402 (100)	0.566 (71)	0.549 (73)
WORD	0.402 (100)	0.566 (71)	0.549 (73)
CPU clock rate (MHz)	8 (100)	6 (75)	6 (75)
Math coprocessor clock rate (MHz)	5.3 (100)	4 (75)	4 (75)
Refresh overhead (%)	7.1	13	9.6
RAM read wait states	1	1	1
RAM write wait states	1	1	1
ROM read wait states	1	1	1
Video write wait states (CGA)	8	11	11
EMM read wait states	1	1	1
EMM write wait states	1	1	1
ATFLOAT			
Performance as percentage of 8-MHz AT	7	7	100
ATDISK			
Sectors/track	17	17	17
Heads	5	5	4
Cylinders	731	731	613
Total space (million bytes)	31.81	31.81	21.34
Track-to-track seek time (ms)	10.0	6.0	9.1
Average seek time (ms)	37.0	37.1	37.5
Effective transfer rate (KB/sec)	170.1	170.1	168.6
DOS file I/O (sec)	7.3	7.5	7.4
Interleave	3	3	3

^aFigures shown in parentheses represent the relative performance expressed as a percentage compared to PC Tech Journal's baseline machine, the 8-MHz, 30MB AT.

These results were taken from several machines and averaged. Variations are apparent in the results from the ATDISK test. Track-to-track seek time on the original IBM AT varied substantially (7.2 ms to 13.3 ms) from machine to machine. The average seek time also varied but by a much lower amount. The effective transfer rate varied even less. The variation can be accounted for by considering the manufacturing tolerances. The drives come from a variety of manufacturers and each will behave in a different way with temperature changes, for example. Because the effective transfer rate is relatively constant, this apparent variation is negligible. Note, however, that the numbers obtained from the new model AT were consistent from machine to machine, showing tighter manufacturing tolerances.

the number of wait states that occur for the various types of memory accesses. The program is written in Microsoft C with assembly language subroutines. In addition to listing the actual times for the various operations, ATPERF displays relative performance numbers that compare the machine being tested to the new 8-MHz AT (a value of 1 is equivalent to the new AT; a value of 2 is twice as fast; etc.) Listing 3 shows the C source code of this program, and listing 4 shows the assembly language subroutine TIME.ASM.

For all of its timings, ATPERF uses timer number 2 of the programmable interval timer (an Intel 8254-2 chip). This is the timer that is normally used with the speaker. The program assumes that the timer frequency is 1.193180 MHz, as documented in the data sheet for the Intel chip. To ensure this value is accurate, each tested computer will be programmed to sound a 1,000-Hz tone, which will be measured by connecting a microphone to a frequency meter calibrated to the National Bureau of Standards radio station WWV. If the measured frequency of timer number 2 is incorrect in the computer being tested, the value used in the program will be adjusted accordingly.

ATPERF performs all measurements in the same general fashion. The main program calls an assembly language subroutine that turns on timer number 2, executes several operations in sequence (usually 1,000), and turns off the timer. To minimize the loop overhead, the timed operations are coded 100 or more to a loop rather than having a single-instruction loop. The number of clock ticks is then returned to the main program where it is turned into actual time. The subroutine is called many times (usually 100) and the combined results are averaged.

ATPERF's first measurement calculates the processor clock rate by calling a subroutine named _MULTIME to take 100 measurements of 1,000 multiply instructions. Multiply instructions are used because each MUL instruction takes 21 clock cycles, much longer than the time needed to fill up the processor's instruction queue. Therefore, the measurements are based purely on the processor speed, not on the speed of fetching instructions from RAM.

The formula for calculating the amount of time for each processor clock cycle determines the amount of time for the operation (the number of timer ticks divided by the timer rate) and divides it by the number of processor clock cycles that occurred during

LANGUAGES THAT ARE CAUSING THE BIGGEST PROGRAMMING BACKLOG IN HISTORY ARE ALSO EATING NICE BIG HOLES IN OUR POCKETS.

Whether it's BASIC, COBOL, Pascal, "C", or a data base manager, you're being held back.

Held back because the language has frustrating limitations, and the programming environment isn't intuitive enough to keep track of what you're working on.

In the real world, there's pressure to do more impressive work, in less time, and for more clients.

We've been given some incredibly powerful hardware in recent times, but the languages aren't a whole lot better than they were 20 years ago.

So, whatever language you have chosen, by now you feel it's out to get you — because it is.

Sure, no language is perfect, but you have to wonder, "Am I getting all I deserve?"

And, like money, you'll never have enough.

Pretty dismal, huh?

We thought so, too.

So we did something about it.

We call it CLARION™

You'll call it "incredible."

Distributed on 7 diskettes, CLARION consists of over 200,000 lines of code, taking 3+ years to hone to "world-class" performance.

With CLARION you can write, compile, run and debug complex applications in a New York afternoon.

Even if you're in Savannah.

It gives you the power and speed to create screens, windows and reports of such richness and clarity you would never attempt them with any other language.

Because you would have to write the code.

With CLARION you simply design the screens using our SCREENER utility and then CLARION writes the source code AND compiles it for you in seconds.

Likewise, you can use REPORTER to create reports.

Remember, only CLARION can recompile and display a screen or report layout for modification.

And with no time wasted.

All the power and facilities you need to write great programs, faster than you ever dreamed of.

Programs that are easy to use. Programs that are a pleasure to write.

And to you that means true satisfaction.

You've coveted those nifty pop-up help windows some major applications feature. But you can't afford the time and energy it takes to write them into your programs.

That's the way it used to be.

So we fixed that, too.

CLARION's HELPER is an interactive utility that let's you design the most effective pop-up help screens that you can imagine. And they're "context sensitive," meaning you can have help for every field in your application.

Unlike the other micro languages, CLARION provides declarations, procedures, and functions to process

dates, strings, screens, reports, indexed files, DOS files and memory tables.

Imagine making source program changes with the CLARION EDITOR. A single keystroke terminates the EDITOR, loads the COMPILER, compiles the program, loads the PROCESSOR and executes the program. It's that easy!

Our data management capabilities are phenomenal. CLARION files permit any number of composite keys which are updated dynamically.

A file may have as many keys as it needs. Each key may be composed of any fields in any order. And key files are updated whenever the value of the key changes.

Like SCREENER and REPORTER, CLARION's FILER utility also has a piece of the CLARION COMPILER. To create a new file, you name the Source Module. Then you name the Statement Label of a file structure within it.

FILER will also automatically rebuild existing files to match a changed file structure. It creates a new record for every existing record, copying the existing fields and initializing new ones.

Sounds pretty complicated, huh?

Not with CLARION's documentation and on-line help screens. If you are currently competent in BASIC, Pascal or "C" you can be writing CLARION applications in a day. In two days you won't believe the eloquence of your CLARION programs.

Okay, now for the best part of all. You can say it in CLARION for \$295.00—plus shipping and handling. All you need is an IBM® PC, XT, AT or true compatible, with 320 KB of memory, a hard disk drive, and a parallel port. And we'll allow a full 30 day evaluation period. If you're not satisfied with

CLARION, simply return it in its original condition for a full refund.

If you're not quite ready to take advantage of this no-risk opportunity, ask for our detailed 16 page color brochure. It vividly illustrates the elegance of CLARION. Consider it a preview of programming in the fast lane.

Either way, the 800 call's a freebie.



SAY IT IN

CLARION™

A2TJ/3

1-800-354-5444



BARRINGTON SYSTEMS, INC. 150 EAST SAMPLE ROAD POMPANO BEACH, FLORIDA 33064 305/785-4555

IBM is a registered trademark of International Business Machines Corporation. CLARION™ is a trademark of Barrington Systems, Inc. ©1986 Barrington Systems

CIRCLE NO. 105 ON READER SERVICE CARD

that time. An overhead factor is included in the number of processor clock cycles to allow for any extra time caused by the loop and turning on and off timer number 2.

The instruction fetch time is calculated using a similar formula. Instead of timing MUL operations, the instruction fetch test `_WMOVTIME` times MOV operations. These take only two clock cycles, which is also the minimum amount of time for an instruction fetch. The performance of this test depends not on how fast the processor can execute the instruction, but on the speed of the instruction fetch.

ATPERF calculates memory read and write times by using the processor's string-operation instructions, which move and store words or bytes. With the move instructions (MOVSB and MOVSW), bytes or words are read from DS:SI and written to ES:DI. The CX register specifies the number of bytes or words to move. With the store instructions (STOSB and STOSW), bytes or words are written from the AX register to ES:DI. As with the move instructions, the CX register indicates the number of times to store the value in AX, with DI being incremented each time.

The memory-write time is calculated directly from the store operations because they are pure write operations. The memory-read time is calculated using both the store time (which measures a write operation) and the move time (which measures both a read and write time). In fact, the store time is subtracted from the move time in order to obtain the read time.

ATPERF checks four kinds of memory: RAM, ROM, video memory (on a color/graphics adapter only), and EMM (expanded memory manager on the Intel Above Board). If no expanded memory is present in the computer, ATPERF skips the EMM checks. The program could be modified to check the video memory on the monochrome adapter by changing the hard-coded 0B800H value in the `_WVIDTIME` and `_BVIDTIME` routines to 0B000H.

For RAM and EMM memory, both read and write times are measured. Only the read time is measured for ROM (by using MOVSB and MOVSW to read from ROM and write to RAM, and then subtracting the time required for STOSB and STOSW to write to RAM). For video RAM, only the write time is measured, because rarely is any other kind of operation performed during normal system operation.

When checking memory speed, ATPERF measures the times for both

byte and word accesses. This is done to check whether the computer truly contains 16-bit data paths. Where 16-bit data paths exist, the times for byte and word accesses are the same. For 8-bit data paths, the word accesses take twice as long as byte accesses.

Several assembly language routines (shown in listing 4) measure the memory access times. `_BMVSTIME` times MOVSB instructions using normal RAM; `_WMVSTIME` measures similar MOVSW instructions. `_BROMTIME` times MOVSB

Unlike ATPERF, which takes great pains to isolate the operations it measures, ATFLOAT measures the type of floating-point operation that would naturally occur in a real-world application.

instructions that transfer data from ROM to RAM; `_WROMTIME` measures similar MOVSW instructions. `_BSTOTIME` times STOSB instructions using normal RAM; `_WSTOTIME` is used to time similar STOSW instructions. `_BVIDTIME` and `_WVIDTIME` clock the video memory write times. `_BEMSTIME`, `_WEMSTIME`, `_BEMMTIME`, and `_WEMMTIME` measure the access times for expanded memory on the Intel Above Board.

Next, ATPERF calculates the math coprocessor (80287) clock rate. As with the EMM test, the program checks for the existence of a math coprocessor before proceeding. If no 80287 is present, this portion of the test is skipped.

Part of the math coprocessor calculation is analogous to the CPU clock rate test, in which the program calls `_FPTIME` to measure the time required to perform floating-point divide (FDIV) instructions. Because floating-point instructions take much longer to execute than other instructions, `_FPTIME` executes fewer loops than the other test routines are able to execute. If it did not, the 16-bit count in the timer would overflow during the test.

The final part of the math coprocessor calculation is similar to the CPU clock rate test; the amount of time taken to execute the instructions is divided by the number of math coprocessor clock cycles that occurred. Because

the `_FPTIME` routine contains no looping, no loop overhead needs to be included in the calculation.

The ATPERF program also measures the refresh overhead. This value is the percentage of memory access time the computer uses in refreshing the memory (that is, rewriting it to prevent it from losing data).

Memory refresh is required for all computer systems that contain dynamic RAM. The cells in a dynamic RAM chip are essentially capacitors that form gates of a transistor. These capacitors are either charged or discharged to denote the 1s or 0s of the bits. If the memory is not refreshed, this charge leaks out of the capacitors in just a few milliseconds. In PCs, ATs, and any computer that uses the PC bus, a refresh signal occurs every 15 microseconds. This causes the computer to generate special refresh cycles, in which it rewrites all of the data contained in RAM.

In order to determine the refresh overhead, ATPERF uses the value it calculated for RAM read time and divides it by the value for a CPU clock cycle. This gives the number of clock cycles for the read operation. Because a RAM read operation should take an integral number of clock cycles, the fractional part of the result is due to memory refresh operations that occur during the 10,000 read operations of the test. This fraction of a memory cycle is then divided by the number of CPU cycles required for a read operation and is displayed as a percentage.

ATPERF's final test calculates the number of wait states that are associated with accessing the various types of memory. A wait state is an extra clock cycle during which the CPU remains idle while waiting for a response from memory. The CPU requires two clock cycles from the time it issues a memory read or write until it is ready to issue another one. If at that time, the memory has not sent a ready signal to indicate that the last read or write is finished, the processor idles for a clock cycle before it checks for the ready signal again. Each one of these extra clock cycles is a wait state.

The ANALYZE subroutine determines the number of wait states for the various types of memory by using the memory read and write times calculated earlier. It subtracts the amount of time required for two CPU clock cycles from the time required for the memory access. The result is divided by the time for a single CPU cycle to give the number of extra cycles (the wait states). A smaller number of wait states indi-

cates a higher level of performance, because the processor is wasting fewer clock cycles idling.

In addition, ANALYZE determines the width of the data path for the different memory types. It does so by comparing the times for the corresponding word and byte accesses. If these values are nearly the same, that memory is accessed an entire word at a time. If a word access takes approximately twice as long as a byte access, the data path is only one byte long.

When displaying the final results, ATPERF includes relative numbers that reflect how well the tested computer compares with the new 8-MHz AT in read and write times and clock rates. The program contains hard-coded values for the AT that were calculated using ATPERF. These numbers are divided by the calculated values to obtain a relative value.

The Microsoft C compiler and the Microsoft assembler are used to produce the object code of the ATPERF program. Assuming that ATPERF.C contains the C source code and TIME.ASM contains the assembly language source code, the following commands are used to compile and link the program:

```
msc atperf.c;
masm time.asm/r;;
link
    atperf + time,,,slibfp.lib + slibc.lib + em.lib;
```

The /r option on the masm command directs the assembler to generate floating-point instructions that can be executed on the 80287 coprocessor.

ATPERF is written specifically for AT-compatible computers. Running this program on PC-compatible computers will produce inaccurate results.

ATFLOAT. ATFLOAT, which is written in Microsoft C (listing 5), measures the performance of floating-point operations. Unlike ATPERF, which takes great pains to isolate the operations it measures, ATFLOAT measures the type of floating-point operation that would naturally occur in a real-world application. Instead of stringing together floating-point multiply instructions, ATFLOAT measures the time taken to perform 100 multiplies on a 20-by-20 matrix. Although the vast majority of the time is taken up by floating-point processing, the measurement also includes CPU time for looping through the matrices; this is time that would also be spent in any real floating-point application.

The test begins by filling the 20-by-20 matrix with random numbers. Then ATFLOAT performs 100 matrix multiplies while using the Microsoft C time

function to record the number of seconds required. The result of the test is displayed as a relative number that compares the tested computer with a new 8-MHz AT that contains an 80287.

The Microsoft C compiler produces the object code of ATFLOAT. Assuming that ATFLOAT.C contains the C source code, the following commands are used to compile and link the program:

```
msc atfloat.c/FPi,,atfloat.cod;
link atfloat/map,,,slibfp.lib + slibc.lib;
```

The /FPi option on the msc command generates code that uses the 80287 if one is present in the computer. If the 80287 is not present, the Micro-

The ATDISK program's measurement of the effective disk-transfer rate allows the interleave value to be determined empirically.

soft floating-point emulator is used. Running ATFLOAT on a computer without an 80287 takes as long as 15 minutes (as compared to a minute or so with the 80287).

ATFLOAT.COD, which is specified in the msc command, is a file in which the compiler places the assembly language instructions for the code that it produces. This file can be examined to see the floating-point instructions that are generated.

ATFLOAT will produce accurate results when run on both AT-compatible and PC-compatible computers. **ATDISK.** ATDISK returns the characteristics of the computer's hard disks and measures two types of disk performance: one uses BIOS calls to isolate and time low-level disk operations; the other measures disk performance during normal system operations by using DOS function requests to perform standard file I/O. ATDISK is written in Microsoft C (listing 6), with assembly language subroutines listed in the file called PDISKIO.ASM (listing 7).

To measure the time that is required to perform the operations in this program, ATDISK uses the clock count maintained by the BIOS in a four-byte area of RAM beginning at absolute location 46CH. With each clock tick (approximately 18.2 times per second), the BIOS increments the value in this four-

byte RAM area. The assembly language subroutine a_tick reads this data area before and after a test. The difference between the two values is the number of clock ticks that have occurred during a test. ATDISK then converts this number to elapsed time.

ATDISK's first type of performance check, determining the low-level performance characteristics of the disk (including how many disk drives are connected to the computer), uses the disk services of BIOS interrupt 13H. The subroutine disk_io is used to invoke these services three times, with the function request number being the first parameter of the subroutine:

- BIOS disk function request 8 (get current drive parameters) determines the size of the disk and the number of sectors, heads, and cylinders.
- Function request 12 (the BIOS seek function) measures the track-to-track seek time. The program seeks from sector 1, head 0, cylinder 0 to sector 1, head 0, cylinder 1 and back again. Therefore, it seeks between two adjacent tracks 500 times, for a total of 1,000 seek operations.
- The third measurement calculates the average seek time. This test measures the time taken to seek to 1,000 random locations on the disk. It divides the total seek time by the number of seeks to obtain the average seek time.

ATDISK's second performance check calculates the effective disk-transfer rate, which is the speed at which data can be transferred to or from a formatted disk. (This is different from the absolute disk-transfer rate, which is how fast a stream of bits can be transferred from the read/write head to the media or vice versa. The effective transfer rate includes the effects of disk formatting—that is, the interruption of data flow due to sectoring and interleaving. This is the rate that would occur during normal system operation.)

ATDISK measures the effective transfer rate by using the BIOS read sectors service (function 2 of interrupt 13) to read track 0 a total of 1,000 times. The rate is calculated by dividing the number of kilobytes read by the time taken to read that information.

Measuring the effective transfer rate of the disk allows the interleave value of the hard disk to be determined. The interleave is a measure of the spacing of logical, as opposed to physical, sectors on the disk.

Each disk is divided into a number of equal-sized sectors (usually 17 on an XT or AT hard disk), which are numbered sequentially from 1 to 17. These

are the *physical* sector numbers. The computer does not necessarily access the sectors in sequence, however. For example, if the computer writes a block of data that is longer than a sector, it might put the first sector of data in physical sector 1, skip sector 2, and put the next part of the data block in physical sector 3. The order in which the physical sectors are accessed to read or write sequential data is the *logical* numbering of the sectors.


The interleave value, then, is the distance, in sectors, between two logical sectors. An interleave of 1 means that logical sectors are next to each other (in other words, logical and physical sector numbering is the same). An interleave of 2 means that there is a sector between two sequential logical sectors. An interleave of 3 means that two sectors occur between logical sectors. Figure 1 shows the logical sector numbering of a disk set up with an interleave value of 2; figure 2 shows an interleave value of 3.

The interleave value is important for overall disk performance. The disk is always spinning, so if the computer needs to access a sector that is not directly under the disk's read/write head, it must wait until that part of the disk moves around under the head again. With a judicious choice of interleave, the time required by the computer between sector accesses (either to dispose of the information it just read or to prepare the next information to write) is the same as the time required to spin the next logical sector under the read/write head.

An interleave value that is too large can hurt performance because the computer will be forced to wait longer for the appropriate sector to move under the head. Likewise, when the interleave value is too small, the sector will have passed under the read/write head before the computer is ready, causing the computer to wait almost a complete revolution until the sector moves under the head again.


Although practically any interleave value can be selected for any disk drive, the optimum choice really depends on the speed of the processor and the performance of the drive. A higher-performance computer will tend to have a smaller optimum interleave than a lower-performance computer, and the smaller interleave will mean increased throughput. However, the way in which a disk controller manages the drive (and the data coming from or going to the drive) also can have a major effect on I/O performance. Therefore, a com-

FIGURE 1: Interleave Value of 2



When a disk has an interleave of 2, a logical sector is two physical sectors from the next logical sector. Logical sectors are numbered in the order they are accessed. Generally, a higher-performance computer has a smaller optimum interleave.

FIGURE 2: Interleave Value of 3



A disk with an interleave of 3 is not necessarily slower than one with an interleave of 2 because the optimum choice depends on the speed of the processor and the performance of the drive. If the value is too high or too low, the disk has to wait a long time before the next sector is moved under the head.

puter with an optimum interleave of 2 might not always exhibit better disk performance than a computer that has an optimum interleave of 3.

The hard disks on both the 6- and 8-MHz ATs use a default interleave value of 3. ATDISK's measurement of the effective disk-transfer rate enables the interleave of each AT-compatible computer to be determined empirically. This is accomplished by first running the ATDISK program when the hard disk is formatted for the default interleave, then rerunning the program after the hard disk has been reformatted for specific interleave values (such as 1, 2, and 3). Because the interleave affects the performance of I/O operations, the values for the DOS disk test will be different each time the interleave is changed. The default value can be determined by comparing the first result with the results of all the later tests.

ATDISK measures the performance of disk operations that occur during normal day-to-day activities by accessing the hard disk via DOS function requests. This test has two phases. During the first phase, ATDISK creates a file, writes 20KB of information to the file in 2KB increments, and closes the file. It creates and fills 10 different files in this manner. The files are given the names

ATDISK.~n, where *n* is a number between 0 and 9. During the second phase, the test reopens each file, reads the entire file in 2KB increments, and deletes the file. The test displays the time required to perform both phases.

The system performance measured by this final ATDISK test will vary significantly according to the number of I/O buffers used and where on the disk the test files are located. To allow meaningful comparisons to be made among various computers, the test will be run with the default number of I/O buffers (no BUFFERS= statement will be included in the CONFIG.SYS file) and a freshly formatted hard disk.

To activate this disk system performance test, which actually creates and deletes files on the hard disk, command line ATDISK -d should be used instead of just ATDISK. This ensures that if the hard disk already contains files called ATDISK.~n, those files will not be deleted accidentally.

The Microsoft C compiler and assembler are used to produce the object code of the ATDISK program. Assuming that ATDISK.C contains the C source code and PDISKIO.ASM contains the assembly language source code, the following commands can be used to compile and link the program:

```
msc atdisk.c;
masm pdiskio.asm/r;;
link atdisk + pdiskio,;
slibfp.lib + slibc.lib + em.lib;
```

Although ATDISK was written expressly to test AT-compatible computers, it does not include any AT-specific code. It will run on any AT- or XT-compatible computer.

UPCOMING REVIEWS

A review of the Compaq Deskpro 286, which follows this introduction on p. 80, inaugurates this series on AT compatibles. Future articles will examine other compatibles that *PC Tech Journal* considers significant. This series will provide the facts needed to choose an AT-compatible computer based on performance and compatibility. It will give insight to those pleasant extras and unfortunate design mistakes that can characterize these AT clones.



Steven Armbrust is a freelance technical writer. Ted Forgeron works for Intel Scientific Computers as a software project manager. They recently completed writing the Programmer's Reference Manual for IBM Personal Computers, to be published by Dow Jones-Irwin in October 1986. Paul Pierce is a microcomputer software consultant who also collects and repairs old mainframe computers in his spare time.

LISTING 1: ATBIOS.PAS

```
< ATBIOS -- PC Tech Journal AT BIOS Information Display Program >
< Version 1.00 >
< Last modified 05/23/86 >
< Copyright (c) 1986, PC Tech Journal >
< Program by: Paul Pierce, Ted Forgeron, Steven Armbrust >
< Displays pertinent information from the BIOS code and data >
< areas. >
< This program is written in Turbo Pascal. However, it can >
< be easily ported to any Pascal compiler that allows absolute >
< addressing. >

PROGRAM at_bios_info ;
CONST
  at_id = $fc ;
  printer_mask = $c000 ;
  game_mask = $1000 ;
  serial_mask = $0e00 ;
  dma_mask = $0100 ;
  drive_num_mask = $00c0 ;
  video_mask = $0030 ;
  ndp_mask = $0002 ;
  drive_mask = $0001 ;
  co40 = $0010 ;
  co80 = $0020 ;
  mono = $0030 ;
VAR
  i : integer ;
  romdate : ARRAY [1..9] OF char absolute $f000:$fff5 ;
  machine_id : byte absolute $f000:$fffe ;
  copyright : ARRAY [1..80] OF char absolute $f000:$e000 ;
  equip_flag : integer absolute $40:$10 ;
  mem_size : integer absolute $40:$13 ;
  key_buf : ARRAY [1..32] OF char absolute $40:$1e ;
  video_mode : byte absolute $40:$49 ;
BEGIN
  clrscr;
```

```
write('ATBIOS -- PC Tech Journal AT BIOS Information ');
writeln('Display');
writeln('Version 1.00, Copyright (c) 1986 PC Tech Journal');
writeln;
writeln('ROM BIOS date is ',romdate);
IF machine_id = at_id THEN
  writeln('Machine ID is AT COMPATIBLE')
ELSE
  writeln('Machine ID is NOT AT');
write('Copyright Statement is ');
window(40,6,80,7);
gotoxy(1,1);
write(copyright);
window(1,1,80,25);
gotoxy(1,8);
write('Diskette Drives Installed ');
if (equip_flag and drive_mask) <> 0
then writeln(((drive_num_mask and equip_flag) div 64) + 1)
else writeln('0');
write('80287 Math Coprocessor ');
if (equip_flag and ndp_mask) <> 0
then writeln('YES')
else writeln('NO');
write('Initial Video Mode ');
case (equip_flag and video_mask) of
  co40: writeln('CGA 40x25 B/W text');
  co80: writeln('CGA 80x25 B/W text');
  mono: writeln('Monochrome 80x25 text');
end;
write('Current Video Mode ');
case video_mode of
  00: writeln('CGA 40x25 B/W text');
  01: writeln('CGA 40x25 16-color text');
  02: writeln('CGA 80x25 B/W text');
  03: writeln('CGA 80x25 16-color text');
  04: writeln('CGA 320x200 4-color graphics');
  05: writeln('CGA 320x200 4-gray graphics');
```



```

06: writeln('CGA 640x200 B/W graphics');
07: writeln('Monochrome 80x25 text');
08: writeln('JR 160x200 16-color graphics');
09: writeln('JR 320x200 16-color graphics');
10: writeln('EGA 640x200 4/64-color graphics');
13: writeln('EGA 320x200 16-color graphics');
14: writeln('EGA 640x200 16-color graphics');
15: writeln('EGA 640x350 4-color graphics');
end;
write('DMA Present      ');
if (equip_flag and dma_mask) <> 0
then writeln('NO');
else writeln('YES');
writeln('RS-232 Serial Ports      ',
      (equip_flag and serial_mask) div 512);
write('Game Adapter Present      ');
if (equip_flag and game_mask) <> 0
then writeln('YES');
else writeln('NO');
writeln('Parallel Printer Ports      ',
      abs((equip_flag and printer_mask) div 16384));
writeln('Memory Size in K Bytes      ',mem_size);
write('Keyboard Buffer Contents      ');
i := 1;
while i <= 32 do
begin
  if (key_buf[i] < '!') or (key_buf > '>') then
    write('.');
  else write(key_buf[i]);
  i := i + 2;
end;
writeln;
END.

```

LISTING 2: ATKEY.ASM

```

; ATKEY -- PC Tech Journal AT Keyboard Compatibility Test
; Version 1.00
; Last modified 05/23/86
; Copyright (c) 1986, PC Tech Journal
; Program by: Paul Pierce, Ted Forgeron, Steven Armbrust
; Checks for AT keyboard compatibility by trying to speed
; the keyboard typematic rate to 30 reps per second and a
; keyboard delay of 1/4 second.
; See AT Technical Reference Manual pages 4-5 thru 4-8 for
; more information on programming the AT keyboard.

code segment public

assume cs:code,ds:code

org 100h ;set up as a COM file
start: jmp begin

msg db 0dh,0ah
db 'ATKEY -- PC Tech Journal AT Keyboard Compatibility '
db 'Test',0dh,0ah
db 'Version 1.00, Copyright (c) 1986 PC Tech Journal',
db 0dh,0ah,0ah,'$'
badmsg db 'Keyboard is incompatible with IBM PC/AT keyboard',
db 0dh,0ah,'$'
goodmsg db 'Keyboard is compatible with IBM PC/AT keyboard',
db 0dh,0ah,0dh,0ah
db 'Keyboard will now repeat at 30 characters per second',
db 0dh,0ah,'with 1/4 second delay.',0dh,0ah,'$'

begin: mov ax,cs ;set up ds
mov ds,ax ;to same seg as cs
mov dx,offset msg ;print msg on screen
mov ah,09h ;dos print string funct
int 21h ;call dos
mov al,0f3h ;typematic rate cmd
mov dx,60h ;8042 scan/diag port
mov cx,2000 ;ack retry count
out dx,al ;send command to 8042
ack: in al,60h ;in from 8042
dec cx ;decrement retry count
jnz cont ;try again
mov dx,offset badmsg ;print msg on screen
mov ah,09h ;dos print string funct

```

```

int 21h ;call dos
jmp done ;give up and terminate
cont: cmp al,0fah ;is it an ack?
jne ack ;no, try again
mov al,0 ;set rate to code for 30
out dx,al ;output command to 8042
mov dx,offset goodmsg ;print msg on screen
mov ah,09h ;dos print string funct
int 21h ;call dos
done: mov ah,4ch ;dos terminate process
int 21h ;call dos
code ends ;end of code segment
end start ;start is the entry point

```

LISTING 3: ATPERF.C

```

/*
 * ATPERF -- PC Tech Journal AT Hardware Performance Test
 * Version 1.00
 * Last modified 05/17/86
 * Copyright (c) 1986, PC Tech Journal
 * Program by: Paul Pierce, Ted Forgeron, Steven Armbrust
 * Measures clock rates and memory speeds
 * of AT compatible computers.
 */

#define vars 14

/* Timer rate in MHz */
#define TIMER2_RATE 1.193180
/* Number of processor clocks in a multiply instruction */
#define MULCLKS 21
/* Overhead in the multiply test */
#define MULOVRH ( 15 + 14*count/100 )
/* Overhead in the mov instruction test */
#define MOVVRH ( clktime * (15 + 14*count/100) )
/* Overhead in the stringop tests */
#define STROVRH ( clktime * 8 )
/* Number of numeric processor clocks in a FP divide */
#define FPCLKS 203
/* Processor overhead in the FP divide test */
#define FPOVRH ( clktime * 9 * FPCOUNT )
/* Count for most tests */
#define COUNT 1000
/* Count for the f. p. divide test */
#define FPCOUNT 100
/* Number of trials for each test */
#define TRIALS 100

double clkrate; /* Processor clock rate, MHz */
double clktime; /* Processor clock period, usec */
double fprate; /* FP processor clock rate, MHz */
double fpacc; /* FP processor clock period accumulator */
int emmok; /* Set if extended memory is present */
int ndpok; /* Set if math coprocessor is present */

/*
 * Main program.
 */
main(argc, argv)
int argc;
char **argv;
{
  double raw, brw, wrw; /* Variables for raw data */
  double acctime[vars]; /* Accumulators for speeds */
  int count; /* Number of ops per trial */
  int trials; /* Number of repetitions */
  register int i;

  count = COUNT;
  trials = TRIALS;
  /*
   * Measure the clock rate by executing
   * multiply instructions. Each multiply
   * takes a fixed number of clock cycles.
   */
  clktime = 0;
  for (i = 0; i < trials; i++) {
    /*
     * Obtain the number of clock ticks for
     * "count" multiplies.
     */
    raw = multime(count);
  }
}

```



```
acctime[1] += raw/(TIMER2_RATE*count);
raw = wrmtime(count) * wrw;
acctime[5] += raw/(TIMER2_RATE*count);
/*
 * If EMM is present, do measurements
 * on it using the same techniques.
 */
if (emmok) {
    /*
     * Measure byte write,
     * calculate byte read.
     */
        brw = bemstime(count);
        acctime[12] += brw/(TIMER2_RATE*count);
        raw = bemtime(count) * brw;
        acctime[10] += raw/(TIMER2_RATE*count);
    /*
     * Measure word write,
     * calculate word read.
     */
        wrw = wemstime(count);
        acctime[13] += raw/(TIMER2_RATE*count);
        raw = wemtime(count) * wrw;
        acctime[11] += raw/(TIMER2_RATE*count);
}
/*
 * Measure byte and word writes
 * into video RAM (assuming CGA adapter.)
 */
raw = bvidtime(count);
acctime[6] += raw/(TIMER2_RATE*count);
raw = wvidtime(count);
acctime[7] += raw/(TIMER2_RATE*count);
}
/*
 * Calculate averages for all measurements.
 */
for (i = 0; i < vars; i++)
    acctime[i] /= trials;
/*
 * Release EMM memory page.
 */
if (emmok)
    finish_emm();
/*
 * Calculate numeric processor clock
 * rate using floating point divide
 * instructions, using the same
 * technique as was used to measure
 * the processor clock rate.
 */
if (ndpok) {
    fprate = 0;
    for (i = 0; i < trials; i++) {
        raw = fptime(FPCOUNT);
        fpacc += (raw / TIMER2_RATE - FPOVH) /
            FPCCLKS / FPCOUNT;
    }
    fpacc /= trials;
    fprate = 1.0/fpacc;
}
/*
 * Display the basic measurement results and
 * performance index relative to a 6 MHz AT.
 */
printf("\n\n\n\n\n\n\n\n\n\n\n\n\n\n\n\n\n\n\n\n\n\n");
printf("ATPERF -- PC Tech Journal AT Hardware ");
printf("Performance Test\n");
printf("Version 1.00, Copyright (c) 1986 PC Tech ");
printf("Journal\n");
printf("IBM PC/AT model 339 (8 MHz) = 1.00 for relative ");
printf("measurements.\n\n");
printf("Byte Word Relative\n");
printf("Average RAM instr. fetch: ");
printf(" ");
printf("%10.3g uS", acctime[8]);
printf("%10.2g\n", 0.403/acctime[8]);
printf("Average RAM read time: ");
printf("%10.3g uS ", acctime[9]);
```



```

printf("%10.3g uS", acctime[1]);
printf("%10.2g\n", 0.401/acctime[1]);

printf("Average RAM write time:  ");
printf("%10.3g uS  ", acctime[2]);
printf("%10.3g uS", acctime[3]);
printf("%10.2g\n", 0.401/acctime[3]);

if (emmok) {
    printf("Average EMM read time:  ");
    printf("%10.3g uS  ", acctime[10]);
    printf("%10.3g uS", acctime[11]);
    printf("%10.2g\n", 0.402/acctime[11]);

    printf("Average EMM write time:  ");
    printf("%10.3g uS  ", acctime[12]);
    printf("%10.3g uS", acctime[13]);
    printf("%10.2g\n", 0.402/acctime[13]);
}

printf("Average ROM read time:  ");
printf("%10.3g uS  ", acctime[4]);
printf("%10.3g uS", acctime[5]);
printf("%10.2g\n", 0.401/acctime[5]);

printf("Average Video write time:  ");
printf("%10.3g uS  ", acctime[6]);
printf("%10.3g uS", acctime[7]);
printf("%10.2g\n", 2.415/acctime[7]);

printf("\nClock rate:  ");
printf("%4.1g MHz", clkrate);
printf(" Relative: %4.2g\n", clkrate/8.0);

if (ndpok) {
    printf("Numeric processor clock rate: ");
    printf("%4.1g MHz", fprate);
    printf(" Relative: %4.2g\n", fprate/5.33);
}

/*
 * Calculate refresh overhead from instruction
 * fetch time by assuming that each fetch takes
 * an exact multiple of the clock period. The
 * difference between average time and the time
 * for an individual fetch is due to memory
 * refresh cycles.
 */
raw = acctime[0] / clktime;
printf("Refresh overhead:  %2.1g%%\n",
       ((raw - (int)raw) / (int)raw) * 100);

/*
 * Print information about the memory based
 * on the speed measurements.
 */
printf("\nMemory  ");
printf(" Access width      Wait states\n");
analyze("RAM read", acctime[0], acctime[1]);
analyze("RAM write", acctime[2], acctime[3]);
if (emmok) {
    analyze("EMM read", acctime[10], acctime[11]);
    analyze("EMM write", acctime[12], acctime[13]);
}
analyze("ROM read", acctime[4], acctime[5]);
analyze("Video write", acctime[6], acctime[7]);
}

/*
 * analyze
 * This procedure deduces information about the memory based on
 * the measured times.
 * If byte (8 bits) and word (16 bits) times are different then
 * the memory is byte oriented since each word operation takes
 * two byte operations. Otherwise, if the byte and word
 * times are about the same, the memory is word oriented and can
 * access either a word or a byte in a single memory cycle.
 *
 * Each memory access takes an exact number of processor clock
 * cycles. The first two are required by the processor, but
 * any additional cycles are determined by the memory and are
 * called wait states (because the processor is waiting for
 * the memory.)
 */

```

```

analyze(name, btime, wtime)
char    *name;
double  btime;
double  wtime;

{
    /*
     * Print the heading
     */
    printf("%-12s", name);
    /*
     * Determine whether the memory is byte
     * oriented, word oriented, or neither.
     * (If neither, the data are suspect.)
     */
    if (btime > wtime*0.75 &&
        btime < wtime*1.25)
        printf("      Word ");
    else if (btime*2 > wtime*0.75 &&
             btime*2 < wtime*1.25)
        printf("      Byte ");
    else
        printf("      Strange");

    /*
     * Determine the number of wait states
     * by subtracting two processor clock times,
     * dividing by the clock period,
     * and rounding down to an integer.
     */
    printf("          %6.0f\n",
           (btime - 2*clktime) / clktime);
}

```

LISTING 4: TIME.ASM

```

NAME      TIME

_TEXT     SEGMENT BYTE PUBLIC 'CODE'
_TEXT     ENDS
CONST     SEGMENT WORD PUBLIC 'CONST'
CONST     ENDS
_BSS      SEGMENT WORD PUBLIC 'BSS'
_BSS      ENDS
_DATA     SEGMENT WORD PUBLIC 'DATA'
_DATA     ENDS
DGROUP    GROUP CONST, _BSS, _DATA
          ASSUME CS: _TEXT, DS: DGROUP, SS: DGROUP

TESTSEG   SEGMENT WORD PUBLIC 'TEST'

TESTSEG_START  DW      32767 DUP (?)

TESTSEG ENDS

PPI_PORT      EQU     061H
TIMER2_PORT   EQU     042H
TIMER_CTRL    EQU     043H

_DATA         SEGMENT

EMMBASE       DW      9000H
PID           DW      ?
EMM_NAME      DB      "EMMXXXXD"

_DATA         ENDS

_TEXT         SEGMENT

;*****
;
;      _MULTIME
;      TIME EXECUTION OF MULTIPLY INSTRUCTIONS
;
;*****
;*****
;*****

PUBLIC _MULTIME
_MULTIME     PROC     NEAR

    PUSH     BP                ; SAVE FRAME
    MOV      BP, SP           ;
    PUSH     DI                ; SAVE DI
    CALL     SETUP_TIMER      ; SET UP TIMER

```



```

MOV  DI, 0          ; CLEAR DI
MOV  AX, [BP+4]     ; GET COUNT ARGUMENT
ADD  AX, 99         ; ROUND UP
MOV  CX, 100        ; DIVIDE BY 100 =
DIV  CL             ; NUMBER OF INSTRUCTIONS
MOV  CL, AL         ; PER PASS
IN   AL, PPI_PORT   ; GET CURRENT CONTROL
MOV  BL, AL         ; SAVE IN BL
OR   AX, 1          ; SET TIMER ENABLE BIT
CLI                     ; STOP INTERRUPTS
OUT  PPI_PORT, AL   ; ENABLE TIMER
ML:  MUL  DI         ; DO 100 MULTIPLIES
    ...

```

<<<<The above line is repeated a total of 99 times>>>>

```

DEC  CX             ; COUNT THIS PASS
JZ   MD             ; JUMP IF COMPLETE
JMP  ML             ; LOOP BACK IF NOT DONE
MD:  MOV  AL, BL     ; RESTORE CONTROL VALUE
    OUT  PPI_PORT, AL
    STI                     ; START INTERRUPTS
    CALL GET_TIMER        ; OBTAIN FINAL COUNT
    POP  DI             ; RESTORE DI
    POP  BP             ; RESTORE BP
    RET                  ; RETURN

```

_MULTIME ENDP

```

;*****
;
;  _WMOVTIME
;  TIME EXECUTION OF MOV INSTRUCTION (INSTR. READ TIME)
;
;*****

```

```

PUBLIC _WMOVTIME
_WMOVTIME PROC NEAR

```

```

PUSH  BP          ; SAVE FRAME
MOV  BP, SP
PUSH  DI          ; SAVE DI
CALL  SETUP_TIMER ; SET UP TIMER
MOV  DI, 0        ; CLEAR DI
MOV  AX, [BP+4]   ; GET COUNT ARGUMENT
ADD  AX, 99       ; ROUND UP
MOV  CX, 100      ; DIVIDE BY 100 =
DIV  CL           ; NUMBER OF INSTRUCTIONS
MOV  CL, AL       ; PER PASS
IN   AL, PPI_PORT ; GET CURRENT CONTROL
MOV  BL, AL       ; SAVE IN BL
OR   AX, 1        ; SET TIMER ENABLE BIT
CLI                     ; STOP INTERRUPTS
OUT  PPI_PORT, AL  ; ENABLE TIMER
IL:  MOV  DX, BX   ; DO 100 MULTIPLIES
    ...

```

<<<<The above line is repeated a total of 99 times>>>>

```

DEC  CX             ; COUNT THIS PASS
JZ   ID             ; JUMP IF COMPLETE
JMP  IL             ; LOOP BACK IF NOT DONE
ID:  MOV  AL, BL     ; RESTORE CONTROL VALUE
    OUT  PPI_PORT, AL
    STI                     ; START INTERRUPTS
    CALL GET_TIMER        ; OBTAIN FINAL COUNT
    POP  DI             ; RESTORE DI
    POP  BP             ; RESTORE BP
    RET                  ; RETURN

```

_WMOVTIME ENDP

```

;*****
;
;  _BMVTIME
;  TIME EXECUTION OF REP MOVSB INSTRUCTION
;
;*****

```

```

PUBLIC _BMVTIME
_BMVTIME PROC NEAR

```

```

PUSH  BP          ; SAVE FRAME
MOV  BP, SP
PUSH  DS          ; SAVE DS
PUSH  ES          ; SAVE ES
PUSH  SI          ; SAVE SI
PUSH  DI          ; SAVE DI
CALL  SETUP_TIMER ; SET UP TIMER
MOV  DI, TESTSEG  ;
MOV  ES, DI
MOV  DS, DI
LEA  SI, TESTSEG_START ; DS:SI -> TEST SEGMENT
LEA  DI, TESTSEG_START ; ES:DI -> TEST SEGMENT
MOV  CX, [BP+4]     ; GET COUNT ARGUMENT
IN   AL, PPI_PORT   ; GET CURRENT CONTROL
MOV  BL, AL         ; SAVE IN BL
OR   AX, 1          ; SET TIMER ENABLE BIT
CLI                     ; STOP INTERRUPTS
CLD                     ; SET FORWARD DIRECTION
OUT  PPI_PORT, AL   ; ENABLE TIMER
REP  MOVSB          ; RUN TEST
MOV  AL, BL         ; RESTORE CONTROL VALUE
OUT  PPI_PORT, AL   ;
STI                     ; START INTERRUPTS
CALL  GET_TIMER      ; OBTAIN FINAL COUNT
POP  DI             ; RESTORE DI
POP  SI             ; RESTORE SI
POP  ES             ; RESTORE ES
POP  DS             ; RESTORE DS
POP  BP             ; RESTORE BP
RET                  ; RETURN

```

_BMVTIME ENDP

```

;*****
;
;  _LMVTIME
;  TIME EXECUTION OF REP MOVSW INSTRUCTION
;
;*****

```

```

PUBLIC _LMVTIME
_LMVTIME PROC NEAR

```

```

PUSH  BP          ; SAVE FRAME
MOV  BP, SP
PUSH  DS          ; SAVE DS
PUSH  ES          ; SAVE ES
PUSH  SI          ; SAVE SI
PUSH  DI          ; SAVE DI
CALL  SETUP_TIMER ; SET UP TIMER
MOV  DI, TESTSEG  ;
MOV  ES, DI
MOV  DS, DI
LEA  SI, TESTSEG_START ; DS:SI -> TEST SEGMENT
LEA  DI, TESTSEG_START ; ES:DI -> TEST SEGMENT
MOV  CX, [BP+4]     ; GET COUNT ARGUMENT
IN   AL, PPI_PORT   ; GET CURRENT CONTROL
MOV  BL, AL         ; SAVE IN BL
OR   AX, 1          ; SET TIMER ENABLE BIT
CLI                     ; STOP INTERRUPTS
CLD                     ; SET FORWARD DIRECTION
OUT  PPI_PORT, AL   ; ENABLE TIMER
REP  MOVSW          ; RUN TEST
MOV  AL, BL         ; RESTORE CONTROL VALUE
OUT  PPI_PORT, AL   ;
STI                     ; START INTERRUPTS
CALL  GET_TIMER      ; OBTAIN FINAL COUNT
POP  DI             ; RESTORE DI
POP  SI             ; RESTORE SI
POP  ES             ; RESTORE ES
POP  DS             ; RESTORE DS
POP  BP             ; RESTORE BP
RET                  ; RETURN

```

_LMVTIME ENDP

```

;*****
;
;  _BROMTIME
;  TIME EXECUTION OF REP MOVSB INSTRUCTION FROM ROM
;
;*****

```



```

PUBLIC _BROMTIME
_BROMTIME PROC NEAR

    PUSH BP                ; SAVE FRAME
    MOV BP, SP             ;
    PUSH DS                ; SAVE DS
    PUSH ES                ; SAVE ES
    PUSH SI                ; SAVE SI
    PUSH DI                ; SAVE DI
    CALL SETUP_TIMER       ; SET UP TIMER
    MOV DI, TESTSEG        ;
    MOV ES, DI             ;
    MOV DI, 0F000H         ; SET DS TO ROM START
    MOV DS, DI             ;
    MOV SI, 0              ; DS:SI -> ROM
    LEA DI, TESTSEG_START  ; ES:DI -> TEST SEGMENT
    MOV CX, [BP+4]         ; GET COUNT ARGUMENT
    IN AL, PPI_PORT        ; GET CURRENT CONTROL
    MOV BL, AL             ; SAVE IN BL
    OR AX, 1               ; SET TIMER ENABLE BIT
    CLI                    ; STOP INTERRUPTS
    CLD                    ; SET FORWARD DIRECTION
    OUT PPI_PORT, AL       ; ENABLE TIMER
    REP MOVSB              ; RUN TEST
    MOV AL, BL             ; RESTORE CONTROL VALUE
    OUT PPI_PORT, AL       ;
    STI                    ; START INTERRUPTS
    CALL GET_TIMER         ; OBTAIN FINAL COUNT
    POP DI                 ; RESTORE DI
    POP SI                 ; RESTORE SI
    POP ES                 ; RESTORE ES
    POP DS                 ; RESTORE DS
    POP BP                 ; RESTORE BP
    RET                    ; RETURN

```

_BROMTIME ENDP

```

;*****
;
; _WROMTIME
; TIME EXECUTION OF REP MOVSW INSTRUCTION FROM ROM
;
;*****

```

```

PUBLIC _WROMTIME
_WROMTIME PROC NEAR

    PUSH BP                ; SAVE FRAME
    MOV BP, SP             ;
    PUSH DS                ; SAVE DS
    PUSH ES                ; SAVE ES
    PUSH SI                ; SAVE SI
    PUSH DI                ; SAVE DI
    CALL SETUP_TIMER       ; SET UP TIMER
    MOV DI, TESTSEG        ;
    MOV ES, DI             ;
    MOV DI, 0F000H         ; SET DS TO ROM START
    MOV DS, DI             ;
    MOV SI, 0              ; DS:SI -> ROM
    LEA DI, TESTSEG_START  ; ES:DI -> TEST SEGMENT
    MOV CX, [BP+4]         ; GET COUNT ARGUMENT
    IN AL, PPI_PORT        ; GET CURRENT CONTROL
    MOV BL, AL             ; SAVE IN BL
    OR AX, 1               ; SET TIMER ENABLE BIT
    CLI                    ; STOP INTERRUPTS
    CLD                    ; SET FORWARD DIRECTION
    OUT PPI_PORT, AL       ; ENABLE TIMER
    REP MOVSW              ; RUN TEST
    MOV AL, BL             ; RESTORE CONTROL VALUE
    OUT PPI_PORT, AL       ;
    STI                    ; START INTERRUPTS
    CALL GET_TIMER         ; OBTAIN FINAL COUNT
    POP DI                 ; RESTORE DI
    POP SI                 ; RESTORE SI
    POP ES                 ; RESTORE ES
    POP DS                 ; RESTORE DS
    POP BP                 ; RESTORE BP
    RET                    ; RETURN

```

_WROMTIME ENDP

```

;*****
;
; _BSTOTIME
; TIME EXECUTION OF REP STOSB INSTRUCTION
;
;*****

```

```

PUBLIC _BSTOTIME
_BSTOTIME PROC NEAR

    PUSH BP                ; SAVE FRAME
    MOV BP, SP             ;
    PUSH ES                ; SAVE ES
    PUSH DI                ; SAVE DI
    CALL SETUP_TIMER       ; SET UP TIMER
    MOV DI, TESTSEG        ;
    MOV ES, DI             ;
    LEA DI, TESTSEG_START  ; ES:DI -> TEST SEGMENT
    MOV CX, [BP+4]         ; GET COUNT ARGUMENT
    IN AL, PPI_PORT        ; GET CURRENT CONTROL
    MOV BL, AL             ; SAVE IN BL
    OR AX, 1               ; SET TIMER ENABLE BIT
    CLI                    ; STOP INTERRUPTS
    CLD                    ; SET FORWARD DIRECTION
    OUT PPI_PORT, AL       ; ENABLE TIMER
    REP STOSB              ; RUN TEST
    MOV AL, BL             ; RESTORE CONTROL VALUE
    OUT PPI_PORT, AL       ;
    STI                    ; START INTERRUPTS
    CALL GET_TIMER         ; OBTAIN FINAL COUNT
    POP DI                 ; RESTORE DI
    POP ES                 ; RESTORE ES
    POP BP                 ; RESTORE BP
    RET                    ; RETURN

```

_BSTOTIME ENDP

```

;*****
;
; _WSTOTIME
; TIME EXECUTION OF REP STOSW INSTRUCTION
;
;*****

```

```

PUBLIC _WSTOTIME
_WSTOTIME PROC NEAR

    PUSH BP                ; SAVE FRAME
    MOV BP, SP             ;
    PUSH ES                ; SAVE ES
    PUSH DI                ; SAVE DI
    CALL SETUP_TIMER       ; SET UP TIMER
    MOV DI, TESTSEG        ;
    MOV ES, DI             ;
    LEA DI, TESTSEG_START  ; ES:DI -> TEST SEGMENT
    MOV CX, [BP+4]         ; GET COUNT ARGUMENT
    IN AL, PPI_PORT        ; GET CURRENT CONTROL
    MOV BL, AL             ; SAVE IN BL
    OR AX, 1               ; SET TIMER ENABLE BIT
    CLI                    ; STOP INTERRUPTS
    CLD                    ; SET FORWARD DIRECTION
    OUT PPI_PORT, AL       ; ENABLE TIMER
    REP STOSW              ; RUN TEST
    MOV AL, BL             ; RESTORE CONTROL VALUE
    OUT PPI_PORT, AL       ;
    STI                    ; START INTERRUPTS
    CALL GET_TIMER         ; OBTAIN FINAL COUNT
    POP DI                 ; RESTORE DI
    POP ES                 ; RESTORE ES
    POP BP                 ; RESTORE BP
    RET                    ; RETURN

```

_WSTOTIME ENDP

```

;*****
;
; _BVIDTIME
; TIME EXECUTION OF REP STOSB INTO VIDEO MEMORY
;
;*****

```

PUBLIC _BVIDTIME


```

_BVIDTIME    PROC    NEAR

    PUSH    BP                ; SAVE FRAME
    MOV     BP, SP            ;
    PUSH    ES                ; SAVE ES
    PUSH    DI                ; SAVE DI
    CALL    SETUP_TIMER       ; SET UP TIMER
    MOV     DI, 0B800H        ;
    MOV     ES, DI            ;
    MOV     DI, 0              ; ES:DI -> VIDEO MEMORY
    MOV     CX, [BP+4]         ; GET COUNT ARGUMENT
    IN      AL, PPI_PORT       ; GET CURRENT CONTROL
    MOV     BL, AL             ; SAVE IN BL
    OR      AX, 1              ; SET TIMER ENABLE BIT
    CLI                     ; STOP INTERRUPTS
    CLD                     ; SET FORWARD DIRECTION
    OUT     PPI_PORT, AL       ; ENABLE TIMER
    REP     STOSB              ; RUN TEST
    MOV     AL, BL             ; RESTORE CONTROL VALUE
    OUT     PPI_PORT, AL       ;
    STI                     ; START INTERRUPTS
    CALL    GET_TIMER          ; OBTAIN FINAL COUNT
    POP     DI                 ; RESTORE DI
    POP     ES                 ; RESTORE ES
    POP     BP                 ; RESTORE BP
    RET                      ; RETURN

```

```
_BVIDTIME    ENDP
```

```

;*****
;
;    _WVIDTIME
;    TIME EXECUTION OF REP STOSW INTO VIDEO MEMORY
;
;*****

```

```

PUBLIC _WVIDTIME
_WVIDTIME    PROC    NEAR

    PUSH    BP                ; SAVE FRAME
    MOV     BP, SP            ;
    PUSH    ES                ; SAVE ES
    PUSH    DI                ; SAVE DI
    CALL    SETUP_TIMER       ; SET UP TIMER
    MOV     DI, 0B800H        ;
    MOV     ES, DI            ;
    MOV     DI, 0              ; ES:DI -> VIDEO MEMORY
    MOV     CX, [BP+4]         ; GET COUNT ARGUMENT
    IN      AL, PPI_PORT       ; GET CURRENT CONTROL
    MOV     BL, AL             ; SAVE IN BL
    OR      AX, 1              ; SET TIMER ENABLE BIT
    CLI                     ; STOP INTERRUPTS
    CLD                     ; SET FORWARD DIRECTION
    OUT     PPI_PORT, AL       ; ENABLE TIMER
    REP     STOSW              ; RUN TEST
    MOV     AL, BL             ; RESTORE CONTROL VALUE
    OUT     PPI_PORT, AL       ;
    STI                     ; START INTERRUPTS
    CALL    GET_TIMER          ; OBTAIN FINAL COUNT
    POP     DI                 ; RESTORE DI
    POP     ES                 ; RESTORE ES
    POP     BP                 ; RESTORE BP
    RET                      ; RETURN

```

```
_WVIDTIME    ENDP
```

```

;*****
;
;    _FPTIME
;    TIME EXECUTION OF FLOATING POINT DIVIDE
;
;*****

```

```

PUBLIC _FPTIME
_FPTIME      PROC    NEAR

    PUSH    BP                ; SAVE FRAME
    MOV     BP, SP            ;
    PUSH    DI                ; SAVE DI
    CALL    SETUP_TIMER       ; SET UP TIMER

```

```

    MOV     DI, 0              ; CLEAR DI
    MOV     AX, [BP+4]         ; GET COUNT ARGUMENT
    ADD     AX, 99             ; ROUND UP
    MOV     CX, 100            ; DIVIDE BY 100 =
    DIV     CL                 ; NUMBER OF INSTRUCTIONS
    MOV     CL, AL             ; PER PASS
    IN      AL, PPI_PORT       ; GET CURRENT CONTROL
    MOV     BL, AL             ; SAVE IN BL
    OR      AX, 1              ; SET TIMER ENABLE BIT
    FNINIT                    ; INIT FP
    FLD1                     ; DIVIDE 1.0
    FLD1                     ; BY 1.0
    CLI                     ; STOP INTERRUPTS
    OUT     PPI_PORT, AL       ; ENABLE TIMER
FL:    FDIV     ST(1), ST       ; DO 100 DIVIDES
    FDIV     ST(1), ST         ;
    ...

```

```
<<<<The above line is repeated a total of 99 times>>>>
```

```

    DEC     CX                ; COUNT THIS PASS
    JZ      FD                ; JUMP IF COMPLETE
    JMP     FL                ; LOOP BACK IF NOT DONE
FD:    MOV     AL, BL          ; RESTORE CONTROL VALUE
    OUT     PPI_PORT, AL       ;
    STI                     ; START INTERRUPTS
    CALL    GET_TIMER          ; OBTAIN FINAL COUNT
    POP     DI                 ; RESTORE DI
    POP     BP                 ; RESTORE BP
    RET                      ; RETURN

```

```
_FPTIME      ENDP
```

```

;*****
;
;    _BEMSTIME
;    TIME EXECUTION OF REP STOSB INSTRUCTION
;
;*****

```

```

PUBLIC _BEMSTIME
_BEMSTIME    PROC    NEAR

    PUSH    BP                ; SAVE FRAME
    MOV     BP, SP            ;
    PUSH    ES                ; SAVE ES
    PUSH    DI                ; SAVE DI
    CALL    SETUP_TIMER       ; SET UP TIMER
    MOV     ES, EMMBASE        ; SET UP EMM BASE ADDRESS
    XOR     DI, DI             ; ES:DI -> TEST SEGMENT
    MOV     CX, [BP+4]         ; GET COUNT ARGUMENT
    IN      AL, PPI_PORT       ; GET CURRENT CONTROL
    MOV     BL, AL             ; SAVE IN BL
    OR      AX, 1              ; SET TIMER ENABLE BIT
    CLI                     ; STOP INTERRUPTS
    CLD                     ; SET FORWARD DIRECTION
    OUT     PPI_PORT, AL       ; ENABLE TIMER
    REP     STOSB              ; RUN TEST
    MOV     AL, BL             ; RESTORE CONTROL VALUE
    OUT     PPI_PORT, AL       ;
    STI                     ; START INTERRUPTS
    CALL    GET_TIMER          ; OBTAIN FINAL COUNT
    POP     DI                 ; RESTORE DI
    POP     ES                 ; RESTORE ES
    POP     BP                 ; RESTORE BP
    RET                      ; RETURN

```

```
_BEMSTIME    ENDP
```

```

;*****
;
;    _WEMSTIME
;    TIME EXECUTION OF REP STOSW INSTRUCTION
;
;*****

```

```

PUBLIC _WEMSTIME
_WEMSTIME    PROC    NEAR

    PUSH    BP                ; SAVE FRAME
    MOV     BP, SP            ;
    PUSH    ES                ; SAVE ES

```


ONCE IN A LIFETIME A NEW PRODUCT APPEARS ON
THE HORIZON THAT SHINE ABOVE ALL OTHERS

THE CREATOR™

APPLICATION GENERATOR

by Advanced Development Technologies

- ★ FOURTH GENERATION PRODUCTIVITY
- ★ ELIMINATE DATABASE MANAGEMENT SYSTEMS
- ★ A COMPLETE APPLICATION
GENERATION ENVIRONMENT
- ★ DEVELOP APPLICATIONS IN LESS TIME
- ★ REDUCE CODE REQUIREMENTS
BY 90 PERCENT
- ★ TRAPS ERRORS WITH DETAIL ANALYSIS
- ★ MULTIPLE FILE ACCESS
WITHOUT PROGRAMING
- ★ 99 INDEXES PER DATA FILE
- ★ AUTOMATIC RECORD LOCK
- ★ UNLIMITED FILE AND
RECORD SIZE
- ★ PRODUCES COMPLETE
DOCUMENTATION

\$99

MASTERCARD/VISA

INCLUDES:

Internal Expression Compile
Relational File Structure
ISAM File Access Method
Screen and Report Generator
Rich Library of Functions
Data Dictionary
System and User Defined Variables

For Only \$99 The **CREATOR™** Lets You Develop Applications Without Being Bugged Down By A Lot Of Code. Regardless Of How Simple Or Sophisticated The Applications, Save Hundreds Of Hours Of Programing By Using This Advanced Method Of Application Development. Manages All Phases Of Program Development:

- Program Generation
- Database Defination
- Screen And Report Formation
- Multiple Levels of Menus.

A Complete Development System Available For IBM, PC, XT, and AT Requires 256K RAM Includes Unlimited Run Time

800-528-6060

EXT. 239

CHECKS AND MONEY ORDERS ACCEPTED

© THE CREATOR™ IS A TRADEMARK OF
ADVANCE DEVELOPMENT TECHNOLOGIES

2720 N. 68th St., Suite 5379

Scottsdale, Arizona 85257

602-945-1375

CIRCLE NO. 190 ON READER SERVICE CARD

IBM PC, XT, AT is a
Copyright of International
Business Machines, Inc.


```

SE4          ; TRY AGAIN IF BUSY
AH, AH       ; CHECK FOR ERROR
SEN0         ; JUMP ON ERROR
MOV PID, DX  ; SAVE THE PROCESS ID
;
MOV AH, 44H  ; FUNCTION 5:
XOR BX, BX   ; MAP THE PAGE TO
XOR AL, AL   ; FRAME BASE
INT 67H      ;
CMP AH, 82H  ; CHECK FOR BUSY
JE SE5       ; TRY AGAIN IF BUSY
OR AH, AH    ; CHECK FOR ERROR
JNZ SENC     ; JUMP ON ERROR
;
XOR AX, AX   ;
POP DI       ; RESTORE REGISTERS
POP SI       ;
POP ES       ;
POP BP       ;
RET          ; RETURN 0

SENC: MOV AH, 45H ; FUNCTION 6:
INT 67H      ; CLOSE EMM
CMP AH, 82H  ; CHECK FOR BUSY
JE SENC      ; TRY AGAIN IF BUSY
SEN0: MOV AX, 0FFFFH ;
POP DI       ; RESTORE REGISTERS
POP SI       ;
POP ES       ;
POP BP       ;
RET          ; RETURN -1

SETUP_EMM    ENDP

;*****;
;
; _FINISH_EMM
; CLOSE THE EMM DEVICE, RELEASE THE PAGE
;
;*****;
PUBLIC _FINISH_EMM
_FINISH_EMM PROC NEAR

PUSH BP      ; SAVE REGISTERS
PUSH ES      ;
PUSH SI      ;
PUSH DI      ;
SE6: MOV AH, 45H ; FUNCTION 6:
MOV DX, PID  ; CLOSE EMM
INT 67H      ;
CMP AH, 82H  ; CHECK FOR BUSY
JE SE6       ; TRY AGAIN IF BUSY
POP DI       ; RESTORE REGISTERS
POP SI       ;
POP ES       ;
POP BP       ;
RET          ; RETURN

_FINISH_EMM ENDP

;*****;
;
; SETUP_TIMER
; SET UP THE TIMER FOR MAXIMUM COUNT, TO TIME A RUN
;
;*****;
SETUP_TIMER PROC NEAR

PUSH AX      ; SAVE AX
IN AL, PPI_PORT ; STOP THE TIMER
AND AL, 0FCH ;
OUT PPI_PORT, AL ;
MOV AL, 0B4H ; INITIALIZE THE TIMER
OUT TIMER_CTRL, AL ;
MOV AL, 0     ; CLEAR THE COUNT
OUT TIMER2_PORT, AL ;
NOP          ;
OUT TIMER2_PORT, AL ;
POP AX       ; RESTORE AX

```

```

RET          ; RETURN

SETUP_TIMER ENDP

;*****;
;
; GET_TIMER
; TAKE THE COUNT FROM THE TIMER
;
;*****;
GET_TIMER PROC NEAR

PUSH BX      ; SAVE REGISTERS
IN AL, TIMER2_PORT ; GET LOW BYTE OF TIME
MOV AH, AL   ;
IN AL, TIMER2_PORT ; GET HIGH BYTE
XCHG AL, AH  ; TIME IN AX
NEG AX       ; CORRECT FOR COUNT-DOWN
POP BX       ; RESTORE REGISTERS
RET          ; RETURN

GET_TIMER ENDP

;*****;
;
; _NDP_PRESENT
; CHECK IF 80287 IS PRESENT
;
;*****;
PUBLIC _NDP_PRESENT
_NDP_PRESENT PROC NEAR

PUSH BP      ; SAVE FRAME
MOV BP, SP   ;
INT 11H      ; BIOS EQUIP CHECK
TEST AL, 02H ; IS 80287 BIT SET?
JZ NO        ; NO MEANS NO 80287
MOV AX, 01h  ; RETURN TRUE
JMP EXIT     ; ALL DONE
NO: XOR AX, AX ; SET AX TO FALSE
EXIT: MOV SP, BP ; RESTORE SP
POP BP       ; RESTORE BP
RET          ; RETURN

_NDP_PRESENT ENDP

_TEXT ENDS

END

```

LISTING 5: ATFLOAT.C

```

/*
 * ATFLOAT -- PC Tech Journal Floating-Point Performance Test
 * Version 1.00
 * Last modified 05/23/86
 * Copyright (c) 1986, PC Tech Journal
 * Program by: Paul Pierce, Ted Forgeron, Steven Armbrust
 * Measures the time it takes to multiply two matrices of
 * double-precision floating-point numbers and compares it
 * to the time it takes an 8MHz PC/AT with an 80287 math
 * coprocessor to do the same.
 */
/* Number of iterations the test runs for. */
#define TRIALS 100
/* Dimension of the matrix */
#define SIZE 20
unsigned long time();
unsigned rand();

double drand()
{
    return (double)rand() / 32767;
}

double a[SIZE][SIZE];
double b[SIZE][SIZE];

main()
{
    int i;

```



FREE EXPANDED MEMORY BOARD!

"Make no mistake, the PC-286 is the most awesome piece of high technology you can put in a PC..."

— BUSINESS COMPUTER SYSTEMS

"Of this month's selections, PC-286 was fastest for the spreadsheet recalculation."


— LOTUS MAGAZINE



— 80286 (6, 8, 10, 12.5 MHz)

— Optional 80287 (5, 8, 10 MHz)

- Fully compatible with the industry-standard Lotus/Intel/Microsoft (LIM) Expanded Memory Specification (EMS), version 3.2
- Expandable up to 8 megabytes.
- Compatible with all major productivity software such as Lotus 1-2-3, Symphony, Framework II.



• BUNDLED WITH MICROSOFT WINDOWS •

Top Board processes EMS-applications up to three times faster than any other EMS board on the IBM PC XT. Top Board is the only EMS expanded memory board with both an 8 and 16 bit data bus and can function across the 16 bit wide bus with the STD-powered PC-286 card.

Top Board frees you from the memory limits of 640K. Expand memory up to 2 MB with the confidence of LIM-compatible standards. Unleash this full potential with processor speeds up to 12 MHz when used with our PC-286 board

across the built-in, 16 bit data bus to the Top Board.

Expect performance that exceeds industry standards. Together, the PC-286 and Top Board perform beyond their individual state-of-the-art designs. Your CAD, spreadsheet, database or other software designed to utilize the EMS specification will run up to 8 times faster than an IBM PC XT with this product combination.

The Top Board is fully compatible with the Lotus/Intel/Microsoft Expanded Memory Specification. Its unique design has an efficient

and flexible paging scheme for even greater performance with EMS-compatible applications and multitasking software.

For the performance you and your PC have been waiting for, order a Top Board today. Solve your PC's problems with processing-intensive applications and improve your own personal productivity.

CALL (206) 883-8440

STD

SEATTLE TELECOM
& DATA, INC.
2637 151st Pl. N.E.
Redmond, WA 98052

Top Board and PC-286 are trademarks of STD. Framework is a trademark of Ashton-Tate. Lotus 1-2-3 and Symphony are trademarks of Lotus Development Corporation. IBM PC XT is a trademark of IBM Corp. Contact us regarding optional EGA graphics and multifunction daughter boards.

***Must purchase a 6 or 8 MHz expandable PC-286 board to receive a free 512K Top Board (\$549 value). Offer expires September 30, 1986.**


```

register j, k;
int n;
unsigned long start;
unsigned long total;
unsigned trials;
double t;

trials = TRIALS;
/*
 * Fill matrix with random numbers.
 */
for (i = 0; i < SIZE; i++)
    for (j = 0; j < SIZE; j++)
        a[i][j] = drand();

/*
 * Repeatedly multiply the matrices and
 * report the relative and absolute times.
 */
start = time();
printf("\n\nATFLOAT -- PC Tech Journal AT Floating-Point");
printf(" Performance Test\n");
printf("Version 1.00, Copyright (c) 1986 PC Tech ");
printf("Journal\n");
printf("\nThis test runs for %d iterations ...\n", trials);
for (n = 1; n <= trials; n++) {
    printf("%d\r", n);
    for (i = 0; i < SIZE; i++) {
        for (j = 0; j < SIZE; j++) {
            t = 0;
            for (k = 0; k < SIZE; k++)
                t += a[k][j] * a[i][k];
            b[i][j] = t;
        }
    }
    total = time() - start;
    printf("\rElapsed time is %ld seconds.\n\n", total, trials);
    printf("Floating-point performance index relative\n");
    printf("to 8MHz IBM PC/AT with 80287 = %2.1f\n",
        94.0 / (float) total);
}

```

LISTING 6: ATDISK.C

```

/*
 * ATDISK -- PC Tech Journal AT Hard Disk Performance Test
 * Version 1.00
 * Last modified 05/23/86
 * Copyright (c) 1986, PC Tech Journal
 * Program by: Paul Pierce, Ted Forgeron, Steven Armbrust
 * Uses BIOS INT 13H to measure low-level performance.
 * Uses DOS INT 21H to measure high-level performance.
 */
#include "dos.h"
/* System clock tick rate in ticks/second */
#define TICK_RATE 18.20648
/* Number of trials for each test */
#define TRIALS 1000

struct diskparam {
    int sectors;
    int heads;
    int cylinders;
    int drives;
} diskparam[10];

char buffer[50 * 512];

/* Number of files for DOS file I/O test */
#define FILES 10
/* Size of each file for DOS file I/O test */
#define FILESIZE 20000
/* Size of each read/write request for DOS file I/O test */
#define FILEBUF 2000

char filename[] = "C:ATDISK.---0";

unsigned long tick();
unsigned rand();

double drand()

```

```

{
    return (double)rand() / 32767;
}

#define READ_SECTORS 2
#define GET_PARAM 8
#define SEEK 12

main(argc, argv)
int argc;
char *argv[];
{
    register i, j, k;
    unsigned long start;
    unsigned long total;

    unsigned trials;
    int f;

    trials = TRIALS;
    /*
     * Get the disk drive parameters for each hard disk
     * in the system.
     */
    disk_io(GET_PARAM, 0x80, &diskparam[0], 0, 0, 0, 0);
    for (i = 1; i < diskparam[0].drives; i++) {
        disk_io(GET_PARAM, 0x80 + i, &diskparam[i],
            0, 0, 0, 0);
    }
    /*
     * Display the disk characteristics.
     */
    printf("\n\nATDISK -- PC Tech Journal AT Hard Disk ");
    printf("Performance Test");
    printf("\nVersion 1.00, Copyright (c) 1986 PC Tech ");
    printf("Journal\n");
    printf("\n\nHARD DISK CHARACTERISTICS\n");
    printf("Drive Sectors Heads Cylinders Total ");
    printf("space\n");
    for (i = 0; i < diskparam[0].drives; i++) {
        total = diskparam[i].sectors * diskparam[i].heads;
        total *= diskparam[i].cylinders;
        total *= 512;
        printf("%3d %5d %5d %5d %10lu\n",
            i,
            diskparam[i].sectors,
            diskparam[i].heads,
            diskparam[i].cylinders,
            total);
    }
    printf("\n\nBIOS TEST OF DISK HARDWARE PERFORMANCE\n");
    /*
     * Seek back and forth between tracks 0 and 1.
     */
    for (i = 0; i < diskparam[0].drives; i++) {
        disk_io(SEEK, 0x80 + i, buffer, 1, 0, 0, 0);
        start = tick();
        for (j = 0; j < trials/2; j++) {
            disk_io(SEEK, 0x80 + i, buffer, 1, 0, 0,
                1);
            disk_io(SEEK, 0x80 + i, buffer, 1, 0, 0,
                0);
        }
        total = tick() - start;
        printf("Drive %d track-track seek time: %4.1f ms",
            i, (double)total / ((double)trials) *
            1000.0 / TICK_RATE);
        printf("\n");
    }
    /*
     * Seek to random tracks.
     */
    for (i = 0; i < diskparam[0].drives; i++) {
        disk_io(SEEK, 0x80 + i, buffer, 1, 0, 0, 0);
        start = tick();
        for (j = 0; j < trials; j++) {
            disk_io(SEEK, 0x80 + i, buffer, 1, 0, 0,
                (short)(drand() *
                    (diskparam[i].cylinders - 1)));
        }
        total = tick() - start;
    }
}

```


The LAN Rush is On!



Get a QuickStart... Networking with TiaraLink™

In today's business race, swift communication means the difference between being a success or an also-ran. Local area networks are the key to sharing important business data and resources. But, all too often potential LAN customers are stopped in their tracks by lack of experience.


QuickStart, a new feature, allows users to easily set up the powerful TiaraLink™ LAN — even with no programming or networking experience. This means fast and easy installations. Simple demonstrations. Less sales support. And more satisfied customers.

Now TiaraLink supports DOS 3.1 and a complete NetBIOS. So network application software written to these standards runs on TiaraLink. Already thousands of our networks

are installed on IBM® PC, XT, AT and compatibles. TiaraLink is a **proven** LAN, and more... TiaraLink is the price/performance leader.

Tiara provides more than a high performance network — we offer you an outstanding dealer program: training, support, advertising, and some of the best margins in the industry.

The LAN Rush is on! So, don't be left at the starting line. Investigate the LAN that offers high performance at the best margins: TiaraLink. If you are interested in joining the Tiara dealership team, call us at 1-800-423-1268. In California call 1-800-325-6223. Or write us for more facts on TiaraLink.



Our Prices Leave Everybody
Else in the Dust!

TIARA
COMPUTER SYSTEMS, INC.

2685 Marine Way • Mountain View, CA 94043 • (415) 965-1700 • TLX 4996251 • FAX (415) 965-2677

Trademark/Owners: TiaraLink/Tiara Computer Systems, Inc.; IBM/International Business Machines, Corp.

CIRCLE NO. 246 ON READER SERVICE CARD


```

printf("Drive %d average seek time: %4.1f ms\n",
i, (double)total / ((double)trials) *
1000.0 / TICK_RATE);

/*
Measure transfer rate by repeatedly reading sectors
*/
for (i = 0; i < diskparam[0].drives; i++) {
    disk_io(READ_SECTORS, 0x80 + i, buffer, 1, 0, 0,
    0);
    start = tick();
    for (j = 0; j < trials; j++) {
        disk_io(READ_SECTORS, 0x80 + i, buffer,
        diskparam[i].sectors, 0, 0, 0);
    }
    total = tick() - start;
    printf("Drive %d effective transfer rate: ", i);
    printf("%5.1f Kbytes/second\n",
    (((double)diskparam[i].sectors)*512.0) *
    (double)trials / ((double)total) /
    1024 * TICK_RATE);
}
/*
* This section indicates overall system disk performance
* by using DOS calls to manipulate files. It is only
* executed if the -d command line switch is used since
* the test writes to disk.
*/
if (argc == 1) {
    printf("\nType \"atdisk -d\" to run the DOS ");
    printf("TEST OF DISK SYSTEM PERFORMANCE.\n");
    printf("This test creates, writes, reads and ");
    printf("deletes ten files named \n");
    printf("atdisk.--0 through atdisk.--9.\n");
}
if (argc > 1 && argv[1][0] == '-' && argv[1][1] == 'd') {
    printf("\nDOS TEST OF DISK SYSTEM PERFORMANCE\n");
    printf("This test creates, writes, reads and ");
    printf("deletes ten 20,000 byte files.\n");
    printf("Best results are achieved with blank, ");
    printf("freshly-formatted disks.\n");
    for (k = 0; k < diskparam[0].drives; k++) {
        filename[0] = 'C' + k;
        start = tick();
        /*
        * First create each file, write to it,
        * and close it.
        */
        for (i = 0; i < FILES; i++) {
            filename[11] = '0' + i;
            f = dos_create(filename, 0);
            for (j = 0; j < FILESIZE/FILEBUF;
            j++) {
                dos_write(f, buffer,
                FILEBUF);
            }
            dos_close(f);
        }
        /*
        * Now reopen each file, read it, and
        * then delete it.
        */
        for (i = 0; i < FILES; i++) {
            filename[11] = '0' + i;
            f = dos_open(filename, 0);
            for (j = 0; j < FILESIZE/FILEBUF;
            j++) {
                dos_read(f, buffer,
                FILEBUF);
            }
            dos_close(f);
            dos_delete(filename);
        }
        total = tick() - start;
        printf("Drive %c:", 'C' + k);
        printf("%5.1f seconds\n",
        ((double)total) / TICK_RATE);
    }
}
/*

```

```

* DOS file calls
*
* Each of these routines sets up the regs structure as
* specified in the DOS technical reference and then
* calls DOS using the intdos() function.
*/
/*
* DOS call 3C - create file
*/
int
dos_create(file, attribute)
    char *file;
    int attribute;
{
    struct REGS regs;

    regs.x.dx = (int)file;
    regs.h.ah = 0x3C;
    regs.x.cx = attribute;
    intdos(&regs, &regs);
    if (regs.x.cflag) {
        printf("DOS error %d in create\n",
        regs.x.ax);
        exit(1);
    }
    return regs.x.ax;
}
/*
* DOS call 3D - open file
*/
int
dos_open(file, mode)
    char *file;
    int mode;
{
    struct REGS regs;

    regs.x.dx = (int)file;
    regs.h.ah = 0x3D;
    regs.h.al = mode;
    intdos(&regs, &regs);
    if (regs.x.cflag) {
        printf("DOS error %d in open\n",
        regs.x.ax);
        exit(1);
    }
    return regs.x.ax;
}
/*
* DOS call 3E - close file
*/
dos_close(handle)
    int handle;
{
    struct REGS regs;

    regs.x.bx = handle;
    regs.h.ah = 0x3E;
    intdos(&regs, &regs);
    if (regs.x.cflag) {
        printf("DOS error %d in close\n",
        regs.x.ax);
        exit(1);
    }
}
/*
* DOS call 3F - read file
*/
int
dos_read(handle, buffer, count)
    int handle;
    char *buffer;
    int count;
{
    struct REGS regs;

    regs.x.bx = handle;
    regs.x.cx = count;
    regs.x.dx = (int)buffer;
    regs.h.ah = 0x3F;
    intdos(&regs, &regs);
}

```


DAN BRICKLIN'S DEMO PROGRAM HAS EVERYONE TALKING.

Dan Bricklin's Demo Program is a new concept in prototyping and demo-making. With DEMO you can conceptualize programs, describe them to others, refine their functionality and human interface, and finally, teach users the finished product. The two most common applications are to prototype a product before it is written and to produce a demonstration or tutorial about an existing product or system.

- Create, edit and view a series of slides
- Each slide is 80x25 characters
- All 256 characters supported, including special characters
- All 256 attributes (color, underline, blink, etc.)
- Each slide can be the image of what a running program looks like
- Characters graphics only, no bit-mapped graphics
- Slides are stored compacted, allowing often hundreds and hundreds of slides to fit in memory for instant access (given enough RAM)
- Complete set of editing commands, including cut, paste and move
- Line, box and special character commands built-in
- Includes background "CAPTURE" program for importing screens from running programs
- Learn-mode macro facility
- Run command switches from slide to slide under automatic control
- Options include:
 - ☐ Adjustable delay between each slide
 - ☐ Wait for key or optional timeout
 - ☐ Display different slide next depending upon keystroke
 - ☐ Produce tones
 - ☐ Switch to another set of slides in another file
- Runtime-only version of program included; along with license to make up to 50 copies (see License for details).
- Additional volume runtime licenses available.
- Requires 256k IBM PC/compatible, DOS 2.0 or later. Supports Monochrome, Color/graphics, and EGA Adaptors (text mode only).

Thousands of developers are designing better products faster and producing more effective demonstrations using Dan Bricklin's Demo Program. You can, too. Act now!

ORDER YOUR COPY TODAY

ONLY \$74.95
617-332-2240



Send checks to Software Garden, Inc., Dept. T, P.O. Box 373, Newton Highlands, MA 02161. Massachusetts residents add \$3.75. Outside the U.S.A. add \$15.00.

PRODUCT OF THE MONTH

—PC Tech Journal, 3/86

"A winner right out of the starting gate... After you use DEMO once, you'll wonder how you got along without it." —PC Magazine, 4/29/86

"Everybody who writes software, either commercially or for in-house applications, should immediately order a copy. Period. No exceptions."

—Soft•letter, 4/20/86

"Its low price, superb performance, and range of applications practically guarantee that it will be widely used. Four Floppy Rating (8.0)"

—InfoWorld, 3/31/86

"Apparently has a hit on its hands with... a development tool for personal computer software that has won rave reviews from early users."

—Computerworld, 4/7/86



SOFTWARE GARDEN

"A gem."

—PC Week, 3/18/86


```

(regs.x.cflag) {
    printf("DOS error %d in read\n",
        regs.x.ax);
    exit(1);
}
return regs.x.ax;
}
/*
 * DOS call 40 - write file
 */
int
dos_write(handle, buffer, count)
    int    handle;
    char    *buffer;
    int    count;
{
    struct REGS regs;

    regs.x.bx = handle;
    regs.x.cx = count;
    regs.x.dx = (int)buffer;
    regs.h.ah = 0x40;
    intdos(&regs, &regs);
    if (regs.x.cflag) {
        printf("DOS error %d in write\n",
            regs.x.ax);
        exit(1);
    }
    return regs.x.ax;
}
/*
 * DOS call 41 - delete file
 */
dos_delete(file)
    char    *file;
{
    struct REGS regs;
    regs.x.dx = (int)file;
    regs.h.ah = 0x41;
    intdos(&regs, &regs);
    if (regs.x.cflag) {
        printf("DOS error %d in delete\n",
            regs.x.ax);
        exit(1);
    }
}

```

LISTING 7: PDISKIO.ASM

```

NAME    PDISKIO
PAGE    60,132
;*****;
;
;    PHYSICAL DISK I/O
;
;*****;
_TEXT    SEGMENT BYTE PUBLIC 'CODE'
_TEXT    ENDS
CONST    SEGMENT WORD PUBLIC 'CONST'
CONST    ENDS
_BSS     SEGMENT WORD PUBLIC 'BSS'
_BSS     ENDS
_DATA    SEGMENT WORD PUBLIC 'DATA'
_DATA    ENDS
DGROUP   GROUP CONST, _BSS, _DATA
ASSUME   CS: _TEXT, DS: DGROUP, SS: DGROUP, ES: DGROUP

_TEXT    SEGMENT
;*****;
;
;    char
;    disk_io(cmd, drive, buf, count, sector, head, cylinder) ;
;    4    6    8    10   12   14   16
;*****;

PUBLIC _DISK_IO
_DISK_IO PROC NEAR

```

```

PUSH    BP                                ; SAVE FRAME
MOV     BP, SP                            ; MAKE NEW FRAME
PUSH    ES                                ;
PUSH    SI                                ;
PUSH    DI                                ;
MOV     AH, [BP+4]                        ; PICK UP COMMAND
MOV     DL, [BP+6]                        ; PICK UP DRIVE
MOV     BX, [BP+8]                        ; PICK UP BUFFER
PUSH    DS                                ;
POP     ES                                ;
MOV     AL, [BP+10]                       ; PICK UP COUNT
MOV     DH, [BP+14]                       ; PICK UP HEAD
MOV     CH, [BP+17]                       ; HIGH CYL BITS
SHR     CX, 1                             ; SHF 2 MSB TO CL
SHR     CX, 1                             ;
AND     CL, 0COH                          ; MASK THEM
ADD     CL, [BP+12]                       ; ADD IN SECTOR
INC     CL                                ; PLUS ONE
MOV     CH, [BP+16]                       ; REST CYL IN CH
INT     13H                              ; CALL BIOS
JC      SAVERR                            ; JUMP IF ERROR
MOV     AH, 0                             ; CLEAR RESULT
CMP     BYTE PTR [BP+4], 8                ; DRIVE PARAM CMD
JNE     SAVERR                            ; JUMP IF NOT
MOV     BX, [BP+8]                        ; RESULTS IN BUF
MOV     [BX], CL                          ; SECTORS
AND     BYTE PTR [BX], 03FH               ;
MOV     BYTE PTR [BX+1], 0                ;
INC     DH                                ;
MOV     [BX+2], DH                        ; HEADS
MOV     BYTE PTR [BX+3], 0                ;
MOV     [BX+4], CH                        ; CYLINDERS
SHL     CX, 1                             ; FIX HIGH BYTE
SHL     CX, 1                             ;
AND     CH, 003H                          ;
MOV     [BX+5], CH                        ;
MOV     [BX+6], DL                        ; DRIVES
MOV     BYTE PTR [BX+7], 0                ;
SAVERR: MOV AL, AH                        ; RESULT IN AX
MOV     AH, 0                             ;
POP     DI                                ; RESTORE REGS
POP     SI                                ;
POP     ES                                ;
POP     BP                                ; RESTORE FRAME
RET                                         ; RETURN

```

_DISK_IO ENDP

```

;*****;
;
;    Get the current BIOS clock tick count
;    long ticks();
;*****;

```

```

PUBLIC _TICK
_TICK PROC NEAR
PUSH    BP                                ; SAVE FRAME
MOV     BP, SP                            ; MAKE NEW FRAME
PUSH    ES                                ;
MOV     AX, 0                             ; CLEAR ES TO
MOV     ES, AX                            ; GET BIOS DATA
CLI                                           ; DISABLE INTS
MOV     AX, ES:WORD PTR [046CH]            ; LOW TICK COUNT
MOV     DX, ES:WORD PTR [046EH]            ; HIGH TICK COUNT
STI                                           ; ENABLE INTS
POP     ES                                ; RESTORE REGS
POP     BP                                ; RESTORE FRAME
RET                                         ; RETURN

```

_TICK ENDP

```

;*****;
;
_TEXT    ENDS

END

```


THE PROGRAMMER'S SHOP

helps save time, money and cut frustrations. Compare, evaluate, and find products.

RECENT DISCOVERY

Quick Basic v2.0 - New user interface. Editor, source level error detection, built-in debugger, in-memory compilation, build and link user libraries. BASICA, GW-BASIC compatible. BLOAD, BSAVE PC \$ 79

AI-Expert System Dev't

Arity System - incorporate w/C. PC \$295
 Expertech - Powerful, no limit on memory size. Samples PC \$399
 EXSYS - All RAM, Probability. PC \$339
 Insight 2 - dB2, language. MS \$879
 Others: APES (\$359), Advisor (\$949), ES Construction (\$100), ESP (\$845),

AI-Lisp

BYSO - Common, MacLISP compatible. 250+ functions, fast PC \$150
 GC LISP Interpreter - "Common", rich, Interactive Tutorial Call
 Microsoft MuLisp 85 \$ 250 \$199
 TLC LISP - classes, compiler. MS \$225
 TransLISP - Good for learning MS \$ 75
 WALTZLISP CPM-80 MS \$149
 Others: IQ LISP (\$155), UNIX LISP (\$59), IQC LISP (\$269).

AI-Prolog

ARITY Standard - full, 4 Meg
 Interpreter - debug, C, ASM PC \$ 350
 COMPILER/Interpreter-EXE PC \$ 795
 With Exp Sys, Screen - KIT PC \$1250
 MacProlog MAC \$ 295
 MicroProlog - enhanced MS \$ 229
 Professional MicroProlog MS \$ 359
 Prolog-86 - Learn Fast MS \$ 95
 Prolog-86 Plus - Develop MS \$ 250
 Others: Prolog-I (\$365), Prolog-2 (\$1795)
 TURBO PROLOG by Borland PC \$ 79

National Accounts Center

Special service is provided by a separate team for organizations with over 500 employees. Purchasing agents, evaluators, managers, and programmers all appreciate the extra information, attention to shipping and invoicing, and help finding and evaluating products. Call 800-446-1185.

Our Services:

- Programmer's Referral List
- Compare Products
- Help find a Publisher
- Evaluation Literature FREE
- BBS - 7 PM to 7 AM 617-826-4086
- Dealers Inquire
- Newsletter
- Rush Order
- Over 700 products
- National Accounts Center

C Language-Compilers

Aztec C86 - Commercial PC \$499
 Aztec C65 - Personal Apple II \$199
 C86 by CI - 8087, reliable MS \$299
 Lattice C - from Lifeboat MS \$289
 Lattice C - from Lattice MS \$339
 Mark Williams - w/debugger MS \$399
 Microsoft C 3.0 - new MS \$259
 Q/C 88 by Code Works - Compiler
 source, decent code, cross/native MS \$125
 Wizard C - Lattice C compatible, full sys. III, lint, fast. MS \$389

C Language-Interpreters

C-terp by Gimpel - full K&R MS \$249
 INSTANT C - Source debug, Edit to Run-3 seconds MS \$399
 Interactive C by IMPACC Associates. Interpreter, editor, source, debug. PC \$225
 Introducing C - self paced tutorial PC \$109
 Run/C Professional - Run/C plus create add-in libraries, more. MS \$199
 Run/C - improved MS \$109

C Libraries-Communications

Asynch by Blaise \$149
 Greenleaf - full, fast \$139
 Software Horizons - pack 3 \$119

C Support-Systems

Basic C Library by C Source \$1...
 C Sharp - well supported. Source, realtime, tasks, state system \$600
 C ToolSet - DIFF, xref, source \$ 95
 Lattice Text Utilities \$105
 PC LINT - Checker AMIGA \$89 MS \$119
 The HAMMER by OES Systems \$179
 SECURITYLIB - add encrypt to MSC. C86 programs. Source \$250 PC \$125

C Libraries-General

Application Programmer's Toolkit MS \$375
 Blaise C Tools 1 (\$109), C Tools 2 \$ 89
 C Essentials - 200 functions PC \$ 85
 C Food by Lattice-ask for source MS \$109
 C Power Windows by Entelekon \$119
 C Utilities by Essential - Comprehensive screen graphics, strings. Source. PC \$139
 C Worthy Library - Complete, machine independent, source MS \$295
 Entelekon C Function Library PC \$119
 Greenleaf Functions - portable, ASM \$139
 PforCe by Phoenix - objects PC \$299
 Polytron - for Lattice, ASM source \$ 85

C Libraries-Files

FILES: C Index by Trio - full B + Tree, vary length field, multi compiler
 /File is object only \$ 89
 /Plus is full source \$349
 C to dBASE - with source MS \$139
 CBTREE - multiuser record locking, sequential, source, no royalties MS \$ 99
 CTree by Faircom - no royalties MS \$399
 dbVISTA - full indexing, plus optional record types, pointers, Network.
 Object only - MS C, LAT, C86 \$159
 Source - Single user MS \$429
 Source - Multiuser MS \$849
 dBASE Tools for C PC \$ 79
 dbc Isam by Lattice MS \$199

FEATURE

Multitasking, Windowing for C, Turbo Pascal, or dBASE or . . . in only 12K! SYNERGY

The highly efficient design of Synergy by Matrix gives you the benefits of powerful graphics, windows, pull-down menus, dialog boxes, sophisticated text and icon management, math support, multitasking, and SPEED, all for an incredibly small 12K RAM requirement.

The Synergy Runtime provides character and graphics support for menus, windows, dialog boxes, and more, so you can write programs that work in either mode, with very reasonable, low runtime fees.

Functions include: window management with capabilities like tile and overlap, variable size and placement, process management, to support multitasking and sub-process generation, menus, dialog, and icon management, graphics, text (including a variety of typefaces, fonts, and sizes), and console management.

The Synergy Development Toolkit is a collection of sophisticated tools designed for software developers writing new applications using Synergy, or modifying existing applications to take full advantage of Synergy. Tools include: graphics resource editor for creating and modifying icons and text fonts, graphics resource compiler to construct and manage resource data files, font compiler and manager, debugging tools, sample library, and more.

Supports IBM or Microsoft Macro Assemblers, Turbo, IBM, and Microsoft Pascal, IBM and Microsoft BASIC, Lattice and Microsoft C, and dBASE II and III. CGA, EGA, and Hercules monochrome graphics support.

PCDOS \$395

FEATURE

Multi-User Data Mangement C-INDEX B + TREE LIBRARY

— "Had I known about your product when I was designing and writing dBASE III, I would have certainly used it." — Wayne Ratliff, dBASE author

C-Index can enhance your product development by providing powerful, time tested data management, straight out of the box.

The C-Index Library delivers high performance B + tree indexing with efficient variable length record storage. You get full transportable source code, pre-compiled object libraries, and there are no royalty charges. Additional features include record locking, random and sequential data access, automatic multi-key maintenance, and virtual memory buffering. Single or multiuser, LAN and Xenix compatible.

Highly portable: IBM PC/AT, Macintosh, Cray, VAX, more.

C-Index/Plus (MSDOS, MAC): \$349

C-Index/File (MSDOS)

object only: \$ 89

FEATURE

Oops Protection Plus Complete Disk Control with Disk Toolkit

UNERASE is valuable, but when your file is damaged, it does not work. You need Disk Toolkit's:

- Full-screen FAT table editor
- ASCII Search (or HEX)
- Disk verification to find bad sectors and examine data
- File Allocation Table and full directory access and control
- Ability to copy any sector, track, cluster, file, or area of memory to . . . anywhere — your file on another disk
- Unerase — it can help. Operate in beginner's (keystroke) or advanced mode
- Work on any size hard disk

Disk Toolkit is complete, practical, small (25K), and guaranteed.

PCDOS \$75



We support MSDOS (not just compatibles), PCDOS, Xenix-86, CPM-80, Macintosh, Atari ST, and Amiga.

THE PROGRAMMER'S SHOP

provides complete information, advice, guarantees and every product for Microcomputer Programming.

BetterBASIC SPECIAL BUY NOW

Access full memory, program in a structured environment, utilize true procedures and functions like PASCAL, create user defined keywords like C, and access the 8087/80287 chip. GW-BASIC, PC-BASICA compatible. C-Link allows you to access your existing C Libraries from BetterBASIC.

Order before 8/31/86 and mention this ad for the special prices below:

	LIST	Before 8/31	After 8/31
BetterBASIC	199	139	169
8087 Math Support	99	79	89
Run-time Module	250	179	235
C-Link	99	79	89
Btrieve Interface	99	69	85

RECENT DISCOVERY

APT - Active Prolog Tutor - Guides you in building applications interactively. Arity, Borland, Prolog-86 compatible. PC \$ 95

Fortran & Supporting

Forlib + by Alpha - graph, comm. \$ 59
 MACFortran by Microsoft \$ 229
 MS Fortran - link to C \$ 219
 No Limit - Fortran Scientific \$ 119
 PolyFortran - xref, pp, screen \$ 149
 Prospero - '66, reentrant \$ 349
 RM Fortran - enhanced "IBM Ftn" \$ 395
 Scientific Subroutines - Matrix \$ 149
 Statistician by Alpha \$ 269
 Strings and Things - registers, shell \$ 59

Debuggers

Advanced Trace-86 by Morgan Modify code on fly. PC \$ 149
 Codesmith - visual, modify and rewrite Assembler PC \$ 109
 CSPRITE - data structures PC \$ 139
 DSD87 - windowing, 8087 MS \$ 95
 Periscope I - own 16K PC \$ 269
 Periscope II - symbolic. "Reset Box." 2 Screen PC \$ 129
 Pfix-86 Plus Symbolic Debugger by Phoenix - windows PC \$ 249
 Software Source by Atron - Lattice, MS C, Pascal, Windows single step, 2 screen, log file. MS \$ 115
 w/Breakswitch \$199

Editors for Programming

BRIEF Programmer's Editor - undo, windows, reconfigure PC Call
 C Screen with source 80/86 \$ 75
 EMACS by UniPress - powerful MS \$299
 Epsilon - like EMACS, Full C-like language for Macros PC \$169
 FirstTime by Spruce - Improve productivity. Syntax directed for Turbo (\$69), Pascal (\$229), or C (\$239)
 Kedit - like XEDIT PC \$109
 Lattice Screen Editor-multiwindow, multitasking Amiga \$100 MS \$109
 PMATE - power, multitask 80/86 \$149
 XTC - multitasking PC \$ 85

Atari ST & Amiga

We carry full lines of Manx, Lattice, & Metacomco.

Note: All prices subject to change without notice. Mention this ad. Some prices are specials. Ask about COD and POs. All formats available. UPS surface shipping add \$3/item.

Multilanguage Support

BTRIEVE ISAM MS \$199
 BTRIEVE/N - multiuser MS \$469
 CODESIFTER - Profiler MS \$109
 Halo Graphics - 115+ devices. Animation, engineering, business.
 Any MS language, Lattice, C86 PC \$229
 PANEL - Create screen with editor, generates code. Xenix \$539 MS \$239
 Pfinish Performance Analyzer PC \$249
 PLINK 86 - program-independent MS \$249
 PLINK-86 Plus - incremental MS \$369
 Poly Librarian by Polytron MS \$ 85
 PVCS Version Control MS \$359
 Screen Sculptor - slick, thorough PC \$ 99
 ZAP Communications - VT 100, TEK 4010 emulation, full xfer. PC \$ 95

Xenix-86 & Supporting

Basic - by Microsoft \$ 279
 Cobol - by Microsoft \$ 795
 Fortran - by Microsoft \$ 399
 Xenix Complete Development System \$1149

FEATURE

dBASE Programmers: Translate to C with Less Effort. Use dBx Translator

Users say dBx:
 — "allowed me to concentrate on learning C." -new C programmer
 — "takes grunt work out of conversion."
 -experienced C/dBASE programmer

If you need the portability, speed, and control of C, but all your code is written in dBASE, dBx is for you. Including a translator, C libraries and utilities, dBx produces a clean, maintainable translation of most of your programs. You complete translation then rewrite sections to take advantage of C power, flexibility.

Includes BTree, works with dB-C, CTree, C-Index, Pact, others. Supports CI C86, Microsoft, DeSmet and Lattice C. No royalties. Library source Unix portable, available separately. Call our "translator specialist" for details.

PCDOS \$350

FEATURE

PROGRAMMING TEAMS: Manage and Control Source Versions Efficiently with POLYTRON Version Control System (PVCS)

Duplicated efforts and time wasted rebuilding and cataloging source can be avoided. Reliably delegate control for source & documentation to PVCS.

Save confusion and disk space by letting PVCS maintain the complete current version plus all of the increments, decrements, and related notes needed to rebuild any version. Maintains a complete history of changes. No experience with such a system is assumed. The documentation and examples will help you learn quickly. Privilege levels control access so the administrator knows who is working on each module. Ask about discounts for LAN and multi-keyboard access.

PCDOS \$369

 POLYTRON 

FEATURE

EXPERT SYSTEM DEVELOPMENT: Practical, Complete, and Unlimited Features Help Smoothly Build Expert Systems with EXSYS

EXSYS, Inc. has built a stable and complete toolkit by listening to users and examining what they need. One of the first Expert System Shells for the PC, EXSYS provides the features of just about all of its combined competitors, plus the documentation and examples you will need to learn in this field.

UNLIMITED FEATURES? EXSYS supports backward chaining of IF/THEN/ELSE rules, full math support, probabilities, explanations, the ability to call external programs including spreadsheets, database managers, or custom-written front ends with data passed to and from the external program, plus the ability to handle substantial applications of up to 5,000 rules. All user input is either English text, menu selection, or algebraic expression.

The systems developed can explain why information is needed and how it will be used. The ability to "change and rerun" allows expert system modelling of problems. Written entirely in C, EXSYS provides very high speed execution and efficient memory utilization.

But if these features are not enough, use the interface to Lotus, dBASE, BASIC, C, or any other .EXE or .COM file. Already in use at over 1,000 sites with many complex and powerful expert systems developed. Several expert systems have been marketed with a low-cost runtime license. Single computer use is only \$349. Unlimited runtime distribution is available for an additional \$539.

PCDOS \$349

Call for a catalog, literature, advice and service you can trust

HOURS

8:30 AM - 8:00 PM EST.

800-421-8006

THE PROGRAMMER'S SHOP™

128-P Rockland Street, Hanover, MA 02339

Mass: 800-442-8070 or 617-826-7531 6/86

CIRCLE NO. 151 ON READER SERVICE CARD

"I appreciate your service to the programming community, your prices more than fair and your newsletter amongst the finest in the business."

Lawrence Fooian Systems, Inc.

With our free offer, these boards

The boards are the Above™ Board series from Intel.

The coprocessors are 8087 and 80287 Math Coprocessors. Also from Intel.

Put them together and you get one swift system.

And one great offer.

Because now when you buy an Above Board you can get a math coprocessor, free.

These coprocessors accelerate most of the software that supports Above Board: 1-2-3®, Symphony™, Framework II™, SuperCalc®, Auto CAD™ and just about any other math intensive program worth its algorithm.

And you can run your coprocessor with any Above Board you like.



Genuine Intel

Above Board PS/AT

Personal Computer Enhancement

Lotus is a registered trademark of Lotus Development Corporation. Microsoft is a registered trademark of Microsoft Corporation. 1-2-3 is a registered trademark of Lotus Development Corporation. Symphony is a trademark of Lotus Development Corporation. Framework II is a trademark of Ashton-Tate. SuperCalc is a registered trademark of Computer Associates International. Auto CAD is a trademark of Autodesk, Inc. Offer Valid June 23-September 30, 1986. Good only in USA, Canada, and USA territories. Void where prohibited, taxed or restricted by law. Valid for all versions of Above Board. Redeemable only through Intel. Above is a trademark and Intel a registered trademark of Intel Corporation. © 1986 Intel Corporation.

coprocessor will be going fast.

Like the new Above Board PS/AT.

It gives you expanded memory—which meets the Lotus®/Intel/Microsoft® spec, conventional memory—up to 640K, and extended memory—capable of supporting protected mode operating systems.

Plus serial and parallel ports, print buffer, and RAM



disk. All packaged into a single slot. And all guaranteed to run at 8 MHz.

Of course there are also Above Boards that provide this same memory—with and without ports—for your PC/AT, XT and compatibles.

Details on how to get your free coprocessor chip are in specially marked Above Board packages.


Or call us at
(800) 538-3373.

But you'd better hurry. Because after September 30, this offer will be long gone.



intel®

CIRCLE NO. 216 ON READER SERVICE CARD



OUT FROM THE SHADOW OF IBM.

Compaq Deskpro 286

Operated as either a 6-megahertz or an 8-megahertz machine, the Deskpro 286 carries on Compaq's tradition of overall quality and IBM compatibility.

STEVEN ARMBRUST and TED FORGERON

From the introduction of its first computer, the Compaq Portable, Compaq has gained a reputation for quality and compatibility that has enabled its computers to be accepted and used wherever IBM PCs are used. It therefore seems appropriate that a computer from Compaq should be the first one tested in *PC Tech Journal's* series on AT-compatible machines. The Deskpro 286, like other Compaq machines, is a rugged, high-quality computer that can be an ideal alternative to the AT for users who need some of the extra features provided. A speed selection switch on the Deskpro 286 allows users to change from 6-MHz to 8-MHz on the

same machine, a definite advantage over IBM. Other extras include an integrated tape backup system, dual-mode monitor and adapter that displays high-resolution text characters and produces graphics compatible with the IBM Color Graphics Adapter.

Compaq offers three models of the Deskpro 286, each distinguished by the amount of memory and the kinds of peripherals. The top-of-the-line model 3 was used for this review. This machine was equipped with 512KB of memory, a 30MB hard disk, 1.2MB diskette drive, 10MB tape backup system, asynchronous communications port, parallel printer port, and single-color monitor

connected to Compaq's video display controller card. The features available with all three Deskpro 286 models are listed in the accompanying sidebar, "Deskpro 286 Vital Statistics."

Unlike some of the other AT-compatible computers on the market, the Deskpro 286 does not try to mimic exactly the exterior styling of the AT. Instead, it conforms to the style introduced with the original Compaq Portable and is almost a dead ringer for the 8086-based Deskpro. The system unit of the Deskpro 286 measures 19¾ inches by 16½ inches by 6¼ inches. Photo 1 compares its footprint to that of the AT. (The photo shows the top of the AT sys-

PHOTOGRAPH BY MARG DAVID COHEN



PHOTO 1: *System Unit Footprint*




PHOTO 4: *Inside the System Unit*




PHOTO 2: *Keyboard Comparison*



PHOTO 5: *Head-locking Device*




PHOTO 3: *Rear Panel*




Photo 1: Compaq did not try to imitate the shape of the IBM AT. Its system unit is 19 $\frac{3}{4}$ by 16 $\frac{1}{2}$ by 6 $\frac{1}{4}$ inches, indicated by dotted lines, compared to 21 $\frac{1}{4}$ by 16 $\frac{1}{2}$ by 6 $\frac{1}{4}$ for the AT.

Photo 2: The Deskpro 286 keyboard matches the AT keyboard in most respects, but does not have the solid IBM feel. The status lights are conveniently placed on the keys.

Photo 3: The location of the power switch on the rear panel is inconvenient; the front panel would have been a better position. The 4 $\frac{1}{2}$ -inch fan provides plenty of air flow.

Photo 4: The math coprocessor socket is easy to reach, but a metal brace between the front and rear panels of the system unit blocks convenient access to slot number 1.

Photo 5: Before using the hard-disk drive for the first time, the cotter pin and plastic washer must be removed, and the exposed lever must be pushed into its unlocked position.

tem unit with the Deskpro outline superimposed as a dotted line.) The Deskpro 286 is a big, heavy machine, indicative of its sturdy construction. The heavy-duty hard disk adds its not insignificant bulk to the load. Moving this computer around can be a chore.

Only two exterior features, a key-lock switch and an AT-style keyboard, differ from the 8086 version. Neither of these features is up to the standards set by the similar items on the AT. Instead of the slick chrome keylock available on the AT, the Deskpro 286 has a dull black mechanism stuck incongruously to the front panel of the system unit with a key of the bus-station-locker variety. Part of the mechanism holding the lock in place fell off the test machine while the system unit cover was being removed, hardly inspiring confidence in its ability to deter intruders. An indicator for the locked and unlocked positions is so faint that it can barely be seen, even in direct light.

The Deskpro 286 keyboard is likely to be the source of many complaints for a variety of reasons. Although it conforms for the most part to the layout of the standard AT keyboard (see photo 2) and it offers more tactile feedback than the keyboard on the original Compaq Portable, it still lacks the solid feel of IBM. The oversized keys (Enter and Shift) are particularly flimsy. The computer generates audible keyboard clicks to compensate for the keyboard's lack of tactile feedback. The Ctrl-Alt-minus and Ctrl-Alt-plus key combinations reduce and increase the loudness of the key clicks. (The Deskpro 286's BIOS keeps track of the loudness by storing a value between 0 and 127 at absolute RAM address 416H. The IBM BIOS reserves this byte as a scratch area.)

The keyboard's adjustable legs, which are the same kind that were used on earlier Compaq models, do not lock into position, so any abrupt or sideways motion can cause those legs to collapse. The Compaq 286's keyboard cord also suffers from clumsiness. It is approximately the same length as the one on the AT, but because the Compaq keyboard plugs into the front of the system unit instead of the back as on the AT, the extra cord length tends to get in the way. Perhaps Compaq has overreacted to the criticisms of the Compaq Portable's too-short cord.

The keyboard that arrived with the test machine had problems with sticking keys, particularly Alt and Enter. Whenever the Ctrl-Alt-Del combination was pressed, the system displayed a keyboard error message on the screen

instead of rebooting. This keyboard was replaced with another, but after typing a single word into a word processor with the new keyboard, a never-ending stream of spaces spewed out onto the screen, obliterating text at 8 MHz. The Space bar lay plastered to the base of keyboard and only with great effort could it be pried up. This is not to say that all Deskpro keyboards are plagued with sticking keys, but a cautionary note would be to test all the keys before taking a new machine home.

The location of the power switch on the system unit might cause some frustration. Instead of following IBM's lead and placing the switch on the right side of the unit (or better yet, placing it in front for easy access), Compaq put the switch on the rear panel (see photo 3). This location certainly minimizes the risk of accidentally turning off the machine, but it forces the user to reach around to the back and fumble blindly for an invisible switch.

The Deskpro's monochrome display is an example of high-quality construction and good design. Used with Compaq's standard display adapter, which emulates IBM's Color Graphics Adapter and generates high-resolution text comparable to that generated by IBM's monochrome adapter, it displays crisp characters and graphics in an eye-pleasing shade of amber. An especially nice feature of the display is its viewing angle. Because of its almost pyramid

shape, when the display sits on a horizontal surface, the screen tilts slightly upward. This permits comfortable viewing either when the entire machine is sitting on a typing table or when the display is sitting directly on a desktop.

Compaq's 1.2MB diskette drive has a noteworthy feature. When the drive is reading or writing a 1.2MB diskette, the drive light shines green; when the drive accesses a 360KB diskette, the light turns to red. With all the juggling between diskette formats that goes on these days, the different colors can be reassuring, especially when formatting.

Like the AT's 1.2MB diskette drive, the Deskpro 286's 1.2MB drive does not always write 360KB diskettes reliably. Moreover, during testing, the drive sometimes had trouble *reading* 360KB diskettes. For example, the drive would not read two of the Lotus Symphony master diskettes. However, when a PC with 360KB drives was used to make copies of those diskettes, the Deskpro was able to read the copies.

Standard on the Deskpro 286 is a parallel printer port and an asynchronous communications adapter (serial port), which are both on the diskette adapter card. The connectors are identical to those on the AT; the parallel port has a 25-pin, D-shell, female connector, and the serial port has the smaller AT-style 9-pin, D-shell, male connector. Jumpers on the diskette adapter card allow switching or disabling the ports.

DESKPRO 286 VITAL STATISTICS

Model 1: \$3,999

256KB memory
Parallel printer interface
Serial interface
Dual-mode (monochrome and CGA compatible) display adapter
RGB and composite interface
Dual-mode monochrome monitor
Realtime clock
1.2MB or 360KB diskette drive

Model 2: \$4,999

All features of model 1 plus:
512KB memory
30MB hard disk

Model 3: \$5,699

All features of model 1 plus:
512KB memory
30MB hard disk
10MB tape backup

Memory capacity on system board
None

Display adapters

Dual-mode (IBM monochrome and CGA compatible)

Expansion slots

16-bit: 4
8-bit: 2

Available slots

Model 1
16-bit: 3
8-bit: 2
Models 2 and 3
16-bit: 2
8-bit: 2

Extras available

10MB tape backup
Processor speed selection switch
(6 MHz/8 MHz)
Dual-mode display adapter and monitor (monochrome/CGA)

DESKPRO 286

The *Operations Guide* contains no information about these jumpers, but a telephone call to Compaq revealed that the first three jumpers are for enabling or disabling COM1, COM2, and PRN, respectively. The fourth one is removed in order to change the primary address for the floppy-diskette controller from 3F0H to 370H so two more floppy-disk drives can be added to the machine. This information is in the *Maintenance and Service Guide*, which is not supplied with the machine but is available as an option.

The computer tested for this article arrived with Compaq's own hard-disk controller card and a 30MB hard disk. This is recommended because it gives users a high-quality, high-performance disk that is guaranteed to work in their machines. A user who wishes to buy a third-party hard disk should realize that, unlike the AT, the base model Deskpro 286 does not contain a hard-disk controller. Several controllers are available, but Compaq has not tested any of them with the Deskpro 286. The user should test drive a third-party controller before purchasing one.

EXTRAS, EXTRAS!

In addition to all the standard AT features, the Deskpro 286 includes several extras not found in any IBM models. The most notable of these is the tape backup system.

To address the problem of backing up data from a 30MB hard disk, the Deskpro 286 model 3 includes a tape backup unit capable of reading and writing the small DC-1000 tape cartridges from 3M. Although this unit seems to work reliably, it has two problems that suggest it will not become a favorite among users. It is relatively slow, and it cannot back up the entire hard disk on a single tape.

Formatting a tape is normally a time-consuming operation, and the Deskpro 286's tape-formatting is no exception. Approximately 20 minutes are required to format each 10MB tape, and another 20 minutes to fill that tape with backup data. That is one hour to format enough tapes to back up the complete 30MB hard disk, and another hour to copy the data.

Lack of speed would not be a crucial deficiency for the tape drive if the user could invoke the tape backup utility and then walk away while the unit continued to capture the data on the disk. However, each cartridge stores only 10MB of data, so backing up a 30MB hard disk requires at least three tape changes during the process.

Another special feature that all Compaq models have is the dual-mode monitor and display adapter. This monitor/adapter combination allows text to be displayed with the same resolution as IBM's monochrome adapter/monochrome monitor combination. Other characteristics of the monochrome adapter, such as underlining and reverse video, also are supported. The dual-mode monitor/adapter is compatible with the IBM CGA, allowing graphics to be displayed on the screen and a third-party color monitor to be connected.

The Compaq adapter is really just a CGA with the extra capability to support high-resolution characters. Like the

Compaq allows users to switch the processor speed between 6 MHz and 8 MHz by pressing Ctrl-Alt-\. This accommodates those programs that simply will not work at higher speeds.

CGA, it contains 16KB of video memory starting at address B8000H, and it supports video modes 0 through 6 for 40-column text (modes 0-1), 80-column text (modes 2-3), and graphics (modes 4-6). Even though it can generate high-resolution characters, it does not support mode 7, used by IBM's monochrome adapter.

The key to Compaq's ability to display high-resolution characters is in the character generator on the display adapter. Whereas in graphics mode, characters are formed by copying dot patterns that are stored in the system ROM BIOS, in the text modes the character generator is used. In the 80-column text modes, the generator can produce two different kinds of characters, and the dual-mode monitor is capable of displaying either kind.

The two kinds of characters correspond to the high-scan and low-scan modes of the monitor. In low-scan mode, the video signal sent by the display adapter uses a horizontal scanning frequency of 15.7 KHz and a vertical scanning frequency of 60 Hz, noninterlaced. These frequencies, which are the same ones generated by the CGA, are compatible with color monitors. The

display adapter sends characters that use an 8-by-8 dot pattern, just like those generated by the CGA. In addition, the attribute byte associated with each character is the standard color attribute byte (indicating the foreground and background color, the intensity, and whether the character is blinking). Low-scan mode is the only one used for the 40-column text and graphics modes.

In high-scan mode, the video signal sent by the display adapter uses a horizontal scan frequency of 18.5 KHz and a vertical scan frequency of 50 Hz, noninterlaced. The display adapter sends characters that use a 9-by-14 dot pattern, just like those generated by the IBM monochrome display adapter. In addition, the attribute byte associated with each character is the same as that used with the IBM monochrome display adapter (allowing normal, reverse video, invisible, underlined, blinking, and high-intensity characters).

By default, whenever the Compaq is in the 80-column video modes, it displays the characters in high-scan mode. Therefore, even though programs think they are dealing with an ordinary CGA in text mode, the characters that appear on the screen are the higher-resolution variety that is normally associated with the IBM monochrome adapter.

A user can switch between high-scan and low-scan modes by pressing Ctrl-Alt-> (for high-scan) and Ctrl-Alt-< (for low-scan). This can be done while running any program, because an individual program will notice no difference between the two modes. Switching to low-scan mode allows text to be displayed on a third-party color monitor.

Compaq allows users to switch the processor speed between 6 and 8 MHz by pressing Ctrl-Alt-\. This accommodates those programs that just will not work at higher speeds (although with the AT now available in an 8-MHz version, fewer of these programs will be apparent). Once the key combination is pressed, the machine announces the mode by beeping (once for 6 MHz, twice for 8 MHz). The same beeping announcements occur when booting the computer. Although this is a clever way to indicate the processor speed, the double-beep during boot-up is very similar to the BIOS error beeps that occur when the PC experiences a parity error. A more distinctive sound would prevent veteran PC users from experiencing a sudden rush of anguish the first few times they boot their Deskpros.

The processor speed also can be set using the DOS MODE command, which offers an additional (and for-

TABLE 1: Compatibility and Performance Tests

	IBM AT with 30MB disk ^a (8-MHz model)	COMPAQ DESKPRO 286 with 30MB disk Fast ^b	High ^c	COMPAQ PORTABLE II with 10MB disk Fast	High
ATBIOS					
ROM BIOS date	11/15/85	11/20/85	11/20/85	11/20/85	11/20/85
ATPERF					
Average RAM instruction fetch (μ s)	0.403 (100) ^d	0.404 (100)	0.404 (100)	0.404 (100)	0.403 (100)
Average RAM read time (μ s)					
BYTE	0.401 (100)	0.403 (99)	0.401 (100)	0.403 (99)	0.401 (100)
WORD	0.401 (100)	0.403 (99)	0.401 (100)	0.403 (99)	0.401 (100)
Average RAM write time (μ s)					
BYTE	0.401 (100)	0.404 (99)	0.402 (100)	0.404 (99)	0.402 (100)
WORD	0.401 (100)	0.403 (99)	0.401 (100)	0.403 (99)	0.402 (100)
Average ROM read time (μ s)					
BYTE	0.401 (100)	0.403 (100)	0.401 (100)	0.403 (100)	0.401 (100)
WORD	0.401 (100)	0.403 (100)	0.401 (100)	0.403 (100)	0.401 (100)
Average video write time (μ s) (CGA only)					
BYTE	1.208 (100)	1.111 (109)	1.013 (119)	1.111 (109)	1.013 (119)
WORD	2.415 (100)	2.217 (109)	2.025 (119)	2.217 (109)	2.025 (119)
Average EMM read time (μ s)					
BYTE	0.402 (100)	0.540 (74)	0.403 (100)	0.540 (74)	0.402 (100)
WORD	0.402 (100)	0.540 (74)	0.402 (100)	0.540 (74)	0.402 (100)
Average EMM write time (μ s)					
BYTE	0.402 (100)	0.540 (74)	0.402 (100)	0.539 (74)	0.402 (100)
WORD	0.402 (100)	0.540 (74)	0.403 (100)	0.540 (74)	0.402 (100)
CPU clock rate (MHz)	8.0 (100)	7.9 (99)	8.0 (100)	7.9 (99)	8.0 (100)
Math coprocessor clock rate (MHz)	5.3 (100)	4.2 (78)	5.3 (100)	4.2 (78)	5.3 (100)
Refresh overhead (%)	7.1	6	7	6	7
RAM read wait states	1	1	1	1	1
RAM write wait states	1	1	1	1	1
ROM read wait states	1	1	1	1	1
Video write wait states (CGA)	8	7	6	7	6
EMM read wait states	1	2	1	2	1
EMM write wait states	1	2	1	2	1
ATFLOAT					
Performance as percentage relative to AT	100	80	100	80	100
ATDISK					
Sectors/track	17	17	17	17	17
Heads	5	5	5	4	4
Cylinders	731	695	695	304	304
Total space (million bytes)	31.81	30.25	30.25	10.58	10.58
Track-track seek time (ms)	9.9	6.4	6.4	16.9	16.8
Average seek time (ms)	37.0	40.2	40.5	71.6	71.6
Effective transfer rate (KB/sec)	170.1	256.2	256.2	255.0	255.0
DOS file I/O (sec)	7.3	8.1	9.1	10.0	9.3
Interleave	3	2	2	2	2

^a The figures for the IBM AT are the average results from several machines, whereas the results from the Compaq machines are taken only from the review sample model.

^b Fast is the default speed.

^c High is obtained by the MODE SPEED command.

^d Figures shown in parentheses represent the relative performance expressed as a percentage compared to PC Tech Journal's baseline machine, the 8-MHz, 30MB AT.

The 8-MHz Deskpro 286 has an 8-MHz processor and a 6-MHz bus in default mode. Compaq memory has special circuitry that allows it to be accessed with only one wait

state. Third-party memory boards are accessed with two wait states. The DOS command MODE SPEED = HIGH, enables the Deskpro to operate as a full 8-MHz machine.

THE PORTABLE II: MEETING FAMILY EXPECTATIONS

The smallest member of the Compaq family, the new Portable II, compares favorably with its larger and heavier siblings. With a few exceptions, its compatibility and performance figures match those of the Deskpro 286.

Although the Portable II contains almost all the features of Compaq's earlier Portable 286, this redesigned model occupies almost one-third less space. By using one-third-height disk drives, providing only two extra expansion slots (one 8-bit and one 16-bit slot) and locating the function keys on a single horizontal row above the numeric keys, Compaq was able to squeeze an entire AT-compatible computer into a box that measures 13 inches deep, 17½ inches across, and 7¼ inches high. The review computer was a model 3 and contained a single 360KB diskette drive and a shock-mounted 10MB hard disk. It weighed in at a mere 23.6 pounds, 17 percent lighter than a comparably-equipped Portable 286. At this size and weight, carrying a computer through a busy airport and trying to store it under an airline seat at long last becomes a manageable proposition.

Compaq compromised little to achieve the smaller size. The screen is a 9-inch dual-mode monitor that is even a little larger than the ones that have graced previous Compaq portables. The diskette drive, a one-third-height model, uses ordinary 360KB 5¼-inch diskettes. Even the keyboard is an AT-style model, with the only difference being the position of the 10 function keys. Compaq chose not to provide a 1.2MB diskette drive with



the Portable II, which may be a wise move judging from the difficulties the Deskpro 286 experiences in reading and writing 360KB diskettes.

The Portable II offers the same extra features as the Deskpro 286, such as the dual-mode monitor and speed selection switch (but not the tape backup system). However, Compaq has made some design improvements to address the most common complaints made of its earlier models. The Portable II has an acceptably long keyboard cable, which slides out from a deep trench under the diskette drive. It is long enough for the user to

set the computer on a desk and lean back with the keyboard in his lap.

The adjustable legs on the computer have been redesigned. The keyboard legs open by tilting back, instead of to the side, making the keyboard less likely to collapse due to sideways jarring. The tilt-up legs are gone from the main unit too, replaced by a wide brace that doubles as a door to the power-cord container. This new design makes the unit much more stable and allows for convenient storage of the power cord.

The plastic outer shell on the Portable II is a single piece, so users

merly undocumented) high-speed mode that is not available with the keyboard sequences.

MODE SPEED=FAST is the 8-MHz mode described above. This default mode sets the CPU to 8 MHz and the bus to 6 MHz. MODE SPEED=COMMON is the 6-MHz mode that sets the CPU and bus to 6 MHz. Setting the mode via DOS does not provide any audible indication as does the Ctrl-Alt- key combination. The Deskpro 286 processor also can be set to run at 8 MHz with an 8-MHz bus using MODE SPEED=HIGH. This is not the default mode—it cannot be accessed using Ctrl-Alt- , and it is undocumented in all but the most recent Compaq manuals

(scheduled to be released this summer). Nonetheless, it is available to enable the machine to be run at its fastest speed. The current mode of the machine can be determined using the command MODE SPEED. The response will be FAST, COMMON, or HIGH.

EASE OF INSTALLATION

One of the most difficult parts of installing hardware in the Deskpro 286 involves the screws. The cover of the system unit is fastened with three screws on the rear panel, among a total of eight similar-looking screws, so selecting the right ones can be a guessing game. Furthermore, most of the screws on the Deskpro 286 are the Torx T-15

type, which are great for automating Compaq's manufacturing process, but difficult to remove with common screwdrivers (and few ordinary people actually own Torx screwdrivers).

The Deskpro's system unit cover is a wraparound design similar to that of the PC and AT. It slides forward and then lifts straight up and off. Because the keyboard is attached at the front of the unit, it must be removed before taking off the cover. (Nonetheless, this is much more accessible than fumbling around the back of an IBM model to attach and detach the keyboard.)

Despite these few inconveniences, installing hardware in the Deskpro 286 is, for the most part, an easy process.

who are used to prying the side walls off the old portables can save their fingernails. When the computer is sitting so the handle points up, the shell lifts straight up and off. However, some energetic prying is required to maneuver the plastic protrusions around the power switch.

Like the Deskpro 286, the Portable II uses Torx screws. The plastic case has a different size (T-15) than the aluminum panels and slot covers (T-10); neither set has grooves for flat blade screwdrivers. Compaq does not include screwdrivers of either size with the Portable II.

Unlike the Deskpro, the Portable II's system board has room for 640KB of RAM. In addition, Compaq offers a special memory board, with room for up to 1.5MB of memory, that plugs directly into the back of the system board instead of requiring an expansion slot. This extra memory can be treated only as extended memory, with addresses beginning at 1MB. By allowing for more than 2MB of memory connected directly to the system board, the competition for expansion slots is minimized.

The Portable II has only four expansion slots, of which two are in use. In the model 3 tested, slot 1 contains the controller for the hard disk and diskette drive. This controller also contains an asynchronous communications port and a parallel printer port. Slot 2 contains the dual-mode video display adapter. Slot 3 is a 16-bit and slot 4 is an 8-bit slot. This lack of expansion slots could be a problem for users who have many options to install. The Portable II is no different from other portable computers in this area, however. Small size and ade-

quate room for expansion cards seem to be mutually exclusive.

Slot 4 on the Portable II is set apart from slot 3 to allow room for an internal modem's speaker—a natural option on such a machine. However, the space between slot 3 and the neighboring slot 2 is insufficient to install a piggyback card. This limitation prevents Intel's 4MB Above Board from being installed in the Portable II. The video card in slot 2 cannot be moved to the other 8-bit slot (slot 4) to make more room, because the ribbon cable connecting the display to the adapter is too short to allow the adapter to reside in the farther slot. Only the 2MB version of Above Board (without the piggyback) can be installed. This narrow slot will probably cause the same problem when installing any 16-bit card with a piggyback.

Another problem with installing Above Board is that the board is too tall to fit properly unless the plastic support bracket is removed from the Portable II's board slot access cover. Whether Compaq or Intel is at fault here is open to question. Users who plan to use expanded memory should be aware of the difficulties of squeezing the Intel board into the Portable.

The same compatibility and performance tests were run on the Portable II as were run on the Deskpro 286, and for the most part, the same results were obtained. The Portable II was able to run all the sample software and, except for the difficulty in installing Above Board, it worked with the add-on hardware products.

Like the Deskpro 286, the Portable II failed the video adapter test in the IBM AT Advanced Diagnostics, it ran the 80287 math coprocessor at

only 4.2 MHz in the default mode, instead of the expected 5.3 MHz, and it used two wait states instead of one when accessing expanded memory, again in the default mode (indicating a 6-MHz instead of an 8-MHz expansion bus). But also like the Deskpro 286, accessing the video memory on the color/graphics adapter was 60 percent faster than on the AT. Full 8-MHz capabilities (expansion bus and CPU) are available in the same way as on the Deskpro 286 by using the DOS `MODE SPEED=HIGH` command.

The Portable II did not measure up to the Deskpro 286 in hard-disk performance. As table 1 in the main article shows, the seek time of the Portable II's 10MB drive, both track-to-track and average, was double that of the Deskpro 286's 30MB unit. These figures are comparable to a lower performance XT-class machine. Compaq recently announced a 20MB hard disk for the Portable II, but it was not available in time for this review.

The Portable II offers the state of the art in portable computing without the unpleasantness of LCD displays or the compatibility problems of 3½-inch diskettes. Although the 10MB drive does not measure up to the standards expected for 80286 computers, the nondisk performance figures match those of the Deskpro 286, and the Portable II is as compatible as any Compaq model. Its hard-disk deficiencies and lack of expansion slots preclude the Portable II from being effective as a user's primary, high-performance computer. But as a business computer to take on the road, or for transporting between home and office, it is an ideal solution.

—Steven Armbrust and Ted Forgeron

Photo 4 shows the interior of the system unit. Adding an 80287 math coprocessor is simple (even though the Deskpro's *Guide to Operations* manual does not mention the 80287 socket), because the socket is located under board slot 1 where it is quite easy to reach, rather than near the power supply as on the AT. One minor annoyance is a metal brace that fastens between the front and rear panels of the system unit and is positioned directly over slot 1; the brace must be taken out before any board can be installed in or removed from that particular slot.

The peripherals (diskette drive, tape drive, and hard disk) are surrounded by a sheet-metal enclosure,

preventing any sensitive components or mechanical pieces from being jostled or damaged while working in other areas of the unit. In fact, the metal enclosure is solid enough to hold test equipment or additional drives that need to be tested before installation.

Because of the kind of hard-disk drive that Compaq uses (a rugged-looking piece of Control Data equipment), a manual head-unlocking step must be performed before using the computer initially. As shipped from the factory, the drive's locking lever is pulled out in its locked position and held there with a plastic washer and cotter pin arrangement (see photo 5). Before applying power to the computer, the user must

remove the cotter pin and plastic, push the lever into its unlocked position, and plug the unit into the power supply (which could not be done before because the locking mechanism blocked the connector). A sticker on the front of the drive warns users that they must follow this procedure. Of course, when preparing the unit for moving, this process must be reversed in order to lock the heads again.

The manual head-locking procedure perhaps is less convenient than using software to lock the heads, but a certain comfort is derived from knowing—really knowing—that the drive's heads are securely locked during a bumpy move.

Orchid's TurboEGA™

The world's *fastest* EGA

Introducing the only Enhanced Graphics Adapter with Pcturbo™ speed.

The experts agree: the EGA is the breathtaking new graphics standard, but the sophisticated software written for it places a big burden on the PC's processing speed. Beautiful graphics, crisp text, but too slow.

Everyone else rushed their EGAs to the market, but Orchid Technology took the time to do it right. Orchid's TurboEGA™, from the inventors of PC TurboProcessing, packs a high-speed Turbo and an EGA into one slot, for the world's fastest EGA.

Graphics with Speed

TurboEGA makes IBM PCs and XT's run faster than an AT. It brings dazzling speed to sluggish graphics programs. All types of software run faster, so you finish more quickly. Transparent to the user, you won't know it's there until you see its speed.

We are so confident that our TurboEGA is the ultimate graphics card that we decided to give away a free copy of Microsoft's Windows™ with each TurboEGA*. Even Microsoft recommends that you run Windows on an AT. Now Orchid's TurboEGA gives you AT speed so XT users can use this number one windowing software at the speed they demand.

The Complete Solution

Only Orchid puts this much performance into one slot and comes fully loaded with 256K of RAM, so there's no hidden cost. TurboEGA is the complete graphics solution.

Pick up the phone and find out how you can have the EGA the competition wishes they had: Orchid's TurboEGA, the world's fastest.

If you have an AT or a system with 80286 speed, ask about the Orchid EGA™—four graphic-card compatibility in one slot.

Features:

- Powered by 7.2MHz 80286
- Optional 5 or 8MHz 80287
- 256K of on-board RAM
- Four graphics modes: EGA, CGA, MDA, Hercules
- Supports the long list of EGA software:
 - Microsoft Windows & Word
 - Lotus 1-2-3 & Symphony
 - Topview
 - Framework
 - Chart-Master
 - AutoCAD
 - PC Paint Plus
 - and more...



47790 Westinghouse Dr.
Fremont, CA 94536
415/490-8586
Tlx: 709289

*Offer good only on TurboEGA purchases until July 31, 1986. Please allow two weeks for delivery.

TurboEGA, OrchidEGA, and Pcturbo and trademarks of Orchid Technology. Microsoft Windows is a trademark of the Microsoft Corporation. All other product names are trademarks of their manufacturers. CGA screen by PC Paint Plus.

CIRCLE NO. 142 ON READER SERVICE CARD

INSIDE THE SYSTEM UNIT

The Deskpro 286 has eight expansion slots—six 16-bit slots and two 8-bit slots. In the unit tested, four of those slots (all 16-bit) were occupied. Three of the four were used by the drive controllers for the hard disk, tape, and diskette (the diskette controller also contains an asynchronous communications port and a parallel printer port).

The fourth slot contained a memory card. Bucking the trend to put more and more memory on the system board, the Deskpro 286 contains no memory whatsoever there; all of its memory resides on expansion cards. Although this may be a waste of slots, it has certain advantages. If a soldered memory chip goes bad (even the Deskpro's memory card uses one row of soldered chips), the system board does not need to be removed. Further, when higher capacity 1-megabit chips become available, a new memory board can be added rather than having to replace the entire system board.

The Deskpro 286's hard-disk drive is impressive. A 30MB Control Data model, it is encased in cast aluminum with cooling fins protruding in all directions, just like an old air-cooled Volkswagen engine. It looks sturdy enough to survive a drop out a window, although it was not subjected to that test during this review.

The power supply is a 120-volt, 4-amp model that should adequately handle any expansion cards or peripherals that are installed. (The AT has a 115-volt, 5-amp power supply). The Deskpro's power supply also has a sloping top face with a 4½-inch fan for plenty of cooling air flow. The AT's power supply contains a 3-inch fan.

The Deskpro 286 comes equipped with Compaq DOS 3.1 and GW-BASIC. For the most part, Compaq DOS is the same as PC-DOS. The only items missing from the Compaq package are the BASIC.PIF and BASICA.PIF files (Top-View program information files) and VDISK.LST (the source listing of the DOS RAM-disk device driver).

Compaq DOS offers several commands not available with PC-DOS. CMPQADAP.COM adapts the system so that it can display and print characters in other languages. DISKINIT.COM is a multipurpose utility that formats disks, creates partitions on hard disks, sets the date and time, copies system files and utilities to the formatted disk, and creates AUTOEXEC.BAT and CONFIG.SYS files. SETCLOCK.COM displays and sets the date and time in the proper format and language based on

the country code. TAPE.EXE performs tape operations such as backup, restore, format, and directory.

Another Compaq DOS extra is ENHDISK.SYS (for enhanced disk), which is a device driver that partitions the hard disk into multiple logical drives, each of which can be referred to by a unique drive letter. Four additional keyboard drivers (KEYBDA.COM, KEYBNO.COM, KEYBSU.COM, and KEYBSV.COM) are included in Compaq DOS to accommodate users working with foreign keyboards. According to

T*he Deskpro's 30MB Control Data hard-disk drive looks sturdy enough to drop out a window, although it was not subjected to that test during this review.*

Compaq, the information required to install these drivers is supplied when the computer is sold into the relevant European market.

TESTING

Two kinds of tests were run to check the compatibility and performance of the Deskpro 286. First, a selected set of add-on products and popular applications was installed and tested. Then the *PC Tech Journal* AT Evaluation Suite was run. This is a set of compatibility and performance tests written especially for the *PC Tech Journal* series on AT-compatible machines. (For more information about these tests, see the preceding article, "Out from the Shadow of IBM," Steven Armbrust, Ted Forgeron, and Paul Pierce, p. 52.)

The add-on products installed were an Intel Above Board AT with 4MB of memory, a Microsoft bus mouse, a Hayes Smartmodem 1200B, and an IBM Enhanced Graphics Adapter and display. Every one of these products worked with the Deskpro 286. Only Above Board showed performance differences in the default mode of the Deskpro 286. It ran with two wait states on the Deskpro 286 and only one wait state on the AT. The cause of that anomaly is discussed later in this article.

The applications tested included the graphics-intensive programs Microsoft Windows and Microsoft Word; the

memory-resident programs SideKick, SuperKey, and Turbo Lightning, all from Borland; the expanded-memory program Ready!, from Living Video Text; and the communications program Smartcom II, from Hayes. Although not every feature of every program was tested, those that were tested worked as intended, including printing on a parallel printer and communicating via the asynchronous communications adapter.

The IBM AT SETUP program and the IBM Advanced Diagnostics were run on the Deskpro 286. The SETUP program worked fine, except that it forced the Compaq dual-mode monitor into its medium-resolution mode (the Compaq set-up program leaves the monitor in high-resolution mode). The Deskpro 286 passed all of the advanced diagnostic tests except for the color/graphics test (test 500), due to its dual-mode monitor and display adapter.

Table 1 compares the results of the *PC Tech Journal* compatibility and performance programs—ATBIOS, ATKEY, ATPERF, ATFLOAT, and ATDISK—with those obtained when the tests were run on an 8-MHz AT with a 30MB hard disk. Two columns are listed for the Deskpro 286: one for the default mode (8-MHz processor and 6-MHz bus) and one for the high-speed mode (8-MHz processor and bus). To compare these figures with other IBM computers, refer to table 1 in "Out from the Shadow of IBM," this issue, p.52. (The compatibility and performance tests also were run on the Compaq Portable II. See the accompanying sidebar, "The Portable II: Meeting Family Expectations.")

ATBIOS was used to check the BIOS and BIOS data areas to glean information about the BIOS and to determine whether commonly used information is stored in the same locations as in the AT. ATBIOS showed that the BIOS is manufactured by Compaq, the BIOS and its data areas are compatible with the IBM counterparts for the areas tested, and the configuration of the system is as described earlier.

ATKEY tested the keyboard for compatibility and found that the Deskpro 286 uses the same 8042 keyboard processor chip that the AT uses. As a further check, an AT keyboard was plugged into the Deskpro. Although no extensive tests were performed using this set-up, the AT keyboard worked fine during normal operation on the Deskpro. This should be good news for those who want to abandon Compaq's keyboard in favor of one from the AT.

The performance of the CPU, the math coprocessor, and the memory



MAKE THE CONNECTION . . .

Our **Connection** systems will solve your problem of trying to read and write diskettes or tapes from almost any computer system using your PC.

The **Diskette Connection** is a hardware system that enables the IBM PC or compatible to read and write most 8 inch, 5¼ inch, or 3½ inch diskettes.

With our **File Connection** software programs you can transfer data files between most computer systems, including CP/M, DEC, Honeywell, Univac, IBM 3740, S/1, S/3, S/23, S/32, S/34, S/36, and S/38.

Our **Word and Typesetting Connection** programs use IBM standard Document Content Architecture (DCA-RFT) to transfer document files between most word processing and typesetting systems, including Compugraphic MCS, CPT, Displaywriter, OS/6, Multiset, NBI, Quadex, Xerox, and Wang.

Our **Tape Connection** system will read and write IBM or ANSI standard ½ inch 1600 BPI magnetic tape. A full size 2400 foot tape can store a 45 MByte file and be written in 6 minutes.

Since 1982, we have supplied thousands of systems to customers around the world, including IBM, NASA, AT&T, Kodak, and General Motors.

Our specialty is conversion systems and we can provide a solution to your problem. Call us today to discuss your requirements.

This ad is one of a series featuring NASA missions. For a free poster, send us your written request.

Box 1970 Flagstaff, AZ 86002
(602) 774-5187 Telex 705609

CIRCLE NO. 153 ON READER SERVICE CARD

. . . FLAGSTAFF ENGINEERING

were tested using the ATPERF program. In the default mode, the CPU clock rate tested slower than the advertised 8-MHz rate. The math coprocessor clock rate also was slower than expected. In an 8-MHz AT, both the CPU and math processor clock rates are derived from a 16-MHz crystal. The CPU clock rate is one-half the rate of the crystal (8 MHz); the math processor rate is one-third the crystal rate (5.3 MHz). Therefore, if Compaq used a technique similar to IBM, the math coprocessor should have run at 5.3 MHz instead of the 4.2 MHz that was measured during testing. Once the Deskpro 286 was switched into high-speed mode, however, both the CPU and math coprocessor ran at their expected rates.

ATPERF was used to investigate a difference between the Deskpro 286 and the AT when using Intel's Above Board. As mentioned earlier, when the Deskpro is in its default mode (MODE SPEED=FAST), the expanded memory manager (EMM) runs with two wait states in the Deskpro, compared with only one in the AT. The ATPERF results revealed why an 8-MHz computer is not always an 8-MHz computer.

As it turns out, the Deskpro 286's expansion bus is the culprit, not Above Board. Even though the 80286 CPU runs at 8 MHz (or almost 8 MHz), the expansion bus, through which all expansion cards communicate with the CPU, runs at only 6 MHz in the default state. Thus, accessing memory on an expansion card takes just as long in 8-MHz mode as it does in 6-MHz mode. (With two wait states, four clock cycles are required: two that the CPU normally uses and two wait states; with one wait state, three clock cycles are required. Four 8-MHz clock cycles take the same time as three 6-MHz clock cycles. Therefore, an 8-MHz computer operating with two wait states is the same as a 6-MHz computer operating with one wait state.)

The Deskpro 286's own memory card has special circuitry to allow that memory to run at 8 MHz in the default mode, which explains why the Deskpro's conventional memory runs with one wait state. However, to run third-party products, such as Above Board, AST RAMPAGE!, or others, with the minimum number of wait states, the DOS command MODE SPEED=HIGH should be used. This cannot be switched with the keyboard sequence Ctrl-Alt-\, and the Deskpro does not give an audible indication that it is in the high mode.

When Compaq introduced the Deskpro 286, no 8-MHz IBM machine yet existed. Compaq probably reasoned

that a 6-MHz bus would ensure compatibility with expansion cards built for the 6-MHz AT. So, even though it made a bus that can be switched between 6 MHz and 8 MHz, it made the 6-MHz bus the default. With an 8-MHz AT now available, however, it becomes clear that Compaq's flexibility in providing compatibility and performance has paid off. If compatibility is crucial, the bus can be left running at 6 MHz. If speed is important, a switch to an 8-MHz bus (although formerly undocumented) is possible. In addition, the time required to write to video memory (using the Deskpro's dual-mode adapter) is 8-percent less than for the AT.

Even though the 80286 CPU runs at 8 MHz (or almost 8 MHz), the Deskpro 286's expansion bus runs at only 6 MHz when it is in the default state.

ATFLOAT confirmed the poor performance of the 80287 in the Deskpro 286's default mode. In high-speed mode (MODE SPEED=HIGH), the Deskpro 286 measured up to the 8-MHz AT.

The results of ATDISK show that the performance of the Deskpro 286's hard disk is in the same league as the high-performance AT models. One interesting note is that although both IBM and Compaq advertise a 30MB drive, the Compaq disk has 36 fewer cylinders and 1,566,720 fewer bytes of storage.

In addition to compatibility and performance tests, a very important factor in judging a computer is its technical documentation. Compaq documentation has come a long way from the early days of the Compaq Portable. The manuals are now printed on heavy, high-gloss paper, and contain information that is well laid-out and easy to find. The *Operations Guide* still lacks the detailed information found in the IBM manual—for example, Compaq excludes mention of the 80287—but for the most part, the documentation is helpful and well-organized.

CONTINUING TRADITION

The Deskpro 286 is a well-built computer that continues Compaq's tradition of compatibility and added value. It is

better than the AT in that it offers both 6- and 8-MHz speed on the same machine. Its video write time is faster than that on the 8-MHz AT.

However, it is unfortunate that Compaq did not make the Deskpro 286's fastest operating speed (MODE SPEED=HIGH) the default speed for the computer and, further, that it did not provide a Ctrl-Alt-\ option to switch the Deskpro 286 into the faster mode from the keyboard. Obviously, the system designers included two different 8-MHz modes in the Deskpro 286 because they were not sure whether the expansion bus on the 8-MHz IBM AT was going to run at 6 MHz or 8 MHz. By making the conservative choice of the 6-MHz bus (MODE SPEED=FAST) to be the default mode, they seem to have guessed wrong.

Nonetheless, the designers should have allowed the high-speed mode to be set with the Ctrl-Alt-\ keyboard sequence. This is a quick and easy way to switch speeds even from within a program; furthermore, it offers audible feedback on the choice. As it stands now, the only way to ensure that the Deskpro 286 will always be operating at its highest speed is by placing a MODE SPEED=HIGH command into the AUTOEXEC.BAT file.

Just as unfortunate is Compaq's decision not to document the high-speed mode in its original manuals, although, by the time this review appears in print, Compaq probably will have added the description to the documentation.

Of course, only the benefit of hindsight shows Compaq's decisions on speed selection to be faulty. It is to the company's credit, and typical of Compaq, that it chose to make the Deskpro 286 compatible with the then-current IBM AT, but included enough options to allow it to perform as fast as the new 8-MHz AT. Like other computers in the Compaq family, the Deskpro 286's reputation for compatibility and performance is warranted.



Deskpro 286
Compaq Computer Corp.
2033 FM 149
Houston, TX 77070
713/370-0670
CIRCLE 352 ON READER SERVICE CARD

Steven Armbrust, a freelance technical writer, and Ted Forgeron, software project manager for Intel Scientific Computers, will be reviewing several AT-compatible computers for this series. They are the authors of the Programmer's Reference Manual for IBM Personal Computers to be published by Dow Jones-Irwin in October 1986.

OFFICE AUTOMATION

Tech PC, we're out to capture your micro-computer business. No one matches our diverse line of high performance products, or our comprehensive system of support, warranty, and third party maintenance service options. Tech PC is a large Southern California computer design and manufacturing firm with computer research and design specialists, production engineers, technical assistance staff, qualified sales personnel, and a strong management and investment team to provide you with state of the art products, state of the art reliability, and state of the art economy.


PORTABLES

Tech PC Portable Computers come in four different base models to match your computing needs. Our entry level **Tech PC/XT** portable computer is designed to provide a non-obstructive profile, and has a capacity to hold two thirty megabyte hard disks, a high resolution monochrome monitor with a Hercules compatible graphics card to drive it with 800 by 400 lines resolution, and never before heard of 6 expansion slots in a portable computer. If 4.77 MHz of Intel 8088 power isn't fast enough, try our **Turbo 4.77 to 8 MHz 8088-2** or optional NEC V-2 microprocessor based portable machine. Designed to increase speed up to 170 percent of a standard PC/XT, the **Tech PC/AT and Tech Turbo PC/AT portable units are state of the art in portable performance.** The 80286 microprocessor based units can be fitted with up to 240 megabytes of high speed voice coil hard disk technology, and with the Turbo AT's 10 MHz math co-processor socket and 10 MHz

80286 microprocessor the unit can manipulate large spreadsheets with unparalleled performance.

DESKTOPS

Tech PC Desktop Computers are designed for survival. The **XT's** leave your desktop looking comfortably empty with their slim non-obtrusive profile; The **AT's** give you a powerful presence with a clean lined sturdy chassis. Combined with a 14 inch, 800 by 400 line amber monochrome monitor or a 14 inch, 1280 by 800 black and white monochrome monitor you've got **State of the Art** staring straight back at you. If 8 MHz 80286 power isn't fast enough for you... try the **Tech Turbo PC/AT** with its 10MHz 80286 and 10 MHz 80287 math co-processor socket. The **Tech Turbo PC/AT** gives you the **strongest, most powerful 80286** performance available from anyone, anywhere... available with up to 16 megabytes of memory and hard disks up to 1 gigabyte with our new optical storage disk, the Tech Personal



Computer Desktops represent the cutting edge of desktop microcomputer technology.

Tech Personal Computers, Inc. is a full service manufacturer of Micro Computer Products and offers a complete line of Desktop, Portables and Multi-User Computer Systems as well as an accessory line of over one hundred enhancement products. **Tech Personal Computers, Inc.** are all backed by a full one year warranty with additional maintenance coverage and extended maintenance contracts available through Momentum Service Corp. For more information concerning hundreds of MSC Service Centers throughout the United States, contact **Tech Personal Computers, Inc.** at (714) 754-1170.



OFFICE ON LOCATION

DESKTOPS

TECH PC/XT DESKTOP\$ 529

Options:

Tech PC/XT with 20MB Hard Disk\$ 979

Tech PC/XT with 20MB Hard Disk, Monochrome Monitor, Hercules® Compatible Mono/Graphics Card\$1179

TECH TURBO PC/XT DESKTOP\$ 629

Options:

Tech Turbo PC/XT Desktop with 20MB Hard Disk\$1079

Tech Turbo PC/XT 20MB Hard Disk, Monochrome Monitor, Hercules® Compatible Mono/Graphics Card\$1279

TECH PC/AT DESKTOP\$1399

Options:

Tech PC/AT with 20MB Hard Disk\$1799

Tech PC/AT with 20MB Hard Disk, Monochrome Monitor, Hercules® Compatible Mono/Graphics Card\$1999

TECH TURBO PC/AT DESKTOP\$1599

Options:

Tech Turbo PC/AT Desktop with 20MB Hard Disk\$1999

Tech Turbo PC/AT with 20MB Hard Disk, Monochrome Monitor, Hercules® Compatible Mono/Graphics Card ..\$2199

PORTABLES

TECH PC/XT PORTABLE\$ 899

Options:

Tech Turbo PC/XT Portable with 20 MB Hard Disk\$1349

Tech Turbo PC/XT Portable with 1200 Baud Internal Hayes Compatible Modem and 20 MB Hard Disk\$1549

TECH TURBO PC/XT PORTABLE\$ 999

Options:

Tech Turbo PC/XT Portable with 20 MB Hard Disk ...\$1449

Tech Turbo PC/XT Portable with 1200 Baud Internal Hayes Compatible Modem and 20 MB Hard Disk\$1649

TECH PC/AT PORTABLE\$1799

Options:

Tech PC/XT Portable with 20 MB Hard Disk\$2199

Tech PC/XT Portable with 1200 Baud Internal Hayes Compatible Modem and 20 MB Hard Disk\$2399

TECH TURBO PC/AT PORTABLE\$1999

Options:

Tech PC/XT Portable with 20 MB Hard Disk\$2399

Tech PC/XT Portable with 1200 Baud Internal Hayes Compatible Modem and 20 MB Hard Disk\$2599

All TECH PC PORTABLES available with tape backups, hard disks up to 1 gigabyte, networking systems, and hundreds of other hardware and software accessories.

TECH PC

714/754-1170

2131 South Hathaway, Santa Ana, California 92705
Telex 272006 Answer Back - TECH FAX: 71415568325



A time-tested storage technology also connects PC users to mainframes and minicomputers. These eight subsystems offer consistent performance and control over data storage and transfer.

Nine-track Tape Systems

ROGER ADDELSON

The nine-track, one-half-inch tape subsystem has provided a standard, reliable interchange medium for more than 30 years. Although its acceptance is practically universal, some of the old protocols and standards have become obscure in today's computer environments. Other protocols have evolved to take their places.

Densities have matured from 200 bits of data per inch (bpi) through 556, 800, 1,600, 3,200, to the 6,250 bpi seen today. Tapes once held four tracks, then seven, and finally emerged with the nine-track standard now in use. One byte is represented by eight bits plus a parity bit, which are stored in parallel fashion with one bit on each of the nine tracks of the tape.

Reviewed in this article are nine-track tape subsystems from eight companies: Alloy Computer Products, Inc., Catamount Corporation, Cipher Data Products, Inc., Digi-Data Corporation, Emerald Systems Corporation, Flagstaff Engineering, Innovative Data Technology, and Overland Data, Inc.

TECHNOLOGY IN COMMON

These tape devices usually record nine tracks of data in parallel along the tape using a separate head coil for each track. Many tape units use separate

read, write, and erase head coils so that the tape can be written, read for validation, and erased (if an error is detected) without stopping and backspacing the tape. A head that uses separate coils for read and write operations is called a dual-gap head. An additional erase head positioned after the read head is called a downstream-erase head.

Older 200-, 556-, and 800-bpi tape units implemented a standard format called NRZI (nonreturn to zero invert), which records a logical 1 as a flux reversal in the magnetic field and 0 as an absence of flux reversal. The mechanical requirements for this type of drive are more critical than for the high-density 1,600- and 3,200-bpi recorders that apply a PE (phase-encoded) format. PE format begins a logical 1 with a flux reversal from the non-erased direction to the erased direction and a logical 0 as a flux reversal from the erased to the nonerased. To ensure that the flux is in the proper direction in order to accomplish a reversal, a second flux reversal occurs for each bit that is recorded when the next bit is the same value, thus resetting the direction so it may again be reversed.

Most mainframe tape systems are capable of reading and writing 1,600-bpi tape, but will not recognize 3,200-

bpi formats. For 6,250-bpi tapes, the standard format is GCR (group-coded records), which records bits like the NRZI format does. It uses a translation table to map "artificial" bit patterns (five bits recorded for every four actual data bits) to eliminate bit patterns that yield more than two 0 bits in a row and more than one 0 bit starting or ending a subgroup. GCR also further expands every seven bits to eight using a sophisticated polynomial algorithm. The 6,250-bpi GCR format requires sophisticated electronics and is much more expensive (by about \$5,000) than 1,600-bpi PE systems. The tape subsystems that are considered in this review fall within the 1,600-bpi PE category.

Data are written to the tape in blocks, with a gap of .5 to 1.5 inches of erased or unrecorded tape between each block. This gap (normally .6 inch) is called an interblock or interrecord gap (IRG). Besides separating blocks, the IRG also functions to allow for data correction. When write errors occur (which are usually caused by a crease in the tape or an otherwise bad portion of the media), the bad section of tape is erased, and thus becomes an extended IRG. The block is written again further down on the tape.

The blocks of data on unlabeled tapes are separated into files with *tape marks*. A tape mark, or file mark, is recorded by writing an erase gap of roughly 3.5 inches, followed by several hundred high-frequency flux reversals at the maximum frequency allowed by the format (NRZI, PE, or GCR). This gap and the flux reversals are located on tracks 1, 2, 4, 5, 7, and 8, while tracks 3, 6, and 9 are held constant in the erased direction. This sequence cannot be mistaken for any binary data on the tape and thus is a place holder instantly recognized by the transport. Labeled tapes have additional header and trailer records surrounding the data blocks representing a file. (See figures 1 and 2).

IRGs require space on the tape. Because an IRG occurs between each block, it is prudent to have more than one record per block. For example, if a 1,600-bpi PE tape has one 80-byte record per block, the record would consume $\frac{80}{1,600}$ (.05) inch of tape. Adding the .6-inch IRGs, a foot of tape would hold only about 22 records. If, however, the records were combined into blocks of 40 records (3,200 bytes each), then about 200 records would fit on a foot. This format is called *fixed* blocking. (Some variable-length record blocking techniques use a prefix that contains a count and record length, but these

formats are not supported on most microcomputer tape subsystems.)

Two universally accepted ANSI-standard physical tape formats (labeled and unlabeled) are available, as well as an IBM/OS format. All are independent of density and recording method.

The standard for labeled tapes (figure 1) specifies 80-byte volume and header labels, followed by a tape mark, then the data blocks separated by IRGs, another tape mark and optional end-of-file (EOF) records, followed by a tape mark. The volume label is always at the beginning of a labeled tape. The record contains the six-character volume identifier and is created when the tape is initialized. The tape is then used repeatedly without reinitializing the volume label. ANSI and IBM tape labels are similar except that ANSI labels are in ASCII and IBM labels are in EBCDIC.

The ANSI standards for unlabeled interchange tapes consist of a series of data blocks, separated by IRGs, followed by a tape mark (figure 2). This sequence is repeated for each file on the

These tape subsystems have mainframe or minicomputer transport drives with interface cards and software for microcomputers.

tape. Some unlabeled tapes have a tape mark at the beginning of the tape just as labeled tapes have a volume label. Two tape marks occur after the last file on the tape; these two marks together specify the logical end of tape (EOT).

The speed of a tape system in general is dependent upon several factors: data density in bpi; transport speed, which varies from 25 to 100 inches per second (ips); and transport type. In addition to the actual tape unit speed, the speed at which data are transferred to the PC is also an important factor. For 100 ips at 1,600 bpi, 160 Kbps are available for transfer.

The most common method in which an interface processes data at this speed is via one of the PC's DMA channels, which allow a large block of data to be transferred directly to memory without the constant involvement of the CPU. The chip executes one command to begin the transfer, and then is free to handle other tasks. The PC has four

DMA channels available. Channel 0 is reserved for RAM refresh, and, conventionally, channel 1 is used by LANs, channel 2 by floppy-disk controllers, and channel 3 by hard-disk controllers. For the tape interface board, it is prudent to use a DMA channel that is not being used by another device during the transfer. Because two devices cannot use the same DMA channel at the same time, transfers are significantly slowed when the tape unit shares a channel. Therefore, determine the primary device to and from which data will be transferred, and choose a DMA channel for the tape interface that will not conflict with that device. Every system reviewed except one (the IDT package) offers the very useful feature of permitting the board and software to be configured for the DMA channel and I/O address the user chooses.

Surprisingly, most of these tape subsystems work more slowly on a PC/AT than on a PC or PC/XT. The problem lies in the way DMA requests are resolved: the AT system board contains two DMA controllers—one for byte transfers, one for word transfers. The byte controller is slaved to the word controller in such a way that *both* are involved in a request for byte-wide DMA. This additional hardware arbitration for control of the bus does not always allow operation at 100 ips (a typical high speed) on the AT without its dropping an occasional byte, whereas the PC and XT, which have only a single 8237A DMA controller chip, can operate a tape system at that speed safely.

TAPE OPTIONS

All of these tape subsystems consist of mainframe or minicomputer transport drives with interface cards and software developed for microcomputers. They use drives with the industry-standard Pertec/Cipher formatter protocol. The formatter is the microprocessor-based hardware interface between the host controller and the physical tape transport motors and tape heads. It is nearly always located within the tape transport itself, and provides a standard interface to diverse transport mechanisms, in the same fashion that virtually all hard-disk drives today use the ST-506 interface originated by Shugart.

The tape controller or interface board in the PC is typically connected to the transport formatter with two 50-conductor cables. Several of the manufacturers use the same physical tape transport, and differ only in their interface board and software design. Two of the companies represented in this re-


PHOTOS: Six Varieties of Nine-track Tape Transport




The Qualstar 1043 (top photo) was the smallest transport tested, but it works very speedily because it is equipped with an efficient set of driver software. Cipher Data's packaging of its own F880 transport (center) features a lift-top case. Alloy Computer Products and Emerald Systems both use the Pertec FS1511-19 transport (bottom). The Cipher and Pertec transports both load from the front.

Digi-Data's 2010-T tabletop transport (top photo) is small and moves tape very quickly. It also can be purchased in a rack-mounted version. Catamount Corporation packages the Cipher F880 transport (center) with its PCT-9S system. Catamount supplies a case that slides off to the rear. Innovative Data Technology furnishes a TOMACO TM-S transport (bottom) with its LEO tape system.

PHOTOGRAPHS: CHRISTINE ARMSTRONG / BLAKESLEE LANE

FIGURE 1: *Labeled Tape Format*

Header and volume label information, typically used only by mainframe JCL and applications for tape control purposes, cannot be read by some of these systems.

FIGURE 2: *Unlabeled Tape Format*

Files on unlabeled tapes have no headers or labels, and tape marks serve to separate files. Two adjacent tape marks with no intervening data or IRGs are recognized as logical EOT.

view, Cipher and Catamount, use identical transports, controllers, and software, and offer essentially the same product. (See table 1 for a comparison of product features and table 2 for controller specifications. Photographs of each type of system are shown on page 97.)

Each system was evaluated on ease of installation, quality of documentation, diagnostics, level of control over the tape hardware, and, of course, benchmark time tests. (Note that the order in which the products are reviewed does not reflect any judgment made as to their quality.) For the purposes of this analysis, both labeled and unlabeled test tapes were developed containing ASCII and EBCDIC files of varying lengths and types. The EBCDIC tapes were created on an IBM 3081D under

MVS, the ASCII tapes on a PDP-11/44 under UNIX. The tapes were read by the systems under examination, and written to another tape to be read by the host IBM and PDP-11. The results of these read/write operations were scrutinized closely to ensure that all data were read and written correctly.

Finally, two benchmark timing tests were run (see table 3). The first involves reading a 256KB ASCII file from tape to a DOS file on drive A: of a 4.77-MHz IBM PC. This test is a good indicator of the speed with which data can be transferred between the controller and a tape, and of the efficiency of a controller's DMA facility. The other test times the process of skipping 1,000 tape marks. Intervening data were not read, so this second test is an indicator of the

average speed with which selected files can be located on a large tape containing many files—it can be thought of as a test of the system "seek" time.

Flagstaff Engineering. The Flagstaff controller card and software (included in its model 8820 system) were evaluated with the Qualstar 1043 transport.

Flagstaff's installation instructions were excellent and installation went fairly well. It is, however, a bit awkward to pull the two 50-pin ribbon cables through the back of the PC, attach them both to the board, and then try to seat the board on the bus. A suggestion implemented by several other manufacturers is to combine the cables at the PC end into one large DB-style connector, and plug it into the card externally on the PC backplane. Software installa-

TABLE 1: Tape System Features

	ALLOY COMPUTER PRODUCTS	CATAMOUNT CORP.	CIPHER DATA PRODUCTS	DIGI-DATA CORP.	EMERALD SYSTEMS CORP.	FLAGSTAFF ENGINEERING	INNOVATIVE DATA TECHNOLOGY	OVERLAND DATA
PRICE	\$6,595	\$4,950	\$5,995	\$3,995	\$7,295	\$3,495	\$4,295	\$3,795
LANGUAGE INTERFACE	●	●	●	●	○	○	●	●
LAN SUPPORT	●	○	○	○	●	○	○	○
DIAGNOSTICS	○	○	○	●	●	●	●	●
LABEL SUPPORT								
INIT	○	○	○	○	○	●	○	○
READ	○	○	○	○	●	●	●	○
WRT	○	○	○	○	○	●	○	○
● = Yes ○ = No								

Full tape label support (which is provided only by the Flagstaff Engineering subsystem) is less important in a PC than in a mainframe environment. Tape label support is built into much mainframe system software and many applications; however, no such support exists in DOS, for which tape is still an infrequently used storage medium.

tion went much easier, requiring only that the FLAGIO.SYS device driver be added to CONFIG.SYS and that CONFIG.SYS have at least four buffers defined. To change the DMA channel or I/O address (interrupt channels are not used), only the jumpers on the controller board need to be changed and a parameter list added after the line DEVICE = FLAGIO.SYS in CONFIG.SYS.

Flagstaff's package comes with a diagnostic routine called TAPETEST. With a scratch (test) tape on the transport, the user brings the transport on-line and runs the routine, which writes 50 blocks of 10,000 bytes of data to the tape, rewinds, then reads back the data to verify the system operation. If any errors occur, the block in which they develop will be displayed on the screen.

The nine-track tape utility software is also well documented. It includes a menu-driven utility that processes both labeled (IBM and ANSI format) and unlabeled tapes. Output to tape supports fixed-length, variable-length, and string records; input from tape supports only fixed-length and string records. The utilities allow the skipping of files, of records within files, and of characters within records. The software provides for definition of logical record length, record terminator, and blocking factor (records per block) or block size. It also supports ASCII/EBCDIC conversion.

Flagstaff's utilities provide many convenient functions, including listing data sets on labeled tapes, initializing labeled tapes, and position commands such as file forward, file backward, block forward, block backward, go to EOT, rewind, rewind and unload, write tape mark, and erase to EOT. The tape

dump utility displays the tape contents on the screen in EBCDIC, ASCII, and/or HEX; the tape duplication utility duplicates tapes between two daisy-chained transports. (*Daisy-chained* transports are placed in parallel and selected by way of a code set by jumpers within the transport.) Flagstaff also provides control over tape speed (25 to 100 ips), although high speed is not supported on the AT (because of the problem discussed above). Other controllable parameters include IRG length, density (1,600 or 3,200 bpi), and buffer size.

An important feature of nine-track tape systems is the ability to do backup and restore operations between tape and the PC's fixed disk. Flagstaff's TAPEBKR utility provides the standard functions found in one-fourth-inch streaming tape backup systems. It allows wild cards and archival select (which backs up only files that are new or modified since the last backup). It permits the user to append additional files to existing backup tapes. The software provides a DIR function for files on tape and the same control functions (speed, density, positioning) as the regular nine-track utility.

The software performed well, with two exceptions. First, it will direct the transport to skip only 99 tape marks in one operation. A tape that has a great many small files (see the benchmark test that skips 1,000 tape marks) will require multiple skip operations. This, in turn, makes it cumbersome and time consuming to position the tape at the correct point (as is reflected in the benchmark results).

The second problem was considerably more serious. During the read-

from-tape-to-disk benchmark test, the final block of one test file on the tape was smaller than the block size because it contained fewer records than defined by the blocking factor. The software failed to transfer this block to the disk file. In a production job, any data contained in this final short block would have been omitted from the disk output file. In every other aspect, however, the software performed acceptably.

Overland Data, Inc. Like Flagstaff's tape controller card, the TC-50M included with Overland Data's model 1052 tape system uses the Pertec/Cipher formatter standard and can interface with most industry-standard formatted tape drives. The card and software can read both PE and NRZI format at 800, 1,600, 3,200, and 6,250 bpi, although the tape transport provided for testing, the Qualstar 1043, runs only at 1,600 and 3,200 bpi.

The installation portion of Overland's documentation is excellent, with step-by-step instructions and diagrams. The Overland package also supports the system's use with IBM XENIX System 3 and SCO XENIX System V. The XENIX utilities are included in the package.

Overland's package includes the BTEST diagnostic program, which, when used with a scratch tape, tests the write data, write file mark, erase fixed length, read data with verify, read file mark, space forward block, and rewind functions. On dual-speed transports, it tests high- and low-speed operation.

This package has a complete set of tape control functions in its DEPOT (data exchange program with optional translation) utility. DEPOT allows data interchange from tape to disk and disk to tape, ASCII/EBCDIC conversion, and

C Programmers!

First Database Exclusively for C is also Royalty Free

Designed exclusively for C, **db_VISTA™** is a royalty-free programmer's DBMS. Both single and multi-user versions take full advantage of C, through ease of use, portability and efficiency.

**Says, Dave Schmitt, President,
Lattice, Inc.**

"If you are looking for a sophisticated C programmer's database, **db_VISTA** is it. In either a single or multi-user environment, **db_VISTA** lets you easily build complex databases with many interconnected record types. The multi-user implementation handles data efficiently with a LAN and RAIMA's customer support and documentation is excellent. Source code availability and a royalty-free runtime is a big plus."

- **Written in C for C Programmers**
- **Royalty-Free. You only pay once**
- **Source Code Available**
- **Multi-user and LAN capability**
- **Fast B-tree indexing method**
- **Transaction processing**
- **Faster without Data Redundancy**
- **Complete Documentation Included**

Operating system support for MS-DOS, PC-DOS, Unix, Xenix, Macintosh or Amiga. **C compiler support** for Lattice, Microsoft, DeSmet, Aztec, Computer Innovations, Xenix and Unix.

Introducing **db_QUERY™**

With royalty-free **db_QUERY** you can ask more of your database, **db_QUERY** is a linkable, SQL-based ad hoc query and report writing facility.

Special Rebate Offer*

	db VISTA	Rebate
<input type="checkbox"/> Single-user	\$195	
<input type="checkbox"/> Single-user w/Source	\$495	\$ 50
<input type="checkbox"/> Multi-user	\$495	\$ 50
<input type="checkbox"/> Multi-user w/Source	\$990	\$100

Free 90 days application development support
All software not copy protected

30 day Money-Back Guarantee

Try **db_VISTA** for 30 days, if not fully satisfied, return it for a full refund.

Call Toll Free Today!

1-800-843-3313

at the tone touch 700-992



RAIMA™
CORPORATION

12201 S.E. Tenth Street
Bellevue, WA 98005 USA
(206) 747-5570 Telex: 91033303000

* Limited offer available to end-user purchases directly from Raima Corporation.

NINE-TRACK

TABLE 2: Controller Specifications

	ALLOY COMPUTER PRODUCTS	CIPHER DATA PRODUCTS ^a	EMERALD SYSTEMS CORP.	FLAGSTAFF ENGI- NEERING	INNOVATIVE DATA TECHNOLOGY DATA ^b	OVER- LAND DATA ^b
DEFAULT DMA CHANNEL	N/A	1	1	2 ^c	N/A	1
DEFAULT I/O ADDRESS	300H	220H	300H	350H	330H	36CH
DEFAULT IRQ	N/A	3	2	N/A	N/A	N/A
CHANGE DEFAULTS	Only I/O address	●	●	●	○	●
CODINGS						
NRZI	●	○	○	○	○	●
PE	●	●	●	●	●	●
GCR	○	●	○	●	●	●

^a This controller is also used by Catamount Corporation.

^b This controller is also used by Digi-Data Corporation.

^c Default DMA setting for PC/XT.

● = Yes ○ = No

The tape transport places only magnetic flux reversals on tape; the controller determines how those flux reversals represent data. Only Overland Data's controller provides the flexibility of support for all three major encoding systems.

tape positioning to an arbitrary location prior to data read. Like Flagstaff, Overland provides control over logical record length, block factor, block size, appending to existing tape, and positioning by skipping blocks and tape marks.

Overland's TAU (tape archive utility) is designed with features similar to those of one-fourth-inch streaming tape backup units. TAU permits individual DOS file backup and restore, use of wild cards, and data encryption. It can append to existing tapes and display a directory of files on a tape. It does not, however, have an archival-select feature. Overland's BACKUP utility produces a mirror-image backup, and restores at higher speeds than file-by-file backup. BACKUP copies data byte for byte to tape. The restoration process overwrites the previous contents of the disk with the restored mirror image.

Overland includes an important feature that the Flagstaff package does not—a programming language interface subroutine that gives a user program complete control over the drive. Examples are provided in C.

The TC-50M controller and software passed all tests and performed well. The software demonstrated great flexibility and ease of use. The package's one shortcoming is that it can neither read nor initialize tape labels. The user must manually skip over the appropriate number of tape marks to find the first file on a labeled tape.

Digi-Data Corporation. Although primarily a manufacturer of tape transports, Digi-Data also offers a complete nine-track tape system that incorporates its own model 2010-T transport with Overland

Data's TC-50M controller and software. (See the discussion above.)

Digi-Data's 2010-T transport is the tabletop model of its 2010 rack-mounted tape transport. The 2010-T is smaller than any other transport tested except the Qualstar 1043. The tape reel is loaded from the top of the drive, beneath a transparent lid.

A comparison of this system's performance to that of Overland Data's provides an interesting insight into the influence of a tape transport on the performance of the system as a whole. The Digi-Data tape system turned in the best performance in moving tape through the transport, as measured by its ability to skip tape marks. In reading and writing tape data, however, Digi-Data finished considerably behind Overland Data's tape system, which uses the Qualstar 1043 transport.

The transport and the Overland Data controller and software functioned as described, without difficulty.

Emerald Systems Corporation. Emerald markets its own tape controller and software bundled with a Pertec FS1511-19 tape transport system and calls the package the Emerald Series 7000 Subsystem. This subsystem can read and write both 1,600- and 3,200-bpi unlabeled tapes, but offers only limited label support for labeled tapes.

The documentation includes a well-written, illustrated section on installation. Like the other units that have large ribbon cables, the process was awkward. The default DMA (channel 1), I/O address (300H), and IRQ (2) can be changed via a DIP switch on the board. The changes are implemented in the

LOOKING FOR THE BEST VALUE IN PC/AT COMPATIBLES?



INTRODUCING THE \$1495 A★STAR™

Looking for a lower priced, higher quality PC/AT compatible than our new A★Star™ is like looking for a needle in a haystack. You're more apt to come up with a case of hayfever.

A★Star gives you features you won't get from any other vendor. Not IBM. Not Compaq. Not even those foreign manufacturers. Features like a 220 watt power supply, eight available expansion slots and "network ready" multi-user operation. All for only \$1495. And that price includes a 1.2MB diskette drive, 512KB memory, a fixed disk/diskette drive controller, a tactile feedback keyboard (you'll love it!) and a 6/8MHz switch/software selectable 80286 CPU.

Best of all, A★Star is quality built right here in America by Wells American Corporation - an American Stock Exchange manufacturer. So now you

can buy with confidence from a vendor you can trust, just like you've trusted IBM. And you'll get a genuine, top quality product (not a cheap imitation) for a price even less than those "questionable" mail order clones. And if that's not enough, it's all money-back guaranteed!

The \$1495 Wells American A★Star.™



A PC/AT FOR ONLY \$1495? THAT'S NOTHING TO SNEEZE AT!

[Hurry! This offer is limited.]

- ☐ I'm tired of sneezing! Have someone call me immediately to take my order.
- ☐ A★Star sounds terrific. Tell me more.

Name: _____

Company: _____

Phone: _____

Address: _____

City: _____

State: _____ Zip: _____



Wells American

803/796-7800 • TWX 510-601-2645
Sunset Boulevard • West Columbia, SC 29169

TABLE 3: *Benchmark Timings*

	ALLOY COMPUTER PRODUCTS	CATAMOUNT CORP.	CIPHER DATA PRODUCTS	DIGI-DATA CORP.	EMERALD SYSTEMS CORP.	FLAGSTAFF ENGINEERING	INNOVATIVE DATA TECHNOLOGY	OVERLAND DATA
CONTROLLER MANUFACTURER	Alloy Computer	Cipher Data Prod.	Cipher Data Prod.	Overland Data	Emerald Systems	Flagstaff Engineering	Innovative Data Tech.	Overland Data
TRANSPORT DEVICE	Pertec FS1511-19	Cipher F880	Cipher F880	Digi-Data	Pertec FS1511-19	Qualstar 1043	TOMACO TMS B	Qualstar 1043
SKIP 1,000 MARKS^a	11:40	5:00	4:59	4:02	16:08	52:32 ^b	4:30	4:23
256KB FILE READ^a	1:49	2:02	1:59	2:11	2:23	2:08	1:55	1:25

All timings in minutes: seconds. The configuration used was a dual-floppy-disk 640KB PC running a 4.77-MHz 8088.

^a (100 ips, 1,600 bpi).

^b The software can skip only 99 tape marks in one operation. This represents an average of five reads of 99 tape marks times 10.

Data read performance of a tape subsystem is constrained somewhat by standard tape speeds and densities. Speed of skipping tape marks is much more dependent on the design of the transport, as reflected by the considerable variation in times.

software through a parameter list when calling the program.

The diagnostics program, TTU (tape test utility) is the most comprehensive of any tape system tested. It checks all features, such as setting density, rewind and unloading, erasing, searching, positioning, reading, writing and speed selection, all under user control. The diagnostic portion of TTU includes a quick test, comprehensive test, nondestructive read test, and write test. These tests check for the on-line, drive ready, and Pertec/Cipher formatter ready signals; check to see that the tape has reached the load point; write different patterns until EOT is encountered; rewind the tape; read the written blocks; and then read the blocks in the reverse direction. The diagnostics display the status of 30 different functions on the screen as the test proceeds.

The tape utility software TIE (tape import export) does not function as well as TTU. Although it provides many of the functions found in other vendors' utility packages, it is a higher level product that gives the user less control over actual nine-track tape functions. For example, the user cannot specify a blocking factor for input from a tape; instead, TIE uses the block size found on the tape—a figure that cannot be overridden. Neither can the user specify such basic parameters as record length.

Emerald's "high-level" solution to this limitation is to provide RFS (record format specification), a utility feature that enables users to define the format of their input and output. This is nice if the data format is to be converted between tape and disk, but it is cumbersome for verbatim reading and writing of preformatted data because the user must specify an RFS format for each dif-

ferent record type written, even if the format does not change. The software does provide a helpful feature for reading data into a format for spreadsheets or database packages: the CSV (comma-separated variable) record. This feature, which uses RFS, writes data from a record with variables surrounded by quotes and separated by commas.

The package's support for labeled tapes is limited to RFS. If the user knows the format of the label, it can be specified under RFS; otherwise the label must be skipped. Likewise, label initialization must be performed from a DOS file to tape using an RFS specification for the label. TIE does include control over density, rewinding, block count, ASCII/EBCDIC conversion, output block size (not blocking factor), and positioning for tape marks and blocks.

An important facility offered by the Emerald and Alloy systems is the ability to run under Novell's NetWare and Advanced NetWare LANs. Emerald provides excellent, detailed instructions on determining the I/O address, interrupt level, and DMA channel to prevent conflicts with the network hardware and software, and includes specialized network installation worksheets. The tape controller is installed in a network node and not in the server itself. The tape software is network-tolerant rather than network-cooperative because no customized version is provided: Although network file servers may be backed up to nine-track tape, Novell's network security scheme is not preserved by Emerald's tape software during a restore of a file server. Alloy's network support, described below, is a great deal more comprehensive.

Emerald Systems has a comprehensive file archival system called ASP

(archival storage protector). It supports two modes: streaming file-by-file and streaming track-by-track. Streaming file-by-file mode is twice as fast as conventional file-by-file backup/restores and provides a directory for file location. It allows the user to back up and restore only part of a disk's contents. Files can be selected individually, by time and date of last modification, or by wild card. Users on a Novell LAN can specify the server to back up. They also can associate a password with a backup operation; the password will be needed to initiate a restore. Emerald's nine-track ASP is essentially the same software that is included with its one-fourth-inch streaming tape backup.


Streaming track-by-track is available for use only with an Emerald hard-disk subsystem. It provides no directories and requires a complete backup or restore for an entire disk volume. It is, however, about five times as fast as a conventional file-by-file backup/restore.

The Emerald system performed as documented. The lack of control over record size and blocking factor can be annoying. In addition, performance of the write-to-disk tests, which went well on other systems, was much more time consuming on this system. Each record had to be formatted with RFS and fitted to a predetermined block size to ensure that the time tests would not be affected by inefficient blocking. Without the exact format of the individual file headers, a tape label cannot be read. The Emerald system was tested by skipping file marks for the volume and header records on the test labeled tapes. It is unclear whether the high-level features offered by RFS are worth the restrictions on the system's versatility, especially for more technical users.

A remarkable breakthrough for LANs—one that's easy to use: Tapestry

No matter what local area network hardware you choose—your next choice should be Tapestry network operating software from Torus Systems. Here are 6 reasons why.

1 IBM chose Tapestry, for its overseas market, and it quickly became the hottest LAN system in Europe.



This is the friendly screen that caught Big Blue's eye.

2 It's the world's easiest-to-use networking software—much simpler than Novell, 3Com, or IBM because Tapestry is managed with icons. To use it, you just point to graphic symbols: the "in-tray" to get mail, the "cabinet" to access files, and so on.

You even use icons to configure the system, so almost anyone can set up a Tapestry network—and keep it running smoothly.

3 Tapestry is the most complete LAN software money can buy.

The basic system gives you:

- **Advanced electronic mail**

Compose memos with the Torus text editor. Send them to any person or group on the network, just by pointing to names. Track the mail you've sent. Get messages instantly.

- **Cost-effective sharing of hard disks, printers and modems**


You can have up to 100 Tapestry workstation/servers and access any one of them by touching the right icon. Since all Tapestry servers are undedicated, each station is free for business as usual. You don't have to invest in specialized hardware, or sacrifice your valuable PCs.

- **Advanced communications capabilities**

Need information from the company mainframe or an outside service? Just point to the desired Service icon. Torus offers a family of network gateways* that automatically make the connection and speed your information through.

- **And there's more!**

Tapestry also provides central storage of all your applications so they too can be accessed with icons. Automatic file locking so you can safely run single-user applications not originally designed for networks. File Manager icons that let you manipulate files without using DOS commands. And a Telephone Manager that places your calls and maintains a personal electronic rolodex.



What good is a network if your people don't know how to use it? Tapestry's screens are so easy to understand, anyone can net great results without special skills or training.

4 Tapestry supports all the standards, like IBM Token-Ring, PC Network and 3Com hardware. Like PC-DOS 3.1 and NETBIOS. So you can choose the LAN hardware that's best for you, and you won't have to worry if your software will run.**

5 Tapestry is proven and reliable.

Thousands of Tapestry stations have been installed in both large and small companies in the U.S. and around the world. Customers include: Proctor & Gamble, EDS, the White House, the IRS, Prime Computer, TRW, NBC News, Shell Oil, Exxon and Citicorp.

6 With this coupon you get a **FREE Network Manager** AND a money back guarantee! Usually, Tapestry costs \$495 for your first workstation (the Network Manager) and \$295 for each additional station.† BUT NOW YOU CAN GET A TAPESTRY STARTER PACK (BOTH THE MANAGER AND THE SECOND STATION) FOR ONLY \$295!

And we're so confident you'll love Tapestry, we'll let you return it—for any reason—within 30 days of shipment and we'll gladly refund your purchase price (less \$50.00 restocking fee).

So send this coupon to us, take it to your Torus Dealer, or call in your order today, and start networking the easy way.

Name _____

Company Name _____

Address _____ City _____

State _____ Zip _____ Phone _____

Networking Hardware _____

Number of Workstations in Office _____

Subtotal **\$295!**

Add \$7.00 shipping/handling \$ _____

California residents add 6½% sales tax (\$19.18) \$ _____

Amount enclosed \$ _____

Payment VISA MC Check _____

Credit Card Exp. Date _____ / _____

Card # _____

Act now: offer expires August 15, 1986.

This offer is good only in U.S. and Canada.

TORUS 495 Seaport Court, Suite 105
Redwood City, CA 94063
(800) 872-5335

System Requirements: Station 1: IBM PC, XT, AT or compatible 384K, 10MB hard disk. Station 2: IBM PC, XT, AT or compatible 320K. Plus suitable networking hardware.

Notes: *ASYNCR is standard, while VT100, 3270 SNA, and Remote Access are purchased separately. **Tested applications include: dBase III Plus, MultiMate Advantage, Open Systems Accounting, Displaywrite 3, WordPerfect, MS Word, Lotus 1-2-3, AutoCAD.

†6 Station Pack—\$1495, 24 Station Pack—\$3995.

Torus and Tapestry are registered trademarks of Torus Systems, Ltd. Trademarks: 3Com—3Com Corp; IBM, Displaywrite 3 and PC-DOS—IBM Corp; MS Word—Microsoft, Inc; dBase III Plus—Ashton-Tate; 1-2-3 and Lotus—Lotus Development Corp; WordPerfect—Satellite Software International; AutoCAD—Autodesk, Inc; MultiMate Advantage—MultiMate International; Novell—Novell, Inc; Open Systems Accounting—Open Systems, Inc.

© 1986 Torus Systems, 495 Seaport Court
Redwood City, CA (415) 363-2418

Alloy Computer Products, Inc. The Alloy Q-TIP system, like the Emerald system, includes Alloy's ITS-PC tape controller card, along with TIP-6 and PC 9-Track software, bundled with Pertec's FS1000 series formatter and tape transport. It can read and write PE-formatted, 1,600- and 3,200-bpi tapes.

The documentation provides step-by-step, illustrated installation instructions. This system suffers the same awkward hardware installation as the other interface cards reviewed so far. Alloy's technical support confirmed that the system does not use either interrupts or DMA, but that fact was not mentioned in the documentation. The manual does, however, show how to change the default I/O base address of 300H and transport type via DIP switches and jumpers. The Cipher Microstreamer is the default transport type. The PC 9-Track software is modified to reflect the base I/O address change with Alloy's TINSTALL program. After entry of the desired hexadecimal I/O address, TINSTALL modifies the PC 9-Track's TREAD, TWRITE, and TDUMP routines to reflect the new I/O address. The TIP-6 programs are similarly modified with Alloy's PATCH routine. It is disappointing to note that Alloy does not provide diagnostic routines.

The documentation is geared toward the end user—it is difficult to glean much technical information. Even Alloy's language interface routine, TLINK, is written for BASIC programs. The TLINK examples are excellent, but additional routines for other languages, such as Macro Assembler or C, would have been a welcome addition.

Functionally, the PC-9 Track utilities provide excellent control over the transport. Although the software cannot read labeled tape labels, the user can determine record length, blocking factor, record and block padding, record terminator, and ASCII/EBCDIC conversion. The software also affords control of tape position with commands to skip tape marks and skip records.

A strong point of Alloy's package is its support of Novell's NetWare and Advanced NetWare LANs. The tape controller can be installed in either a network node or the file server, if the server is using an Alloy hard-disk subsystem. The network installation process is well documented, and complements Novell's installation guide nicely. In addition, Alloy provides a special version of its QTIP Archival software called QTIP-Novell. Not only does it allow backup and retrieval of all files on the network, but it archives the Directory Access Masks and

Directory Trustee Masks, which are necessary to preserve the network's security during file restoration. This strong compatibility is a powerful recommendation of the Alloy Tape system for use with a Novell LAN configuration.

Another of the Alloy product's assets is its TIP-6 hard-disk archival software. It has all the features of Alloy's PC-QICTAPE one-fourth-inch streaming tape backup: initialize tape, disk-to-tape backup, disk-to-tape append, tape-to-disk restoration, tape directory, and file verification (see "Moving up to Tape," Steven Armbrust and Ted Forgeron, November 1985, p. 62). However, like PC-QICTAPE, it does not support mirror-image backup/restore; it is file oriented only. The tape system does include wild cards, query (which allows a user to enter Y/N for individual file backup/restore), archival select, exclusion of files meeting user-defined criteria, and logging. It includes special commands to give the TIP-6 software specific control

T*he Emerald and Alloy systems offer the important facility of running under Novell's NetWare and Advanced NetWare LANs.*

of the nine-track tape: set track, skip to block, skip to saveset (Alloy's term for a backup session written to tape), write end of data (EOD), and rewind. Like its little brother QICTAPE, TIP-6 has an excellent on-line help feature.

The software worked as promised, affording the user moderate control over the tape transport. No major problems arose during testing.

Cipher Data Products, Inc. With Pertec, Cipher is the originator of the Pertec/Cipher formatter standards. The Cipher Series 9000 Tape Subsystem includes the Cipher F880 transport (the M990 is available as an option for reading GCR 6250-formatted tapes). The F880 uses PE formats for 1,600- and 3,200-bpi tapes.

The Cipher system was the easiest installation of all. Cipher is the only tape controller on a short-slot card: instead of large ribbon cables attaching directly to the surface of the controller card, a shielded data cable, terminated by a D-type connector, connects to the back of the card. Software installation consists of renaming Cipher's

TCONFIG.SYS file to CONFIG.SYS, or editing an existing CONFIG.SYS to include Cipher's device driver. The package includes two device drivers, one for use with the PC and XT and one for the AT that suppresses high-speed data transfers and does not use interrupts.

The documentation describes Cipher's use of the DMA channels, I/O address, and interrupt (see table 2), but does not include instructions on reconfiguring the controller hardware. The manual does discuss reconfiguration of the software with the TINSTALL program. TINSTALL delivers a highly detailed, narrative instruction on reconfiguring the jumpers on the board as well as performing a reconfiguration of TDS.SYS, Cipher's device driver. Conspicuously absent from this package are diagnostic routines. Cipher suggests using its tape backup routine with a /RO command-line switch first, to test the functionality of the transport and interface before overwriting a valid backup tape with new information.

This product includes a complete hard-disk archival package, with TBACKUP and TRESTORE. DT (disk/tape) supports tape-to-disk and disk-to-tape file transfers, and TDS provides access to tape data by emulating a disk-type device and a character-type device within DOS. Utility programs are provided for positioning and erasing tapes, and performing tape dumps. Two separate utilities permit tape system access from user-written programs: BPS provides BASICA programming support for interpreter versions of BASIC, while GPTR supports most languages that link external routines via DOS LINK. DT is used to copy, and optionally reformat, data between the tape drive and a DOS device or file. It provides significant control over the transport, with commands to control block size, logical record length, record deliniator, tab expansion, data append, and ASCII/EBCDIC conversion. It provides positional control with options to skip tape marks, and skip to beginning of tape (BOT) or EOT.

Cipher's TBACKUP and TRESTORE resemble DOS BACKUP and RESTORE, with enhancements to take advantage of one-half-inch tape capabilities. TDIR provides a directory of archived files. Users may classify files to restore groups of files selectively from a tape that contains multiple backup sessions. BACKUP has been extended to allow archiving of multiple disk volumes in a single operation. DOS BACKUP's archival bit and modification date support have been retained. Reset of the archival bit on write-protected disks has

FOR TURBO PASCAL

...one package stands out as the best support available for Turbo Pascal programmers: Blaise Computing's Turbo Power Tools. This definitive set of prewritten Pascal functions and procedures will make the life of any programmer—from the beginner to the hard-core professional—easier and more productive.



ANOTHER PLUS FROM BLAISE COMPUTING

The best just got better! Turbo POWER TOOLS, acclaimed as the best programmer support package for Turbo Pascal, now has even more functions, more detailed documentation and more sample programs.

NO SECRETS

Turbo POWER TOOLS PLUS is crafted so that the source is efficient, readable and easy to modify. We don't keep secrets! We tell you exactly how windows are managed, how interrupt service routines can be written in Turbo Pascal, and how to write memory resident programs that can even access the disk. Maybe you've heard of some undocumented DOS features that resident programs use to weave their magic. Turbo POWER TOOLS PLUS documents these features and lets you make your own magic!

Here's just part of the PLUS in Turbo POWER TOOLS PLUS:

- ◆ **WINDOWS** that are stackable, removable, with optional borders and a cursor memory.
- ◆ **FAST DIRECT VIDEO ACCESS** for efficiency.
- ◆ **SCREEN HANDLING** including multiple monitor and EGA 43-line support.
- ◆ **POP-UP MENUS** which are flexible, efficient and easy to use, giving your applications that polished look.
- ◆ **INTERRUPT SERVICE ROUTINES** that can be written in Turbo Pascal without the need for assembly language or inline code.

Power Tools Plus™ Window Routines. Memory Resident Routines. Routinely.

- ◆ **INTERVENTION CODE** lets you develop memory resident applications that can take full advantage of DOS capabilities. With simple procedure calls, you can "schedule" a Turbo Pascal procedure to execute either when a "hot key" is pressed, or at a specified time.
- ◆ **PROGRAM CONTROL ROUTINES** allow you to run other programs from Turbo Pascal, and even execute DOS commands.
- ◆ **MEMORY MANAGEMENT** allows you to monitor, allocate and free DOS-controlled memory.
- ◆ **DIRECTORY AND FILE HANDLING** support to let you take advantage of the newer features of DOS including networking.
- ◆ **STRING** procedures allowing powerful translation and conversion capabilities.
- ◆ **FULL SOURCE CODE** for all included routines, sample programs and utilities.
- ◆ **DOCUMENTATION, TECHNICAL SUPPORT** and attention to detail that

have distinguished Blaise Computing over the years.

Turbo POWER TOOLS PLUS supports Turbo Pascal Version 2.0 and later and is just \$99.95.

Another quality product from Blaise Computing: **Turbo ASYNCH PLUS™**

A new package which provides the crucial core of hardware interrupt support needed to build applications that communicate. ASYNCH PLUS offers simultaneous buffered input and output to both COM ports at speeds up to 9600 baud. The XON/XOFF protocol is supported. Now it also includes the "XMODEM" file-transfer protocol and support for Hayes compatible modems.

The underlying functions of Turbo ASYNCH PLUS are carefully crafted in assembler for efficiency and drive the UART and programmable interrupt controller chips directly. These functions, installed as a runtime resident system, require just 3.2K bytes. The high level function are all written in Turbo Pascal in the same style and format as Turbo POWER TOOLS PLUS. All source code is included for just \$99.95.

BLAISE COMPUTING INC.

2560 Ninth Street, Suite 316 Berkeley, CA 94710 (415) 540-5441

ORDER TOLL-FREE 800-227-8087

Calif. residents call (415) 540-5441

YES, send me the PLUS I need! Enclosed is \$_____ for
☐ Turbo POWER TOOLS PLUS ☐ Turbo ASYNCH PLUS ☐ OTHER _____
 (CA residents add 6 1/2% Sales Tax. All domestic orders add \$10.00 for Federal Express shipping.)
 Name: _____ Phone: (____) _____
 Shipping Address: _____ State: _____ Zip: _____
 City: _____ Exp. Date: _____
 VISA or MC #: _____

AT performance at an XT price. Introducing the TeleCAT-286. \$2995. Complete.



With TeleVideo, you always settle for more.

For some time, you've known exactly what kind of PC you could get with a mid-range budget.

But now, you can settle for a whole lot more. With the new TeleCAT-286™ from TeleVideo.

It starts you off with IBM AT compatibility. 512K RAM. A 20MB hard disk. A 1.2MB floppy. And everything else you need. Like an Intel 80286 CPU that runs at either 6 or 8 MHz. Even a high-resolution 640 x 400 pixel monitor for text and graphics.

To make even better use of internal space, we socketed the TeleCAT-286 for one MB of RAM, and also included serial and parallel ports on the motherboard. As a result, we can still give you three extra expansion slots.

And we didn't stop there. We've also designed more ergonomic features into the TeleCAT-286. Including sculptured keycaps on a high-quality keyboard. LEDs right on top of the three critical locking keys, so they won't get covered up by overlays. And a footprint that's 28% smaller

than the IBM AT's. So you get more of your desk back, too.

There's a lot more we could say about the TeleCAT-286. But it's an even better idea to get your hands on it. So call 1 (800) TELECAT, Dept. 154, and we'll tell you where you can try one.

The TeleCAT-286. Our 20MB version is \$2995; 30MB, \$3495. For high performance at a low price, don't settle for less.



TeleVideo®
Settle for more.

TeleVideo Systems, Inc., 1170 Morse Avenue, Sunnyvale, CA 94088-3568 • (408) 745-7760

©1986 TeleVideo Systems, Inc. IBM is a registered trademark of International Business Machines, Inc. Screen graphics by Chartmaster ©Decision Resources, Inc.

CIRCLE NO. 182 ON READER SERVICE CARD

NINE-TRACK

always been a problem; but Cipher's TBACKUP includes an option to bypass altering the bit. In addition to wild cards, it can exclude specified groups of files from backup. Mirror-image backups are not supported.

Cipher's package is complete, functions as documented, and performs well. It was one of the fastest packages tested and offered a wide array of features. For non-networked applications, this is the package of choice.

Catamount Corporation. The PCT-9S tape system evaluated for this article was found to be identical in all respects to the Cipher Series 9000 reviewed above. The tested configuration included Cipher's F880 transport, short-slot controller board, software from DataTrac, and D-connector-equipped shielded data cable. Catamount purchases its software and controller from the same sources as Cipher. In fact, the software program files were identical byte for byte to those shipped with the Cipher system. An advantage to Catamount's product is that the company can provide other transports besides the Cipher F880, including the Qualstar 1052 (with transport-specific software), the Kennedy 9600, the Cipher M990 (for 6,250-format tapes), and the Qualstar 701, a compact, lightweight unit for use with seven-inch tape reels.

In testing also, the Catamount system operated identically to the Cipher Series 9000. (Refer to table 1.)

Innovative Data Technology, Inc. IDT offers the most unique package. The model 1012 tape system includes a TOMACO TM-S transport, with the Pertec/Cipher formatter-compatible LEO tape controller and software. The device supports PE and GCR formats for densities of 1,600, 3,200 and, optionally, 6,250 bpi.

LEO is unique because it is the only controller tested that does not use the PC's DMA channels to transfer the tape data to and from memory. The company instead employs a technique that it calls "buffer swapping." The LEO controller uses two data buffers, one of which is always resident in the PC's memory, the other is in the controller card's memory. When the buffers are swapped, IDT claims that essentially a zero-time, DMA-like transfer between the controller and PC is accomplished. The company suggests that this process dramatically increases the throughput of the controller. Its claim was partially verified by the benchmark tests.

IDT's installation documentation is nonexistent. The company provides complete engineering-level specifications, and the schematic had to be read

to determine where to attach the cable connectors to the transport. Again, connection to the PC was awkward because of the two ribbon cables. Although IDT alludes to an ability to reconfigure the base I/O address in the future, for now it is preset to 300H. If that conflicts with an existing device, nothing can be done. The package does include TT (tape test) diagnostic routines that perform a rather comprehensive test verifying the basic controller command functions, controller status reporting functions, formatter functions, transport movement, and basic data integrity. TT also performs data and blocking function checks, position function checks, media and read-write performance checks, and offers the ability to define custom test sequences.

As it is, the manual is virtually useless to the nontechnical user. Complex technical information is mixed in with the operational instructions. The level of documentation is good, but the technical notes should be separated from the functional instructions.

The LEO tape system includes several software utilities. The MT standard device driver provides an extension to DOS that makes the tape device look like a standard data file opened for sequential access, permitting most assemblers, compilers, and interpreters to work with the tape device. The ANSI tape utility program allows files to be transferred to and from single- and multiple-volume, industry-standard, one-half-inch nine-track magnetic tape in the format defined by ANSI X3.27-1978. Files may be transferred to and from a PC, XT, or AT under DOS 3.1 or later.

The utilities permit the user to specify DOS or ANSI path name, ASCII/EBCDIC conversion, tape positioning (BOT, EOT, FILE), block size and blocking factor. The TCMD tape command program includes 20 commands to select drive, rewind, status query, ASCII/EBCDIC conversion, speed, write both data and tape marks, space forward and reverse n blocks or n files, tape dump, tape compare, and help.

LEO provides a good high-level language interface for both C and BASIC. Many of LEO's routines include a C listings from which a programmer can easily lift sections of code. LEO uses a standard DOS device driver that is loaded at boot time. IDT's ANSI and IBM tape utilities and TCMD (tape command) program offer a wide range of tape-to-disk read/write and position options. The ANSI routines do not offer much control over blocking and de-blocking or specific positioning, but

C & PASCAL PROGRAMMERS

Blaise Computing provides a broad range of programming tools for Pascal and C programmers, with libraries designed for serious software development. You get carefully crafted code that can be easily modified to grow with your changing needs. Our packages are shipped complete with comprehensive manuals, sample programs and source code.

C TOOLS PLUS

\$175.00

NEW! Full spectrum of general-purpose utility functions; windows that can be stacked, removed, and accept user input; interrupt service routines for resident applications; screen handling including EGA 43-line text mode support and direct screen access; string functions; and DOS file handling.

PASCAL TOOLS/TOOLS 2

\$175.00

Expanded string and screen handling; graphics routines; easy creation of program interfaces; memory management; general program control; and DOS file support.

VIEW MANAGER

\$275.00

Complete screen management; paint data entry screens; screens can be managed by your application program; block mode data entry or field-by-field control. Specify C or IBM/MS-Pascal.

ASYNCH MANAGER

\$175.00

Full featured asynchronous communications library providing interrupt driven support for the COM ports; I/O buffers up to 64K; XON/XOFF protocol; baud rates up to 9600; modem control and XMODEM file transfer. Specify C or IBM/MS-Pascal.

Turbo POWER TOOLS PLUS

\$99.95

NEW! Expanded string support; extended screen and window management including EGA support; pop-up menus; memory management; execute any program from within Turbo Pascal; interrupt service routine support allowing you to write memory resident programs; schedulable intervention code.

Turbo ASYNCH PLUS

\$99.95

Complete asynchronous communications library providing interrupt driven support for the COM ports; I/O buffers up to 64K; XON/XOFF protocol; and baud rates up to 9600.

RUNOFF

\$49.95

NEW! Text formatter written especially for programmers; flexible printer control; user-defined variables; index generation; and general macro facility. Crafted in Turbo Pascal.

EXEC

\$95.00

Program chaining executive. Chain one program from another even if the programs are in different languages. Shared data areas can be specified.

ORDER TOLL-FREE 800-227-8087!



BLAISE COMPUTING INC.

2560 Ninth Street, Suite 316 Berkeley, CA 94710 (415) 540-5441

CIRCLE NO. 114 ON READER SERVICE CARD

Fortran Support for IBM PC/XT/AT & Compatibles

Versions Available For:

Microsoft, Supersoft, RyanMcFarland, IBM Professional, Lahev, & IBM Fortran.

Forlib-Plus \$69.95

Supports graphics, interrupt driven communication, program chaining, and file handling/ disk support. A Fortran coded subroutine is included which will plot data on the screen either in linear/linear, log/linear, linear/log, or log/log on the appropriate grid.

Strings & Things \$69.95

Supports string manipulations, command line usage, DOS call capabilities, SHELL generation and data transmission, BATCH file control, music generation, PEEKS and POKES, PORT access, and general register manipulations.

For-Winds \$89.95

Gives the Fortran programmer the capability of generating up to 255 windows on the screen. Each window can be individually scrolled, moved, sized, generated, and removed. Both color and monochrome type displays are supported. Full source code is supplied for customization.

ACS Time Series \$495.00

This is a COMPLETE time series analysis package which contains VERY HIGH SPEED FFTs, Filter generations, convolutions, transfer function calculations, auto and cross spectra calculations, Cepstrum, curve fitting algorithms, coherence calculations, and many other associated routines. The price includes FULL source code.

Fortran Scientific Subroutine Package \$295.00

There are approximately 100 Fortran subroutines included which fall under the following 12 categories:

1) Matrix storage and Operations 2) Correlation and Regression, 3) Design Analysis (ANOVA), 4) Discriminant Analysis, 5) Factor Analysis, 6) Eigen Analysis, 7) Time Series, 8) Nonparametric Statistics, 9) Distribution Functions, 10) Linear Analysis, 11) Polynomial Solutions, 12) Data Screening. Full source code is included.



Alpha Computer Service
5300 Orange Ave., Suite 108
Cypress, California 90630
(714) 828-0286

California Residents
Include 6% Sales Tax

There are NO license fees

CIRCLE NO. 101 ON READER SERVICE CARD
108

NINE-TRACK

TCMD offers better positioning control. IDT's blocking and file control limitations are similar to Emerald's.

LEO's TAP (tape archival program) performs the standard tape backup, restore, and directory functions. Other features include tape initialization and an override for directory names (which allows files restored from a backed-up subdirectory to be written to a new subdirectory, so that the original files may be retained if desired). TAP is a command-line oriented program to which all parameters are passed on a single line. The backup function features selection by wild card, archival bit, and modification date.

IDT's routine performs as documented, although the ANSI tape functions are limited. The high-level language interface is good, but it has the same blocking and deblocking limitations as the utilities.

WHITHER TRACK?

All the systems tested conform closely to the standard Pertec/Cipher formatter specifications. All were essentially free of bugs once installation problems were resolved. None could in any way be thought of as unacceptable.

These systems exhibited good tape archival and restore utilities for PC fixed-disk backup, but the packages were divergent in the level of control offered over tape-to-disk and disk-to-tape transfer functions. Variations in speed also were evident, especially in the speed of tape positioning by skipping file marks. Cipher is the best overall system for non-networked applications, with Overland Data and Flagstaff Engineering coming in a close second. Only Emerald and Alloy offer systems suitable for application in networked environments. Moreover, Alloy's maintenance of file server network security through a full backup/restore cycle makes it stand out as the system of choice for users with a Novell LAN.

Although the nine-track tape may seem an anachronism when considered in a PC context, it offers important advantages as a link between the PC and the mainframe: no new technology is required at the mainframe end; it is more secure than telecommunications links because it can be sent by courier or hand carried between locations; carefully-formatted data tapes can be read by virtually any modern mainframe computer; and the tape control procedures already in place at most MIS sites facilitate control of access to tape-transmitted data. Furthermore, while nine-track tape is not as cost-effective as

fixed-disk backup alone, backup ability is a no-extra-cost advantage when tape support is required for other purposes. Like COBOL, nine-track tape has been around for a long time. And, like COBOL, a strong set of standards is the key to that longevity.



Q-TIP, with PC-9: \$6,595
Alloy Computer Products, Inc.
100 Pennsylvania Avenue
Framingham, MA 01701
617/875-6100
CIRCLE 344 ON READER SERVICE CARD

PCT-9S Tape Subsystem: \$4,950
Catamount Corporation
2243 Agate Court
Simi Valley, CA 93065-1898
805/584-2233
CIRCLE 345 ON READER SERVICE CARD

Tape Subsystem: \$5,995
Cipher Data Products, Inc.
10225 Willow Creek Road
P. O. Box 85170
San Diego, CA 92138
800/4-CIPHER; 619/578-9100
CIRCLE 346 ON READER SERVICE CARD

2000 PC: \$3,995
Digi-Data Corporation
8580 Dorsey Run Road
Jessup, MD 20794
301/498-0200
CIRCLE 347 ON READER SERVICE CARD

Series MTM80-7000: \$7,295
Emerald Systems Corporation
4757 Morena Blvd.
San Diego, CA 92117
619/270-1994
CIRCLE 348 ON READER SERVICE CARD


Model 8820: \$3,495
Flagstaff Engineering
1120 Kaibab Lane
Flagstaff, AZ 86001
602/774-5188
CIRCLE 349 ON READER SERVICE CARD

Model 1012: \$4,295
Innovative Data Technology
5340 Eastgate Mall
San Diego, CA 92121
619/587-0555
CIRCLE 350 ON READER SERVICE CARD

Model 1052: \$3,795
Overland Data, Inc.
5644 Kearny Mesa Road
San Diego, CA 92111
619/571-5555
CIRCLE 351 ON READER SERVICE CARD

Roger Addelson is the assistant director of academic computing at Loyola University of Chicago. The author gratefully acknowledges the assistance of Joseph Kaplenk in the testing of these tape subsystems.

Digital has it now.



The first open-ended multi-user software system that integrates your custom application with a full range of standard business programs.

The A-to-Z™ Integrated System for MicroVAX II™ and MicroPDP-11™. Now you can integrate any number of your custom multi-user applications with word processing, graphics, spreadsheet, data management, accounting, and thousands of VAX™ and PDP-11 programs. Same menus, commands and files with no need for a system manager.

Tell me about A-to-Z on MicroVAX™ and MicroPDP-II™ ☐ Reseller ☐ Developer

Name

Title

Company

Phone

Address

City

State

Zip

Send to: Digital Equipment Corporation, Inquiry Dept.,
NR02-1/H3, 444 Whitney Street, Northboro, MA 01532.

digital™

Smooth Curves

Connecting a set of points with a smooth line requires special techniques. This procedure imposes an intuitive polynomial interpolation to achieve smooth curves.

MICHAEL A. COVINGTON

Drawing a smooth curve that connects an arbitrary set of points is a classic problem in computer graphics. It arises frequently in picture drawing—especially from data entered with a mouse or graphics pad—and in drawing graphs from numerical data. An algorithm that produces smooth curves also provides a way to eliminate the raggedness that results from magnifying a picture composed of a limited number of pixels. This, in turn, makes it possible to draw characters or symbols from very concisely stored descriptions; each character can be summarized by just a few points if the computer can connect them appropriately.

Using the Turbo Pascal program provided here, SMOOTH.PAS (listing



1), a user can mark points on the screen that the program then connects with a smooth curve. The curve passes through the points in the order in which they were marked, crossing over itself as many times as necessary to do so. This curve-fitting procedure can be adapted for use in other programs. The computation does not rely on features specific to Pascal so translation into other languages should be easy.



Users should note that this program was written for use with the IBM Color Graphics Adapter (CGA); making it run well from an IBM Enhanced Graphics Adapter (EGA) requires some modifications. It can be made to run without the unexpected yellow background by taking the comments out of


the invocation of **graphback-ground(black)** in the two places it occurs. The EGA does not respond in the same way as the CGA to Turbo Pascal's built-in **hirescolor** procedure. On the EGA, the **hirescolor** specified becomes the background color unless **graphback-ground** also is specified, and the default foreground color is green. This is because Turbo Pascal uses the CGA in a mode that the EGA does not emulate.

Mathematically speaking, the problem of smooth curve creation is actually one of *interpolation*. The position of

The screen shots below show examples of the smooth curves obtainable using the program presented here. The points are joined in the order they are entered.







Ever for Excellence

Evercom™ ... 1200 baud, \$249

Now the EVEREX Evercom modem is available on a half-size card, perfect for the short slots in the IBM XT, Portable, and many compatibles. EVEREX has combined innovative engineering and technology to produce a quality

Hayes-compatible 1200 baud modem that out performs the competition at a lower price. EVEREX engineering is the key ingredient that delivers **QUALITY** and **FEATURES** without sacrificing **PRICE**.

Compatibility Guaranteed!!

The Evercom short card modem is guaranteed to be compatible with the Hayes 1200B or your money back for the first 30 day evaluation period.

Call today for dealer pricing and start getting EVEREX VALUE... **QUALITY** and **FEATURES** at the **LOWEST POSSIBLE PRICE**. Why settle for less?

1-800-821-0806

in California

1-800-821-0807

EVEREX
EVER for EXcellence

48431 Milmont Dr. Fremont CA 94539
(415) 498-1111

Before you buy a modem, check these features:

	EVEREX EVERCOM	HAYES NEW 1200B
• Automatic dialing, answering, and redialing	YES	YES
• Half-size card	YES	YES
• Call progress monitoring	YES	YES
• Works in short slot of XT	YES	NO
• Automatic data-to-voice transition	YES	NO
• Reports serial port speed mismatch	YES	NO
• Detects receiver off-hook	YES	NO
• Configurable from COM1 - COM4	YES	NO
• Supports 132 columns	YES	NO
• Communications software included	YES	\$80 extra
• List Price	\$249	\$489

Evercom is a trademark of Everex Systems, Inc. IBM PC and XT are registered trademarks of International Business Machines Corp.

Hayes 1200B is a trademark of Hayes Microcomputer Products Inc.

CIRCLE NO. 169 ON READER SERVICE CARD

SMOOTH CURVES

each point on the curve is described by two coordinates, x (the column number) and y (the row number). For some points, both x and y are given. A method is needed to connect the points so that for any x , an appropriate value of y can be computed, making it possible to fill in the whole curve.

The interpolation function must pass through all the known points and behave reasonably between them. It also must be easy to compute. Some mathematical functions, such as sines and logarithms, take a long time to evaluate on a conventional computer. As far as possible, it is best to avoid these functions and use only addition, subtraction, multiplication, and division.

This suggests that the interpolating function should be a polynomial, an equation of the form

$$y = ax^n + bx^{n-1} + \dots + cx^2 + dx + e$$

where a , b , c , d , and e (the coefficients) are constants, and n is used to represent the degree of the polynomial.


The degree determines the complexity of the polynomial's curve: the maximum number of bends in the curve is equal to the degree minus 1. A polynomial of degree 1 (a linear equation) describes a line (with no bends) and therefore can be fitted to any two points. A quadratic, the degree of which is 2, describes a parabola (that has one bend) and can be fitted to any three points. A cubic, of degree 3, describes a curve that bends twice and can be fitted to any four marked points.

In general, for any k points, a polynomial of degree $k-1$ exists that passes through all of them; using this polynomial is known as *Lagrangian interpolation*. The polynomial that passes through all the points may behave very oddly between them. In figure 1, a ninth-degree polynomial is fitted to a set of ten points. The hairline curve represents the Lagrangian interpolation. Near the middle, the curve is not bad, but at the ends, it differs wildly from an intuitive idea (as shown in the tint line) of what a smooth curve connecting the points should look like. The Lagrangian interpolation approach, then, does not produce the desired result here.

SPLINE CURVES

What is meant by a *smooth curve*? The intuitive idea of smooth curvature comes mostly from looking at what happens when flexible materials are bent. In fact, the traditional tool for drawing smooth curves is a drafting instrument called a spline, a flexible strip that can be anchored at points on the paper.

FIGURE 1: Polynomial Interpolation between 10 Points



Lagrangian interpolation (the hairline curve) does not produce curves that are intuitively satisfying. Here, a ninth-degree polynomial is fitted to a set of 10 points. The curve passes through all points, but its behavior between them is not what the arrangement of the points would suggest. The same set of 10 points are linked (with the tint line) by an intuitive interpolation that might have been drawn free-hand. This is the kind of curve that a good curve-fitting program should generate.


The curvature of a spline is described by a series of cubic equations. At the point where the curve changes from one cubic equation to another (the *knot*), the slopes of the two cubics are equal; thus the curve is smooth through those points. As mentioned earlier, a cubic equation can be fitted to any four points; it can be fitted equally well to two points and two slopes. The values of the slopes are not known at the outset, but they can be assigned unique values by specifying that the second derivative—the rate of change of the slope—must be 0 at the knots.

The remaining question is what to do at the ends of the curve. The most common approach is the so-called natural spline condition, which stipulates that the second derivative should be zero at the endpoints as well as the knots. A more satisfying type of cubic spline, devised by Carl de Boor (see the references at the end of this article), specifies that the second point and the next-to-last point are not knots—although the curve must pass through them, it does not change from one cubic to another as it passes. The first and last cubics are thus constrained by three points and one slope, rather than two points and two slopes. This helps control the curve's behavior at the ends.

Thus far, the assumption has been made that y is a function of x (that for any x only one y exists). In graphical

terms, this means that only one pixel in each column can be illuminated, and the curve cannot pass above or below itself. This seems a severe restriction, and it has an easy resolution. Instead of having y be a function of x , x and y can both be treated as functions of another variable called t . Then the curve can be drawn by calculating both x and y for given values of t . The curve then can be two dimensional—it can wander all over the screen instead of just varying in height as it goes from left to right.

Several methods can be used to obtain t . In general, each point's t value should be greater than that of the previous point. This will force the resulting curve to pass through the points in the order in which they were entered. It may be satisfactory to say that $t = 1$ for the first point entered, $t = 2$ for the second, and so on, but SMOOTH.PAS takes a more sophisticated approach. The program begins with $t = 0$ and adds to t , at each point, the straight-line distance between that point and the previous one. This makes t roughly proportional to the length of the curve, so that the curve-fitting algorithm "knows" whether any two consecutive points are nearby or far apart. Thus, the program can decide how much curvature is acceptable between points: if points are close together, the line joining them should be relatively straight; if they are far apart, a kinkier line is allowed.



Enhancer™ ... EGA card, \$399

The EVEREX Enhancer is the IBM compatible EGA card that delivers value with price, performance, and features!

No Options Needed.

With other EGA cards you have to pay extra for options like 256K screen memory and a parallel printer port. With the Enhancer these features are standard and there are no extras to buy.

11 Display Modes

There's 16 colors from a palette of 64 in 640x350 resolution. Text is displayed in readable 8x14 character format in text mode. And the Enhancer's monochrome mode can support monochrome graphics on a monochrome monitor. In addition to 6 EGA modes and a monochrome mode, there's 4 color modes.

Software Switched

The Enhancer comes with EGMODE menu-driven software that lets you change display modes, even monitors, without opening your chassis, with the push of a button. Useful help windows take all the mystery out of each possible display mode.

The Perfect Adapter

For enhanced color graphics, monochrome text, and standard color text and graphics, the EVEREX Enhancer is the perfect adapter to pair up with your software library. Call your local dealer for a demo, or call EVEREX to get all the facts on our new line of video adapters.

1-800-821-0806 1-800-821-0807

In California

48431 Milmont Dr.
Fremont, CA 94538
(415) 498-1111


EVEREX

EVER for EXcellence

Enhancer is a trademark of EVEREX SYSTEMS, INC. IBM is a trademark of International Business Machines Corp.


CIRCLE NO. 139 ON READER SERVICE CARD

PHOTO 1: Selection of Points



The program lets the user enter values for x and y by moving the cursor around the screen and marking points. At least four points are needed; the number of the next point to be entered is shown at the bottom of the screen.

PHOTO 2: Resultant Curve



When all the required points have been entered, the program calculates the cubic equations that are necessary to link them. The cubics are calculated by simultaneous equations with two known points and two known slopes.

THE DIVINING ALGORITHM

If x and y are treated as functions of t , then two spline curves must be computed, one for x and one for y . The computation of each spline curve is itself broken into two steps.

First, the coefficients of all the cubics that are chained together to make the complete curve are computed. The coefficients are found by solving simultaneous linear equations. At the knots, the values of t , t^2 , t^3 , and x (or y) are known, as are the second derivatives (which are all 0); in addition, the first derivatives (slopes) must match at the points where the segments join. Only the coefficients are unknown, and because none of the coefficients is raised to a power, the simultaneous equations are linear even though they describe cubic polynomials. The equations are solved by a process called *Gaussian elimination* (explained in the Sedgewick book listed herewith).

The second step is to compute x (or y) for the desired values of t . Because a different cubic is used between each pair of knots, the first step in handling a given t is to find out which knots it falls between. When this has been done, the appropriate set of coefficients can be looked up and the cubic can be evaluated.

The heart of the program is **spline**, a procedure designed to be used unchanged in other programs. The only external definitions it relies on are constants **arraysize** and **splinesize** and types **point_array** and **spline_array**.

The input to **spline** consists of two arrays, **f** and **t**, and an integer, **count**, which tells how many elements of **f** and **t** are used. For any **n** between 1 and **count** inclusive, **f[n]** and **t[n]** define a known point. The routine assumes that **f** is a function of **t**, that the arrays are sorted so that **t** is in ascending order, and that no value of **t** occurs twice.


The output consists of an array **calct** containing equally spaced values of **t**, and an array **calcf** containing the corresponding interpolated values of **f**.

The program decides how much curvature is acceptable between points: if points are close together the line joining them is relatively straight; if they are far apart a kinkier line is allowed.

The number of calculated points is specified by the constant **splinesize**. In this program, **calct** is never used because the final display is a plot of x versus y . **Calct** would be important if the interpolation were one-dimensional rather than two-dimensional.

The remainder of the program provides a quick and simple demonstration

of **spline**. Note that because a major goal was to keep the program short, the routines other than **spline** are not particularly efficient. With the procedure **get_points**, the user inputs a set of points by moving the cursor around on the screen (see photo 1). **Get_points** treats both x and y as functions of t , which is the total linear distance between points. After the spline has been computed, the procedure **display** displays it on the screen (see photo 2). Several examples of the different curves that can be produced with this program are presented on the opening pages of this article, 112 to 113.

Spline will find purpose in many applications: especially attractive is its ability to store graphics images as only a few points, which is an economical use of memory. Perhaps what makes the program most useful is its ability to determine the distance between points and use this key in producing the smoothest of smooth curves. 

REFERENCES

- de Boor, Carl. *A Practical Guide to Splines*. New York, NY: Springer-Verlag, 1978.
Sedgewick, Robert. *Algorithms*. Reading, MA: Addison-Wesley, 1983.

Michael A. Covington, Ph.D., is a research associate at the Advanced Computational Methods Center, University of Georgia, where he is implementing a Prolog-like language on a CYBERPLUS supercomputer. The assistance of McLowery Elrod, Ph.D., on this article is gratefully acknowledged.

LISTING 1: SMOOTH.PAS

```
program smooth_curve;
```

```
( Turbo Pascal demonstration of parametric cubic splines )
( Michael A. Covington 1986 )
```

```
( This program draws a smooth curve connecting points )
( marked on the screen by the user. The points do not )
( have to define a function; internally, both X and Y )
( are functions of T, the approximate distance traveled )
( as the curve moves around the screen. )
```

```
( NOTE: We are using 640x200 graphics but treating it as )
( 320x200. Thus all X coordinates are multiplied by 2 )
( before being plotted on the screen. The graphical )
( cursor occupies the odd-numbered columns in which data )
( is never plotted. )
```

```
const arraysize = 100; ( maximum number of known points )
      splinesize = 400; ( number of points that are
                          calculated to draw the curve )
```

```
type point_array = array[1..arraysize] of real;
      spline_array = array[1..splinesize] of real;
```

```
var X, ( x-coordinates of known points )
    Y, ( y-coordinates of known points )
    t: point_array; ( t-coordinates of known points )
```

```
count: integer; ( number of known points )
```

```
calcx, ( x-coordinates of calculated points )
calcy, ( y-coordinates of calculated points )
calct: spline_array; ( t-coordinates of calculated points )
( CALCT is not actually used in this program, but is )
( included because other similar programs may use it. )
```

```
reply: char; ( user's reply to 'Again?' )
```

```
procedure get_points;
```

```
( Allows the user to move a cursor around the screen and )
( mark points. X, Y, and T are recorded for each point. )
```

```
const esc = #27;
      enter = ^M;
      up = ^H;
      down = ^P;
      left = ^K;
      right = ^M;
      beep = ^G;
```

```
var
  key: char;
  ix, ( current screen position )
  iy: integer;
```

```
function inkey: char;
( Waits for a key to be pressed and returns its code. )
( Returns the second byte if a 2-byte key is pressed. )
```

```
var
  c: char;
begin
  read(KBD,c);
  if keypressed then read(KBD,c);
  inkey := c;
end;
```

```
procedure graphics_cursor(ix,iy,color: integer);
( Puts the graphics cursor at ix, iy, )
( which are x and y expressed as integers. )
```

```
var
  i,dx,dy: integer;
begin
  for i:=1 to 5 do
  begin
    dy:=i;
    dx:=i+1;
    plot(ix+ix+dx,iy+dy,color);
    plot(ix+ix+dx,iy-dy,color);
```

```
    plot(ix+ix-dx,iy+dy,color);
    plot(ix+ix-dx,iy-dy,color);
  end;
```

```
function dist(x1,y1,x2,y2:real):real;
( Distance between two points )
begin
  dist := sqrt(sqr(x1-x2)+sqr(y1-y2));
end;
```

```
function same_point_again:boolean;
( True if the current point is the same as )
( the most recently entered point. )
begin
  if count < 1 then
    same_point_again := false;
  else
    same_point_again :=
      (ix = x[count]) and (iy = y[count]);
  end;
```

```
begin ( get_points )
```

```
  textmode;
  clrscr;
  writeln('Move cursor with arrow keys. ');
  writeln('Mark points with Enter key. ');
  writeln('Press Esc when finished. ');
  writeln;
  writeln('You must mark at least 4 points. ');
  writeln('Esc will not work until you do. ');
  writeln;
  writeln('You cannot mark more than ',arraysize,' points. ');
  writeln('You cannot mark the same point twice unless ');
  writeln('you have marked a different point in between. ');
  writeln;
  writeln('Erroneous input will result in a beep. ');
  writeln;
  writeln('Press Enter to begin... ');
  readln;
```

```
  hires;
  hirescolor(yellow);
  ( graphbackground(black); Uncomment to run on EGA )
```

```
  ix:=160;
  iy:=100;
  count:=0;
  key := ' ';
```

```
  while (count<4) or (key<>esc) do
  begin
    gotoxy(1,25);
    write('Point ',count+1,' x =',ix,' y =',iy,
          ' (Enter to mark, Esc to quit) ');
```

```
    graphics_cursor(ix,iy,1);
    key := inkey;
    graphics_cursor(ix,iy,0); ( erase previous cursor )
```

```
  case key of
    up: iy:=iy-1;
    down: iy:=iy+1;
    left: ix:=ix-1;
    right: ix:=ix+1;
    enter: if same_point_again or (count=arraysize) then
      write(beep)
    else
      begin
        count := count+1;
        x[count] := ix;
        y[count] := iy;
        if count=1 then
          t[count] := 0
        else
          t[count] := t[count-1] +
            dist(x[count],y[count],
              x[count-1],y[count-1]);
```


Read what the experts say about the PC's Limited AT.

"I have no qualms recommending this system to experienced users who need the added speed."

—Sol Libes,
Micro/Systems Journal,
January/February 1986

30 DAY
Money-Back
Guarantee



"The PC's Limited AT™ proved to be the functional equivalent to the IBM® product, only faster. Priced at roughly one-third less, it rates as one of the best bargains available."

—Winn L. Rosch,
PC Magazine,
February 25, 1986

"If price is your primary consideration, skip both AT&T® and TI® and choose this issue's best buy, the PC's Limited AT™. Check its benchmark results—you won't be sacrificing performance to save money."

—*PC Magazine*,
Editor's Choice,
February 25, 1986

**And if that's not enough to convince you,
now we've got a 30-day money-back guarantee.**



- One Year Limited Warranty
- 80286-based System Unit (Runs at 6MHZ. 8MHZ option included at no extra charge.)
- 1024K on Mother Board
- 1.2 Meg Floppy Drive
- Combined Floppy/Hard Drive Controller Card
- AT Keyboard
- 192W Power Supply
- 2 Serials and 1 Parallel Port
- Clock/Calendar with Battery Backup
- Operations Manual

\$1495

I'm Michael Dell, President of PC's Limited. And I want you to know about your latest industry-leading step. We're so sure that you'll like everything about our PC's Limited AT that we're willing to offer you a 30-day money back guarantee on it. This machine, with 1024K on the Mother Board and an 8MHZ option included at no extra cost, has been a standout since we introduced it. So give us a chance to show you what it can do for your operation. With a deal like this, there's no way you can lose. (And see the opposite side of this page for information about our Turbo PC™, plus details on our guarantee.)

Michael Dell

When a PC's Limited Turbo PC is on your desk, you'll think it's a headliner too.

"... a good machine. And a heck of a buy... a fine box. One I'd happily choose over Big Blue's original... no status... beyond the status that attaches to getting twice as much for your money."

—Jim Seymour,
PC Week,
August 13, 1985

"It almost sounds unbelievable."

—*MIS Week,*
August 21, 1985

"We tested a wide variety of software on the machine and everything ran well... The bottom line for anyone considering buying one of these computers would seem to be this: PC's Limited sells quality systems for extraordinarily low prices."

—*PC Week,*
October 29, 1985

TOTAL SATISFACTION GUARANTEE WARRANTY

For Warranty Service: One year Limited Warranty on PC's Limited products. Contact Technical Support for a Return Authorization Number (RMA). Returns must be accompanied by your RMA, the invoice, and a brief explanation. During the Warranty Period, PC's Limited will repair or replace items at our option.

30-DAY TOTAL SATISFACTION GUARANTEE

Any item bought from PC's Limited may be returned within 30 days from the date it was shipped for a full refund of your purchase price. Returned items must be as new, not modified or damaged, with all warranty cards, manuals, and packaging intact. Returned items must be shipped prepaid and insured, and must bear a PC's Limited Credit Return Authorization (CRA) on the shipping label. Call PC's Limited's Customer Support Department for CRA. No credit issued after 30 days from date of shipment.

CONSUMER TIP

When shopping for PC products, ask our competitors about their refund policies.

- 16-bit 8088-2 System Unit (runs at 4.77 or 6.66MHZ)
- 640K on Mother Board
- 360K Floppy Drive
- AT Keyboard
- 130W Power Supply
- Operations Manual
- One Year Limited Warranty


\$795

Microsoft GW Basic™ \$95 • IBM DOS 3.1 \$85 • 8087-2 \$149



Our Turbo PC™ has sold in large quantities since the first week we introduced it. Of course, that's not surprising, since we were the first company to break the \$800 barrier with a machine that outruns the "Big" name by a 40% speed factor. Now, we're going to extend the margin even further by offering a 30-day money back guarantee. If that sounds good, it'll look even better when one of our Turbo PC's is on your desk. So call us today. We're guaranteeing you'll like what you get.

Some quantities may be limited. PC's Limited sells equipment certified to be compliant with FCC Class B standards. Where equipment manufactured by PC's Limited has not yet received certification, PC's Limited will substitute equivalent certified equipment. All prices are subject to change without notice. We are an independent sales organization.



PC'S LIMITED™

SALES CALLS OUTSIDE TEXAS, 1-800-426-5150

SALES CALLS INSIDE TEXAS, 1-800-252-8336

1611 Headway Circle, Building 3, Austin, Texas 78754

Sales Calls from anywhere in the country, (512) 339-6962

Technical Support Calls, (512) 339-6963 Customer Service Calls, (512) 339-6964

*Limited Warranty

Telex No 9103808386 PC LTD FAX (512) 339-6721



Call for latest prices.

FREE SHIPPING

in the Continental United States via UPS Ground.

NO SURCHARGE FOR



OR




Floppy Disk Drive

Also available for AT™
in Gray Color.

MITSUBISHI
ELECTRONICS

Half-Height, DS/DD

\$95



PC'S LIMITED 20 MEG HARD DISK ON A CARD


\$409

- 3 1/2" Winchester Hard Disk
- Easy to install
- One Year Warranty



PC's Limited AT Multifunction Card

- Expandable To 3 Meg
(1.5 on Board/1.5 on Piggy Back Board)
- Supports 64 or 256K Rams
- Parallel Port
- Serial Port (2nd Serial Optional)



\$199


Piggy Back
w/OK Board \$59 w/OK

PC's Limited Mini I/O

- Serial Port
- Parallel Port
- Clock
- Software
- Fits In Short Slot

\$99

300/1200 Baud Hayes Compatible Modem Fits in Short Slot




\$159

UNIVERSAL GRAPHICS CARD II

\$199


- Fully compatible with IBM CGA.
Plantronics COLORPLUS,
IBM Monochrome,
and Hercules compatible graphics modes.
- Includes Parallel Port and fits in a "short" slot.



Seagate

20 30 and 40 MEG
High Speed
40 MS Access Time
Hard Drives for AT™

Uses Linear
Voice Coil
Activator.



Heads park automatically
at power down.

20 MEG \$579
30 MEG \$699
40 MEG \$819

Includes Seagate Full Height Hard Disk,
Cable, and Mounting Rails.
Boots from Hard Disk. One Year Warranty.

PC'S LIMITED Six Function Card

- Upgradable to 384K
- Clock/Calendar
- Includes Software
- Parallel Port
- Serial Port
- Game Port




Two Year Warranty

w/OK \$99 w/384K \$149

PC's Limited PC-576 RAM Board

- Expandable to 576K
- Supports 64K or 256K RAMS
- Fits in Short Slot


\$69 w/OK



SOLVE YOUR POWER PROBLEM.


XT™ POWER 130W

\$99




Directly replaces power
supply in PC.™
Fully XT™ compatible.
One Year Warranty

MONO-II
\$129



- Flat screen
- Tilt and swivel base
- New circuit yields
outstanding display

**PC'S LIMITED
RGB-1 MONITOR**
\$459




- .31MM dot pitch
- RGB input
- 12-inch screen
- 690x240 resolution
- 16 colors

Wangtek 60 MEG Tape Backup System

- Backs up 5 Megs per minute
- Runs under MS DOS or PC DOS, Novell, Xenix
- Pulse Software Included

\$795



Tandon HD Western Digital Controller 20 MEG Hard Disk System for PC™



Internal
\$409

Includes Tandon Hard Disk, Western Digital Controller, Cables, Manual, Software, and Mounting Hardware. Boots from Hard Disk One Year Warranty

Or add a second 20 MEG Hard Drive to your system with the PC's Limited Hard Disk Kit—Two 20 MEG Hard Disks daisy-chained together, plus a controller card—\$495.

Our Hard Disk Systems are compatible with the latest versions of the following Computers: IBM PC, IBM XT, AT&T 6300, Compaq Deskpro, Tandy 1000, Tandy 1200, PC's Limited Turbo PC, Leading Edge PC (Both Models), Sperry PC, Wyse PC, Compaq Deskpro, Televideo PC, Corona PC, Eagle PC, AT&T 6300, Tandy 1000 and Tandy 1200 are trademarks of their respective companies.

PLEASE SPECIFY YOUR COMPUTER TYPE WHEN ORDERING.

WARRANTY

For Warranty Service: One Year Limited Warranty on PC's Limited products. Contact Technical Support for a Return Authorization Number (RMA). Returns must be accompanied by your RMA, the invoice, and a brief explanation. During the Warranty Period, PC's Limited will repair or replace items at our option.

30-DAY TOTAL SATISFACTION GUARANTEE
Any item bought from PC's Limited may be returned within 30 days from the date it was shipped for a full refund of your purchase price. Returned items must be as-new, not modified or damaged, with all warranty cards, manuals, and packaging intact. Returned items must be shipped prepaid and insured, and must bear a PC's Limited Credit Return Authorization (CRA) on the shipping label. Call PC's Limited's Customer Support Department for CRA. No credits issued after 30 days from date of shipment.

CONSUMER TIP

When shopping for PC products, ask our competitors about their refund policies.



PC'S LIMITED™

SALES CALLS OUTSIDE TEXAS, 1-800-426-5150

SALES CALLS INSIDE TEXAS, 1-800-252-8336

1611 Headway Circle, Building 3, Austin, Texas 78754

Sales Calls from anywhere in the country, (512) 339-6962

Technical Support Calls, (512) 339-6963

Customer Service Calls, (512) 339-6964 and MCI MAIL: PC's LIMITED

Telex No. 9103808386 PC LTD FAX (512) 339-6721

Panasonic, TEAC, Mitsubishi, Intel, IBM, Hercules, Plantronics, Seagate, Western Digital, AT&T, Compaq, Tandy, Leading Edge, Sperry, Wyse, Televideo, Faraday, Corona, Eagle, and ITT are registered trademarks of their respective companies. IBM PC, IBM XT, IBM AT are trademarks of IBM Corporation. Leading Edge PC, Sperry PC, Wyse PC, Compaq Deskpro, Televideo PC, Corona PC, Eagle PC, AT&T 6300, Tandy 1000 and Tandy 1200 are trademarks of their respective companies.

Some quantities may be limited. PC's Limited sells equipment certified to be compliant with FCC Class B standards. All prices are subject to change without notice.

Ad Number A08/86


```

        plot(2*ix, iy, 1)
    end
    else ( do nothing );
    end ( case )
end
end;

procedure spline(f,t:point_array;
    count:integer;
    var calcf,calct:spline_array);

    ( Fits a cubic spline to F[1..COUNT] as a function of )
    ( T[1..COUNT], then calculates equally spaced values )
    ( of T, places them in CALCT[1..SPLINESIZE], computes )
    ( the corresponding interpolated values of F, and )
    ( returns them in CALCF[1..SPLINESIZE]. )

    ( At least 4 points must be given. The points are )
    ( assumed to be sorted in order of increasing T. )

    ( Adapted from the FORTRAN routine CUBSPL (Carl de Boor, )
    ( A PRACTICAL GUIDE TO SPLINES, New York: Springer, 1978). )

var
    a,b,c: point_array; ( spline coefficients )
    d,e,g,h, ( used in finding spline coefs. )
    wt,dt: real; ( used in calculating points to plot )
    i,j: integer; ( loop counters )

begin
    ( Compute first differences of T and F )

    for i:=2 to count do
        begin
            b[i] := t[i]-t[i-1];
            c[i] := (f[i]-f[i-1])/b[i]
        end;

    ( Take care of beginning of curve )

    c[1] := b[3];
    b[1] := b[2] + b[3];
    a[1] := ((b[2] + 2*b[1])*c[2]*b[3] + b[2]*b[2]*c[3]) / b[1];

    ( Forward pass of Gaussian elimination )

    for i:=2 to count-1 do
        begin
            g := -b[i+1] / c[i-1];
            a[i] := g*a[i-1] + 3*(b[i]*c[i+1] + b[i+1]*c[i]);
            c[i] := g*b[i-1] + 2*(b[i]+b[i+1])
        end;

    ( Take care of end of curve )

    g := b[count-1] + b[count];
    a[count] := ((b[count]+g)*c[count] * b[count-1]
        + b[count] * b[count]
        * (f[count-1]-f[count-2]) / b[count-1]) / g;
    g := -g / c[count-1];
    c[count] := b[count-1];

    ( Complete the forward pass )

    c[count] := g*b[count-1] + c[count];
    a[count] := (g*a[count-1] + a[count])/c[count];

    ( Back substitution )

    for i := count-1 downto 1 do
        a[i] := (a[i]-b[i]*a[i+1]) / c[i];

    ( Generate cubic coefficients )

    for i:=2 to count do
        begin
            d := (f[i]-f[i-1])/b[i];
            e := a[i-1] + a[i] - 2*d;

```

```

        b[i-1] := 2*(d-a[i-1]-e)/b[i];
        c[i-1] := (e/b[i])*(6/b[i])
    end;

    ( Compute the points to be plotted as function of WT )

    wt := 0;
    dt := t[count] / (splinesize-1);
    j := 1;

    for i:=1 to splinesize do
        begin
            ( Ensure that wt is between t[j] and t[j+1] )
            while t[j+1] < wt do j:=j+1;
            ( Calculate a point )
            calct[i] := wt;
            h := wt - t[j];
            calcf[i] := f[j]+h*(a[j]+h*(b[j]+h*c[j]/3)/2);
            ( Move to next point )
            wt := wt+dt
        end
    end;

    procedure fit_curve;
    begin
        gotoxy(60,25);
        write('Calculating...');
        spline(x,t,count,calcx,calct);
        spline(y,t,count,calcy,calct)
    end;

    procedure display;

    ( Displays the fitted curve and the original points. )

    var i,k,ix,iy: integer;

    begin
        hires; hirescolor(yellow);
        ( graphbackground(black); Uncomment to run on an EGA )

        ( Draw crosses at the original points )
        for i:=1 to count do
            begin
                ix := 2*round(x[i]);
                iy := round(y[i]);
                draw(ix-4,iy-2,ix+4,iy+2,1);
                draw(ix+4,iy-2,ix-4,iy+2,1)
            end;

        ( Plot the spline curve )
        for i:=2 to splinesize do
            draw(round(2*calcx[i-1]),
                round(calcy[i-1]),
                round(2*calcx[i]),
                round(calcy[i]),
                1);

        gotoxy(1,25);
        write(' (Press Enter when finished viewing) ');
        readln
    end;

    ( main program )

    begin
        repeat

            get_points;
            fit_curve;
            display;


            textmode;
            write('Again? (Y/N) ');
            readln(reply)
            until reply in ['N','n']

        end.

```


ASYSTANT scientific software. Flexible menu-driven environment gets you up and running—fast.

Fully integrated analysis, graphics, and processing functions operate directly on large datasets.




Lets you interact visually with your data. Just scroll, select curve segments, and watch your results appear.

Unique features give you flexibility not found in most menu-driven packages.

On-line help is always available by typing "?".

Acquired data is immediately available for analysis and graphics. You never have to shuffle programs.



Gives you more power for the price than any other software for the IBM PC.

A single keystroke lets you import data from spreadsheet and other data file formats.

Presentation-quality scientific graphics easily output to plotters.

The PC software of choice when you don't want to program.

Now get the power of widely acclaimed ASYSTTM Scientific Software in a stand-alone menu-driven package: ASYSTANT Ready-to-Run Scientific Software.TM Easy to learn and use whatever your computer background, ASYSTANT is a fully integrated analysis and graphics package. It's versatile, too. Unlike other menu-driven products, ASYSTANT gives you an extensive feature set and macro capability to tackle your toughest applications.

Built-in functions include FFT, smoothing, integration, differentiation, curve fitting, statistics, differential equations, and matrix and polynomial operations. And all analysis functions are fully linked to powerful graphics capabilities, including axonometric and contour plotting. ASYSTANT menu-driven scientific software—just \$495.

Optional data acquisition with ASYSTANT +. Get all the features of the ASYSTANT package, *plus*

one-touch data acquisition, with ASYSTANT +. No extensive prompt lists. No tedious set-up. Just choose the "metaphor" of the collection instrument you wish to simulate—such as XY or strip chart recorder, data logger, or signal averager—and you're ready to go. Only \$895.

Free technical support. 60 days of free technical support help you design, set up, and fine-tune the perfect system. It's your guarantee of trouble-free operation.

**30-Day No-Risk Offer.
CALL 1-800-348-0033**

In New York state, (212) 702-3241.

Macmillan Software Co.

An affiliate of Macmillan Publishing Company
630 Third Avenue, New York, NY 10017

ASYSTANT Ready-to-Run Scientific Software and ASYSTare trademarks of Macmillan Software Co.
ASYST and ASYSTANT were developed by Adaptable Laboratory Software, P.O. Box 18448, Rochester, NY 14618

RAMpage AT™ The Cure for



the AT Blues.



Doc plays sax down at Al's on Wednesday nights. That's blues night at Al's. And sometimes, if you shut your eyes and listen to that sultry, wailing music, you'd swear there's more than just one, lone sax playing. Doc knows his sax...been playing the same one over thirty years. And he plays it for all it's worth.

At AST we know the IBM® PC AT. We were the first to produce and ship an AT enhancement product. Like Doc's sax, your PC AT is a remarkable instrument with great potential. But if you're not using our RAMpage AT expanded memory solution, you're not playing it for all it's worth.



A Sure Cure For The AT Blues. Our RAMpage AT with up to 2 megabytes of RAM and DESQview™ multitasking/windowing software lets your PC AT soar to its maximum potential. And lets you realize your full AT investment value.

RAMpage AT For Multitasking Power. The RAMpage AT's powerful features combined with the PC AT's speed offer fast and functional multitasking capability.

Only with RAMpage AT can you sort a database, watch on-line stock quotations, calculate a spreadsheet, print labels and write a letter using your favorite word processing package...all at the same time...on the same PC AT. And with DESQview's windows you'll view and access up to nine applications instantly. You'll work faster and avoid time-consuming workflow interruptions.

Compatibility You Can Rely On. Our Enhanced Expanded Memory Specification is simply a more powerful, fully compatible version of the Lotus®/Intel®/Microsoft® (LIM) Expanded Memory Specification (EMS). With RAMpage AT you can use *All EMS Software*.



It's even certified compatible by Lotus Development for 1-2-3® Release 2 and Symphony® 1.1.

Powerful Features. RAMpage AT offers up to two megabytes of expanded memory that can also be used as extended memory, DESQview multitasking/windowing software, SuperPak™ utilities and our two-year warranty. Additionally, AST offers several models of the RAMpage AT-Pak, an optional module featuring serial, parallel and game ports.

Play Your AT For All It's Worth With RAMpage AT. For more information call our Product Information Center (714) 863-1480. Or send the coupon to AST Research, Inc., 2121 Alton Avenue, Irvine, California 92714-4992.

RAMpage AT and SuperPak trademarks of AST Research, Inc. IBM registered trademark of International Business Machines Corp. DESQview trademark of Quarterdeck Office Systems. Lotus, 1-2-3 and Symphony registered trademarks of Lotus Development Corp. Microsoft registered trademark of Microsoft Corp. Intel registered trademark of Intel Corp. The RAMpage AT Expanded Memory Board has successfully passed compatibility testing with 1-2-3 Release 2 and with Symphony 1.1 on an IBM AT with PC-DOS 3.1. Two megabytes of memory were installed. The Lotus logo is used by permission of Lotus Development Corp.

AST

RESEARCH INC.

Copyright © AST Research, Inc., 1986. All rights reserved.

CIRCLE NO. 140 ON READER SERVICE CARD

Yes, I want the cure for the AT blues. Please send me more information about RAMpage AT.

Name

Title

Company

Address

City State Zip

Phone

AST Research, Inc., 2121 Alton Avenue, Irvine, CA 92714-4992.

PCTR/AT-B1

The DataFlex logo is positioned at the top of the advertisement. It features the word "DATA" in a blue-to-yellow gradient and "FLEX" in a green-to-magenta gradient, both in a bold, sans-serif font. Below the logo, a wide, multi-colored beam of light, resembling a rainbow, extends downwards towards the bottom of the page. The beam is composed of several vertical stripes of color: blue, orange, red, yellow, green, and magenta. The background of the entire advertisement is black.

DATA FLEX[®]

*The World's
Best Selling
Multi-User
Database
For Five Years
Running.*

DataFlex versions are available
for all popular single-user and multi-user
operating systems, including Xenix.

For a free copy of this poster
(minus ad copy), write Data Access Corp.
or leave a message on our
Bulletin Board System: (305) 238-0640.

DATA ACCESS CORPORATION
8525 S.W. 129th Terrace—Miami—FL—33156-6565 (305) 238-0012—Telex 469021 DATA ACCESS CI

CIRCLE NO. 118 ON READER SERVICE CARD


Software Sprites

Although the IBM PC is hindered by a lack of animation hardware, some unusual programming work-arounds can yield rather sophisticated results.

MICHAEL ABRASH and DAN ILLOWSKY

IBM PC animation is crude in comparison to arcade-quality games. Where game machines—which include personal computers far less expensive than the PC—routinely animate many large objects without flicker or interference, PC animation tends to feature a few small, flickering images. Worse, odd color and fringe effects occur when objects overlap on the PC, instantly destroying the illusion by reveal-

ing the animated objects as nothing more than arrangements of pixels. This is the case because the PC simply was not built as a game machine, and consequently lacks basic animation hardware. It is often true, however, that clever software can replace hardware. This holds for animation: software emulation of the hardware animation capabilities of game machines is a realizable, albeit difficult, goal for the PC.



COMPUTER GRAPHIC • LINDA GOTTFRIED

ILLUSTRATION • AKIO MATSUYOSHI

The key to sophisticated animation for the PC is the emulation by software of the hardware sprites that make animation on game machines so spectacular, yet simple to implement. From a programmer's perspective, a hardware *sprite* is a screen object for which all the details of drawing the corresponding image are handled in hardware. Animation hardware generally supports many sprites, allowing multiple objects to be animated simultaneously. When sprites overlap, the sprite with the higher priority is displayed in front of the others, making the objects seem solid and the screen three-dimensional. Objects with lower priorities are clearly visible around the edges and through transparent areas of higher-priority sprites. Sprites are nondestructive, so the programmer never has to worry about restoring the background or other sprites when one is moved. Once a sprite has been reprogrammed with the new location of an object, the hardware assumes all responsibility for updating the screen correctly, leaving the programmer free to concentrate on the design of a program rather than the messy details of animation.

The IBM PC has no sprite hardware, nor anything resembling it. Animation for the PC must be performed entirely by the 8088, a task of such complexity and realtime constraints as to make software sprites seem impossible. The history of microcomputers, however, has proven many times over that the seemingly impossible often is achievable if a programmer will not let such an assumption get in the way of searching for a solution.

This article traces the design and implementation of a software sprite driver that concedes nothing save a little time and memory to hardware sprites. The actual implementation also illustrates many features of animation programming. Software sprites were created for both the IBM Color Graphics Adapter (CGA) and the Enhanced Graphics Adapter (EGA) and will take advantage of the little-known vertical interrupt feature of the EGA to make that implementation more powerful and program-independent. Finally, some finer points of realtime animation and a few design approaches through which animation programs using software sprites can achieve even more striking effects are discussed.

A SPRITE ENGINE

The animation driver must handle all the details of smoothly drawing multiple objects so that when they overlap,

each will appear to exist in a separate plane. Software sprites will support object overlap, background preservation, display priority, transparency, and independent background processing—all the properties that make hardware sprites so visually effective—and one other feature as well: independent background processing.

The hardware in game machines draws sprites independently of the application (except when the program is reprogramming a sprite). The same sort of animation independence is desirable in software sprites. The EGA version of this driver is controllable from any program via a standard interface; it operates in the background, transparently and asynchronously to the calling pro-

T*o display only the end product of erasing all the objects and redrawing them (and thus avoid flicker), the cycle must be completed during nondisplay time.*

gram and apart from the interface calls. When an application program notifies the sprite driver of a change in the coordinates of an object, the driver automatically erases the object at its old location and redraws it at its new location during the next available drawing time. This driver is, therefore, appropriately called a *sprite engine* because once programmed it supports self-contained and complete animation. The CGA version requires the application to emulate the vertical interrupt feature of the EGA, which makes it less application-independent, but in all other respects it supports true software sprites.

Some familiarity with animation, including both the relocating of images to create the illusion of motion and the organization of display memory in 320-by-200, four-color graphics mode, is assumed on the reader's part. (See "Animation Techniques," Michael Abrash and Dan Illowsky, July 1986, p. 46 and "The IBM Color Graphics Adapter," Thomas V. Hoffmann, July 1983, p. 26.)

The first requirement in creating the sprite engine is an animation driver that causes each object to appear to be in a separate plane, so that objects clearly will pass behind and in front of

each other. When an object is moved, the area it covered at the old location must be restored to the object or objects that are "behind" it, or to the background if no other objects were at that place. In addition, when the object is redrawn at its new location, it must be overlapped by more forward objects and must overlap more rearward objects. While other workable solutions to the overlap problem are available, the method outlined below keeps this driver simple and flexible.

A straightforward way to ensure that a certain object always appears in front of some objects and behind others is to redraw all the objects from scratch in the same order each time any object is drawn (in increasing order of priority—the object that appears to be nearest the background first, one that appears to be nearest the viewer last). A considerable amount of processing time is required here, the more so because all the objects must be erased (that is, restored to the background) before they can be redrawn. However, this process ensures that the higher-priority objects will be drawn over the lower-priority objects whenever the two overlap, which creates the illusion that the higher-priority objects are in front.


While this approach is fundamentally correct, problems remain. The objects will vanish frequently (and flicker as a result) as they are erased and redrawn. A special driver is required to allow rearward objects to show through and around the edges of the forward objects. In order to display only the end product of the cycle of erasing all the objects and then redrawing them (and thus avoid flicker), the entire cycle must be completed during nondisplay time. This explanation requires some familiarity with the nature of bit-mapped graphics and the display controller.

BIT-MAPPED GRAPHICS

The EGA and CGA are bit-mapped graphics adapters, which consist of two parts: memory and a display controller that constantly scans that memory, translates the contents of the memory into video data, and sends the video data to a monitor. The monitor then uses the video data to control the electron beam that is scanning pixels onto the screen. The correspondence of display memory to pixels is shown in figure 2 of "Animation Techniques" (July 1986, p. 49). However, this figure conveys only a static sense of the dynamic process of mapping display memory to pixels.

Pixels actually are drawn one at a time by the scanning electron beam,

FIGURE 1: *Electron Beam Scan*



The beam is turned off while moving through retrace upward or rightward. The portion of the beam that falls outside of display memory is called *overscan*.

which traces a pattern like that shown in figure 1 (of this article). This figure is a simplification of display monitor scanning, but illustrates two important points: the electron beam scans left to right while progressing downward, and margins are present at all four sides of the screen where the pixels generated by the display controller are not based on the contents of display memory.

The electron beam scans pixels onto the screen from left to right, then returns rapidly to the left margin upon receiving the horizontal synchronization pulse from the display controller. The video data sent to the display is based on the contents of display memory except during the left and right margins (the horizontal retrace period). Likewise, the beam progresses downward as it scans left to right, returning rapidly to the top of the screen upon receiving the vertical synchronization pulse. The vertical retrace period is that time at the top and bottom margins of the screen when display memory does not affect what is being displayed on the screen. The time required to scan the entire display and return to the upper left corner is called the *frame time*, while the time required to scan a single line and return to the left side of the screen is called the *scan line time*.

Together these two figures (figure 2 from the July article and figure 1 here) illustrate the direct correspondence of memory scanning to display scanning over time. At any one time, one area of memory (at most) is being scanned to provide video data for one

area of the display. During the retrace periods, however, memory is not being scanned for video data at all, and bit-mapped video data is not being sent to the screen. As a result, any changes made to a given area of display memory during the retrace period will not be seen immediately; in fact, such a change will not be apparent until the point in the next frame when that area of memory is next scanned for video data.

Consequently, if a display memory byte is changed twice during the same retrace period, only the second change will show up on the screen. This is precisely the technique needed to rid the sprite engine of flicker; if objects are erased and redrawn during the same retrace period, the erasure will never be seen. To the viewer, the objects will appear to have moved from one location to the next with no transition.

Erasing and redrawing during a single retrace period, however, is more easily said than done. Even the highly efficient driver developed here requires a substantial amount of time to erase and redraw an object. A medium-size object, for example, takes roughly one or two milliseconds (ms) to draw (including erasing and redrawing), and *all* objects must be erased and redrawn every time any one object is moved (although the erase step may be skipped for certain objects, as discussed below). The next step, then, is to find adequate consecutive retrace time.

The horizontal retrace period clearly is too brief to be useful in supporting sprites. In 320-by-200 graphics



It's good for your system.

FULLY Integrated, Data Entry Windows!

- Complete input formatting
- Unlimited Validation
- Full attribute control
- Multiple virtual windows
- Fully automatic, collision proof overlay and restore
- Print to & scroll background windows
- Animated window "zoom"
- Move, grow, shrink, hide, or show any window
- "Loop function" allows processing while awaiting input

AND MUCH MORE!

\$149.95

Includes 100% source, tutorial, reference manual, examples, and sample programs.

Specify Microsoft, Lattice v2 or v3, Computer Innovations, Aztec, DeSmet, or Mark Williams. Ask about Unix.

100% Money Back Guarantee

NOW ... VCScreen!

Our new interactive screen "painter" actually lets you draw your data entry windows! Define fields, text, boxes & borders. Move them around. Change attributes. Then the touch of a button generates C source code calls to the Vitamin C routines!

\$99.95

Requires Vitamin C Library above. For IBM & compatibles.


For Orders Or Information, (214) 245-6090

Creative Programming Consultants, Inc.
Box 112097 Carrollton, TX 75011-2097

Include \$3 ground, \$6 air, \$15 overnight shipping. \$25 if outside USA. Texans add 6% tax. All funds must be in U.S. dollars drawn on a U.S. bank.

creative
PROGRAMMING

Now 3 CPU Boards from I-Bus



I-Bus now has 3 processor cards for board-level, dedicated OEM systems on the PC Bus: **Y88**. With RS-232/422 console support for upload/download. Lots (256K) of on-board EPROM for dedicated applications. Doesn't need a keyboard or display.

B88. Closer to a clone. It can use a standard IBM® keyboard.

R188. Has 80188 processor that runs on the PC Bus but executes the AT's instruction set.

All have an enhanced BIOS for disk or diskless operation, and optional ROM debugger. We also have a full line of chassis and card cages with PC Bus backplanes.

If you're into systems, I-Bus speaks your language. Call now TOLL FREE 800-382-4229 for the latest on board level PCs. (In Calif. call (619) 569-0646.)



I-BUS SYSTEMS

9235 Chesapeake Drive
San Diego, CA 92123

CIRCLE NO. 202 ON READER SERVICE CARD

SPRITES

mode, for example, an entire horizontal scan line takes only 62.5 microseconds. Trying to do any redrawing during this period is out of the question. However, each full frame takes much longer—16.7 ms, a rate of 60 frames per second. Thus, the vertical retrace period provides sufficient consecutive retrace time to implement a useful sprite engine.

Note that the EGA's highest-resolution mode (350 scan lines) has virtually no vertical retrace period at all, so the sprite engine cannot be implemented. However, in the modes with 200 scan lines, including the CGA-compatible graphics modes and the 16-color graphics modes, just under one-quarter of each frame (about 4 ms) is in vertical retrace; this is ample time in which to perform effective animation. The CGA-compatible 320-by-200, 4-color mode is used in this article because it allows the same routines to be used in both the CGA and EGA versions and because handling multiple colors in a single image is much easier with the CGA mode than the EGA. However, the EGA's 320-by-200 and 640-by-200 16-color modes certainly could be supported by the sprite engine with modifications to the graphics driver.

Thus, the problem of flickering objects is solved by performing all erasing and redrawing during the vertical retrace period in a 200-scan-line mode. Applications that demand higher vertical resolution require a different technique. As is often the case, no general solution exists: challenges must be dealt with on a case-by-case basis.

A SPRITE-LIKE DRIVER

The remaining problem is to draw objects in a sprite-like fashion, with one object clearly in front of the other and with no interference effects—and to do so reasonably quickly. The AND/OR driver solves this problem neatly.

Like other graphics drivers, the AND/OR driver modifies an area of display memory that controls a rectangular area of the screen; it operates from a table of bytes that describe the object to be drawn. The unusual aspect of the AND/OR driver is that each byte of the final image written into display memory is controlled by a pair of image table bytes. The first image table byte of each pair is used to mask off bits in display memory with the AND instruction; the purpose of the masking is to clear the bits controlling the pixels where the new object is to go without disturbing the bits controlling the pixels that the new object does not affect. The second image table byte of the pair is the actual

MathCAD

The Engineer's Scratch Pad

↓ FOURIER.MCD ↓


FOURIER RECONSTRUCTION: SQUARE WAVE

N := 40 j := 0 .. N ... 40 points

S_j := 1 - 2 · 2(j - 20) ... step function

Reconstruct function, using first two terms of Fourier series i := 1,3 .. 3

$$R_j := \frac{4}{\pi} \sum_i \frac{1}{i} \sin \left[i \cdot 2 \cdot \pi \cdot \frac{j}{N} \right]$$



A powerful computation and documentation tool for your IBM-PC.

With MathCAD you simply and interactively create, edit and display formulas on the screen the way you are used to writing them. Equations are instantly computed and the results displayed on the screen as a single number or a plot. Text may be added to the screen and everything may be printed out as an integrated document.

MathCAD has built-in hyperbolic and circular functions, performs all calculations with real and complex numbers, performs iterative calculations, handles all units, performs error checking and dimensional analysis and much more...

The price of MathCAD—\$189.

In Massachusetts add 5% sales tax.

To order send check, p.o., call us with your MasterCard number or call us for the nearest dealer.


1.800.MathCAD or 617.577.1017

Math Soft

Σ + √ - = × ∫ ÷ δ

One Kendall Square
Cambridge, Massachusetts 02139

CIRCLE NO. 250 ON READER SERVICE CARD
PC TECH JOURNAL

FIGURE 2: AND/OR Driver Operation

In the first frame, just the background is visible. In the second, the AND pass of the AND/OR driver clears those bits where the object will appear. Finally, the OR pass inserts the bits from the object itself without disturbing the background bits.

pixel data for the object, which is inserted into the masked display memory byte with the OR instruction.

This approach allows objects to cross without the odd color effects that are typical of exclusive-or drivers or the rectangular blanking fringe around objects that occurs with a byte-move driver, and allows the background to show through transparent (background-colored) areas of an object. (Any background-colored area may be made opaque simply by using the mask byte to mask out the background.)

Figure 2 illustrates how the two steps of the AND/OR driver work together to insert an object into display memory. The left frame shows the background before the object is drawn. The middle frame shows the display after the bits where the object is to appear have been masked off with the AND instruction (only those pixels where the object is to appear have been affected). The right frame shows the display after the object has been inserted into display memory with the OR instruction. All pixels other than those belonging to the object remain unchanged, so the object is inserted into display memory without interference effects.

Unfortunately, this approach is not particularly fast, even when in-line code is used, because two image table bytes must be read for every display memory byte modified. Also, because the AND and OR logical functions must be performed, little advantage can be derived from the use of the highly efficient string instructions. If faster drawing is required, a byte-move driver, which simply moves a rectangular block of image table data into display memory, can be used as a substitution for the AND/OR driver; in this case, however, it would cause the objects to be surrounded by blanking fringes, and transparency would not be supported.

Nevertheless, a driver like the byte-move driver is used for another pur-

pose in the sprite engine: to erase the objects. An uncomplicated way to support an arbitrarily complex static background is to store the entire background in a separate buffer in normal memory that corresponds on a byte-to-byte basis with the display memory buffer, and then erase each object (restore it to the background) by copying the bytes corresponding to the area covered by that object from the background buffer to display memory. To do this, the driver simply calculates a single offset, which applies to both the background buffer and display memory, and then uses in-line code to copy the background data into display memory.

These two drivers put the last piece of the sprite engine into place. The screen will be updated each time any object moves: all objects will be erased by restoring their area of display memory to the background first and then redrawing them with the AND/OR driver, all during a single vertical retrace period. With this in mind, consider a unique feature of the EGA that makes the sprite engine efficient and easy to implement.

THE VERTICAL INTERRUPT

The graphics driver described here requires that the erasing and redrawing sequence start at the very beginning of

Turbo Pascal Programmers:

Turbo-Task allows any Turbo Pascal Program to run in Foreground or Background

Turbo-Task will make your program resident in memory just like Sidekick, but with one big difference: your program can also operate in background! Turbo-Task is simple to use and complete in its operation. You only add two lines to your source code. Turbo-Task takes responsibility for all multitasking duties. You specify the invoke key that will bring the program to the foreground (it will pop up just like Sidekick) and you specify a time-slice weight the program will have when operating in background. A non-zero weight will allow the program to continue operation if the user moves it to the background. It will still have full access to disk and printer. When it completes its job, (i.e. processing data on disk and printing a report), it has the option to reset its weight to zero, thus remaining dormant until the user presses its invoke key and brings it to the foreground again. Meanwhile, the user has been running other software undisturbed by this background task. Up to 16 programs can use Turbo-Task at the same time, each with its own invoke key, independent foreground window, and time-slice weight. You do not need to understand multitasking theory to use Turbo-Task. All the work is done for you. Turbo-Task does not interfere with SIDEKICK. Works with TURBO EDITOR and GAMEWORKS.

Ram-Page provides a Virtual Screen of any Size

Ram-Page takes heap space to create up to 16 pages that can be used as virtual screens. The dimensions you select are only limited by system memory. 256k of heap could be allocated to a single Page with 80 chars by 1600 lines! All of Turbo's text handling routines will operate on the Pages. Write, Writeln, Crlf, CrlfEol, InLine, DelLine, Window, and Gotoxy will be redirected to work on the Page you specify. View-Page allows you to display any portion of a Page on the screen. This "view window" is automatically updated as writes are made to the Page. These windows can appear, disappear, move, and overlap. Text written to a hidden window will be there when the overlapping window disappears. Text can be moved between pages. Foreground and background attributes are maintained separately for each Page. Ram-Page also provides two new routines: InsColumn and DelColumn.

Turbo-Linker breaks the 64k Code Segment Barrier

Turbo-Linker performs two important functions: it allows your program to grow beyond 64k, and it eliminates the need to continually recompile debugged routines. Turbo-Linker will convert a set of your procedures into a module that can be loaded into the heap at run time. These procedures will operate in the heap thus freeing space in the code segment for the main program. In effect, it is using the heap for overlays, except these "overlay" module can be shared by any number of programs. Once you create a module, you never have to recompile it. You can maintain a library of modules of your frequently used procedures. There is no limit on the number of modules that can be loaded or the number of routines in any module. A loaded module can be "disposed" and a new module loaded in its place. Handles global variables. Allows calls between modules.

All these utilities — ONLY \$70

Tangent Technologies

180 North Wacker Drive • Suite 350 • Chicago, IL 60606 • (312) 263-0024
MC/VISA Requires Turbo 3.0 for PC compatibles

Turbo Pascal, Turbo Editor, Gameworks and SideKick are trademarks of Borland Intl.

Get a Grip on Assembly Language.

The award winning
Visible Computer:
8088.



The Visible Computer is a book and software combination for mastering the elusive skills of assembly language.

It's an animated simulation of the PC's microprocessor that lets you see with your own eyes how assembly language works. You'll be using it as a debugging tool for years to come.

It's a tutorial. A lot of people think the 350 page manual is the best book on assembly language ever written.

It's 45 demonstration programs you'll execute with the simulator, from simple register loads to advanced programs that manipulate interrupts and perform file I/O.

- Applies to all 86 family processors, including 80186 and 80286.

- PC Tech Journal "Product of the Month."

\$49.95

Copy Protected

\$79.95

Unprotected

The Visible Computer for IBM PC/XT/AT and true compatibles. If your dealer doesn't have it, order direct: Software Masters, 2714 Finfeather, Bryan, TX, 77801. (409) 822-9490. Please include \$3.00 shipping. Bank cards accepted.



TVC takes you inside the processor as it executes programs.

Software Masters™

SPRITES

THE EGA'S VERTICAL INTERRUPT STATUS BIT

IBM suggests that each hardware interrupt handler check to make sure that the interrupt to which it is responding was generated by the device it handles, passing along the interrupt to the next handler for that interrupt if it is not. This approach, if followed by all devices, allows multiple devices to share the same interrupt level and expands the PC's device-handling capabilities in addition to reducing potential conflict between peripherals. The IBM EGA provides a vertical retrace status bit (bit 7) in the Input Status 0 register for just this purpose. IBM specifies that when an interrupt occurs on IRQ2, the routine handling the EGA's vertical interrupt should check this bit, passing the interrupt along to the next handler if the bit is low and handling it if the bit is high.

That, at any rate, is the theory.

Two factors complicate the interpretation of the vertical retrace status bit, however, rendering it of limited usefulness, and, in fact, making it desirable in many circumstances to ignore the vertical retrace status bit entirely. First, some EGA-compatible adapters, including Quadram's QuadEGA+, return an inverted vertical retrace status bit, with the status low when the video adapter has generated the interrupt and high otherwise. This will be corrected in the near future, but by that time, tens of thousands of old-style boards will be in use. (To complicate the matter further, IBM's *Technical Reference Options and Adapters*,

Volume 2, has the polarity of the vertical retrace status bit backward.) The developer is in danger here, as vertical interrupt-based software that runs perfectly on an EGA will lock up on some compatible adapters.

While methods are available to determine the polarity of the vertical retrace status bit via software for any given board, the need for this is much removed by the second complication, the physical nature of the vertical retrace status bit. The status bit is tied directly to the IRQ2 bus line, and as a result indicates only whether the IRQ2 line has been raised to generate an interrupt, *not* whether the interrupt was specifically generated by the EGA.

The upshot is that determining whether an IRQ2 interrupt was generated by an EGA vertical interrupt is not a simple matter of sampling a single bit. Considering that few peripherals use IRQ2, the best approach for a developer using the vertical interrupt might well be to forget about the vertical retrace status bit and assume that all IRQ2 interrupts are indeed vertical interrupts. This removes all danger of misinterpretation and speeds up interrupt response slightly.

If it is essential that other devices share IRQ2 with the EGA, a less-than-perfect solution is available. First, the polarity of the vertical retrace status bit must be determined. The easiest way to do this is to clear interrupts and toggle the vertical interrupt enable bit low and then high, forcing

the vertical retrace period, in order to maximize the amount of time available for updating the objects. Two problems arise on the CGA. First, the standard means of checking for the vertical retrace period on the CGA is to poll the vertical synchronization pulse status bit; however, because the pulse begins well into the period, a good portion of the retrace period is lost. (Some methods are available for finding the beginning of the vertical retrace period on the CGA, but they are neither entirely standard nor simple to explain.) Worse, the status bit must be polled constantly because the leading edge of the pulse must be found in order to allow maximum drawing time. This constant polling restricts the use of program time for other purposes. Although the polling could be interleaved into other program activities, or the program could

be designed so it would take just under one frame time in between drawing times, approaches such as this make polling for synchronization the overriding factor in program design and thereby restrict the designer's options. While this approach was used in the CGA version of the sprite engine, the EGA provides a superior means of detecting the start of vertical retrace.

The EGA's *vertical interrupt* (discussed further in the sidebar above) simplifies retrace detection. When this feature is enabled, the EGA generates an interrupt on IRQ2 each time that the vertical display end setting is reached: this is the start of each vertical retrace period. (A 1982 edition of the IBM *Technical Reference* manual lists level 2 as the interrupt level of the CGA's vertical retrace, a feature that was never implemented.) The sprite engine must be

such an interrupt to occur. (Given that the vertical interrupt is in an enabled and cleared state, one is generated whenever its enable bit is toggled high to disable the vertical interrupt. Users should be aware of this when turning off the vertical interrupt and restoring the original IRQ2 interrupt vector.) Once the vertical interrupt has been forced, read the vertical interrupt status bit, then clear the interrupt and read the status bit again. The first state read is the vertical interrupt *active* status, the second is the vertical interrupt *not active* status. If the readings are identical, then another interrupt is being signaled on IRQ2; interrupts should be enabled and this other interrupt allowed to occur, then the entire process should be repeated until the vertical retrace status bit is made to toggle. When the status bit does toggle, an EOI should be issued to the interrupt controller before interrupts are enabled to wipe out the test vertical interrupt just generated because no handler was set up for it.

Once the polarity of the vertical retrace status bit is known, a vertical interrupt handler can be set up. The only information this handler can derive from the status bit is as follows: if, when handling an IRQ2 interrupt, the vertical interrupt is cleared and the vertical retrace status bit remains active, then another device is signaling an interrupt on the IRQ2 line. Unfortunately, this does not mean that the EGA is not signaling one as well, as

two (or more) interrupts could be signaled simultaneously.

In the case where the vertical retrace status bit remains active when the vertical interrupt is cleared, one of two assumptions can be made: the handler can assume that *both* the vertical interrupt and another interrupt occurred, or the handler can assume that *only* another interrupt occurred. Too little information is available to make a full evaluation, and as a result this approach is not ideal. The handler can either deal with such cases by handling the interrupt as if it were a vertical interrupt and then passing it along to the next IRQ2 handler (assuming both interrupts occurred), or it can skip the vertical interrupt handling and go directly to the next IRQ2 handler (making the assumption that another interrupt occurred). These assumptions will not always be correct, but adding or missing an occasional vertical interrupt will have no noticeable impact on most animation applications, therefore this approach generally is an adequate solution to vertical interrupt handling.

Nevertheless, the simplest solution is to assume that IRQ2 is reserved for the EGA. Perhaps the next generation of the EGA will have a more useful status bit. Unfortunately, the hundreds of thousands of EGAs and compatibles already installed mean that the quirks of the vertical retrace status bit will be around for years.

—Michael Abrash and Dan Illowsky

set up as the interrupt handler for IRQ2, with the EGA vertical retrace interrupt enabled; the sprite handler will run virtually transparently in the background while the application program processes in the foreground.

To enable the vertical interrupt, bit 5 of the EGA's vertical synchronization end register (CRTC register 11H) must be set to 0. Each time the vertical interrupt occurs, it must be cleared by setting bit 4 of the register to 0, then reenabled by setting bit 5 to 0. Because bits 0 to 3 of this register define the character count at which the vertical synchronization pulse is to end, these bits must be set correctly for the current display mode whenever bit 4 or 5 is modified. Bit settings for all modes are provided in the *IBM Technical Reference, Options and Adapters*, volume 2, in the section on the EGA.

In order to use the vertical interrupt, the interrupt controller must be set to allow IRQ2 to occur by setting bit 2 of port 21H to 0. IRQ2 is handled by the routine pointed to by interrupt vector 0AH, at address 0000:0028, so this vector must be set to point to the vertical interrupt handler. However, devices other than the EGA may be using IRQ2 as well. In fact, in the PC/AT, the real-time clock interrupt and the hard-disk interrupt are among the eight interrupts cascaded through the IRQ2 interrupt. Consequently, any program using the vertical interrupt is mandated to restore the interrupt 0AH vector and the interrupt controller IRQ2 bit to their original states upon terminating.

The vertical interrupt handler also must make sure that each IRQ2 interrupt it handles was in fact generated by the EGA, and pass on to the routine

NEW! Break the 64K Data Limit THE INSIDE TRACK 3.1



Now updated and expanded! **THE INSIDE TRACK** is a collection of advanced utilities for PC/XT/AT and compatible

programmers. Break the 64K data limit, do **WINDOWS** and much more. Most programs run on ANY MS-DOS machine. You'll receive **80+ programs**, a **comprehensive manual**, fold out reference sheet with **memory map** and **BIOS calls**. Add our assembler code to your programs with **NO ROYALTIES!** BASIC routines are compatible with Quick BASIC and IBM BASCOM2. **All Source code included!** NOT COPY PROTECTED. Some programs require DOS 2.00 or above.

THE INSIDE TRACK

shows you how to:

- Go **beyond** the 64K data limit
- Do **fast WINDOWS** in your program
- Display data up to 10 times **faster**
- **Reserve memory** for your use
- Read/write files as **fast** as DOS
- **Control** the keyboard settings
- Much, much, more... **only \$65.00**

NEW! Break the Lock with PEEKs 'N POKES 3.1 Unprotect for GW-BASIC!



PEEKs 'N POKES has been updated and expanded for DOS 3.10, Quick BASIC and IBM BASCOM2. Learn

where to **PEEK**, **POKE**, **INP** and **OUT**. Swap monitors, swap printers. **DOS/BIOS function calls** to use ALL of your machine's features—not what your language limits you to. Add our routines to your programs with **NO ROYALTIES!** We supply you with **60+ sample programs**, a comprehensive manual and all **BASIC source code**. NOT COPY PROTECTED. A few programs require DOS 2.00 or above.

PEEKs 'N POKES

shows you how to:

- **Unprotect** IBM and **MS BASIC**
- **Disable** Ctrl-Break and Ctrl-C
- Read and change the **keyboard**
- Read and change the **monitor** status
- Access **printer & RS-232** status
- Find more **PEEKs** and **POKES**
- Much, much, more... **only \$45.00**

ORDER TODAY! M/C and VISA welcome. Shipping: USA \$3.00/order UPS, COD+3.00; Canada \$5.00/order first class; Overseas \$18.00/item airmail. Call for upgrade info. Dealer inquiries welcome.

MicroHelp, Inc.

2220 Carlyle Dr • Marietta, GA 30062

Call Toll Free: 1-800-922-3383

Tech support

and inside GA: 404-973-9272

PHOTO 1: *Sprites in Action*

The balloon and helicopters are sprites; the moon, stars, and horizon are background. The helicopter windows are transparent to the background and lower-priority sprites. (Note the star visible through the red helicopter's window.)

PHOTO 2: *Overlapping Sprites*

In this enlarged view of the screen, the higher-priority balloon overlaps the green helicopter and obscures it. The red helicopter (out of view), were it to cross them, would obscure both because its priority is the highest of the three.

pointed to by the original interrupt 0AH vector any interrupts not belonging to the EGA. Bit 7 of the EGA's input status register 0 (port 3C2H) will indicate whether the vertical interrupt has occurred; if this bit is 1, the IRQ2 to which the vertical interrupt handler is responding was generated by the EGA.

This completes the design of the sprite engine, which will provide independent background processing, controlled by the application program through a standard interface. All drawing is done during the vertical retrace period, so no flicker occurs. Sprite-like animation is supported, with distinct precedence of objects; the background is preserved, and object transparency is supported. But can this driver handle enough objects to make it useful? The answer is yes, with a few tricks.

FUNCTIONAL PARTS

The program in listings 1, 2, and 3 is a fully functional application of the sprite engine. To see it in action on an EGA, assemble the listings with the Microsoft Macro Assembler (4.0 was used for testing), link them, and run the resulting .EXE file. To run the CGA version (which operates on an EGA but without the vertical interrupt), change the value equate for the `ega` flag in listings 1 and 2 to 0, then assemble, link, and execute as for the EGA version.

This program animates two helicopters (14 pixels high by 24 wide) and a balloon (20 by 16) against a backdrop of stars, a crescent moon, and a horizon (see photo 1). The helicopters have large windows, through which the stars, moon, balloon, and even the rearward helicopter can be seen (see photo 2). All other objects are visible around even the most detailed parts of each object. One helicopter periodically vanishes for a short time. No flicker is present when operating on the EGA, and the background is perfectly preserved. Moreover, the program spends most of its time in a wait loop that regulates execution speed, which leaves plenty of spare time for more sophisticated processing on the part of the program. It could, for example, detect collisions, keep score, or orchestrate the action on the screen. Because the vertical interrupt lets the sprite engine operate only when needed and without intervention from the main program, the main program can use all of display time productively if it needs to.

Listing 1 is the application program using the sprite engine (listing 2) and a graphics driver (listing 3). The EGA implementation differs markedly from the CGA version because the EGA is driven by the vertical interrupt. Only the EGA version is discussed here. Listings 1 and 2 contain some code delineated by

if...endif conditional assembly blocks, with assembly conditional on the state of the `ega` or `cga` flag. When the `ega` flag is nonzero, the code appropriate for the EGA is assembled by the blocks starting with `if ega`.

The sprite engine breaks down into four functional parts: initialization, update, termination, and interrupt handler. These routines center around a queue containing all relevant information for the objects to be drawn, including a screen position and a pointer to an image table for each object. The queue may be predefined to support any number of objects by changing the `number_of_objects` variable. The object with the highest queue number has the highest drawing priority (it is drawn after all other objects) and so appears to be farthest forward. Any queue entry can be inactivated easily, so it is not required that all queue entries be active at once. This provides a simple mechanism whereby the relative display priorities of the objects being animated can be changed (see below).

The initialization, update, and termination sections can be called as near procedures when linked with an applications program; the interrupt handler updates the objects, as needed, on each vertical interrupt. The interface to the first three routines is described in the comments of listing 2.

Test IBM PC's and XT's in Less Than 60 Seconds!



Introducing the Vu-Data AID/88 Low Cost Solution to PC Troubleshooting.

IBM® COMPATIBLE. Using the 8088 μ P, the AID/88 monitors the diagnostic instructions executed by IBM's own BIOS as it performs power-on self testing of the system board, reporting when the system halts and giving the reason.

STAND ALONE. The AID/88 verifies kernel integrity of the system board through complete built-in testing of the +5 volt supply, clock, address bus and data bus.

PRODUCTIVE & COST EFFECTIVE.

The AID/88 brings PC and XT system board maintenance "in-house" by extending repair capability beyond present IBM disk-based software. It pays for itself through reduced board float, and the delay and expense associated with "outside" repair.

USER READY & FRIENDLY. The AID/88 is pre-programmed with 10K bytes of software. Even an entry level technician is able to operate it guided by simple front panel instructions.

Start repairing PC's
for only
\$2995



9180 Brown Deer Road, San Diego, CA 92121
(619) 452-7670

IBM, IBM PC and IBM XT are registered trademarks of International Business Machine Corporation.

CIRCLE NO. 212 ON READER SERVICE CARD
AUGUST 1986

SPRITES

The initialization routine, `initialize`, sets the sprite engine's internal variables to indicate that the object queue is empty. The address of the buffer containing the background information used to erase objects is set as passed from the application program, as well. In addition, `initialize` sets variable `need_to_draw_something_flag` to indicate that the screen need not be updated on the next vertical interrupt.

Next, `initialize` sets up the vector for interrupt 0AH (the vector used by IRQ2), to point to the routine `put_objects_on_screen`, which updates the screen as required on each EGA vertical interrupt. (The CGA version pushes the flags and executes a long call to `put_objects_on_screen` to emulate IRQ2.) The original interrupt 0AH vector is set aside for two purposes: to be restored at the end of the program and to allow IRQ2 interrupts not generated by the EGA to be passed on by the interrupt handler.

The state of IRQ2 is read from the interrupt controller at I/O address 21H and stored so it can be restored when the program ends. IRQ2 is then enabled, so that the vertical interrupt will be passed along by the interrupt controller to interrupt the CPU. Interrupts must be disabled while the state of the interrupt vector is modified, otherwise an interrupt might occur in the middle of modification and find an invalid (because it is partially changed) vector.

The update routine, `object_services`, is called by the application to register changes in the status of an object, such as a change of location or a new form table for internal animation. Internal animation of a sprite may be accomplished by defining several form tables for a single sprite, each containing one *frame* of the animated figure's motion. The software cycles through the sequence of form tables by repeated calls to `object_services`. (This is how the blades and tail rotor of the helicopter sprites are animated.)

The queue entry for the object with the number indicated by the application is updated on the basis of the information passed to `object_services`. Parameters such as the offset from the end of one scan line of the object to the start of the next and the offsets to call in the erasing and redrawing in-line code are calculated now, so that when the vertical interrupt occurs, these values can be read directly from the queue entry, saving precious time during the vertical retrace period. Finally, `object_services` sets `need_to_draw_something_flag` to true, to indicate that

Does **YOUR** disk Look Like
THIS?



Let
H.D. Tuneup
cleanup your act!

H.D. Tuneup tunes your disk file system, making it better than new. File loads speed along like new. Directory searches are faster than new.

H.D. Tuneup reallocates all of your files to be contiguous. Each file is placed in its proper location, adjacent to its neighbors in the directory.

Disk operations run faster when your files have been Tuned.

H.D. Tuneup relocates your sub-directories into one area of your disk, as close to the root as possible. All deleted entries are actually removed.

Your drive head moves less from directory to directory than when your disk was new. TREE/F will fly when listing all of your files.

H.D. Tuneup requires IBM PC/XT/AT compatibility, 196k, and DOS 2.x/3.x. Fixed disks up to 32mb may be tuned, along with any 5.25" diskette.

NOT COPY PROTECTED!


ONLY \$39.95 plus \$3.00 S/H

SofCap Inc.
P.O. Box 131
Cedar Knolls, N.J. 07927

Visa (201) 386-5876 M/C

N.J. residents add 6% sales tax.

**For the best performance
from your disk
TUNE IT UP!!**



Visa, Master Card, Checks, Money Orders, or COD only.

CIRCLE NO. 164 ON READER SERVICE CARD
133

the screen must be updated on the next vertical interrupt because the object's status has changed. As with `initialize`, interrupts are disabled while the queue is updated, preventing the vertical interrupt handler from acting on information that is only partially updated.

The `terminate` routine turns off the vertical interrupt, and restores the vertical interrupt vector to its original value and the control bit for IRQ2 in the interrupt control register at port 21H to its original state. As discussed above, the restoration of IRQ2 to its original state is particularly important in the AT, because failure to restore it could result in a nonfunctional hard disk.

The initialization, update, and termination routines are merely support for the heart of the sprite engine—the vertical interrupt handling routine `put_objects_on_screen`, which is executed whenever an IRQ2 interrupt occurs. The first action of this interrupt handler is to determine whether the IRQ2 interrupt was in fact generated by the EGA, by checking bit 7 of the status register at port 3C2H. If this bit is 0, the EGA did *not* generate the interrupt and control must be passed to the original interrupt 0AH vector, as stored by the initialization routine. Again, this action is essential in the AT.

If the interrupt was generated by the EGA, the interrupt handler increments `vert_int_modulo_count`, a public variable that may be accessed by the application program. A change in this variable notifies the application that a vertical interrupt has occurred, allowing implementation of a constant time base synchronized to the frame rate of the EGA. The interrupt handler then checks to see if any of the objects have changed, as would be indicated by `need_to_draw_something_flag`. Animation activity is required only if at least one object has changed. If nothing has changed, the interrupt handler issues a general end-of-interrupt (EOI) command to reenables IRQ2, clears and reenables the EGA bits that control the vertical interrupt, and restores the registers that it modified. Interrupt handlers must preserve all registers, because they may be invoked if interrupts are enabled. This can happen during the execution of any code. The interrupt handler then terminates immediately; as a result, very little overhead is incurred when none of the objects has changed since the last vertical interrupt.

If one or more objects indeed has changed, the interrupt handler must erase and then redraw all of the objects in the queue. To erase all objects at the

location at which they were last drawn, the interrupt handler executes a loop that calls a precalculated entry point in in-line code for each object; the in-line code transfers the rectangular area of the background corresponding to the location of the object from the background buffer to display memory. This erases the object, by restoring the area it occupies to the background state.

One special feature of this queue is that it does not erase the object under certain circumstances. If, for example, the object has not moved since the last time it was drawn, and if the object's image is the same as when it was last drawn, then erasing the object is not necessary, because it will be drawn over exactly the same pixels that would be erased. This provides one way to support an extra object or two during the limited vertical retrace period: if the application can guarantee that only half of the objects being animated change during any given vertical frame, then the erase time for half the objects is always saved, freeing up drawing time for additional objects. Also, if the queue contains the special 0FFFFH entry for the offset at which the object was last drawn, the object is not erased. This can save time when an object is made to vanish, because an invisible object does not need to be drawn or erased.

After all objects have been erased at their old locations, they are redrawn at their new locations. This is accomplished in a second loop using the AND/OR driver. Like the erase driver, the AND/OR driver in-line code is called directly via a vector precalculated for each object in the update routine.

The implementation of the AND/OR driver shown in listing 2 uses word operands for maximum speed. For an image that is an odd number of bytes wide, an extra mask byte of 0FFH and image byte of 00H can be added to the end of each line of the image table, with no adverse effects because this pair of bytes causes the AND/OR driver to leave display memory unchanged. The driver also uses string instructions as much as possible, but because the AND and OR logical functions have no string equivalents, the driver must rely largely on slower 8088 instructions. This driver is not nearly as fast as the byte-move driver in listing 3, but it is remarkably speedy considering its sprite-like characteristics.

Like erase, the redraw loop does not draw objects with a screen offset of 0FFFFH. This provides a handy way to disable an object. The method works as follows: if the application calls the up-


PERSTOR™

Removable Hard Disk Cartridge Expansion Systems

BERNOULLI ALTERNATIVE!

- High Performance Fixed and Removable from 10 to 560 mbyte

- Internal or external mount



- The only Removable Hard Disk Cartridge Drive that attaches directly to the IBM PC-AT Controller*—internally mounted

PERSTOR™ products provide portability, storage and backup for IBM-PC, AT, XT and compatibles.

DOS, Xenix, Multi-User and Networks

Combine a removable (12MB) with another drive—removable or fixed (26MB-140MB) for a highly flexible systems solution!

SYSTEMS & SOFTWARE, INC. (602) 948-7313
7825 East Redfield Road, Scottsdale, AZ 85260

*Patent Pending Copyright 1985 Perstor® is a trademark of Systems and Software, Inc. IBM-PC, AT, XT, are registered trademarks of International Business Machines Corp.

CIRCLE NO. 231 ON READER SERVICE CARD



XENIX RISING

“It was back in 1986 that we first grasped the full significance of SCO XENIX®.

“We had been thinking of it as just an ‘operating system’ — as we used to call them — when it was really much more. It was the foundation of a whole new approach to shared information and resource computing for PCs: networked DOS *and* XENIX workstations.

“The ‘SCO XENIX solution’ integrated XENIX and DOS, multiuser and LAN, and PCs and mainframes, into a unified environment unprecedented in its power, productivity, and price performance per user for personal computers.

“SCO’s solution included not only 16-user licensed SCO XENIX itself, but also SCO XENIX-NET XENIX/DOS networking; SCO Professional™ and SCO FoxBASE™; SCO’s XENIX-based workalikes of 1-2-3® and dBASE II™; SCO Lyrix™ Word Processing System, and other productivity tools; and SCO uniPATH™ SNA-3270 Mainframe Communications, plus languages and graphics packages.

“Together with unparalleled SCO hot-line support, documentation, and training, plus the explosive growth of the XENIX applications base, it changed the way we would look at personal computers forever.

“In short, it was the ‘SCO XENIX solution’ that turned personal computers into *real* computers.”

SCO SALES AND INFORMATION
(800) 626-UNIX

(800) 626-8649

(408) 425-7222

TWX: 910-598-4510 SCO SACZ

uucp: ...decvax!microsoft!sco!info



from “XENIX RISING:
*The Ascent of Shared Information
Computing from 1979 to 1999*”

SCO XENIX System V is available for
IBM® PC AT®, PC XT®, ITT XTRA® XL and other
compatibles, and AT&T PC 6300 Plus—now!

XENIX is a registered trademark of Microsoft Corporation. • SCO Professional and Lyrix are trademarks of The Santa Cruz Operation, Inc. • FoxBASE is a trademark of Fox Software, Inc. • 1-2-3 is a registered trademark of Lotus Development Corporation. • dBASE II is a trademark of Ashton-Tate. • uniPATH is a trademark of Pathway Design. • UNIX is a trademark of AT&T Bell Laboratories. • IBM, AT and XT are registered trademarks of International Business Machines Corporation. • ITT XTRA is a trademark of ITT Corporation. The Santa Cruz Operation, Inc., P.O. Box 1900, Santa Cruz, CA 95061

©1986 The Santa Cruz Operation, Inc. 6/86

CIRCLE NO. 121 ON READER SERVICE CARD

AUTHORIZED
Phoenix
COMPATIBILITY

**DART - The first CAD computer
with a super high performance
AT™ Compatible.**

**System 286 - The first high
speed AT priced below the
IBM XT™.**


The ADVANCED LOGIC RESEARCH computer has been tested for IBM compatibility with PHOENIX'S compatibility test suite using the PHOENIX AT-COMPATIBLE ROM BIOS, and the PC-COMPATIBLE ROM BIOS.

WE DON'T THINK YOUR PERFORMANCE SHOULD BE LIMITED BY THE 'STANDARD'

At ALR we don't think your performance should be limited by the 'Standard'. So preoccupied are today's computer makers with meeting the 'Standard', they seem to have overlooked the opportunity to do something much more worthwhile.


Namely, the concept of improvement beyond that 'Standard' acceptable level.

Examine the DART. The first CAD computer with a super high performance AT™ Compatible. The DART system is powered by a 10 MHz 80286 cpu with support for an 8 MHz 80287 math co-processor, when compared to the IBM® AT's 6 MHz cpu and 4 MHz co-processor, the DART system will process your next CAD design in almost half the time, with DIRECT ACCESS RESPONSE TIME (DART).




*Based on the Norton Utility SI-System Information Command.

Explore the opportunity of the System 286 - The first high speed AT below the price of an IBM XT™. The low cost of this system did not reduce the performance, with the cpu speed of 8 MHz and co-processor speed of 5 MHz. This System 286 is ready to calculate spread sheets and sort data base in a flash!




LIST PRICES AS OF APRIL 1986

The concept of having enough memory is misleading. It seems yesterday's 64K of memory was enough. Today, computers require at least 512K in order to run popular programs such as Symphony™ or Framework®. The result? ALR System 286 and DART system both have four times the memory capability built into its 'motherboard' so you don't have to pay for it tomorrow.



Option I/O device? That usually implies you need it and it costs more. ALR believes a computer needs to interface with at least a printer and in most cases modems, plotters and other computers, so we design our systems to include more standard I/O.



High performance and more features usually results in a more expensive system. However, the ALR System 286 and DART system does not match the 'Standard' price and this is one category we're glad to be considered 'sub-standard'.

Let one of our sales engineers or dealers show you the ALR System 286, DART system, Turbo XT and AT Hirise IBM compatible systems that are designed to limit your cost not your standard of performance.

CIRCLE NO. 199 ON READER SERVICE CARD

ADVANCED LOGIC RESEARCH, INC.
10 CHRYSLER
IRVINE, CA 92714
(714) 581-6770
ALR IN CANADA
416-229-6477

ENGINEERING ADVANCED COMPUTERS

ALR

date routine with SI equal to 0FFFFH, the routine sets the screen offset for that object to 0FFFFH. Upon encountering this object, the erase loop erases it; the new offset of 0FFFFH is guaranteed to be different from the offset of the old location. The redraw loop does not redraw the object because it ignores objects with an offset of 0FFFFH. Thus, the object vanishes.

The erase loop also ignores objects with screen offsets of 0FFFFH, so the object not only vanishes, but it is never erased again and requires little overhead. This makes it possible to change the relative drawing priorities of objects; a single object can be assigned several priorities (queue numbers), all but one of which is set to 0FFFFH at any one time. To make the object appear far forward, a high-priority (high-numbered) queue entry would be activated; to make the object appear far to the rear, a low-priority (low-numbered) queue entry would be turned on. In combination with the use of larger images for the more forward versions of the object to simulate perspective, priority-switching can produce very convincing animation effects.

Once the objects have been erased and redrawn, the vertical interrupt handler is done. The interrupt handler issues a general EOI command to reenale IRQ2, clears and reenables the vertical interrupt, restores all 8088 registers, and terminates.

An important note about the vertical interrupt handler: interrupts are enabled soon after the handler is entered and are kept enabled throughout. If another, higher-priority interrupt, such as the timer interrupt, occurs while the vertical interrupt handler is active, the vertical interrupt handler will be halted for an indeterminate period. Because the visual effect of the sprite engine is dependent upon its finishing during the vertical retrace period, this would seem to pose a significant problem, but actually it does not. If an interrupt does cause the sprite engine to run over into display time, the worst that will happen is a single flicker; if the interfering interrupt is handled quickly, no visible effect may be detected at all, although a frequent and long interrupt could cause problems. Also, IBM apparently has never specified a maximum allowable period for which interrupts can be disabled by an interrupt handler; in the absence of such a specification, interrupt-off periods always should be kept as brief as possible.

Note that only the graphics driver in-line code portion of the sprite

engine has been optimized. This code absorbs most of the time used by the engine during vertical retrace, and it is only during this period that time is critical. Besides, at levels above the driver level, clarity and flexibility are as important as sheer speed, except when the application dictates otherwise.

APPLYING THE SPRITE

The application program sets up and drives the sprite engine to animate the helicopters and the balloon. This program comprises three parts: initialization, animation, and termination.

The initialization section selects medium-resolution graphics mode, places the stars and the horizon in the background buffer, and uses the byte-move driver shown in listing 3 to put the moon in the background buffer. (To make the byte-move driver draw into the background buffer instead of display memory, ES is set to the background buffer segment.) The completed background buffer is then copied into display memory to establish the background. The initialization code concludes by calling the sprite engine initialization routine, which sets up the queue and the vertical interrupt.

The animation section performs only three actions: animation control,

check for exit, and synchronization. The program first loops through each object, checking whether the delay for each object has counted down. If it has, it moves the object based on its current motion increment, then cycles to the next form table on the list of form tables for that object, in order to produce internal animation. (The helicopter's blades and tail rotors move through a process of internal animation.) If the repeat factor for the current motion has counted down, then the next set of control variables is obtained from the control string for that object.

The control strings, which are `copter0_control`, `copter1_control`, and `balloon_control`, fully describe the motion and appearance of the objects throughout program execution, so changing the animation of an object is a simple matter of altering the appropriate string. For example, it may be instructive to set the delays in the control strings to higher values to slow down the program in order to more closely observe the effects when objects cross.

When an object is moved, a call is made to `object_services`, the sprite engine's update routine, to register the change. This done, the application has provided the sprite engine with all the information it needs to do its work and

FORTRAN FROM THE HIGHEST AUTHORITY.

Namely, RM/FORTRAN™ from Ryan-McFarland. It's nothing less than a mainframe FORTRAN compiler for a pc. It's also a full ANSI 77, complete with mainframe extensions and GSA-certified error-free at the highest level. And, thanks to our high optimizing compiler, it's the fastest pc FORTRAN you can buy. To do just that, call us at 213-541-4828.

Or write 609
Deep Valley Dr.,
Rolling Hills
Estates, CA 90274. **Masters of the Language.**



**RYAN-
McFARLAND**

RM/FORTRAN is a trademark of Ryan-McFarland Corporation. ©1986 Ryan-McFarland Corp.

SPRITES

is free to perform other tasks. The application then checks for a keystroke. If it finds one, the program is terminated immediately; if a keystroke is not found, the program synchronizes to the EGA's frame rate by waiting for the variable `vert_int_modulo_count` to change. Recall that the sprite engine increments this variable each time a vertical interrupt occurs, so waiting for it to change forces the execution speed of the applications program to exactly 60 iterations per second, matching the 60 frames per second rate of the EGA. This provides

the program with a constant time base; at all times and under all circumstances, this program will animate at the same speed, with a control resolution of one-sixtieth of a second. This is true even on an AT, regardless of clock speed.

When a keystroke is detected, which indicates program termination, the sprite engine's termination routine is called to restore the vertical interrupt to its original state, text mode is restored, and the program is ended.

The key aspect of the sprite engine application is the degree to which its

use reduces the code and complexity required to implement effective animation. The actual animation code is only a couple of dozen lines long. Yet those lines support a powerful and extensible table-driven animation interpreter. Amazingly, this program is not very far from being a full-fledged game.

CGA IMPLEMENTATION

The sprite engine can be implemented for the CGA as well, although less elegantly. When running on the CGA, the application must emulate the vertical interrupt by waiting for the vertical synchronization pulse and then calling the sprite engine. The problems associated with this approach have been discussed.

To assemble the sample program for the CGA, change the equates for the `ega` variable at the start of listings 1 and 2 to 0, rather than 1, thus enabling the conditional assembly blocks that start with `if cga` and disabling those that start with `if ega`. The CGA version will run equally well on an EGA because the EGA without the vertical interrupt enabled is the same as the CGA (for the purposes of this program). A review of the two versions in quick succession, however, reveals the significant difference that exists between them.

The balloon often flickers when it reaches the top of the display in the CGA version. (This effect occurs only on 4.77-MHz PCs; faster machines should produce no flicker.) This effect is almost expected because insufficient time is available to draw all the objects during the vertical retrace period, the result of invoking the sprite engine at the beginning of the vertical synchronization pulse rather than the beginning of the vertical retrace period. However, some far more profound lessons can be learned from this event: one pertains to the nature of realtime bit-mapped animation, the other to a method of maximizing the capabilities of the sprite engine through program structure rather than code optimization.

(As an aside, note that the balloon flickers only when the green helicopter is visible. Remember that when an object is invisible, it is neither erased nor redrawn. This is a visual reinforcement of the concept that the balloon flickers because too little time is available to erase and redraw three objects during the period that is used.)

ANIMATION DYNAMICS

It is natural to think of the time during which the sprite engine can safely modify display memory as being static. Given that the last 60 scan lines of each

SideTalk™

It minds the phone while you do your work

No more interruptions! Because now SideTalk can transfer your files or receive your mail while you're using your computer for other important matters. And SideTalk is programmable with its own BASIC-like language. What's more, you're never more than a keystroke away from all of the power of SideTalk.

When we say SideTalk is the best telecommunications program on the market, we're not just talking out of the side of our mouth.



Lattice

To place your order:
Lattice, Incorporated
Post Office Box 3072
Glen Ellyn, Illinois 60138
312-858-7950
TWX 910-291-2190



Only
\$119.95






Tough Choice. Easy Answer.

**EMS
OR
EEMS?**

QuadEMS+TM

The Only Memory Board
For Your PC-XT With
Both EMS and EEMS.



Memory And I/O

QuadEMS+ delivers 2Mb RAM when you move up to expanded memory. And supports both expanded memory specifications: EMS and EEMS. Each is independently engineered into the board. Plus, there's a printer port, communications port, and clock/calendar to enhance your system.

Memory Only

If all you're after is memory, QuadEMS+ also comes without I/O. Pure RAM. Either way, QuadEMS+ lets your system take advantage of the power of expanded memory without worrying about compatibility problems that might crop up later.

So Smart, It Installs Itself

Available now for your PC-XT and XT work-alikes, QuadEMS+ is easy to use. Just plug it in. It does the rest. It's designed to automatically configure itself to your system requirements. For more information visit the Quadram dealer nearest you. Or contact us at One Quad Way, Norcross, Georgia 30093; 404-564-5566.

QuadEMS+ is a trademark of Quadram Corp. Quadram and the Quadram logo are registered trademarks of Quadram Corp.

CIRCLE NO. 171 ON READER SERVICE CARD

QUADRAM 
An Intelligent Systems Company



SIM3278/PC

A MICRO-MAINFRAME CONNECTION IN A CLASS OF ITS OWN

Data Decisions Gives SIM3278/PC High Marks

Data Decisions reviewed and evaluated SIM3278/PC, giving it high marks for **User Interface, Ease of Use and Systems Interface. Their conclusion: "Simware has demonstrated an understanding of the user's need to maximize productivity gains possible with computers."*

Using inexpensive asynchronous or X.25 network communications, SIM/PC provides you with advanced features such as error free file transfer, printer support and an intelligent command processor. "Unlike many communications packages that present primarily a menu-driven user interface, SIM/PC's command language is a very powerful enhancement over simple 3270 emulation."

SIM/PC eliminates the need for expensive add-on boards and gives you the most flexible micro-to-mainframe link available.

A corporate license entitles you to make multiple copies of SIM/PC without paying any additional per copy price every time another PC is added to your network.

CALL TODAY FOR A FREE EVALUATION SYSTEM AND JUDGE FOR YOURSELF.


SIMWARE

a practical approach to communications

14 Concourse Gate, Ste. 100
Nepean, Ontario K2E 7S6
(613) 727-1779 Telex: 053-4130
Toll Free: 1 (800) 267-9991

Distributed in Europe by:
The European Software Company

* Source: recent analysis by
Data Decisions on Product
Quality Ratings for SIM3278/PC.



SIM3278/PC is a trademark
(pending) of Simware Inc.

SPRITES

frame are in the vertical retrace period, it seems obvious that the time during which those lines occur is the time available for modifying display memory without the results being displayed until the operation is complete. This is the truth, but not the whole truth.

Actually, a given area of display memory can be modified at any time during which the display controller is not fetching that particular area of memory to convert it to video data. Any operation that is begun after the controller has read the area of display memory to be modified, and finished before the controller completes a frame and returns to read the affected memory again, will not cause flicker. Completing all operations during the vertical retrace period is merely a special case of modifying memory between successive passes of the display controller.

The exceedingly dynamic nature of realtime bit-mapped animation is evident in the manner in which the balloon vanishes. The expectation might be that during those frames when the balloon flickers (the frames during which the balloon is still erased when the display controller encounters it), the balloon would vanish smoothly, two scan lines (the increment of its vertical motion) at a time, as if passing behind a dark wall, as it rises to the point at which it encounters the display controller scan (and by extension the scanning electron beam on the display). To the contrary, the balloon vanishes from the top in two large chunks and is gone. (To see this effect, force the sprite engine to redraw all forms on every vertical interrupt by making two changes to `put_objects_on_screen`: replace the line `je process_queue` with `jmp process_queue`, and comment out the six lines that start with `je skip_this_object` and end with the next instance of `je skip_this_object`.)

Moreover, it takes some reflection to understand why it is the top of the balloon that vanishes first. After all, the balloon is drawn from the top down; it is reasonable, therefore, to assume that the portion of the balloon that is drawn first should be visible after the rest of the balloon has vanished.

The explanation lies in the interaction of the display controller and the graphics driver. Both are scanning display memory in much the same fashion and at much the same speed. The controller is scanning one line from left to right every 62.5 microseconds, progressing downward. At the same time, the graphics driver is drawing the balloon from left to right, progressing

downward. While the exact time per scan line of the balloon is difficult to figure out, an approximation arrived at by adding instruction cycle times is 73 cycles per word, or somewhere around 200 cycles for each of the two-word-wide balloon scan lines, including overhead, wait states, and prefetch queue effects. This works out to 42 microseconds, or two-thirds of the time the display controller takes per scan line.

The balloon vanishes the way it does because the graphics driver actually starts drawing the balloon in mem-

ory that the display controller has already scanned past during the current frame. However, the driver is only slightly behind the controller, and, because it is faster, the driver overtakes the controller. Up to this point, nothing drawn by the graphics driver is visible, because that memory was erased when the display controller read it. Consequently, the top of the balloon vanishes.

Soon the graphics driver passes the display controller and starts to modify memory just before that memory is read for video data. At this point, the

nine track tape users Micro to Mainframe Connection

The Model TC-50 ½-inch tape subsystem provides a standard medium for transmission of mainframe data base information to PC users, while maintaining mainframe isolation and data integrity. Use ODI subsystems to import data to data base programs like dBase III.

The TC-50 subsystem also provides fast back-up capability as well as a device driver and interface software for popular compilers.

The TC-50 subsystem includes tape drive controller, cables and documentation. All ODI products carry a 30 day unconditional money-back guarantee, and are warranted for one year, parts and labor.

Overland Data has manufactured high-capacity storage and data interchange products since 1980. All ODI equipment is designed and engineered for long-term reliability. Satisfied customers include Fortune 500 companies, major hospitals and universities, laboratories and research organizations.



Put Overland Data's experienced, professional staff to work on your company's data availability problems. Call today!

Overland Data, Inc.

5644 Kearny Mesa Road
San Diego, CA 92111
Tel. (619) 571-5555
Telex 754923 OVERLAND

Also Available –
XENIX tape
subsystems
for the
IBM AT

bytes drawn by the driver become visible, because the data are there in time to be read by the display controller. As a result, the lower part of the balloon is visible on the screen.

But why does the balloon disappear in two large chunks, rather than two scan lines at a time? The answer is that the graphics driver takes about three scan lines to catch up to one scan line on the display controller; therefore, when the balloon moves up two scan lines, a half dozen or so additional scan lines vanish as the graphics driver takes longer to catch up. Note, however, that it is mere coincidence that the balloon is just the right size and the driver the right speed to produce this effect. When a helicopter is substituted for the balloon, for example, it vanishes from the bottom up, rather than the top down. Because each helicopter scan line is three words long, not two, it takes slightly longer to draw a helicopter scan line than the display controller takes to scan a line, thus, the controller catches up with the driver rather than the other way around.

The variables in animation, then, cannot be considered in isolation from each other, for they are synergistic and the effects of their interaction are not always obvious or predictable.

ENHANCED ANIMATION

The following are two examples of superior animation. One draws on an understanding of the dynamic nature of animation, the other highlights the illusory nature of animation in general.

First, suppose a user wanted to add one or two more objects to the animation program. The CGA version certainly will not support any more objects; the EGA version does not have much surplus animation time, either. Yet, with a few restrictions, another object or two can be added and the CGA's balloon problems cured, all at once.

The balloon's tendency to vanish can be solved by simply not letting the balloon rise as high as the point at which it starts to disappear. Cheating? Not really. The objective in animation is to produce the desired effects within the limitations of the host hardware, and unless some compelling reason exists as to why the balloon must rise all the way to the top of the screen, the game designers could just make the very top of the screen the scoreboard, or the boundary line, or just blank space. (In many games for the Apple II, for example, the far right of the screen was not part of the playing field—often occupied instead by cheering creatures or the scores—because that area of the

screen could not be addressed with a single-byte column coordinate.)

Recall also that the red helicopter is actually drawn after the balloon; it appears to be the most forward of the objects. In the CGA version, then, the red helicopter is drawn entirely during vertical display time. Yet this helicopter does not flicker or vanish at all, an effect that would be understandable given the examination of realtime animation dynamics above.

The effect achieved is the trick needed to add a few extra objects to the animation: objects are added so the forward-most objects are restricted to the lower portion of the screen. This ensures that the objects drawn last—during display time—are drawn ahead of the display controller's scanning of memory. Display time takes up about three-quarters of the total time, providing considerable latitude in adding objects, as long as the program is structured to keep the drawing of all objects ahead of the display controller. Remember that all objects are erased before any redrawing takes place, so the addition of an object inevitably forces all objects to be drawn a little later relative to the start of vertical retrace.

An alternative means of supporting additional objects would be to reduce

How to get started in expert systems ...for only \$950.

Personal Consultant™ and Personal Consultant *Plus* software from Texas Instruments—now you have two ways to get started in expert system development and delivery on PCs. Both run on TI Professional Computers, including the Business-Pro™ computer, as well as the IBM® PC/XT™, Personal Computer AT™ and compatibles.

Personal Consultant is the low-cost, high functionality tool for the rapid prototyping and development of expert system applications. It can get you started for only \$950.*

Personal Consultant *Plus* is a larger, more powerful family member with extra features to handle more complex problems, priced at \$2950.*

And, if you order Personal Consultant and decide to move up to Personal Consultant *Plus*, you can apply


the \$950 towards the new purchase—and keep both products!

To order, or for more information, call toll-free:

1-800-527-3500


*Suggested list price.

Personal Consultant and Business-Pro are trademarks of Texas Instruments Incorporated. IBM is a registered trademark and PC/XT and Personal Computer AT are trademarks of International Business Machines Corporation.


**TEXAS
INSTRUMENTS**

Creating useful products
and services for you.

©1986 TI 261765-03



How we improved Structured Query Language.

Actually, we didn't change a thing.

We just combined it with the best relational database management system. Introducing INFORMIX®-SQL.

It runs on either MS™-DOS or UNIX™ operating systems. And now with IBM's SQL as part of the program, you can ask more of your database. Using the emerging industry-standard query language.

To make your job easier, INFORMIX-SQL comes with the most complete set of application building tools. Including a full report writer and screen generator. Plus a family of companion products that all work together.

Like our embedded SQLs for C and COBOL. So you can easily link your programs with ours. File-it!™ our easy-to-use file manager. And C-ISAM™, the de facto standard ISAM for the UNIX operating

system. It's built into all our products, but you can buy it separately.

And when you choose RDS, you'll be in the company of some other good companies. Computer manufacturers including AT&T, Northern

Telecom, Altos and over 60 others. And major corporations like Anheuser Busch and The First National Bank of Chicago.

Which makes sense. After all, only RDS offers a family of products that work so well together. As well as with so many industry standards.

So call us for a demo, a manual and a copy of our Independent Software Vendor Catalog. Software vendors be sure to ask about our new "Hooks" software integration program. Our number: 415/322-4100.

Or write RDS, 4100 Bohannon Drive, Menlo Park, CA 94025.

And we'll show you how we took a good idea and made it better.



RELATIONAL DATABASE SYSTEMS, INC.

INFORMIX is a registered trademark and RDS, C-ISAM and File-it! are trademarks of Relational Database Systems, Inc. IBM, UNIX and MS are trademarks of International Business Machines Corporation, AT&T and Microsoft, respectively. © 1985, Relational Database Systems, Inc.

Strangled by the limitations of your DBMS?



ZIM. The system for serious developers

Your data base system was easy to learn. You were building your first simple applications within hours. You have a menu driven interface and pop up menus with online context sensitive help. Now you are ready to build your first real application. Instant Strangulation!

The Symptoms

- There is no real 4th Generation Language — what you see at the menu driven level is what you get.
- There are all sorts of built-in limitations which no real problem ever obeyed
- Your database which runs like a superstar on a few files and 500 records, chokes when faced with several files of 50,000 records
- You cannot efficiently run your applications in UNIX, VAX VMS and MS-DOS without major surgery, or finding a new DBMS

- Your DBMS supplier asks, "what is networked multiuser anyway?"
- Your database is too big to live on one disk but your DBMS doesn't support multiple disks
- Your database can't answer simple questions like "tell me which inventory items have NOT sold in the past 3 months?"
- You built your application using the nice easy interface, but now it won't get out of the way to allow you to modify the application
- You can't compile your applications and there is no runtime system

Diagnosis

Extreme stress and frustration in your development staff and applications crippled at birth.

THE CURE

ZIM is the 4th Generation Language/DBMS for serious application developers. ZIM is a top performer in all of its environments (UNIX, XENIX, MS-DOS, Novell Networks, VAX VMS, QNX), for all types of information application. ZIM's easy menu driven interface with context sensitive help is not meant just for novice users, and it stays discreetly out of the way when it isn't needed.

You need never suffer the symptoms of Database strangulation again.

ZANTHE INFORMATION INC.
1200-38 Antares Drive
Nepean, Ontario, Canada K2E 7V2

Sales (US) 800-267-9972 (CDN) 613-727-1397



ZIM™

CIRCLE 219 ON READER SERVICE CARD

SPRITES

the average size of the objects. Again, the proper balance between the hardware's capabilities and the needs of the application is the key.

A second example of enhanced animation is a program structure that supports an arbitrarily large number of objects. Observe that no matter what tricks are played with the sprite engine discussed above, the limitation on the total number of objects that can be animated is the number that can be erased and redrawn during a single frame. However, this is true only as long as all objects can overlap. If the motion of the objects is restricted such that any object can overlap only with objects within a certain group, and the periodicity with which the groups of potentially overlapping objects need to be redrawn is arranged so that only one group ever needs to be redrawn during any given frame, then dozens of objects can be animated. Only as many objects as can be redrawn within a single frame can be in any group (as discussed above), but the interleaving on a frame-by-frame basis of the redrawing of the groups makes the illusion of simultaneous animation easy to create.

An obvious candidate for such animation is a shooting gallery game, where the many rows of targets do not overlap. No one would ever notice in a frenzied shoot-'em-up game that only certain subsets among dozens of moving objects ever actually cross. It is all illusion, and it is the organization of the animation that makes the illusion work.

FUTURE FLEXIBILITY

The programs presented here provide the user with groundwork that can expand in many directions. The sprite engine could be designed with expanded functionality to relieve the application of additional work. For example, the sprite engine could be provided with the address of the movement control vector for each sprite, then it could move the sprites independently of the application. The sprite engine also could assume responsibility for collision detection, because it is already scanning the objects frequently anyway.

The code used to control the movements of the sprites in listing 1 is a very simple interpreter. Any degree of sophistication can be introduced simply by adding (for each sprite) a queue entry that is a vector to a handling routine for that sprite. The sprite-handling routines could include movement, collision detection, event generation, and other functions. Many methods of implementing a powerful animation inter-


preter are available. The important point is that with the proper design, an animation interpreter can be flexible and extensible, so that adding features requires only the modification of the control tables and perhaps the addition of a couple of routines.

The sprite engine can be used in conjunction with other animation techniques. In a shooting gallery game, for example, the primary object (perhaps a spaceship) might never intersect other objects without wiping them off the screen (or vice versa). In this case, the primary object need not be drawn by the sprite driver, because no possibility of overlap exists. It also may be desirable to move the primary object faster and with more flexibility than the other objects; this may be a good application for a faster byte-move driver operating in the foreground, with the sprite engine running independently in the background. No driver is best for all applications. Look to innovative program structure and the proper mix of animation techniques for the best results.

When considering potential animation applications, remember that results can be much different with other 8086-family processors. The 80286 processor, in particular, has great potential for animation applications. The sprite engine

described here was designed for the slowest CPU, the 8088, because it is also the most common. Drivers reoptimized for the 80286 could support two to three times as many objects.

Finally, be aware that objects have been horizontally byte-aligned rather than pixel-aligned, for the sake of simplicity and reduced program length. Pixel alignment, along with smaller movement increments for the objects, would provide smoother motion and allow more finely detailed internal animation; it is strongly recommended for serious animation applications.

This sprite engine is a standardized, fully functional solution to the animation problems that were created by IBM's decision not to include animation hardware in the PC. This engine provides visually superb animation while shielding programmers from its details, thereby expanding their perspective in crafting application code, drivers, and hardware into a smoothly working whole. This surely can result only in better animation software. 

Michael Abrash is a senior software engineer for Tseng Laboratories in Pennsylvania. Dan Illowsky is president of Funstastic. Together and separately they have written video games for the IBM PC and Apple II.

COPY II PC™

BACKS UP PROTECTED SOFTWARE.

The backup insurance you need to protect your software investment, COPY II PC makes a floppy backup of most protected software quickly and easily. (We update COPY II PC regularly to handle new protections; you as a registered owner may update at any time for \$15 plus \$3 s/h.)

RUNS PROTECTED SOFTWARE FROM YOUR HARD DISK.

COPY II PC makes using your hard disk as convenient as it should be. No longer will you have to keep your floppy disk in drive A with some of the most popular business software. Call for current list.



Backup utilities also available for the Macintosh, Apple II, Commodore 64/128 and Atari ST.

PC TOOLS NOW AVAILABLE!

Put all the most popular disk utilities (even undelete) together with a powerful

MINIMUM REQUIREMENTS:

IBM PC, XT, AT, 256K jr and most compatibles. One or two disk drives. 128K memory (all available memory fully supported).

Call 503/244-5782, M-F, 8-5:30 (West Coast time) with your   in hand. Or send a check for \$39.95 U.S. plus \$3 s/h, \$8 overseas.

\$39.95

Central Point Software, Inc.
9700 S.W. Capitol Hwy. #100
Portland, OR 97219

*Central Point
Software*
INCORPORATED

DOS interface. Then make them resident and you have PC Tools. PC Tools lets you run nearly any DOS command within any other running program. Just \$39.95 plus \$3 s/h.

LISTING 1: SPRITES1.ASM

```

;
;This program demonstrates the use of a set of routines which
; allow smooth, non-flickering, and non-destructive animation
; of objects on an IBM CGA or EGA graphics adapter. The program
; moves two helicopters and a balloon along programmed paths while
; internally animating the helicopter's rotors, and orientation. You
; will see no undesirable fringe or overlap effects. Objects look
; as if they are in separate planes, and blank areas within an object
; such as the windows of the helicopters appear to be transparent.
;
; Link with Listings 2 and 3 with the command:
;   link sprites1+sprites2+sprites3;
; to generate the executable sprite application file sprites1.exe.
;
stack segment para stack 'STACK'
    db 100 dup('Stack')
stack ends
;
;Segment used to hold memory image of the background. It is used to
; restore the background before an object is moved.
;
background_segment segment para 'DATA'
    db 4000h-((4000h-16000)/2) dup(0); last 192 bytes of the
background_segment ends ; 16K video memory
;
; buffer are never used
cseg segment para public 'cseg'
    assume cs:cseg,ds:cseg,es:nothing
    extrn byte_move_form_driver:near
    extrn initialize:near,terminate:near,object_services:near
    extrn vert_int_modulo_count:word
    extrn put_objects_on_screen:far
;
;The flag below must be set properly before assembling this program
;
ega equ 0; 1 to assemble for use on an Enhanced Graphics Adapter
; 0 to assemble for use on a Color Graphics Adapter
cga equ (ega xor 1); the opposite status of ega
;
if ega
old_vert_count dw 0 ;holds number used to synchronize this
; program to vertical interrupt
endif
;
screen_buffer_addr equ 0b800h ;video mode 4's buffer
; paragraph address
;
num_objects equ 3 ;this program will move three objects
;
;Below is a table which holds all the parameters which govern the
; movement of the three individual objects
x dw 15, 38, 64
y dw 90, 180, 164
xinc dw 1, 0, -1
yinc dw 0, -2, 0
form dw bcptr_rt_tbl, balloon_tbl, rcptr_lft_tbl
formbase dw bcptr_rt_tbl, balloon_tbl, rcptr_lft_tbl
formmax dw bcptr_rt_tbl_max, balloon_tbl_max, rcptr_lft_tbl_max
control dw copter1_cinit, balloon_cinit, copter0_cinit
controlbase dw copter1_control, balloon_control, copter0_control
controlmax dw copter1_cntl_max, balloon_cntl_max, copter0_cntl_max
delay dw 01, 01, 01
delaybase dw 04, 12, 06
repeat dw 47, 91, 55
;
;Below are lists of parameters which control the sequence of
; parameters used to define the movement patterns, and shapes.
; The parameters are listed in the following order:
; xinc, yinc, form, formmax, delay, repeat
;
copter0_control dw -1,0
dw rcptr_lft_tbl,rcptr_lft_tbl_max,06,54
copter0_cinit dw 0,-2
dw rcptr_lft_tbl,rcptr_lft_tbl_max,06,35
dw 1,0
dw rcptr_rt_tbl,rcptr_rt_tbl_max,06,4
dw 1,2
dw rcptr_rt_tbl,rcptr_rt_tbl_max,08,10

```


```

dw 1,-2
dw rcptr_rt_tbl,rcptr_rt_tbl_max,08,8
dw 1,-2
dw rcptr_rt_tbl,rcptr_rt_tbl_max,08,4
dw 0,0
dw rcptr_rt_tbl,rcptr_rt_tbl_max,10,10
dw 1,-2
dw rcptr_rt_tbl,rcptr_rt_tbl_max,08,4
dw 1,-2
dw rcptr_rt_tbl,rcptr_rt_tbl_max,08,9
dw 1,2
dw rcptr_rt_tbl,rcptr_rt_tbl_max,08,15
dw 0,2
dw rcptr_rt_tbl,rcptr_rt_tbl_max,10,35
copter0_cntl_max label byte
;
copter1_control dw 1,0
dw bcptr_rt_tbl,bcptr_rt_tbl_max,04,46
copter1_cinit dw -1,0
dw bcptr_lft_tbl,bcptr_lft_tbl_max,04,46
dw 1,0
dw bcptr_rt_tbl,bcptr_rt_tbl_max,04,46
dw -1,0
dw bcptr_lft_tbl,bcptr_lft_tbl_max,04,46
dw 0,0
dw disappear_table,disappear_table_max,300,1
copter1_cntl_max label byte
;
balloon_control dw 0,-2
dw balloon_tbl,balloon_tbl_max,12,70
balloon_cinit dw 0,2
dw balloon_tbl,balloon_tbl_max,12,70
balloon_cntl_max label byte
;
;Below are tables used to sequence the internal animation
;
rcptr_lft_tbl label word
dw rcptr_left0
dw rcptr_left1
rcptr_lft_tbl_max label word
;
rcptr_rt_tbl label word
dw rcptr_right0
dw rcptr_right1
rcptr_rt_tbl_max label word
;
bcptr_lft_tbl label word
dw bcptr_left0
dw bcptr_left1
bcptr_lft_tbl_max label word
;
bcptr_rt_tbl label word
dw bcptr_right0
dw bcptr_right1
bcptr_rt_tbl_max label word
;
balloon_tbl label word
dw balloon
balloon_tbl_max label word
;
disappear_table label word
dw 0ffffh
disappear_table_max label word
;
;Below are the forms used to define the various images of the objects
; in a form suitable for an AND-OR type form driver. The format is:
; byte 0 - height in lines (h)
; byte 1 - width in bytes (w)
; followed by w X h (mask word, image word) pairs.
;
rcptr_left0 label byte
db 00eh, 006h, 000h, 000h, 0ffh, 0ffh, 000h, 00fh, 0ffh, 0f0h
db 0ffh, 0ffh, 000h, 000h, 0ffh, 0f0h, 000h, 00fh, 000h, 00fh
db 0ffh, 0f0h, 0ffh, 0ffh, 000h, 000h, 0ffh, 0f0h, 000h, 00fh
db 0ffh, 0ffh, 000h, 000h, 0ffh, 0ffh, 000h, 000h, 0fch, 000h
db 002h, 0AAh, 003h, 0ffh, 0A8h, 000h, 0ffh, 0ffh, 000h, 000h
db 0f3h, 0ffh, 008h, 000h, 0c0h, 0ffh, 02Ah, 000h, 0ffh, 03fh
db 000h, 0c0h, 0cfh, 0ffh, 020h, 000h, 0f0h, 03fh, 00Ah, 080h
db 0ffh, 03fh, 000h, 0c0h, 03fh, 0ffh, 080h, 000h, 0f0h, 00ch
db 00Ah, 0A2h, 03fh, 03fh, 080h, 0c0h, 03fh, 0ffh, 080h, 000h

```


MDBS III[®]

ATTN:
APPLICATION
DEVELOPERS



... DELIVERS THESE ESSENTIAL FEATURES.
DOES YOUR DBMS?

MDBS III is more powerful than most mainframe data base management systems... and less expensive. MDBS III was designed for serious application developers like you. Like the developers of Solomon III, the "Number One" accounting system. And all the others who demand these essential features MDBS III provides:

DATA STRUCTURING—So flexible it captures any data relationship you can imagine. So comprehensive you'll design complex data bases faster than ever.

TRUE MULTI-USER—Few DBMSs give you as many facilities to guard against haphazard concurrent data modification as MDBS III does, down to the locking of individual data records.

PERFORMANCE—MDBS III gives you fast data modification and retrieval plus extensive performance tuning facilities.

DATA INTEGRITY—MDBS III provides airtight integrity assurances... from range checking to transaction-logging to enforcement of data relationships... *all automatically.*

PHYSICAL DATA PROTECTION—

You get automatic recovery from media as well as from physical data destruction.

DATA SECURITY—Protect your data using passwords, encryption, and read/write access down to the field level.

PORTABILITY—MDBS III runs on a range of mini and micro computers, including LANs, and supports a variety of host language interfaces.

SUPPORT—**mdbs** is there when you need us, with in-depth seminars, telephone support, individual consulting and contract programming to help you develop and install your applications.

Call us today at 800-323-3629 for more information; in Canada or Illinois, dial 312-303-6300. Or write **mdbs**, P.O. Box 248, Lafayette, IN 47902, TELEX 209147 ISE UR.

MDBS III[®]
ABSOLUTE POWER

CIRCLE NO. 211 ON READER SERVICE CARD

mdbs is a registered trademark and MDBS III is a trademark of Micro Data Base Systems, Inc. IMS is a trademark of IBM; IDMS of Cullinet.



DB	0F0h	003h	00Ah	0A0h	0C0h	000h	03Fh	0FFh	03Fh	0FFh
DB	0ACh	00Fh	0C0h	003h	00Ah	0A0h	03Fh	0FFh	000h	0C0h
DB	000h	000h	00Ah	0A0h	000h	03Fh	0AAh	000h	0FFh	03Fh
DB	000h	0C0h	0C0h	000h	02Ah	0AAh	000h	0FFh	0AAh	000h
DB	0FFh	03Fh	000h	0C0h	0F0h	000h	00Ah	0AAh	003h	0FFh
DB	0A8h	000h	0FFh	0FFh	000h	000h	03Ch	0FFh	0C3h	000h
DB	0CFh	03Fh	030h	0C0h	0FFh	0FFh	000h	000h	0C0h	000h
DB	03Fh	0FFh	000h	0FFh	0FFh	000h	0FFh	0FFh	000h	000h
recopter left label byte										
DB	00Eh	006h	000h	000h	0FFh	0FFh	000h	00Fh	0FFh	0F0h
DB	0FFh	0FFh	000h	000h	000h	000h	0FFh	0FFh	0FFh	0FFh
DB	000h	000h	0FFh	0FFh	000h	000h	0FFh	0F0h	000h	00Fh
DB	0FFh	0FFh	000h	000h	0A0h	0FFh	000h	000h	0F0h	000h
DB	002h	0AAh	003h	0FFh	0A0h	000h	0FFh	0FFh	000h	000h
DB	0F3h	0FFh	000h	000h	0C0h	0FFh	02Ah	000h	0FFh	0FFh
DB	000h	000h	0CFh	0FFh	020h	000h	0F0h	03Fh	00Ah	080h
DB	0F3h	0F3h	00Ch	00Ch	03Fh	0FFh	080h	000h	0F0h	00Ch
DB	00Ah	0A2h	03Ch	0CFh	083h	030h	03Fh	0FFh	080h	000h
DB	0F0h	0A0h	000h	0A0h	0C0h	03Fh	02Ah	0C0h	03Fh	0FFh
DB	080h	000h	0C0h	00Ch	02Ah	0A2h	03Ch	0CFh	083h	030h
DB	000h	000h	0AAh	0AAh	000h	03Fh	000h	000h	0F3h	0F3h
DB	00Ch	00Ch	0C0h	000h	02Ah	0AAh	000h	0FFh	0AAh	000h
DB	0FFh	0FFh	000h	000h	0F0h	000h	00Ah	0AAh	003h	0FFh
DB	0A8h	000h	0FFh	0FFh	000h	000h	03Ch	0FFh	0C3h	000h
DB	0CFh	03Fh	0C0h	0C0h	0FFh	0FFh	000h	000h	0C0h	000h
DB	03Fh	0FFh	000h	0FFh	0FFh	000h	0FFh	0FFh	000h	000h
recopter right label byte										
DB	00Eh	006h	0FFh	0FFh	000h	000h	0F0h	000h	00Fh	0FFh
DB	000h	000h	0FFh	0FFh	0FFh	0FFh	000h	000h	0FFh	0FFh
DB	000h	000h	000h	000h	0FFh	0FFh	0FFh	0FFh	000h	000h
DB	0FFh	0FFh	000h	000h	0FFh	0FFh	000h	000h	0F0h	0FFh
DB	000h	000h	0FFh	0C0h	000h	02Ah	000h	03Fh	0AAh	080h
DB	0FCh	0FFh	003h	000h	0FFh	023h	000h	0A0h	0FFh	0CFh
DB	000h	020h	0FCh	0FFh	003h	000h	0FCh	00Fh	002h	0A0h
DB	0FFh	0F3h	000h	008h	0FCh	0FCh	003h	002h	030h	00Fh
DB	08Ah	0A0h	0FFh	0FCh	000h	002h	000h	003h	0FFh	0FCh
DB	0C0h	00Fh	02Ah	0A0h	0FFh	0FCh	000h	002h	0FCh	0FCh
DB	003h	002h	0C0h	003h	08Ah	0A0h	0FFh	0FCh	000h	002h
DB	0FCh	0FFh	000h	000h	0FCh	000h	002h	0AAh	000h	000h
DB	0AAh	0AAh	0FCh	0FFh	003h	000h	0FFh	000h	000h	0AAh
DB	000h	003h	0AAh	0A8h	0FFh	0FFh	000h	000h	0FFh	0C0h
DB	000h	02Ah	000h	0FFh	0AAh	0A0h	0FFh	0FFh	000h	000h
DB	0FCh	0F3h	003h	00Ch	0FFh	03Ch	000h	0C3h	0FFh	0FFh
DB	000h	000h	0FFh	0C0h	000h	0FFh	000h	003h	0FFh	0FCh
recopter right label byte										
DB	00Eh	006h	0FFh	0FFh	000h	000h	0F0h	000h	00Fh	0FFh
DB	000h	000h	0FFh	0FFh	0FFh	0FFh	000h	000h	0F0h	000h
DB	00Fh	0FFh	000h	0FFh	0F0h	000h	0FFh	0FFh	000h	000h
DB	0FFh	0FFh	000h	000h	0FFh	0FFh	000h	000h	0FFh	0FFh
DB	000h	000h	0FFh	0C0h	000h	02Ah	000h	03Fh	0AAh	080h
DB	0FFh	0FFh	000h	000h	0FFh	003h	000h	0A0h	0FFh	0CFh
DB	000h	020h	0CFh	0CFh	030h	030h	0FCh	00Fh	002h	0A0h
DB	0FFh	0F3h	000h	008h	0F3h	03Ch	00Ch	0C2h	030h	00Fh
DB	08Ah	0A0h	0FFh	0FCh	000h	002h	0FCh	003h	003h	0A8h
DB	0C0h	00Fh	02Ah	0A0h	0FFh	0FCh	000h	002h	0F3h	03Ch
DB	002h	0C2h	000h	003h	08Ah	0A0h	0FFh	0FCh	000h	002h
DB	0CFh	0CFh	030h	03Ch	0FCh	000h	002h	0AAh	000h	000h
DB	0AAh	0AAh	0FFh	0FFh	000h	000h	0FFh	000h	000h	0AAh
DB	000h	003h	0AAh	0A8h	0FFh	0FFh	000h	000h	0FFh	0C0h
DB	000h	02Ah	000h	00Fh	0AAh	0A0h	0FFh	0FFh	000h	000h
DB	0FCh	0F3h	003h	00Ch	0FFh	03Ch	000h	0C3h	0FFh	0FFh
DB	000h	000h	0FFh	000h	000h	0FFh	000h	003h	0FFh	0FCh
recopter left label byte										
DB	00Eh	006h	000h	000h	0FFh	0FFh	000h	00Fh	0FFh	0F0h
DB	0FFh	0FFh	000h	000h	000h	000h	0FFh	0FFh	0FFh	0FFh
DB	000h	000h	0FFh	0FFh	000h	000h	0FFh	0F0h	000h	00Fh
DB	0FFh	0FFh	000h	000h	0FFh	0FFh	000h	000h	0FCh	000h
DB	001h	055h	003h	0FFh	054h	000h	0FFh	0FFh	000h	000h
DB	0F3h	0FFh	0A0h	000h	0C0h	0FFh	015h	000h	0FFh	0FFh
DB	000h	000h	0CFh	0FFh	010h	000h	0F0h	03Fh	005h	040h
DB	0F3h	0F3h	00Ch	00Ch	03Fh	0FFh	040h	000h	0F0h	00Ch
DB	005h	051h	03Ch	0CFh	043h	030h	03Fh	0FFh	040h	000h
DB	0F0h	003h	005h	054h	0C0h	03Fh	015h	0C0h	03Fh	0FFh
DB	0A0h	000h	0C0h	00Ch	015h	051h	03Ch	0CFh	043h	030h
DB	000h	000h	055h	055h	000h	03Fh	055h	040h	0F3h	0F3h
DB	00Ch	00Ch	0C0h	000h	015h	055h	000h	0FFh	055h	000h
DB	0FFh	0FFh	000h	000h	0F0h	000h	005h	055h	003h	0FFh
DB	054h	000h	0FFh	0FFh	000h	000h	03Ch	0FFh	0C3h	000h
DB	0CFh	03Fh	030h	0C0h	0FFh	0FFh	000h	000h	0C0h	000h
DB	03Fh	0FFh	000h	0FFh	0FFh	000h	0FFh	0FFh	000h	000h

[illegible]

Make Flashy Programs.

In dBASE, Turbo Pascal, BASIC, C, COBOL, Fortran, 1-2-3, DOS.

New! Flash-Up™ Windows.

Instantly flash-up menus and help windows.

From within almost any program language or application program. When the user makes a menu selection, a sequence of keystrokes is sent to the running program as if the user were typing it at the keyboard.


A keyboard macro utility that your programs can control!

Just like keyboard macro utilities, Flash-Up Windows can be used to send repetitive keystrokes and simplify commands for your users.

But Flash-Up Windows can do more. Your programs can send commands directly to Flash-Up. Powerful commands that control when and how windows appear. Flash-Up is a perfect tool for controlling programs and entire systems via menus.

The powerful window editor allows you to create windows, change their size, location, and color — all automatically.

Works with DOS, BASIC, Turbo Pascal, C, COBOL, Fortran, dBASE, 1-2-3, R:BASE ...and most other software. \$90.



Flash Code.™ For dBASE II, III and III+.

The most powerful, most complete program developer for dBASE II, III, and III+.

Use Flash Code's advanced screen design editor and see how incredibly easy screen design can be. Draw boxes, lines, and select colors. Specify special parameters for edit checking, initial values, calculated fields, etc. All within one, easy to use editor.

Then tell Flash Code to write the program. Based on your screen designs, Flash Code can generate a full database program. Well written code that you can use as is, or merge with your own programs.


Menus and help windows add a new dimension to your dBASE applications.

Flash Code includes its own dBASE window editor. Use the window module to flash-up windows and screens instantly. The windows are easily converted when you move to the added power of our Flash-Up Windows product.

"... a truly remarkable product. Brand new, state-of-the-art and actually fun to use. The windows make it an even more amazing product."

— Gary N. Prague, Author, "The dBase III Programming Handbook"

Flash Code. \$150.



Screen Sculptor.™ For IBM BASIC, Turbo Pascal, and Quick Basic.

Create screens in minutes, then Screen Sculptor writes the program.

In IBM BASIC, Turbo and Microsoft Pascal, and Quick Basic. Simply "draw" your screens with our advanced screen design editor and replace hours of tedious work with minutes of creative design.

Move pieces of the screen around, select colors from a menu, draw boxes, lines, paint, repeat last character. And more! Specify variable names, data types, acceptable data ranges, pictures for edit checking, etc., and you're ready to go.

Generate tested program source code to merge with your own program.


Based on your screen design. The generated program flashes up the screen, allows data to be entered by the user, and edit checks the input data.

"... so well done that you may not need to refer to the manual."

"... an exceptional product that fills a real need in the development of new programs."

— Computer Language

Screen Sculptor. \$125.



No Risk Demo Offer!

Order any package and receive a separately sealed demo disk of the product. Use the demo and the manual for 30 days. If you're not satisfied — for any reason — return the entire package for a full refund.

Credit card orders call 24 hrs/day:
1(800) 824-7888, operator 268.

All other orders and inquiries call or write
Software Bottling Co., 6600 L.I. Expwy.,
Maspeth, NY 11378. 718-458-3700.

Requires an IBM PC, XT, AT or true compatible, 256K.

Not copy protected.



THE
SOFTWARE
BOTTLING
COMPANY
OF NEW YORK

For \$295 you can draw your own conclusions.

Drafix™ 1. The first high performance CAD software everyone can afford.

Low-cost, high performance computer-aided design & drafting (CAD) software is finally available for use on your PC.

There's never been a professional CAD package so complete at such a low cost.

Drafix 1 from Foresight Resources. Only \$295.

Powerful, full-featured second generation CAD software.

Drafix 1 offers all of the capabilities you expect to find in packages costing \$2,000 or more.

This is not simply a souped-up paint package. Drafix 1 is a breakthrough in design that organizes sophisticated CAD functions into smooth, fast operations. All of the drawing, designing and editing functions that designers demand from a serious CAD tool are included in Drafix 1.

A breakthrough in screen design and visual user interface.

Drafix 1 features the best organized screen design ever devised. Very simply, it displays all the information you need, all of the time.

The entire menu hierarchy is displayed constantly. There's no need to memorize commands or search for menus.

Snap-mode options are continually shown on the left screen border and can be selected "on the fly" by either pointer device or a single keystroke. Roll-down screens provide quick access to the virtually unlimited drawing, display and editing options.

And it's all controlled by a versatile three-button mouse, or digitizer, with on-screen prompts so each button function is clearly defined.

AutoCAD® compatible for easy expansion.

If you or someone in your company already uses AutoCAD, Drafix 1 offers an inexpensive way to add to your capability.

The optional Drafix 1/AutoCAD file exchange utility permits transfer of drawings between Drafix 1 and AutoCAD.

It's the perfect, low-cost alternative for increasing your drafting and design capacity.

Unbelievable low bundle prices.

To get you up and running we offer two special hardware bundles—all the equipment you need at prices you won't believe.

Get Drafix 1 with your choice of Torrington's Manager Mouse or the LOGIMOUSE® C7 for just \$395.00.

Or get Drafix 1 with the SummaSketch 12" x 12" digitizer tablet with stylus for just \$650.00.

Order today. Take advantage of our 30-day, money back guarantee.

We're so certain you'll like the performance and versatility of Drafix 1 you're welcome to try it risk free for 30 days. If you're not completely satisfied, return it to us for a full refund.

Find out just how good CAD software can be. For only \$295.00.

Use our toll-free number and any major credit card to order your copy of Drafix 1 today.

SPECIFICATIONS

Code specifications

Lattice "C" language
Halo graphics
Floating point database
Coprocessor support
PC-DOS/MS-DOS 2.1 or later

Drafix 1 Features

Items
Lines
Pt markers
Arcs & circles
Note text
Polygons & ellipses
Symbols/individual & nested

Item attributes

16 pen colors
255 Layers
8 Linetypes
12 Text fonts
32 Pt marker types

Screen Display

Zoom/Pan/Full
8 Save Views
Slide save/view
Grids on/off
Metric & English Standards
Engineering (decimal/fractional)
Architectural (ft/in)

Project drawing info.

Numeric input

Keyboard and cursor
Absolute/Relative/ Polar
Snap Modes
Gridpoint
Endpoint
Midpoint
Intersect
On Item
Quadrant
Tangent
Arc center
Transform/Copy
Move
Rotate
Scale
Mirror
Align

Modify/Edit

Attributes
Break/Divide
File/Chamfer
Trim
Stretch
Erase
Explode symbols & polygons
Mask
Replace
Merge
Region select
Workgroup

Auto hatching, polygon fill

Auto Dimensions

Linear Hor/Ver/Aligned
Angular
Dia/Radius
Leader/Notes
Ordinate
Chain & Baseline

Check calculations

Coordinates
Distance & angle
Area & perimeter

Item Mapping

Hardware

Computers
IBM PC XT AT and compatibles
AT&T 6300 Plus
Zenith
System Requirements
— 512K RAM
— RS-232C Comm port
— Mouse or digitizer
— Coprocessor recommended

Graphics Display boards

IBM CGA/EGA and compatibles
Hercules, and a wide range of graphics boards

Digitizers & Locators

All popular locator devices supported

Plotters

All popular plotters ("C" size) supported
"E" size plotter option available

Printers

All popular laser and dot matrix printers supported

Order Now! Call Toll-Free!
1-800-231-8574,
Ext. 500

☐ Drafix 1 CAD Package \$295
☐ Drafix 1 with Mouse \$395

Torrington _____
LOGIMOUSE _____

☐ Drafix 1 with SummaSketch tablet \$650
☐ AutoCAD File Exchange Utility \$ 95

Dealer inquiries welcome

Check, money order, Visa
and MasterCard accepted

FORESIGHT
RESOURCES CORP.™

932 Massachusetts
Lawrence, KS 66044
913/841-1121

AutoCAD is a trademark of Autodesk Inc.
IBM PC/XT/AT are trademarks of the IBM Corp.
SummaSketch is a trademark of Summagraphics Inc.
Manager Mouse is a trademark of Torrington Company

CIRCLE NO. 138 ON READER SERVICE CARD




```

DB 014h, 004h, 000h, 000h, 03Fh, 0FCh
DB 000h, 00Fh, 0FFh, 0FFh, 000h, 0FFh, 0FFh, 000h
DB 003h, 0FFh, 0F0h, 000h, 00Fh, 0FFh, 0C0h, 000h
DB 03Fh, 0FFh, 000h, 000h, 03Fh, 0FFh, 000h, 000h
DB 0FFh, 0FFh, 000h, 000h, 0FFh, 0FCh, 000h, 000h
DB 0FFh, 0FCh, 000h, 000h, 0FFh, 0FCh, 000h, 000h
DB 0FFh, 0FCh, 000h, 000h, 0FFh, 0FFh, 000h, 000h
DB 03Fh, 0FFh, 000h, 000h, 03Fh, 0FFh, 000h, 000h
DB 00Fh, 0FFh, 0C0h, 000h, 003h, 0FFh, 0F0h, 000h
DB 000h, 0FFh, 0FFh, 000h, 000h, 00Fh, 0FFh, 0FFh
DB 000h, 000h, 03Fh, 0FCh, 000h, 000h, 000h, 000h
DB 03Fh, 0FFh, 000h, 000h, 000h, 000h, 00Fh, 0FFh
DB 0C0h, 000h, 000h, 000h, 003h, 0FFh, 0F0h, 000h
DB 000h, 000h, 000h, 0FFh, 0FFh, 000h, 000h, 000h
DB 000h, 00Fh, 0FFh, 0FFh, 0C0h, 000h, 000h, 000h
;
;The tables below define the x,y and color of pixels which represent
; stars in a night sky.
;
starx label byte
db 10, 50, 39, 22, 41, 2, 50, 33, 65, 41, 15, 19, 19, 54
db 34, 61, 19, 41, 22, 55, 23, 68, 8, 29, 51, 71, 39, 30
db 41, 9, 21, 13, 68, 61, 43, 70, 40, 17, 39, 19, 29, 45
num_stars equ $-starx
stary label byte
db 7, 33, 90, 100, 80, 35, 92, 172, 106, 97, 123, 168, 42, 88
db 150, 34, 29, 90, 170, 65, 39, 99, 145, 163, 109, 78, 127, 166
db 169, 84, 15, 65, 99, 155, 89, 58, 25, 80, 76, 168, 98, 99
star_color label byte
db 1, 2, 3, 1, 2, 3, 1, 2, 3, 1, 2, 3, 1, 2
db 3, 1, 2, 3, 1, 2, 3, 1, 2, 3, 1, 2, 3, 1
db 2, 3, 1, 2, 3, 1, 2, 3, 1, 2, 3, 1, 2, 3
;
start proc near
cld ;count up
push cs ;most data is kept in code segment
pop ds ;
;set 320x200x4 graphics mode
mov ax, 0004h ;graphics mode 4 is supported by both
int 10h ; the EGA and CGA
;select palette 0
mov ah, 0bh ;set color palette function
mov bh, 1 ;select palette to be used subfunction
mov bl, 0 ;select palette 0 (green/red/yellow)
int 10h ;
;put stars into background buffer
mov ax, background_segment
mov es, ax
mov bx, num_stars-1
mov di, 80 ;lines are 80 bytes long
next_star:
sub di, di ;calculate star's screen buffer
mov al, [starx+bx] ; address based on line number
shr al, 1 ; and byte position from tables
jnc calc_y_offset ;
mov di, 2000h ;odd lines in second bank
calc_y_offset:
mul dl ;number of even lines * 80
mov cl, [starx+bx] ; plus byte position in line
sub ch, ch ; plus odd line offset
add ax, cx ; is screen buffer offset
add di, ax ;
mov al, [star_color+bx] ;get the star image byte (all are
or es:[di], al ; single pixels) and OR it into
dec bx ; the background buffer.
jns next_star ;
;put moon into background buffer
mov ax, background_segment
mov es, ax ;put forms into background buffer
mov bx, 88 ;put moon image on line 88
mov cx, 37 ; and byte 37
mov si, offset moon ;
call byte_move_form_driver
;put horizon into background buffer
mov ax, background_segment ;horizon is two consecutive
mov es, ax ; red lines
mov ax, 0aaaaah ;8 red pixels
mov di, 92*80 ;point to scan line 184
mov cx, 40 ;width of screen in words
rep stosw
mov di, 92*80+2000h ;point to scan line 185

```

```

mov cx, 40 ; and draw it
rep stosw
;copy background to display memory
mov ax, screen_buffer_adr ;
mov es, ax ;
mov ax, background_segment ;
mov ds, ax ;
sub si, si ;
sub di, di ;
mov cx, 2000h ;
rep movsw ;
;
;Initialize the object services routine
;
call initialize
;
;Orchestrate the objects' movements
;
push cs ;object data is kept in
pop ds ; code segment
iteration_loop: ;sequence all objects once
mov di, ((num_objects-1) * 2) ;start with last object
next_object:
;see if it's time to manipulate object
dec [delay+di] ;each delay count is 1/60 second
jnz done_with_object ; so long as program can keep up
;see if it's time to get next set of control variables
dec [repeat+di] ;each count is the number of
jnz reset_delay ; movements using the present set
; of control values
;get next set of control parameters
mov si, [control+di] ;get the addr of the parameter list
lodsw ;get the number of bytes to move
mov [xinc+di], ax ; horizontally each time delay
; counts down to zero
lodsw ;get the number of lines to move
mov [yinc+di], ax ; vertically each count down
lodsw ;get pointer to the table of
mov [form+di], ax ; form address to be sequenced though
mov [formbase+di], ax ; set to repeat with starting form
lodsw ; when the end of the table is hit
mov [formmax+di], ax ;save end of table marker
lodsw ;get next delay count which controls
mov [delaybase+di], ax ; the speed
lodsw ;get the number of times to use
mov [repeat+di], ax ; this new set of control parameters
cmp [controlmax+di], si ;point to next list of control
ja save_control_base ; parameters to be used.
mov si, [controlbase+di] ; recycle when end of list hit
save_control_base:
mov [control+di], si ;next control list entry address
;
reset_delay:
mov ax, [delaybase+di] ;reset iteration count until
mov [delay+di], ax ; next manipulation of this object
;find object's new position
mov cx, [x+di] ;calculate new x and y positions
add cx, [xinc+di] ; and store them
mov [x+di], cx ;
mov bx, [y+di] ;
add bx, [yinc+di] ;
mov [y+di], bx ;
;point to new form for object so that it appears to move internally
mov si, [form+di] ;each time an object is counted down
inc si ; the form used is taken from the
inc si ; next address in table
cmp [formmax+di], si ;
ja setform ;
mov si, [formbase+di] ;
setform:
mov [form+di], si ;cycle to the next form for the object
mov si, [si] ;put pointer to object's form in SI
shr di, 1 ;object number in DI
;BX holds line number, CX byte number
call object_services ;register change in object's status
shl di, 1 ;turn object number into object index
;point to next object
done_with_object:
dec di
dec di
js check_for_keystroke ;see if finished with iteration

```



```

        jmp     next_object      ; if not process next object
;
;Check for keystroke; if so, clear key & end.
;
check_for_keystroke:
        mov     ah,1            ;see if a char is waiting
        int     16h            ;get keyboard status
        jnz     getkey         ;if zero no key waiting
;
;Wait for new vertical sync (CGA) or retrace (EGA) before putting
; objects on screen to avoid undesirable screen breakup and blinking
; effects. Waiting also keeps the objects moving a constant rate.
;
if cga
        mov     dx,3dah        ;point to cga status register
wait_for_not_vert_sync:
        in      al,dx          ;wait for begining of vertical
        and     al,08h        ;sync by starting search from
        jnz     wait_for_not_vert_sync ; outside of sync pulse
wait_for_vert_sync:
        in      al,dx          ;wait for start of sync
        and     al,08h        ;
        jz      wait_for_vert_sync ;
;
        pushf                 ;push flags to simulate an
        call    put_objects_on_screen ; interrupt
endif
if ega
        mov     ax,[old_vert_count] ;synchronize animation loop
wait_for_after_interrupt:
        cmp     ax,[vert_int_modulo_count] ; to vert interrupt so it
        je      wait_for_after_interrupt ; will run at a fixed
        mov     ax,[vert_int_modulo_count] ; smooth rate
        mov     ax,[vert_int_modulo_count] ;save new as old for next
        mov     [old_vert_count],ax ; time
endif
        jmp     iteration_loop ;
;
;Run is completed.
;
getkey:
        sub     ah,ah          ;get key that was hit
        int     16h           ;
done:
        call    terminate ;do any clean up required by the sprite
        ; routines
;Set to text mode
;
        mov     ax,0002h ;set the adapter to video mode 2
        int     10h ;
;
;Return to DOS
;
        mov     ax,4c00h ;terminate program with return code of zero
        int     21h ;
start
cseg
        end     start ;program execution will start at start

```

LISTING 2: SPRITES2.ASM

```

;
;These routines produce the effect of hardware sprites in software
; on IBM PC compatible computers. They put objects onto the screen
; in a manner which preserves the background, and produces no
; undesirable fringe or overlap effects. Operations which affect
; video buffer memory are performed as much as possible during
; video non-display periods to avoid other undesirable effects.
;
; Entry points and parameters:
;
; Initialize - Sets the background buffer address to be used to erase
; objects, resets internal flags and queue, and on EGAs
; sets up the use of the vertical interrupt to drive the
; drawing routines.
;
; Inputs - AX holds paragraph address of background buffer.
; Outputs - None.
;
; Terminate - Resets the EGA vertical interrupt hardware and vector

```

```

;
; Inputs - None.
; Outputs - None.
;
; Object_services - Sets X,Y and Form address for a given object
; to be drawn, and activates #r deactivates the object.
;
; Inputs - CX holds X position in bytes (0-79) of upper
; left hand corner of object. 0 is leftmost.
; - BX holds Y position in lines (0-198) 0 is top.
; BX must be even! Objects cannot start on odd lines.
; Objects must also be an even number of lines high.
; - DI holds object number. Higher numbered objects
; will appear to be in front of lower numbered
; objects when they overlap.
; - SI holds the offset in the code segment of the form
; to be drawn for the object. A value of 0ffffh means
; that the object is to be erased, then ignored.
; Forms must be in the following format:
;
; byte 0 - height in lines (h)
; byte 1 - width in bytes (w)
; followed by w x h (mask word, image word) pairs.
;
; Outputs - None.
;
; Registers - All are saved, except flags
;
; Warning - No bounds checking is done. X,Y or object numbers
; out of range can send your program into hyperspace.
;
; Put_objects_on_screen - This routine should be called by a program
; running on a CGA to put the objects on the screen. It must be
; far-called as if it were an interrupt routine. For example:
;
;         pushf
;         call far ptr put_objects_on_screen
;
; For best results this routine should be called immediately
; upon the sensing of vertical retrace.
;
; Inputs - None.
; Outputs - None.
;
; Vert_int_modulo_count - This memory word is incremented each time
; the objects are put into the screen map. On EGAs it can be used
; to synchronize a program to the constant time base provided by
; the vertical interrupt.
;
; The flag below must be set properly before assembling this program
;
ega     equ 0 ;1 to assemble for Enhanced Graphics Adapter
;0 to assemble for Color Graphics Adapter
cga     equ (ega xor 1) ;the opposite status of ega
;
bios_data_segment segment at 40h ;BIOS keeps its data at 400h;
        org     63h ;at 463h is a word that holds
bios_crtc_base_address dw ? ; the CRT controller's base
bios_data_segment ends ; address
;
;
cseg segment para public 'cseg'
        assume cs:cseg,ds:cseg,es:nothing
        public initialize,terminate,object_services
        public put_objects_on_screen,vert_int_modulo_count
;
;Memory for the parameters used to keep track of objects is reserved
; below. Many of the parameters stored are very code specific so that
; the size and number of objects which could be processed during
; vertical non-display time could be maximized.
;
number_of_objects equ 3 ;this should be set to the maximum number
; of objects or priorities which will
; need to be kept track of at one time.
;
queue label word
;
draw_screen_offset dw ? ;offset in screen memory buffer of upper
; left hand corner of object. 0ffffh if
; object is to be ignored.
dist_to_odd_scan_line dw ? ;distance from end of object on an even

```



```

; scan line to the start of the object
; on the next (odd) scan line
dist_to_even_scan_line dw ? ;distance from end of object on an odd
; scan line to the start of the object
; on the next (even) scan line

erase_parms label word
erase_width dw ? ;the object's screen image width in words
erase_entry_point dw ? ;the address of the inline code to do erase
erase_screen_offset dw ? ;the address where object was last drawn
; 0ffffh if object is not to be erased.
erase_image_offset dw ? ;used to determine if need to erase when
; object is in old position

;
length_of_erase_parms equ $-erase_parms
;
draw_col_entry_point dw ? ;address of the column code for drawing
draw_row_entry_point dw ? ;address of the row inline code for drawing
draw_image_offset dw ? ;offset in the code segment of the image
;
queue_item_length equ ($ - queue) ;number of bytes for each item
distance_from_entry_point_to_next_item equ $ - erase_entry_point
distance_from_image_to_next_item equ $ - draw_image_offset
;
db ( (number_of_objects-1) * queue_item_length ) dup(?)
end_of_queue label word
;
vert_int_modulo_count dw 0 ;incremented each time a vertical
; interrupt occurs
background_segment dw ? ;place to hold the paragraph address
; of the background buffer used to
; erase objects
crtc_base_address dw ? ;will hold register address
;
old_int10_offset dw ? ;place to store the vector contents
old_int10_segment dw ? ; so they can be restored when finished
;
old_int_mask db ? ;place to store the mask register's
; contents so it can be restored
;
true equ 1 ;used for flag values
false equ 0 ;
;
need_to_draw_something_flag db false ;true if a change needs to be
; made to any of the objects'
; screen images
;
screen_buffer_paragraph_adr equ 0b800h
;
;
initialize proc near
cld ;count up
push ds ;
mov cs:[background_segment],ax ;store background adr
mov ax,cs ;make data segment
mov ds,ax ; same as code segment
; since that is where data
mov es,ax ; used by this routine is
mov di,offset queue ;turn off all objects
mov cx,(number_of_objects * queue_item_length)/2
mov ax,0ffffh ;
rep stosw ;
;
mov [need_to_draw_something_flag],false ;nothing to draw
if ega
sub ax,ax ;swapping interrupt
mov ds,ax ; vectors with our
mov bx,(10*4) ; interrupt handler
mov ax,offset put_objects_on_screen ;our vertical int
mov dx,cs ; handler address
cli ;disable interrupts
xchg [bx],ax ;offset
xchg [bx+2],dx ;segment
mov cs:[old_int10_offset],ax ;save old value so we
mov cs:[old_int10_segment],dx ; can restore it upon
; termination
mov ax,bios_data_segment ;find the register
mov ds,ax ; address
assume ds:bios_data_segment ;
mov dx,[bios_crtc_base_address] ;
mov cs:[crtc_base_address],dx ;save it in code seg
mov al,11h ;select vertical

```

```

out dx,al ; retrace end register
mov al,04h ; and flip it off
inc dx ;
out dx,al ;
mov al,14h ; then flip it on
out dx,al ;
;
in al,21h ;enable IRQ2
mov cs:[old_int_mask],al ; save old value
and al,not 4 ;
out 21h,al ;
;
sti ;enable interrupts
endif
pop ds ;restore data segment
ret
initialize endp
;
terminate proc near ;only needs to be used when assembled
if ega ; for use on an EGA
mov dx,[crtc_base_address]
mov al,11h
out dx,al
inc dx
mov al,24h ;bit 5 high to disable, bit 4 low to
out dx,al ; clear vertical interrupt
push ds
sub ax,ax ;restore original interrupt
mov ds,ax ; 10 vector
mov bx,(10*4) ;
mov ax,cs:[old_int10_offset] ;
mov dx,cs:[old_int10_segment] ;
cli ;make sure interrupt
mov [bx],ax ; doesn't occur while
mov [bx+2],dx ; there is an inconsistent
; vector/mask
mov bl,cs:[old_int_mask] ;restore IRQ2 mask bit
and bl,4 ; to state it had when
in al,21h ; Initialize was called
and al,not 4 ;
or al,bl ;
out 21h,al ;
sti
pop ds
endif
ret
terminate endp
;
object_services proc near
cld ;
push es ;save the registers used
push ds ;
push ax ;
push bx ;
push cx ;
push si ;
push di ;
;
mov ax,cs ;everything will be in code segment
mov es,ax ;
mov ds,ax ;
;
shl di,1 ;multiply object number
shl di,1 ; which is in DI by 20 to
mov ax,di ; find object's parameter table
shl di,1 ; offset in queue structure
shl di,1 ; (NOTE: If a code change alter
add di,ax ; queue_item_length this code must
; be changed!)
mov ax,offset queue ;point directly to object's first
add di,ax ; parameter
mov ax,[bx+even_line_screen_offset_table]
add ax,cx ;find screen offset of top left corner
if ega
cli ;can't allow parameters to be just half
; changed if a vertical interrupt occurs
endif
cmp si,0ffffh ;if object is to be turned off then
jne save_position ; need to store a 0ffffh for the draw
mov ax,si ; screen position

```



```

    stosw      ;
    jmp short finish_services
save_position:
    stosw      ;save as first parameter (draw_screen_offset)
    lodsb      ;get the height of the image
    xor     ah,ah ;make height a word
    mov     bx,ax ;store height
    lodsb      ;get the width of the image in bytes
    mov     cx,2000h ;calculate amount to add after even scan
    sub     cx,ax ; lines are drawn to get the address of the
    xchg    ax,cx ; next scan line, and store it in queue
    stosw      ;
    mov     ax,1fb0h ;calculate amount to subtract after odd scan
    add     ax,cx ; lines are drawn to get the address of the
    stosw      ; next scan line, and store it in queue
    mov     ax,cx ;store the width in queue
    shr     ax,1 ; width is stored as number of words
    stosw      ;
    mov     ax,[bx+erase_inline_vector_table-2]
    ; -2 because there is no 0 lines entry point
    stosw      ;store the place to jump to erase an image
    ; of this height
    add     di,4 ;skip erase_screen_offset and
    ; erase_image_offset as these are filled
    ; in when an object is drawn
    xchg    si,cx ;swap image offset with width
    mov     ax,[si+column_inline_vector_table-2] ;inline code adr
    stosw      ; driver operates with words, so there is no
    ; need to divide SI by two to do table lookup
    mov     ax,[bx+row_inline_vector_table-2] ;inline code adr
    stosw      ; which calls column inline code for each row
    mov     [di],cx ;last param to put on queue is image offset
;
finish_services:
    mov     [need_to_draw_something_flag],true ;record change
if ega
    sti      ;all parameters have been put on queue
    ; so interrupts are safe now
endif
    pop     di ;restore those registers that were used
    pop     si ;
    pop     cx ;
    pop     bx ;
    pop     ax ;
    pop     ds ;
    pop     es ;
    ret
object_services endp
;
;This table is used to find the offset of an even scan line in the
; memory map of the color graphics adapter in medium resolution mode.
;
even_line_screen_offset_table label word
xx=0
    rept 100 ;there are 100 even lines
    dw     xx*50h ; each is 50h (80 decimal) long
    xx=xx+1
    endm
;
use_old_vector:
    pop     ax ;restore registers used before
    pop     dx ; jumping to previous IRQ2 handler
    jmp dword ptr cs:[old_int10_offset]
;
put_objects_on_screen proc far
    push    dx ;save registers used by EGA code
    push    ax ;
if ega
    ;must check if interrupt is being signaled
    ; by the EGA card. If not, it needs to be
    mov     dx,3c2h ; handled by another routine in the vector
    in      al,dx ; chain. The PC AT in particular uses
    test    al,80h ; IRQ2 for multiple devices.
    jz      use_old_vector
endif
    inc     cs:[vert_int_modulo_count] ;count vert interrupts
    sti      ;enable interrupts
    cmp     cs:[need_to_draw_something_flag],true ;anything to do?
    je      process_queue ; jmp if there is
if ega
    cli

```

```

    mov     al,20h ;issue a non_specific EOI (End Of Interrupt)
    out     20h,al ; so that interrupt controller chip will
    ; acknowledge future vertical interrupts
    mov     dx,cs:[crtc_base_address] ;re-enable ega card interrupt
    mov     al,11h ; select vertical retrace end
    out     dx,al ; register and clear vertical interrupt
    mov     al,04h ;
    inc     dx ;
    out     dx,al ;
    mov     al,14h ; then enable vertical interrupt
    out     dx,al ;
endif
    pop     ax ;restore original values
    pop     dx ;
    iret
;
skip_this_object:
    add     si,queue_item_length ;point SI to next item
    cmp     si,offset end_of_queue ;see if we are done
    je      draw ; jmp to draw if we are
    jmp     get_next_objects_screen_adr ; if not, erase next
;
process_queue:
    push    bx ;save the rest of the world
    push    cx ;
    push    bp ;
    push    si ;
    push    di ;
    push    ds ;
    push    es ;
;
    push    cs ;setup environment
    pop     ds ; data is in code segment
    cld      ; we will count up
    mov     ax,screen_buffer_paragraph_adr
    mov     es,ax ; ES points to screen memory
;
    mov     si,offset queue ;point to beginning of queue
;
;Erase all the active objects which have old screen positions
; different from their present screen position or have different
; image offsets
;
get_next_objects_screen_adr:
    mov     ax,[si+erase_screen_offset-draw_screen_offset]
    ; get the screen buffer
    ; offset of last draw
    cmp     ax,0ffffh ;if fffffh then object is
    je      skip_this_object ; yet to be drawn
    cmp     ax,[si] ; if new and old positions and
    jne     erase_this_object ; images are same then skip erase
    mov     di,[si+erase_image_offset-draw_screen_offset]
    cmp     di,[si+draw_image_offset-draw_screen_offset]
    je      skip_this_object ;
erase_this_object:
    inc     si ;point to next parameter
    inc     si ;
    mov     di,ax ;save screen buffer adr
    lodsw      ;get distance to odd scan line
    mov     bp,ax ; save in BP for inline code use
    lodsw      ;get distance to even scan line
    mov     dx,ax ; save in DX for inline code use
    lodsw      ;get the width in words for erase
    mov     cx,[si] ;get address of erase inline code
;
    push    si ;save position so next object
    push    ds ; can be found
    mov     ds,[background_segment] ;stuff to erase with
    call     cx ;erase it!
    pop     ds ;restore where
    pop     si ; we left off in queue
    add     si,distance_from_entry_point_to_next_item ;next item
    cmp     si,offset end_of_queue ;see if we are done
    jne     get_next_objects_screen_adr ; jmp if more to erase
;
;Draw all the active objects by AND/ORing into screen buffer
;
draw:
    mov     si,offset queue ;point to beginning of queue
;
get_next_objects_screen_adr2:

```


The Full-Service Source For Programming Software

At Lifeboat, we're committed to more than selling you the best software. We provide tech support for every program we sell. Our expert staff is ready to take your calls on our Tech Support Hotline and help you quickly solve any technical problems you may encounter. Call Lifeboat for the complete solution to your programming needs.

LANGUAGES

Lattice C 3.0 The best selling C compiler has been upgraded to give you more functions and features. Lattice C 3.0 contains 200 new library functions, better code generation, support for new data types (void, enum, unsigned char, unsigned long), support for the 80186/80286 instruction set and the ability to generate in-line 8087/80287 instructions. Lattice C is the C compiler for professional developers.

RUN/C—The C Interpreter Learn C the natural way with RUN/C. The user interface is similar to BASIC with easy, familiar commands. The new 2.0 version of RUN/C comes with a full-screen editor and other enhancements.

RUN/C Professional New RUN/C Professional "... is the overall best choice of a C interpreter." *PC Tech Journal* (5/86). All RUN/C's capabilities plus powerful features for program development. Load your favorite object libraries with RUN/C Professional. Contains a full-screen editor and source code debugging facilities.

Pro Pascal A truly standard Pascal. Produces fast, tight code with plenty of compile time options.

BetterBASIC New Version Now you can program in BASIC and use the full memory of your PC, create structured programs using functions and procedures, make your own library modules and more. Now compatible with Microsoft BASIC.

LANGUAGE UTILITIES

Plink86 Plus An overlay linkage editor for linking 8086/8088 object modules. Contains new features for memory caching, library allocation, file merging and overlay reloading.

Pfix86 Plus A symbolic and source level advanced debugger for programming professionals.

Periscope I & II The symbolic debugger that can debug anywhere within a program at anytime with a simple press of a button. Periscope's breakout button will interrupt infinite loops, gain freedom from a locked up keyboard or help you find out where that slow running program is spending all its time. Periscope I additionally features a protected memory board which shields the debugger from runaway programs.

BASTOC

A BASIC to C translator for the BASIC programmer who wants to upgrade to C.

EDITORS

Brief This programmer's editor has several outstanding features. Brief's macro language compiler allows the programmer to create new commands and assign them to any key. Brief's unique "undo" facility will even let you recover from accidentally entered commands. Create as many windows as will fit on a screen, containing the same or different portions of one or several files. Compile programs without ever having to leave Brief.

FirsTime Speed-up program development with an easy-to-use C and Pascal syntax checking editor. Detects syntax errors, undefined variables and mismatched type assignments. Use function key menus to generate statements or enter your code directly. On-line help available.

VEDIT Plus A full-screen text editor for program development and word processing. It contains powerful features including use of macros, on-line help facility, paragraph formatting, and file comparison.

EMACS Customizable editor including windowing, multi-tasking and special modes for C and Pascal.

FUNCTIONS

The Greenleaf Comm Library

A library of over 120 communication routines. Contains functions to create interrupt driven routines or perform direct I/O to multiple Comm Ports. Its strengths are in asynchronous communications, interrupt mode, modem control, XMODEM, XON/XOFF and flow control.

PforCe New A library of 400 plus functions for interrupt driven communications, background tasks, string/table parsing, data base manipulation, DOS and BIOS functions and more. Superbly written and documented software with complete source code included.

The Greenleaf Functions A mature library of over 200 functions. Version 3.0 offers all new indexed documentation, with an abundance of examples. Source code included.

Essential C Utility Library Over 300 functions, with special attention given to screen handling, windows and business graphics. Source code is included.

BASIC_C Speed-up development time with this BASIC to C library, which acts as a bridge to C providing many of the capabilities of the BASIC language.

GRAPHICS, WINDOWING and SCREEN DESIGN

GSS*CGI GRAPHICS New The GSS Computer Graphics Interface is designed for creating high performance graphics-based applications. GSS*CGI speeds up application development and provides compatibility with a wide range of peripherals. It's the only CGI implementation that provides true device-independence for both raster and vector graphics. Products in the GSS GRAPHICS line include: the GSS*CGI Graphics Development Toolkit, the GSS Kernel System; the GSS Plotting System; and the GSS*CGI Metafile Interpreter.

Essential Graphics New A brand new graphics library for C programmers with the emphasis placed on ease-of-use and portability. No royalties.

WINDOWS FOR DATA New Provides C programmers with complete control over screen display and data entry, within an easy-to-use windowing system. Features include one-step data entry, multiple data types, Lotus-style menu design, full-featured field editing, pop-up entry windows, and much more.

Panel A powerful tool for interactive screen design.

For more information on these and other products in our complete line call:

1-800-847-7078

NY: 914-332-1875

Special Introductory Offer! For a limited time only you can get the new Software Programming Tools Guide from Lifeboat **FREE** by returning this coupon. To receive your copy of this regular \$9.95 value, you must supply all of the information below. Sophisticated programmers won't want to be without this complete guide to product features and selection.

Name _____ Title _____
Company _____ Business phone _____
Address _____ Zip _____

The Full-Service Source for Programming Software

LIFEBOAT

CIRCLE NO. 144 ON READER SERVICE CARD

The names of products listed are generally the trademarks of the sources of the products.

©1986 Lifeboat Associates

INTERNATIONAL SALES OFFICES

Australia:
Fagan Microprocessor Associates
Phone: (61) 3699 9899
Canada: Scantell Systems
Phone: (416) 449 9252
England: Grey Matter, Ltd.
Phone: (44) 364 53499
Italy: Lifeboat Associates, S.p.A.
Phone: (02) 656 841
Japan: Lifeboat Japan
Phone: (03) 293 4711
Spain: Micronet, S.A.
Phone: (34) 1 457 5056
The Netherlands:
GIGA Computer Products
Phone: (31) 10 771846
West Germany:
MEMA Computer GmbH
Phone: (49) (069) 34 72 26
Omnitex
Phone: (49) (076) 23 61820

Lifeboat
55 South Broadway
Tarrytown, NY 10591


```

lodsw                ;get screen buffer offset
mov     [si+erase_screen_offset-draw_screen_offset-2],ax
                ;save what will be old position
mov     di,[si+draw_image_offset-draw_screen_offset-2]
                ;save what will be old image offset
mov     [si+erase_image_offset-draw_screen_offset-2],di
cmp     ax,0ffffh    ;see if object is active
je      skip_this_object2 ; jmp if it isn't
mov     di,ax        ;save screen buffer adr
lodsw                ;get distance to odd scan line
mov     bp,ax        ; save in BP for inline code use
lodsw                ;get distance to even scan line
mov     dx,ax        ; save in DX for inline code use
add     si,length_of_erase_parms ;skip the erase parameters
lodsw                ;get the draw inline row adr
mov     cx,ax        ; save in CX for inline use
lodsw                ;get the draw inline row adr
mov     bx,ax        ; save in BX for call to inline
lodsw                ;get draw_image offset
push    si           ;save pointer to next queue item
mov     si,ax        ;save draw image in SI
call    bx           ;draw it!
pop     si           ;restore where we left off in queue
cmp     si,offset_end_of_queue ;see if we are done
jne     get_next_objects_screen_adr2 ; jmp if more to erase
;
finish_up:
if ega
cli
mov     al,20h ;issue a non_specific EOI (End Of Interrupt)
out     20h,al ; so that interrupt controller chip will
                ; acknowledge future vertical interrupts
mov     dx,cs:[crtc_base_address] ;re-enable interrupt
mov     al,11h ; select vertical retrace end
out     dx,al ; register and clear vertical interrupt
mov     al,04h ;
inc     dx ;
out     dx,al ; then enable vertical interrupt
mov     al,14h ;
out     dx,al ;
endif
pop     es ;restore all registers
pop     ds ;
pop     di ;
pop     si ;
pop     bp ;
pop     cx ;
pop     bx ;
pop     ax ;
pop     dx ;
mov     cs:[need_to_draw_something_flag],false
                ;indicate no reason to draw again until the
                ; queue is changed
iret        ;restore flags and continue where interrupted
;
skip_this_object2:
add     si,(queue_item_length-2) ;point SI to next item
cmp     si,offset_end_of_queue ;see if we are done
jne     get_next_objects_screen_adr2 ; jmp if not
jmp short finish_up ; jmp if all finished
put_objects_on_screen endp
;
;This is inline code for finding the screen address for each line
; of the image and calling the AND-OR inline code.
;
rlabel macro xx ;this macro is used to label the inline code
rline&xx& ; entry points
endm
;
; inline code for rows
;
xx=42 ;there will be an entry point for each even
; number of lines between 2 and 40. They will
; be labeled "rline2", "rline4", ... "rline40"
rept 20 ;each repeat handles two lines
xx=xx-2 ;calculate number of lines for entry point
rlabel %xx ;put in label for entry point

```

```

call    cx ;CX holds address of inline columns code
add     di,bp ;calculate the address to start next line
call    cx ;process image for odd scan line
sub     di,dx ;calculate the address to start next line
endm ; the next line will be an even line
ret
;
;inline code for AND-ORing a line of the image into the screen
;
clabel macro xx ;this macro is used to label the inline code
cline&xx& ; entry points for number of columns to AND-OR
endm ;
;
xx=10 ;this code can handle an image up to ten words
rept 10 ; wide
clabel %xx ;put in label for entry based on number of
; words in a column
lodsw ;get mask word
and     ax,es:[di] ;mask out background
or      ax,[si] ;insert data word
inc     si ;point to next mask word
inc     si ;
stosw ;return modified word to memory
xx=xx-1 ;adjust label number
endm
ret ;this return is executed at the end of every
; line
;
;This table is used as an indirect address for jumping into
; the inline code for image moving.
;
row_inline_vector_table label word ;there is no entry point for zero
; lines. Starting at 2 eliminates
; the need to store a dummy entry
; point address
row_entry_address macro xx ;this macro is used to generate
dw rline&xx& ; the labels corresponding to the
endm ; inline code entry points
;
xx=2
rept 20
row_entry_address %xx
xx=xx+2
endm
;
;This table is used as an indirect address for jumping into
; the inline code for exclusive-ORing columns.
;
column_inline_vector_table label word ;there is no entry point for zero
; lines. Starting at 2 eliminates
; the need to store a dummy entry
; point address
column_entry_address macro xx ;this macro is used to generate
dw cline&xx& ; the labels corresponding to the
endm ; inline code entry points
;
xx=1
rept 10
column_entry_address %xx
xx=xx+1
endm
;
;This is inline code for erasing the image by restoring the screen
; memory map from the background buffer.
;
elabel macro xx ;this macro is used to label the inline code
eline&xx& ; entry points
endm
;
xx=42 ;there will be an entry point for each even
; number of lines between 2 and 40. They will
; be labeled "eline2", "eline4", ... "eline40"
rept 20
xx=xx-2 ;calculate number of lines for this entry point
elabel %xx ;put in label for entry point
mov     si,di ;erase using same offset in background buffer
mov     cx,ax ;put width of image in words in CX to prepare for
rep movsw ; repeated move string on even line
add     di,bp ;calculate address of next line DI + (2000h-width)

```



```

mov     si,di    ;erase using same offset in background buffer
mov     cx,ax    ;put width of image in bytes in CX to prepare for
rep     movsw    ; repeated move string on odd line
sub     di,dx    ;calculate address of next line DI - (1fb0h+width)
endm
ret

;
;This table is used as an indirect address for jumping into
; the inline code for erasing an image.
erase_inline_vector_table label word ;there is no entry point for zero
                                ; lines. Starting at 2 eliminates
                                ; the need to store a dummy entry
                                ; point address
entry_address macro xx          ;this macro is used to generate
                                dw  eline&xx& ; the labels corresponding to the
                                endm          ; inline code entry points
;
xx=2
rept 20
entry_address %xx
xx=xx+2
endm
cseg ends
end

```

LISTING 3: SPRITES3.ASM

```

;Byte-move graphics driver for putting rectangular images into
; the Color/Graphics Adapter's medium-resolution memory map.
;
; Inputs (DS and CS must be the same, ES must contain 0B800h):
; BX - Row at which to put the top of the image. Range is 0 to 198.
;     BX must be even: images cannot start at an odd row.
; CX - The column at which to start the image in bytes. Range is
;     0 to 79.
; SI - Points to data structure which contains the image description.
;     The first byte is the height in lines (h). The second is the
;     width of the image in bytes (w). h*w image bytes follow which
;     contain the values to be placed into the screen memory map.
;     The image bytes are ordered as h consecutive sets of w line
;     image bytes. h must be an even number; images must be an
;     even number of scan lines high.
; Outputs: None. AX,BX,CX,DX,BP,SI,DI destroyed.
;
cseg segment para public 'cseg'
assume cs:cseg,ds:cseg,es:nothing
public byte_move_form_driver
;
byte_move_form_driver proc near
mov     di,[bx*even_line_screen_offset_table] ;find the offset
                                ; of the top
                                ; line of image
add     di,cx ;ES:DI now points to byte at which to put
; the image's upper left corner
lodsb   ;get the height of the image
xor     ah,ah ;make height a word value for calculations
mov     bx,ax ;store height in BX
lodsb   ;get the width of the image in bytes
mov     bp,2000h ;calculate the amount to add after even scan
sub     bp,ax ; lines are drawn to get to the address of the
; next scan line
mov     dx,1fb0h ;calculate the amount to subtract after odd
add     dx,ax ; scan lines are drawn to get to the address
; of the next scan line
jmp     [bx+inline_height_vector_table-2] ;-2 because there is
                                ; no zero lines entry
                                ; point
;This table is used to find the offset of an even scan line in
; the memory map of the color graphics adapter in medium
; resolution mode.
;
even_line_screen_offset_table label word
x=0
rept 100 ;there are 100 even lines
dw x*50h ; each is 50h (80 decimal) long
x=x+1
endm
;
;This is inline code for moving the image into the screen memory map.
;

```

```

label macro x ;this macro is used to label the inline code
line&x&:      ; entry points
endm
;
x=42
;there will be an entry point for each even
; number of lines between 2 and 40. They will
; be labeled "line2", "line4", ... "line40"
rept 20
x=x-2
label %x ;calculate number of lines for this entry point
mov     cx,ax ;put in label for entry point
mov     cx,ax ;put width of image in bytes in CX to prepare
rep     movsb ; for repeated move string on even line
add     di,bp ;calc address of next line DI + (2000h-width)
mov     cx,ax ;put width of image in bytes in CX to prepare
rep     movsb ; for repeated move string on odd line
sub     di,dx ;calc address of next line DI - (1fb0h+width)
endm
ret
;
;This table is used as an indirect address for jumping into
; the inline code for image moving.
;
inline_height_vector_table label word ;there is no entry point for zero
                                ; lines. Starting at 2 eliminates
                                ; the need to store a dummy entry
                                ; point address
entry_address macro x          ;this macro is used to generate
                                dw  line&x& ; the labels corresponding to
                                endm          ; the inline code entry points
;
x=2
rept 20
entry_address %x
x=x+2
endm
byte_move_form_driver endp
cseg ends
end

```

We Speak Your Language At Peripheral Design

(800) 523-5206

Computer Pieces to fit Your Puzzle

After 14 years in the business we know the language. Tell us your problem and we'll give you a solution without a lot of double talk. Whether you need a complete system, want to up-grade a system or are looking for a particular piece to fit your puzzle we're a dealer you can talk to. State of the art equipment from all the leading manufacturers.

We have the right connections.

Over 40 Manufacturers Represented

Alloy Computer Products
Amdek Corporation
AST Research
Core International
D.C.A.-IRMA

IBM Corp.
NCR
Toshiba Inc.
Wyse Technology
Xerox-Diablo

Peripheral  Design

3050 Presidential Dr., Suite 110, Atlanta, Ga. 30340 (404) 457-0041

Professional Print Spooling Software

COMPUTE WHILE YOU PRINT!

PrintQ[®]

FINALLY, A REAL MAINFRAME PRINT SPOOLER FOR YOUR IBM PC OR COMPATIBLE

If you spend part of your PC time running applications. Part of it printing. And a lot of time waiting...

Imagine a program that prints up to 10,000 pages while you run applications.

PrintQ does that. And more.

It's the first really complete print spooling subsystem for your PC. And your biggest time saver ever!

HOW **PrintQ** WORKS

Run your application programs as usual, but instead of stopping after the print command, keep right on computing! **PrintQ** intercepts the documents bound for the printer, spools them to disk, then prints them according to your commands.

NOT COPY PROTECTED

For users of IBM, PC, AT, XT, PCjr and most IBM compatibles.



Dealer Inquiries Invited
Corporate Licensing Available

```

PRINTQ Version 3.00
Active Queue: HOSP
Blocks used: 64 of 3000 Max. Queue Size

Status Display
Queue Sns: READY
Printer Sns: READY

```

Job#	Job Name	Time	Time	Pr	Form	P.L.	FA	Cpy	Diap	Totl	Prid	
9	Cost Accounting	01	22	15	15	1	STD	66	N	1	Y	77
25	Rdy Radiology Transcripts	01	23	18	24	1	STD	66	N	1	Y	2
8	Rdy Infection Control Report	01	23	15	02	5	STD	66	N	1	N	69
27	Rdy Emergency Room Schedule	01	23	20	10	5	STD	66	N	20	Y	2
30	Rdy *PRINTKEY	01	23	22	08	5	STD	66	N	1	Y	1
32	Rdy *COMMAND	02	10	10	23	5	STD	66	N	1	Y	1
28	Rdy Medicare Reimbursement	01	23	21	00	5	2pt	66	N	1	Y	26
26	Rdy Laboratory Reports	01	23	20	00	5	STD	66	N	2	N	2
24	Rdy Material Management	01	23	18	23	5	2pt	66	N	1	Y	2

```

Change specs. Delete. Exit. Hold. Pause. Release
res Exit. View. Write. Queue select

F1 Help F8 Redisplay F9 Allow Printing

```

© 1985, Software Directions, Inc.

"Pop up" status display lets you monitor and control document printing at any time.

*"Using **PrintQ** could become very addicting, and users may never want to go back to ordinary printing again."*

— PC Week

FULLY GUARANTEED

Use **PrintQ**. If you're not convinced **PrintQ** saves time, increases productivity and enhances printer function, return it within 30 days for a full refund.

Order now and you'll receive the **PrintQ** disk, complete easy to understand documentation, and the Quick Start Card which will have you reaping the benefits of **PrintQ** in seconds.

Call toll-free or mail the coupon to order now.

1-800-346-7638

In New Jersey Call
201-584-8466
Same day shipping on phone orders

CIRCLE NO. 245 ON READER SERVICE CARD

SDI Software Directions, Inc. 1572 Sussex Turnpike, Randolph, NJ 07869

YES. Rush me **PrintQ** for just \$89, which includes postage and handling (Canada — add \$10; Foreign — add \$20). If I'm not convinced **PrintQ** saves time, increases productivity and enhances printer function, I'll return it within 30 days for a full refund.

Name _____
Company _____
Address _____
City _____ State _____ Zip _____
☐ Check enclosed. ☐ Visa ☐ MasterCard ☐ Am Ex.
Acct. No. _____ Exp. date _____
Signature _____ Phone # _____

NJ residents add 6% sales tax.

IBM is a registered trade mark of International Business Machines Corporation.

Save 50%
TECH
JOURNAL

**Subscribe to the only IBM PC
magazine written for systems
designers and integrators
and save 50%**

Enter my subscription to PC TECH JOURNAL for:

- ☐ One year (13 issues) for only \$26.70.
☐ Two years for only \$53.35. **SAVE 50%!**

Savings based on annual single copy price of \$53.35.

Mr./Mrs./Ms. _____
please print name in full 4S507

Company _____

Address _____

City _____

State _____ Zip _____

Add \$6. per year for postage in Canada and all other foreign countries—Cash payment U.S. currency only. Basic annual subscription price is \$34.97. Please allow up to 30 to 60 days for delivery of first issue. *Send no money—we will bill you later!*

Save 50%
TECH
JOURNAL

**Subscribe to the only IBM PC
magazine written for systems
designers and integrators
and save 50%**

Enter my subscription to PC TECH JOURNAL for:

- ☐ One year (13 issues) for only \$26.70.
☐ Two years for only \$53.35. **SAVE 50%!**

Savings based on annual single copy price of \$53.35.

Mr./Mrs./Ms. _____
please print name in full 4S507

Company _____

Address _____

City _____

State _____ Zip _____

Add \$6. per year for postage in Canada and all other foreign countries—Cash payment U.S. currency only. Basic annual subscription price is \$34.97. Please allow up to 30 to 60 days for delivery of first issue. *Send no money—we will bill you later!*



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT #66 BOULDER, COLORADO

POSTAGE WILL BE PAID BY ADDRESSEE

TECH
JOURNAL

P.O. BOX 2966
BOULDER, COLORADO 80321



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT #66 BOULDER, COLORADO

POSTAGE WILL BE PAID BY ADDRESSEE

TECH
JOURNAL

P.O. BOX 2966
BOULDER, COLORADO 80321



Sixteen-color Graphics

A little-known low-resolution mode of the IBM CGA makes graphics possible in a full 16 colors.

The Motorola 6845 CRT controller chip on the IBM Color Graphics Adapter (CGA) is, according to the IBM *Technical Reference Manual*, "highly programmable with respect to raster and character parameters. Therefore, many additional modes are possible with clever programming...." One of these modes can be used to add to the four graphics colors of the CGA, providing 16-color graphics—albeit in low resolution (80 by 100).

The resolution of this mode can be increased to 160 by 100 using a software technique that involves splitting the character block into two smaller pixel blocks. Although the character cell in this text mode is 2 pixels high and 8 pixels wide, making the definition of readable characters on the screen quite difficult, it nonetheless can be used to create striking graphics (see photo 1). The Enhanced Graphics Adapter (EGA) does not provide support this mode; however, this point is academic, because a 16-color graphics mode already is provided in the EGA.

The techniques for splitting one character block into two pixel blocks have been implemented in a series of Turbo Pascal procedures that provide the necessary tools for producing low-resolution graphics. These procedures are combined in the sample program MANDEL.PAS to allow the user to draw the Mandelbrot set, a technique featured in the August 1985 issue of *Scientific American* ("Computer Recreations," A. K. Dewdney, p. 16).

Associated with each character cell on the text screen in the low-resolution mode is an attribute byte containing the foreground and background color information. Four bits are allocated to each color; thus, 16 possibilities are available for both foreground and background. (The high bit of the background nibble typically controls blinking, leaving three bits to control color. As a result, only eight colors are possible. However, a




ILLUSTRATION • MACIEK ALBRECHT

mode register setting is available that instructs the CGA to use the fourth bit to control intensity. This yields 16 colors for background as well.)

Because foreground and background colors are independent of each other, the 2-by-8 character cell can be divided into two 2-by-4 cells if the *half-block* character 222 (■) is used to place a point on the screen. To plot the point (100,30) in light red, the text cursor is placed at (50,30) and character 222 is written with background 12 and foreground 0. The point at (101,30) can be plotted in dark blue by writing character 222 at cursor location (50,30) with foreground 1 and background 0.

IBM does not document support for this mode in the IBM *Technical Reference Manual*. Nonetheless, the BIOS can be used in this mode to position a cursor, to read the current attribute of a point, and to plot a point in a given color. Using the BIOS in a CGA driver prevents screen interference (snow) and results in shorter programs. Unfortunately, BIOS calls proved too slow for this application; thus, the program shown in listing 1 (MANDEL.PAS) writes directly to screen memory. Because of this low-level access, both MANDEL.PAS and the alternate version of the program, which is called MANDEL87.PAS (listing 2), will hang an EGA.

A complication occurs when plotting a point. While the foreground and background colors of a cell are independent, they both are contained in the same attribute byte. The user must be sure, when modifying the foreground to plot one pixel, not to change the background and affect the adjacent pixel as well. To plot a new foreground color, the user masks off the old foreground color from the appropriate attribute byte and adds the new foreground color. Changing the background color is more complicated, because the new color must be shifted to the left four bits. (See figure 1 for examples.)


The mathematical ideas upon which MANDEL.PAS is based are relatively simple. In the plane of complex numbers, the function $f(z) = z^2$ is used to describe a simple iterative process. For any given point p the sequence z_0, z_1, z_2, \dots can be generated using the following three equations:

$$\begin{aligned} z_0 &= p \\ z_1 &= f(z_0) + p \\ z_2 &= f(z_1) + p, \dots \end{aligned}$$

Beginning with $p = 1 + 2i$, for example, the result is:

$$\begin{aligned} z_0 &= 1 + 2i \\ z_1 &= (1 + 2i)^2 + (1 + 2i) = -2 + 6i \\ z_2 &= (-2 + 6i)^2 + (1 + 2i) = \\ &\quad (-31 - 22i), \dots \end{aligned}$$

WHEN YOU NEED ACCESS TO FULL MEMORY, STRUCTURE, COMPATIBILITY WITH GW- & PC-BASICA, OR WHEN YOU NEED THE POWER AND FLEXIBILITY OF C OR PASCAL...



... You need BetterBASIC.

The BetterBASIC compiler has become the standard by which other BASICs are evaluated. BetterBASIC is completely compatible with GW-BASIC and PC-BASICA when running on IBM PC's and true clones. You can load and run your existing BASIC programs in BetterBASIC. It uses standard MicroSoft syntax and gives you more than 150 additional statements such as XREF, DEFINE WINDOW, MAKE MODULE, and PROCEDURE. In benchmark comparisons, BetterBASIC is five times faster than interpreted BASIC. There is optional 8087/80287 math chip support, and an optional Runtime System to create stand-alone

EXE. files. BetterBASIC is not copy protected. Technical support is provided for all registered users.

See for yourself why Dick Aarons of *PC Magazine* said "BetterBASIC may be the best of all BASIC programming worlds" and selected BetterBASIC as "Editor's Choice" (Oct. 29, 1985).

BetterBASIC	\$199
8087/80287 Math Chip Support	\$99
Runtime System	\$250
Sample Disk with Tutorial	\$10

Ask your dealer
or call to order:

1-800-225-5800


In Canada, call 416-469-5244

**Better
BASIC™**

BetterBASIC is a registered trademark of Summit Software Technology, Inc. IBM PC, XT, AT are registered trademarks of International Business Machines Corp. Microsoft is a registered trademark of Microsoft Corp. Tandy is a registered trademark of Tandy Corp.

CIRCLE NO. 195 ON READER SERVICE CARD

Summit Software Technology, Inc.™
106 Access Rd. Norwood, MA 02062

PHOTO 1: *Mandelbrot Set Output*

A boundary area of the Mandelbrot Set is displayed in the hybrid 160-by-100 16-color mode. Each pixel represents a point on the complex plane; each pixel's color shows the point's stability under a mathematical transformation.

The sequence generated at point p can wander to infinity, its real and/or imaginary parts becoming larger and larger as it proceeds. In this example the terms of the sequence do not become infinite. Because a computer cannot generate the entire sequence for each point, the distinction between a

wandering and a nonwandering point is determined as follows: if the terms of a sequence do not exceed 2 in magnitude after a certain number of those terms has been computed (in this program, 64), the point p is in the nonwandering set. This distinction is not as arbitrary as it seems—there is a mathematical justifi-

cation. (The magnitude of the complex number $a+bi$ is the square root of a^2+b^2 . The time-consuming process of taking the square root can be avoided by determining instead if a^2+b^2 is greater than 4.)

If the point p is in the nonwandering set, it is plotted in black, and the

FIGURE 1: *Splitting Character Blocks*

bbbb ffff	Old attribute
and 1111 0000	Mask
<hr/>	
bbbb 0000	Yield after and with mask
+ 0000 nnnn	New color
<hr/>	
bbbb nnnn	New attribute
<hr/>	
bbbb ffff	Old attribute
and 0000 1111	Mask
<hr/>	
0000 ffff	Yield after and with mask
+ nnnn 0000	New color shifted to the left 4 bits
<hr/>	
nnnn ffff	New attribute

Horizontal resolution is doubled by treating each 8-bit character block as two 4-bit blocks. The four bits denoted *bbbb* control the background color (top), while the four bits labeled *ffff* control the foreground color (bottom).

CREATE SOPHISTICATED SCREENS & ACCELERATE PROGRAM DEVELOPMENT WITH...

screenplay™

FEATURING:

The Panel Definition Facility

- full screen painting in monochrome & color
- use any ASCII character for lines and borders
- quick & simple field definition
- easy allocation of cursor & control keys
- numerous, friendly help screens

The Panel Management Facility

- store panels in memory resident file
- easy copy, rename & delete
- print panel formats for documentation

The Panel Control Facility

- full control of panels at runtime
- fast & efficient screen I/O
- multiple panels on any screen
- dynamically change panel characteristics
- pop-up menus & help panels

Easy To Use... Yet Powerful & Efficient
Complete with 153 page user guide

Flexus International Corporation
P.O. Box 9119
Morristown, NJ 07960
(201) 895-4724

Screen Management System

Requires DOS 2.0 or higher & 256k memory

Screenplay Supports The Following Languages:

Please Check Box For Required Language

- | | |
|--|----------|
| <input type="checkbox"/> Turbo Pascal | \$100.00 |
| <input type="checkbox"/> IBM/Microsoft Assembler | \$100.00 |
| <input type="checkbox"/> DeSmet C | \$125.00 |
| <input type="checkbox"/> Lattice C | \$150.00 |
| <input type="checkbox"/> IBM COBOL | \$175.00 |
| <input type="checkbox"/> Microsoft COBOL | \$175.00 |
| <input type="checkbox"/> Realia COBOL | \$175.00 |

Please indicate version being used.



☐ Demo Disk & User Guide (Check Language Box)

(demo price credited when you buy Screenplay) .. \$15.00

New Jersey Residents Add 6% Sales Tax

Shipping & Handling \$5.00

Total Amount Enclosed \$

☐ Check ☐ Money Order ☐  ☐ 

_____ Exp. Date _____

Signature _____

☐ Please send more information on screenplay

Name _____ Title _____

Company _____

Address _____

City/State/Zip _____

flexus

program continues to the next point. If the terms in the sequence at p eventually exceed 2 in magnitude, then the point is plotted in a color dependent on the number of terms computed before the magnitude exceeded 2. In this case, the advantage of a possible 16 colors from which to choose is obvious.

The program MANDEL.PAS contains four constants (see the CONST sections of listings 1 and 2), which are to be set by the user. The constants $xmin$ and $ymin$ determine the lower left corner of the domain to be considered; $xrange$ and $yrange$ determine the length and height of this domain. The entire region of interest for the function $f(z) = z^2$ is contained within the square defined by $(xmin, ymin) = (-2, -1.3)$ and $(xrange, yrange) = (2.6, 2.6)$. (Outside this square the sequence immediately exceeds 2 in magnitude.)

An interesting feature of the program MANDEL.PAS is its ability to magnify any selected portion of the domain. This enables the user to view the exceedingly intricate intertwining that occurs between the wandering and the nonwandering sets for this function. Table 1 lists the coordinates of areas of interest along the border of the graph of the Mandelbrot set.

TABLE 1: Coordinate Sets

XMIN	XRANGE	YMIN	YRANGE
-1.6	0.4	0	0.22
-0.29110	0.00004	0.85828	0.00003
-0.2910783	0.0000008	0.8582886	0.0000008
-0.291077855	0.000000015	0.858289110	0.000000015
0.2908	0.0050	-0.0200	0.0075
0.2941	0.0010	-0.0167	0.0010
-0.5575	0.0052	0.6220	0.0052

The four variables $xmin$, $xrange$, $ymin$, and $yrange$ specify the location and size of windows into the graph of the Mandelbrot set. Especially interesting patterns are located at the coordinate sets listed above. The three sets of coordinates shown in the middle of the table demonstrate the zoom feature of the program.

The disadvantage of MANDEL.PAS is its execution time. Each of the 16,000 points requires 10 floating-point calculations to produce each element in its sequence and to compute the square of its magnitude. A point can require that the maximum number of sequence elements (64) be computed; thus, each point could require 640 floating-point operations. If each point requires 320 operations, the entire screen needs 5 million floating-point computations to complete. The 8087 coprocessor would be advantageous.

MANDEL87.PAS is a version of MANDEL.PAS in which Iterate(x,y) has written INLINE using 8087 code. This program requires one-twentieth of the time that is required by MANDEL.PAS to complete a typical screen. In addition, it reduces screen-draw time to two minutes on a 6-MHz PC/AT.

Richard Chandler and Gary Faulkner hold doctorates in mathematics and currently are teaching at North Carolina State University. Michael Davis is a graduate student in mathematics at that university.

"IF YOU'RE LEARNING C AND NOT USING ECO-C88, YOU'RE WORKING TOO HARD!"



Eco-C88 is a full C compiler for MSDOS machines. Everything you need is included in the low price of \$59.95, including a full-screen editor. Here's what some reviewers are saying about the Eco-C88 C Compiler:

"Eco-C performed well on all the benchmarks, generating code that was quite comparable to that of compilers 10 times as costly."

Christopher Skelly, Computer Language, Feb., 1986

"This compiler does handle syntax errors much better than average - no avalanche of spurious messages here."

William Hunt, PC Tech Journal, Jan., 1986

"Eco-C88 is a high-quality package... convenient to use..."

Dr. David Clark, Byte, Jan., 1986

"Eco-C is definitely a bargain... it includes both the compiler and an excellent Turbo-style editor... a useful compiler for advanced applications, and will serve far beyond the beginning phase."

Gary Entsminger, Micro Cornucopia, April-May, 1986

The compiler comes with a standard library of over 200 functions, cc and "mini-make" utilities, ANSI language enhancements (e.g., prototyping), expanded user's manual, plus much more, all for the low price of only \$59.95. Also ask about our support products!

If ordered with the compiler, the C library source code (excluding transcendental) is \$10.00 and the ISAM file handler (as published in the **C Programmer's Library**, Que Corp) in OBJ format is an additional \$15.00. Please add \$4.00 for shipping and handling. To order, call or write:

Ecosoft Inc.


6413 N. College Avenue
Indianapolis, IN 46220
(317) 255-6476 • 8:30-4:30

1-800-952-0472
(orders only)



Trademarks: Eco-C88, Microstat (Ecosoft), CP/M (Digital Research), MSDOS (Microsoft), PC-DOS (IBM), Z80 (Zilog), 8086, 8087, 8088 (Intel).

New Release 4.1



We've continually improved Microstat since it was introduced in 1978, and the latest release includes many new features you've wanted.

Interactive and Batch Processing	Data sets that can exceed memory
Expanded Data Management Subsystem with New Data Transforms	Multiple Regression (including Stepwise)
Reading data files created by other programs (e.g., Lotus)	Scatterplots (including best fit regression)
3 types of Analysis of Variance	Correlation Analysis
Time Series	12 Nonparametric tests
Crosstabs and Chi-Square	8 Probability Distributions
Factorials, Permutations, and Combinations	Descriptive Statistics
Hypothesis Tests	Easy Installation

Microstat's algorithms have been designed to prevent numeric overflow errors and yield unsurpassed accuracy. Microstat's price is \$375.00 including the user's manual and is available for the Z80, 8086, 8088 CPU's and CP/M80, CP/M86, MS-DOS, and PC-DOS. To order, call or write.





"When Teradyne's Financial Systems Group needed DEC terminal emulation software we chose VTERM."

Gregg Prescott,
Teradyne, Inc.

VTERM/220

Quality makes all other DEC terminal emulators obsolete

Over 35,000 VTERM users, like Teradyne's Financial Systems Group, recognize the importance of critically evaluating a DEC terminal emulator. Demanding professionals require high quality, reliable DEC terminal emulation. After painstaking evaluation, Teradyne's Gregg Prescott said, "With VTERM's speed, ease of use, hot key and host control of file transfer, we can build systems around VTERM utilizing distributed PC applications."


Coefficient's VT100 terminal emulator, introduced in 1981, was the first in the industry. Our thorough attention to detail at every stage of the design, development and testing process has won us more satisfied users than all our competition combined. Now, a new more powerful VTERM supports VT220 terminal emulation. Powerful features include:

- Plug compatible VT220 and VT100 video and keyboard emulation with customizable key mappings.
- Optional Tektronix™ 4010/4014 graphics terminal emulation.
- Powerful file transfer including the most thorough implementation of KERMIT available on the PC, plus XMODEM, and our proprietary protocol VTRANS with complete host-side software for VMS™, RSTS/E™, RSX11 M/M+™ and UNIX™.
- Host data capture and conversion to Lotus® 1-2-3®, Symphony® and dBase®.
- 132-column display via horizontal scrolling or optional video board.
- Scrollback buffer for redisplay of up to 2,000 lines (80 screens!).
- "Hot Key" toggle between host session and PC DOS.
- Programmable softkeys with script-like capabilities.
- Full support for multinational and national character sets.

Call 212-777-6707 ext. 185, to get the best there is in DEC terminal emulation and communications software.

Coefficient

The Leader in DEC Emulation Software
Coefficient Systems Corporation
611 Broadway, New York, N.Y. 10012



CIRCLE NO. 189 ON READER SERVICE CARD

Trademarks: DEC, VMS, RSTS/E, RSX11 M/M+, Digital Equipment Corp.; Tektronix, Tektronix, Inc.; Lotus, 1-2-3, Symphony, Lotus Development Corp.; dBase, Ashton-Tate, UNIX, AT&T, Bell Laboratories.

The ultimate solution
for information interchange...

The ultimate 9-track magnetic tape subsystem for the IBM-PC/XT/AT and compatibles!



Innovative Data Technology offers a variety of 1/2 inch 9-track magnetic tape subsystems for the IBM-PC/XT/AT featuring the new "LEO" PC tape controller.

"LEO" is a state-of-the-art PC tape controller that lends itself to the most sophisticated applications including real time data acquisition, multitasking and true streaming disk back-up. "LEO" comes standard with an impressive list of features that include a dedicated microprocessor, up to 64K of RAM for buffering, high speed throughput with memory mapping I/O—no DMA channel required, ASCII to EBCDIC code conversion and external cable connectors for easy installation.

Supplied on a 5 1/4" diskette is the most comprehensive set of software drivers and utilities available. Users have a choice between an installable I/O driver with modules to "Basic" and "C" languages, or an MT-DOS device driver, which allows direct tape access under any language supported by DOS 3.1. Also included is "ANSI," a sophisticated file transfer utility, "TAP" a comprehensive disk back-up and restore utility and "TCMD" tape command, a valuable tool for inspecting tape data and format. All utilities are menu driven with help screens for user friendly operation.

IDT manufactures the complete subsystem... controller and tape drive. With a commitment to excellence, IDT staffs a complete customer service department, offering you assistance to assure top performance at all times. Contact us today for additional information.



**INNOVATIVE
DATA
TECHNOLOGY**

5340 Eastgate Mall • San Diego, CA 92121
(619) 587-0555 • TWX: (910) 335-1610

Western Regional Office:

10061 Talbert Ave., Suite 202
Fountain Valley, CA 92078 • (714) 968-8082

Eastern Regional Office:

One Greentree Center, Suite 201
Marlton, NJ 08053
(609) 596-4538 • TWX: (710) 833-9888

PROGRAMMING PRACTICES

LISTING 1: MANDEL.PAS

Program Mandelbrot;

```
type
  reg      = array[0..11] of byte;
const
  xmin     = -2.0;
  xrange   = 2.6;
  ymin     = -1.3;
  yrange   = 2.6;
  crt_index_reg = $0304; ( Port # of index register of 6845 )
  crt_data_reg  = $0305; ( Port # of input register of 6845 )
  mode_select_reg = $0308; ( Port # of video mode select register )
  color_select_reg = $0309; ( Port # of video color select register )
```

```
var
  c,j,k,n    : integer;
  x,y,dx,dy  : real;
  crt_mode_set
    : byte absolute $0000:$0465; ( Used by BIOS to maintain )
  crt_palette
    : byte absolute $0000:$0466; ( values of mode & color regs )
  screen     : array[1..16384] of byte absolute $8800:$0000;
label
  quit;
```

(----- CLEARS SCREEN -----)

```
Procedure ClearScreen;
begin
  port[crt_mode_select_reg] := 0; ( Disables video to prevent snow )
  FillChar(screen,16384,0); ( Fills screen with chr 0 attribute 0 )
  port[crt_mode_select_reg] := 9; ( Enables video to see screen )
end;
```

(----- SET 6845 CRT CONTROLLER TO LO-RES MODE -----)

```
Procedure LoRes;
const
  regdata : reg = (113,80,90,10,127,6,100,112,2,1,32,0);
var
  i       : byte;
begin
  crt_mode_set := 0;
  crt_palette := 0;
  port[color_select_reg] := 0;
  for i := 0 to 11 do
  begin
    port[crt_index_reg] := i;
    port[crt_data_reg] := regdata[i];
  end;
  ClearScreen;
  crt_mode_set := 9;
end;
```

(----- SET 6845 CRT CONTROLLER TO 80x25 TEXT SCREEN -----)

```
Procedure TextScreen;
const
  regdata : reg = (113,80,90,10,31,6,25,28,2,7,6,7);
var
  i       : byte;
begin
  for i := 0 to 11 do
  begin
    port[crt_index_reg] := i;
    port[crt_data_reg] := regdata[i];
  end;
  crt_mode_set := 41;
  ClnScr;
end;
```

(----- PLOTS POINT AT (x,y) in COLOR c -----)

```
Procedure Point(x,y,c:integer);
begin
  inline($B8,$00,$02/ ( MOV AX,0200H 0200 -> AX )
```


Powerful MS-DOSTM Software.

For the IBM®-PC, XT, AT & others with generic MS-DOS/PC-DOS 2.0 or higher.

Not copy
protected!

Only **\$39⁹⁵** Each!

UTAH **COBOL**TM

Whether student, teacher or professional programmer, this is the one you've heard so much about.

- ☐ It's easy to use. Compiles 5000 statements on a 128K machine.
- ☐ 170 clear error messages, i.e. DATA-NAME IS MISSING OR MISPELLED.
- ☐ Distribute your object code programs royalty free.
- ☐ Small object code programs conserve disk space.
- ☐ Fast compile times to increase programmer productivity. Over 25 times faster than one compiler costing \$995!
- ☐ You get a diskette and 213-page manual with lots of examples and 16 complete COBOL source code programs. **\$39.95.**

Also available: COBOL Application Packages, Book 1 **\$9.95.**

UTAH **PASCAL**TM

- ☐ 14-digit precision, BCD math, no round-off errors with decimal arithmetic for business and floating point + 63 - 64 for scientific.
- ☐ A very nice TRACE style debugging.
- ☐ Arrays up to 8 dimensions and 64K strings.
- ☐ External procedures and functions with dynamic auto-loading.
- ☐ One-step compile, no assembly or link required.
- ☐ You get a 132-page manual and diskette. **\$39.95**

UTAH **PILOT**TM

- ☐ Perfect for industrial training, office training, drill and testing, virtually all programmed instruction, word puzzle games, and data entry facilitated by prompts.
- ☐ John Starkweather, Ph.D., the inventor of the PILOT language, has added a built-in full-screen text editor, and much more.
- ☐ Meets all PILOT-73 standards for full compatibility with older versions.
- ☐ You get a diskette, 125-page manual and ten useful sample programs. **\$39.95.**

Also still available for 8-bit machines with CP/M® is our world famous Nevada Software Series used by 50,000 customers in 40 countries. These include Nevada COBOL, Nevada FORTRAN, Nevada PASCAL, Nevada PILOT, Nevada BASIC and Nevada EDIT. **\$39.95 each.**

Satisfaction guaranteed. If for any reason you're not completely satisfied, just return the package within 15 days in good condition, and we'll refund your money.

IBM is a registered trademark of International Business Machines Corp. CP/M is a registered trademark of Digital Research. MS is a trademark of Microsoft Corp. © 1985 Ellis Computing, Inc.

UTAH **FORTRAN**TM

- ☐ FORTRAN IV based upon ANSI-66 standards.
- ☐ Very fast compile times and easy to use.
- ☐ IF . . THEN . . ELSE constructs.
- ☐ Chaining with blank and named common.
- ☐ Copy statement.
- ☐ ENCODE and DECODE.
- ☐ Free-format input and output.
- ☐ A very nice TRACE style debugging.
- ☐ 150 English language error messages.
- ☐ You get a diskette, and 223-page manual. **\$39.95**

UTAH **EDIT**TM

- ☐ A character-oriented full-screen video display text editor designed specifically to create COBOL, FORTRAN and PASCAL programs.
- ☐ Only requires 15K disk space so it can fit on the same disk as your compilers.
- ☐ Completely customizable tab stops, default file type, keyboard control key layout and CRT by menu selection.
- ☐ Diskette comes with easy to read 58-page manual. **\$39.95.**

UTAH **BASIC**TM

- ☐ This interpreter has a built-in full-screen editor.
- ☐ Single- and Multi-line user definable functions.
- ☐ BCD Math- no round-off errors.
- ☐ Full Matrix operations.
- ☐ You get 220-page manual and diskette. **\$39.95.**

Handling/Shipping: No shipping charge within US. Overseas add \$10 for first package, \$5 each additional. Checks must be in US Dollars, drawn on a US bank.

Utah Software requires 128K RAM and PC-DOS or MS-DOS 2.0 or higher.

HOW TO ORDER. Send check or money order to Ellis Computing, Inc. with VISA or MASTERCARD order by phone. Sorry no COD's.



Ellis Computing, Inc.
5655 Riggins Court, Suite 10
Reno, Nevada 89502
Phone (702) 827-3030

SINCE 1977



ELLIS COMPUTINGTM


```

$30/$FF/      ( XOR BH,BH      0 -> BH      )
$8A/$56/$0B/  ( MOV DL,[BP+8]  x -> DL      )
$D0/$EA/      ( SHR DL,1       x/2->DL,rem->CF )
$8A/$76/$06/  ( MOV DH,[BP+6]  y -> DH      )
$CD/$10/      ( INT 10H        locates cursor )
$B8/$00/$0B/  ( MOV AX,0B00H   0B00 -> AX   )
$CD/$10/      ( INT 10H        read attribute )
$8A/$5E/$04/  ( MOV BL,[BP+4]  c -> BL      )
$73/$05/      ( JNC +5         x even => CF=0 )
$25/$00/$F0/  ( AND AH,FOH     discard old fg )
$EB/$0B/      ( JMP +11        jmp to col asmb )
$D0/$E3/      ( SHL BL,1       x even so     )
$D0/$E3/      ( SHL BL,1       c is bg       )
$D0/$E3/      ( SHL BL,1       shift bg      )
$D0/$E3/      ( SHL BL,1       left 4 bits   )
$25/$00/$F0/  ( AND AH,OFH     discard old bg )
$00/$E3/      ( ADD BL,AH      assemble color )
$B8/$DE/$09/  ( MOV AX,09DE    chr B to AH   )
$B9/$01/$00/  ( MOV CX,01      one to write  )
$CD/$10/;     ( INT 10H        write chr, attr )

end;

(----- DETERMINE NUMBER OF ITERATIONS AT (x,y) -----)

Function Iterate(x,y:real):integer;
var
  n : integer;
  i,r,zi,zr : real;
begin
  zr := x; zi := y;          ( Initialize z      )
  n := 64;                   ( Iteration counter )
  repeat
    n := n-1;                ( Decrement counter )
    r := zr*zr - zi*zi + x;   ( Real part of next z )
    i := 2*zr*zi + y;        ( Imaginary part of next z )
    zr := r; zi := i;        ( Update z      )
  until (zr*zr + zi*zi > 4) or (n = 0);
                                ( Modulus > 4 or 64 iterations )

```

```

Iterate := n;                  ( Return 64 - # of iterations )
end;

(----- MAIN PROGRAM BEGINS -----)

begin
  LoRes;                       ( Switch to LoRes mode )
  dx := xrange/159; dy := yrange/99; ( Scale world to screen )
  y := ymin + yrange;          ( Maximum y to top of screen )
  for j := 0 to 99 do          ( 100 rows on LoRes screen )
  begin
    x := xmin;                 ( Minimum x to left of screen )
    for k := 0 to 159 do       ( 160 columns on LoRes screen )
    begin
      n := Iterate(x,y);       ( Determine number of iterations )
      c := n div 8;            ( Determine color number 0..7 )
      if n mod 8 > 3 then c := c+8; ( If remainder = 4..7 then bright )
      Point(k,j,c);           ( Plot point on screen )
      if keypressed then goto quit; ( Press any key to interrupt/quit )
      x := x + dx;             ( Update x coordinate of point )
    end;                      ( Loop until finished with row )
    y := y + dy;              ( Update y coordinate of point )
  end;                        ( Loop until finished with screen )
quit: repeat until keypressed; ( Hold picture until key pressed )
  TextScreen;                 ( Restore normal text screen )
end.

```

LISTING 2: MANDEL87.PAS

```

Program Mandelbrot87;

type
  reg = array[0..11] of byte;
const
  xmin = -2.0;
  xrange = 2.6;
  ymin = -1.3;

```

FORTRAN PROGRAMMERS

Looking for the right PC FORTRAN language system? If you're serious about your FORTRAN programming then you should be using F77L - LAHEY FORTRAN.

"Lahey's F77L FORTRAN is the compiler of choice. It's definitely a 'Programmers FORTRAN,' with features to aid both the casual and the professional programmer. . . F77L compiled the five files in a total of 12 minutes, which was 4 times as fast as MS FORTRAN and an astounding 6 times as fast as Pro FORTRAN." - PC Magazine

Compare the features and performance of other PC FORTRANs with F77L and you will find that F77L is clearly the superior product.

- Full Fortran 77 Standard (F77L is not a subset)
- Popular Extensions for easy porting of mini and mainframe applications
- COMPLEX*16, LOGICAL*1 and INTEGER*2
- Recursion - allocates local variables on the stack
- IEEE - Standard Floating Point
- Long variable names - 31 characters
- IMPLICIT NONE
- Fast Compile - Increases productivity
- Source On Line Debugger (Advanced features without recompiling)
- Arrays and Commons greater than 64K
- Clear and Precise English Diagnostics
- Compatibility with Popular 3rd Party Software (i.e. Lattice C)
- Easy to use manual
- Technical Support from LCS

F77L - THE PROGRAMMER'S FORTRAN

\$477.00 U.S.

System Requirements: MS-DOS or PC-DOS, 256K, math coprocessor (8087/80287)

FOR MORE INFORMATION: (702) 831-2500




Lahey Computer Systems, Inc.
P.O.Box 6091
Incline Village, NV 89450
U.S.A.

International Dealers:

England: Grey Matter Ltd., Tel: (0364) 53499
Denmark: Ravenholm Computing, Tel: (02) 887249
Australia: Computer Transitions, Tel: (03) 537-2786
Japan: Microsoft Software, Inc., Tel: (03) 813-8222

SERVING THE FORTRAN COMMUNITY SINCE 1967

MS-DOS & MS FORTRAN are trademarks of Microsoft Corporation. Pro FORTRAN refers to Professional FORTRAN a trademark of International Business Machines.



Editor's Choice
- PC Magazine

Now it costs even less to look good.

The Cordata Desktop Printshop™ has always been the best value in PC-compatible laser printers.

With speed and flexibility that the others can't match. Type fonts on diskette, not expensive cartridges. Data transfer up to 30 times faster than Hewlett-Packard's LaserJet+. Features implemented in software, for easy update. And Epson™ emulation, so it runs with most MS-DOS programs.


But now the Desktop Printshop is an even better value:

A menu-driven forms design software program for rapid document creation, the industry-acclaimed Wordstar 2000™ word processing program, and 38 fonts on diskette are included with the Desktop Printshop, for the amazingly low price of \$2995.

So don't settle for just any laser printer. Demand the Desktop Printshop.

All it takes is a call to Cordata at: (800) 621-6746 (in CA: (805) 495-5800; in Canada: (604) 984-0641) for the name of your nearest Desktop Printshop dealer.

After all, how can you afford *not* to look your best?




Not to mention
being easier.

The Desktop Printshop™

CORDATA, 275 E. Hillcrest Drive, Thousand Oaks, CA 91360
TELEX 650-2696270; in Europe: Holland 032-18111

~~\$3395.00~~
\$2995.00



cordata

formerly **corona**
data systems, inc.

Wordstar 2000 is a trademark of MicroPro International Corp. Epson is a trademark of Epson America, Inc.

TASKVIEW™

WHY GIVE UP...

BATCH FILES,

I/O REDIRECTION

SIDEKICK™

DOS MENU PROGRAMS,

MOST OF YOUR RAM,

EXECUTION SPEED?

Compatible, efficient DOS multi-tasking.

We designed Taskview with efficiency in mind. During normal operation, TASKVIEW hides behind DOS, providing you with control of up to 10 concurrent or non-concurrent programs. Just the touch of a key instantly switches a program to the foreground. Included desktop utilities let you cut and paste from program to program. Simple to use and reasonably priced, no well equipped PC user should be without it.

Requires: PC/AT/11 compatible, DOS 2.0-3.1, 256K RAM, 1 Floppy drive.

Taskview trademark of Sunnyside Software
Sidekick registered trademark of Borland Intl.

30-day money back guarantee

Dealer Inquiries Invited.

\$69⁹⁵ plus \$5.00 S&H

Washington residents add 7.9%
International orders add \$5.00
VISA and Mastercard accepted.

To order Toll-Free
call 1-800-367-0651

Sunnyside
Software

13732 Midvale N. Ste. 206
Seattle, WA 98133
(206) 367-0650 M-F, 8-6 PDT



CIRCLE NO. 158 ON READER SERVICE CARD

TURBO PROFESSIONAL™

SERVICE INTERRUPTS

No assembly required

RESIDENT PROGRAMS

Easy, pop-up routines

EXECUTIVE PROGRAMS

Run ANY DOS program

DISK SECTOR I/O

Lowest level access

FAST TEXT WINDOWS

Virtual windowing system

KEYBOARD MACROS

Simple, powerful

LOTS OF EXAMPLES

21+ full example programs

MUCH MORE...

Over 140 routines in all

"If you never thought Turbo Pascal was a systems programming language, you've never seen Turbo Professional."

Darryl Rubin
Computer Language

For programs that move with technology—Turbo Professional—a truly professional library of subroutines.

150 page reference manual.
Full source—many example programs.

No royalties charged for applications.

Requires IBM compatible, DOS version 2.0 or greater, Turbo Pascal 2.0 or greater.

Turbo Professional, trademark of Sunnyside Software
Turbo Pascal, registered trademark of Borland International

Dealer Inquiries Invited.

\$69⁹⁵ plus \$5.00 S&H

Washington residents add 7.9%
International orders add \$5.00
VISA and Mastercard accepted.

To order Toll-Free
call 1-800-367-0651

Sunnyside
Software

13732 Midvale N. Ste. 206
Seattle, WA 98133
(206) 367-0650 M-F, 8-6 PDT



CIRCLE NO. 152 ON READER SERVICE CARD

PROGRAMMING PRACTICES

```

yrange = 2.6;
crt_index_reg = $0304; ( Port # of Index register of 6845 )
crt_data_reg = $0305; ( Port # of Input register of 6845 )
mode_select_reg = $0308; ( Port # of video mode select register )
color_select_reg = $0309; ( Port # of video color select register )

var
  c,j,k,n : integer;
  x,y,dx,dy : real;

crt_mode_set := byte absolute $0000:$0465;
crt_palette := byte absolute $0000:$0466;
  ( Used by BIOS to maintain values of mode & color regs )

screen : array[1..16384] of byte absolute $8800:$0000;
label
quit;

(----- CLEARS SCREEN -----)

Procedure ClearScreen;
begin
  port[mode_select_reg] := 0; ( Disables video to prevent snow )
  FillChar(screen,16384,0); ( Fills screen with chr 0 attribute 0 )
  port[mode_select_reg] := 9; ( Enables video to see screen )
end;

(----- SET 6845 CRT CONTROLLER TO LO-RES MODE -----)


Procedure LoRes;
const
  regdata : reg = (113,80,90,10,127,6,100,112,2,1,32,0);
var
  i : byte;
begin
  crt_mode_set := 0;
  crt_palette := 0;
  port[color_select_reg] := 0;
  for i := 0 to 11 do
  begin
    port[crt_index_reg] := i;
    port[crt_data_reg] := regdata[i];
  end;
  ClearScreen;
  crt_mode_set := 9;
end;

(----- SET 6845 CRT CONTROLLER TO 80x25 TEXT SCREEN -----)
Procedure TextScreen;
const
  regdata : reg = (113,80,90,10,31,6,25,28,2,7,6,7);
var
  i : byte;
begin
  for i := 0 to 11 do
  begin
    port[crt_index_reg] := i;
    port[crt_data_reg] := regdata[i];
  end;
  crt_mode_set := 41;
  CtrScr;
end;

(----- PLOTS POINT AT (x,y) in COLOR c -----)

Procedure Point(x,y,c:integer);
begin
  inline($B8/$00/$02/ ( MOV AX,0200H 0200 -> AX )
    $30/$FF/ ( XOR BH,BH 0 -> BH )
    $8A/$56/$08/ ( MOV DL,[BP+8] x -> DL )
    $D0/$EA/ ( SHR DL,1 x/2->DL,rem->CF )
    $8A/$76/$06/ ( MOV DH,[BP+6] y -> DH )
    $CD/$10/ ( INT 10H locates cursor )
    $B8/$00/$08/ ( MOV AX,0800H 0800 -> AX )
    $CD/$10/ ( INT 10H read attribute )
    $8A/$5E/$04/ ( MOV BL,[BP+4] c -> BL )
    $73/$05/ ( JNC +5 x even => CF=0 )
    $25/$00/$F0/ ( AND AH,F0H discard old fg )
    $EB/$08/ ( JMP +11 jmp to col asmb )
    $D0/$E3/ ( SHL BL,1 x even so )
    $D0/$E3/ ( SHL BL,1 c is bg )
    $D0/$E3/ ( SHL BL,1 shift bg )
  
```


Why your next generation of products should use our 5th generation tools.



Arity's integrated family of programming tools allows you to combine software written in Arity/Prolog, the best of the fifth generation languages, with Arity SQL, the best of the fourth generation languages, and with conventional third generation languages such as C or assembly language to build your smarter application.

You can use Arity/Prolog to build expert systems using the Arity Expert Systems Development Package. Or to build natural language frontends. Or to build intelligent information management systems. Arity/Prolog lets you build advanced technology into your vertical applications package.

And more...

That's not the whole story. Arity's products are all designed to be fast, powerful, serious. Each of our products contains unexpected bonuses. Such as a one gigabyte virtual database integrated into Arity/Prolog. The most powerful of its kind on a PC.

Quality first. Then price.

In order to be the best, we had to prove it to our customers. Our tradition of quality software design is reflected in every product we sell. Quality first. Then price. And we always provide the best in customer support.

Our products are not copy protected. We do not charge royalties. We offer generous educational and quantity discounts. And we have a 30 day money back guarantee.

Try us to know that we keep our promise on commitment to quality and reliability. Try us by using our electronic bulletin board at 617-369-5622 or call us by telephone—you can reach us at 617-371-2422.

Or fill in this coupon. Whether you order today or not, let us send you full descriptions of our integrated family of Arity products.

CIRCLE NO. 136 ON READER SERVICE CARD

arity

We design and distribute high quality, serious application software for the IBM PC, XT, AT and all MS-DOS compatibles.

Please complete this form to place your order and/or request detailed information.

	Quantity	Info only
Arity/Prolog Compiler and Interpreter V4	\$795.00	_____
Arity/Prolog Interpreter V4	\$350.00	_____
Arity Standard Prolog	\$ 95.00	_____
Arity SQL Development Package	\$295.00	_____
Arity Expert System Development Package	\$295.00	_____
Arity Screen Design Toolkit	\$ 49.95	_____
Arity File Interchange Toolkit	\$ 49.95	_____
TOTAL AMOUNT (MA residents add 5% sales tax) (These prices include shipping to all U.S. cities)	\$	_____

NAME _____

SHIPPING ADDRESS _____

CITY/STATE/ZIP _____

TELEPHONE _____

Payment: ☐ Check ☐ PO ☐ AMEX ☐ VISA ☐ MC

Card # _____ Exp. date _____

Signature _____

ARITY CORPORATION • 358 BAKER AVENUE • CONCORD, MA 01742

arity

ProDesign II

\$299. Complete

Many CAD companies are now charging extra for features we consider necessary for a functional CAD system. For example, the price of the Basic AutoCAD System was recently lowered to \$300. However, it costs \$1700 to \$2200 more to get such features as Auto Dimensioning, Area Fill, Mirroring, Filletting, and Curve Fitting. With ProDesign II, you get the entire CAD package for one low price — \$299. Complete.

But there is another, very important reason you should get ProDesign II. ProDesign II is very unique among CAD packages. It is easy to learn and use. When we call ProDesign II "The Easy To Use CAD System", we're not joking. You will be productive with ProDesign II in an hour or two instead of a week or two.

What else does ProDesign II offer? Compatibility. Compatibility with over 100 printers. Compatibility with over 50 plotters. Compatibility with most graphics adapters, digitizing, tablets, and mice. Compatibility with most display adapters. Compatibility with any software that can produce HP plotter commands. Compatibility with mainframe CAD systems (IGES). All at no extra charge!

What additional hardware do you need? None! An IBM PC compatible and 512K RAM are all that you need. ProDesign II produces high resolution drawings on your dot matrix printer - better than .005" resolution on an IBM/Epson compatible printer. And you don't have to get a mouse or digitizing tablet. ProDesign II is designed for easy and efficient keyboard use. You won't even need a math coprocessor, although it is supported. From a small drawing on a dot matrix printer to an E-Size drawing on a large plotter, ProDesign II is the one to use!

ProDesign II — Affordable, Compatible, and Usable!


Where do you get it? See your local dealer or contact:
American Small Business Computers, Inc.
 118 South Mill Street • Pryor, OK 74361
 918/825-4844

	ProDesign II	AutoCAD
Auto Dimensioning	\$299	\$2000
Unit Specifications	299	2000
Attributes	299	2000
Area Fill	299	2000
Angle Display	299	2000
Partial Deletes	299	2000
Length Measurement	299	2000
Fillets	299	2000
Chamfers	299	2000
Mirroring	299	2000
Object Snap	299	2000
Curve Fitting	299	2500
Isometric Views	299	2000
Multiple Colors in Layer	299	N/A
Multiple Line Types in Layer	299	N/A
Single Point Move	299	N/A
High Res. Printer Support for Over 100 Printers	299	N/A
Merge Drawings	299	N/A
Single Keystroke Commands	299	N/A
HPGL Input	299	N/A
IGES Output	299	N/A
DEMO DISK	FREE	

PRODESIGN II — ONLY \$299!

F-18 HORNET

DRAWN USING PRODESIGN II



PROGRAMMING PRACTICES

```

$D0/$E3/      ( SHL BL,1      left 4 bits )
$25/$00/$0F/  ( AND AH,0FH   discard old bg )
$00/$E3/      ( ADD BL,AH    assemble color )
$B8/$DE/$09/  ( MOV AX,09DE  chr B to AH )
$B9/$01/$00/  ( MOV CX,01    one to write )
$CD/$10/;     ( INT 10H     write chr, attr )

end;

(----- DETERMINE NUMBER OF ITERATIONS AT (x,y) -----)

Function Iterate(x,y:real):integer;
var
  scratch : integer;
begin
  Inline
  $B9/$3F/$00/  ( MOV CX,3FH      # iterates -> CX )
  $9B/$D9/$E8/  ( FLD1          1 to 8087 Stack )
  $9B/$D8/$C0/  ( FADD ST(0),ST(0) 2 on Stack )
  $9B/$D8/$C0/  ( FADD ST(0),ST(0) 4 on Stack )
  $9B/$DD/$46/$0C/ ( FLD QWORD PTR [BP+12] x to Stack )
  $9B/$DD/$46/$04/ ( FLD QWORD PTR [BP+4] y to Stack )
  $9B/$D9/$C1/  ( FLD ST(1)       Copy x )
  $9B/$D9/$C1/  ( FLD ST(1)       Copy y )
  ( HERE:      Loop label )
  $9B/$D9/$C1/  ( FLD ST(1)       Copy x )
  $9B/$D8/$C8/  ( FMUL ST(0),ST(0) x*x )
  $9B/$D9/$C1/  ( FLD ST(1)       Copy y )
  $9B/$D8/$C8/  ( FMUL ST(0),ST(0) y*y )
  $9B/$DE/$E9/  ( FSUBP ST(1),ST(0) x*x - y*y )
  $9B/$D8/$C4/  ( FADD ST(0),ST(4) x*x - y*y + x )
  $9B/$D9/$CA/  ( FXCH ST(2)      new x <-> old x )
  $9B/$DE/$C9/  ( FMUL ST(1),ST(0) x*y )
  $9B/$D8/$C0/  ( FADD ST(0),ST(0) 2*x*y )
  $9B/$D8/$C2/  ( FADD ST(0),ST(2) 2*x*y + y )
  $9B/$D9/$C1/  ( FLD ST(1)       Copy x )
  $9B/$D8/$C8/  ( FMUL ST(0),ST(0) x*x )
  $9B/$D9/$C1/  ( FLD ST(1)       Copy y )
  $9B/$D8/$C8/  ( FMUL ST(0),ST(0) y*y )
  $9B/$DE/$C1/  ( FADDP ST(1),ST(0) x*x + y*y )
  $9B/$D8/$DD/  ( FCOMP ST(5)     Greater than 4? )
  $9B/$DD/$7E/$FC/ ( FSTSW [BP-4] Status to Scratch )
  $9B/          ( WAIT          8087 Done? )
  $8A/$66/$FD/  ( MOV AH,[BP-3] Status to AH )
  $9E/          ( SAHF          Status to Flags )
  $77/$02/      ( JA QUIT        x*x+y*y > 4? )
  $E2/$C3/      ( LOOP HERE     No then Loop )
  ( QUIT:      Yes )
  $B9/$4E/$14/; ( MOV [BP+20],CX Return # iterates )

end;

(----- MAIN PROGRAM BEGINS -----)

begin
  LoRes;          ( Switch to LoRes mode )
  dx := xrange/159; dy := yrange/99; ( Scale world to screen )
  y := ymin + yrange; ( Maximum y to top of screen )
  for j := 0 to 99 do ( 100 rows on LoRes screen )
  begin
    x := xmin; ( Minimum x to left of screen )
    for k := 0 to 159 do ( 160 columns on LoRes screen )
    begin
      n := Iterate(x,y); ( Determine number of iterations )
      c := n div 8; ( Determine color number 0..7 )
      if n mod 8 > 3 then c := c+8; ( If remainder = 4..7 then bright )
      Point(k,j,c); ( Plot point on screen )
      if keypressed then goto quit;
      ( Press any key to interrupt/quit )
      x := x + dx; ( Update x coordinate of point )
    end;
    y := y - dy; ( Update y coordinate of point )
  end;
  quit: repeat until keypressed; ( Hold picture until key pressed )
  TextScreen; ( Restore normal text screen )
end.

```

**More Memory
\$199.95**



The HiCard Wins!

WHY SPEND BIG \$\$\$ ON AN EXPANDED MEMORY BOARD WHEN YOU NEED ALL NEW SOFTWARE TO USE IT?

THE HiCard

- Expands DOS to 704KB
- Installs up to 896KB Total Memory
- Supports all your application software (no upgrades required)
- RAM Disks & Spoolers install above DOS
- Works with EGA, EMS, accelerators, networks & other memory expansion

ADVANCED FEATURES

- Multiple Print Spoolers — Supports up to 3 parallel printers simultaneously while you work
- Multiple RAM Disks can be installed & sized as required

DEVELOPERS TOOL

THE DOS LIMITER/EXPANDER

- Extends DOS to 704K or limits the amount of memory DOS can access to verify that your code runs in a given size.

COMPATIBLE WITH IBM PC/XT/AT & COMPATIBLES RUNNING DOS 2.0 or LATER

**BASED ON QUALITY & PERFORMANCE
THE HICARD IS UNEQUALLED!**

2 YEAR WARRANTY PARTS & LABOR

MADE IN U.S.A.

For further information see your local computer dealer or contact:




Electronics, Inc.

5721 Arapahoe Ave., Suite A
Boulder, Colorado 80303
1-800-826-8333
Wait for tone and dial 4444-000

CIRCLE NO. 141 ON READER SERVICE CARD

His mission is to streamline communications by making different brands of micros talk to each other in the same network.



He's just one of 100,000 PC systems experts who uses PC Tech Journal to fulfill his professional responsibilities as a problem-solver. His recommendation is more often than not the last word in his company's computer purchases.

When one person has this much influence, he has to know more about state-of-the-art PC technology than anyone else in his company. That's why he reads PC Tech Journal.


Glues that put him on the right path

The articles in PC Tech Journal act as a compass to direct PC systems experts through the thickening forest of PC products.

This PC expert discovers that Bruce Churchill's articles, "Low cost networking for the IBM PC," points to many of the networking products he will need. And William Colsher's tips on sharing files keep him from wandering into the valley of lost data.

Glue that help him perform his best

It's not only the feature articles that give him direction, though.




The ads, too, keep him on course. They provide him with information on what products are available, at this very moment, to help him complete his task.

Stay hot on his trail

There are other magazines that give you a larger PC/PC compatible audience of IBM users, but none that give you an audience with so much buying power.

Eight out of ten PC Tech Journal systems experts are involved in their company's computer-related purchases. (Nearly 1 in 3 are responsible for seeking out manufacturers when their companies are acquiring LANs).



Lead him to your products

Now that you know PC Tech Journal systems experts are the people responsible for deciding between your product and a competitor's, reach them before the next decision is made.

Make it your mission to influence the buyers who influence their companies. It's easy! Just call your PC Tech Journal sales representative, now, and make PC Tech Journal his guide to your products.

TECH
JOURNAL
Unmatched power in your market





Focus on the technical issues that concern *you* in PC TECH JOURNAL

Let's face it, every day brings new technical challenges with the IBM PC. And just when you think you've met them all, you'll find out that IBM has just introduced DOS 3.1—or the new networking standard is likely to be the IBM token ring.

Where can you turn for accurate and in-depth answers to the technical questions that confront you daily? PC TECH JOURNAL.

PC TECH JOURNAL focuses on the technical what-ifs and how-to's that are crucial to the growth of PC systems.

PC TECH JOURNAL will give you a clear picture of products and technical developments with detailed, objective articles on data management, applications development, communications, and programming. PLUS, you'll receive hard-nosed product evaluations

of both hardware and software.

Your subscription to PC TECH JOURNAL includes the special PC TECH JOURNAL Directory issue, a comprehensive guide to IBM/MS DOS products and index to PC TECH JOURNAL articles!

Subscribe now and save 50% on the magazine that puts technical issues into focus. PC TECH JOURNAL. One year (13 issues) only \$26.70. To subscribe, please use the attached Order Card, or call 1-800-852-5200 for fast service.

Savings based on annual single-copy price of \$53.35.

**Consult with
the Experts.**

**TECH
JOURNAL**
42387

Save 50% on PC TECH JOURNAL

And Sharpen Your Vision on Technical Issues



Every month, PC TECH JOURNAL focuses on the technical what-if's and how-to's that face you every day in your job.

Yes! Enter my subscription to PC TECH JOURNAL (which includes the special PC TECH JOURNAL Directory issue) for the term indicated.

☐ One year (13 issues) only
\$26.70. **50% OFF the annual single-copy price of \$53.35.**

☐ Two years (26 issues) only
\$53.35. **SAVE 50%!**

Name _____ 4S499

Company _____

Address _____

City _____ State _____ Zip _____

☐ Payment enclosed ☐ Bill me later

Consult with the experts in PC TECH JOURNAL.

Please allow up to 60 days for delivery of first issue. Add \$6 per year for postage outside USA, US currency only. Annual subscription price is \$34.97.

CIRCLE 353 ON READER SERVICE CARD

Macros provide a powerful programming tool when working with Lotus 1-2-3. However, Lotus's macros are difficult to write and document. QUICKCODE for 1-2-3 from Fox and Geller, Inc., designed for use with Lotus 1-2-3, makes programming macros easier.

QUICKCODE for 1-2-3 requires Lotus 1-2-3 version 2, DOS 2.0 or later, and 384KB. The program is not copy protected. After QUICKCODE for 1-2-3 has been loaded into memory, it automatically loads Lotus. When the user exits Lotus, QUICKCODE for 1-2-3 automatically removes itself from memory. The program reduces the space available for worksheets by about 126KB.

The QUICKCODE program includes three components. The most impressive is the macro language PL/123, which is similar to BASIC and dBASE languages. The other two components are a key-stroke recording capability, which allows the user to record 999 keystrokes, and a facility for developing databases and supporting macros.

up window using only very basic editing commands. The window limits programs to 300 lines. Because the code produces ASCII files, any word processor can be used.

The facility for recording and playing back keystrokes is the easiest of the QUICKCODE for 1-2-3 functions to use. This facility is a standard keyboard enhancer with the added ability to produce Lotus macros directly. Unfortunately, it is poorly designed and incompatible with SideKick. Although the manual claims that QUICKCODE can store 1,000 keystrokes, the program stops recording after 999 and displays a message stating the buffer has 1 percent of memory remaining. The program allows only one series of keystrokes to be stored in memory at a time. If the user begins to record a second series, the program erases any existing keystrokes without warning. Keystrokes stored in memory can be written to a file or to the current worksheet as a macro.

The user interface has several rough edges. A QUICKCODE prompt reminds the user that Ctrl-S can be used to end the recording of keystrokes, but the prompt disappears when

the user hits the field names. This file also can contain field length, type, default value, and error checking. The manual claims the program can create a database with as many as 204 fields; however, during testing, only 86 fields were possible. Trying to produce a database with a greater number of fields resulted in error 244, which is not mentioned in the manual.

After the specification file is created, a database generation program is run from DOS. The final step in creating a database involves running a third program from Lotus with QUICKCODE in memory. A three-field database created with QUICKCODE during testing required 16KB of memory.

A QUICKCODE database provides a data entry mode and a data viewing mode. The program permits viewing of only one record at a time. The data-entry screen does not display the command that signals the end of data entry. Further, QUICKCODE databases cannot be easily converted to stand-alone databases; the user must be familiar with QUICKCODE commands.

While testing for this review, a number of operations caused QUICK-

CODE to hang the computer. In most instances the problem was the result of incompatibility between QUICKCODE and memory-resident programs, such as SideKick or SuperKey. For example, pressing the help key (F1) more than one time and pressing Ctrl-Break to end a macro, then using the pop-up window to edit a macro program both caused the computer to hang. Trying to save an empty window and pressing more than one key at a time while editing in the window also hung the system.

Pressing Ctrl-Break to end a macro, then using the pop-up window to edit a macro program also hung the system. This problem, however, did not seem to result from QUICKCODE's incompatibility with memory-resident programs.

QUICKCODE's manual is paperback, which is difficult to keep open while working through the tutorial. The installation section of the manual has many minor errors, as do the examples in the tutorial. For example, one program divides by 10, but the text explains it is dividing by 100. Several programs use a counter, but it is not set at the beginning of the program. The resulting macro runs once because the cell used to store the counter value is empty and has a value of 0. The macro will not run

again, however, because, after the first execution, the cell contains the value used to stop the macro. The typeset manual makes it difficult to discern spaces, and in some programs (especially Lotus macros) spaces are critical. With the exception of a single explanation line below each menu choice (similar to menus in Lotus 1-2-3), QUICKCODE provides no help facilities.

The technical support from Fox and Geller, Inc. stated that QUICKCODE users can sell the macros and databases they create without making royalty payments to the company. The manual does not mention this, however.

Fox and Geller, Inc. also makes a QUICKCODE for the dBASE family of products, which is available for \$295. (For a review of the dBASE version, see "Instant Gratification: QUICKCODE," Susan Glinert-Cole, June 1984, p. 129.)

The current release of QUICKCODE for 1-2-3 seems to be a program that was rushed too quickly to market. It cannot be recommended as a keyboard macro program or as a tool for developing databases. However, PL/123 is a valuable tool for writing macros. It is much easier to use and to read than Lotus 1-2-3's native macro language.

—RONNY RICHARDSON

LET'S C

Mark Williams
1430 W. Wrightwood Avenue,
Chicago, IL 60614
312/472-6659

PRICE: \$75



CIRCLE 364 ON READER SERVICE CARD

Let's C from Mark Williams is a smaller and less expensive version of the C Programming System for the PC. However, the Let's C compiler is surprisingly similar to its more expensive counterpart. Features of the Let's C compiler can be compared to those of the C compilers that were reviewed in "The State of C" (William J. Hunt, January 1986, p. 82).

Let's C is intended for the casual or small-project user. It supports only small model programs (64KB of code and 64KB of data). Users interested in writing larger programs can upgrade to the C Programming System compiler and receive a discount equal to the original purchase price of Let's C.

The basic specifications for Let's C are presented in table 1; table 2 provides an outline of the compiler's features. With the exception of the restricted program size, Let's C can be considered a full-featured compiler—it provides full support of the C language (including register variable optimization) as well as several extensions (such as void functions, enumerated types, and structure assignments). Let's C is sufficiently compact to fit easily on a dual-floppy-disk system, and the package includes several convenient UNIX-like utilities, such as *egrep*, *pr*, and *wc*, along with the compiler, linker, and librarian. Like most C compilers in this price range, Let's C includes a small, full-screen editor (a miniature version of the EMACS editor from UNIX) for users who may not want to invest in a full programmer's editor for their system. The editor is provided in source form for customizing and study.

Brand New From Peter Norton A PROGRAMMER'S EDITOR

only
\$50

that's *lightning fast* with the *hot*
features programmers need

THE NORTON EDITOR



Direct from the
man who gave you
The Norton Utilities,
Inside the IBM PC,
and the *Peter Norton
Programmer's Guide*.

"This is the programmer's editor that I wished I'd had when I wrote my *Norton Utilities*. You can *program your way to glory* with *The Norton Editor*."

Peter Norton



*Easily customized, and saved
Split-screen editing
A wonderful condensed/outline display
Great for assembler, Pascal and C*

Peter Norton Computing, Inc., 2210 Wilshire Boulevard,
Santa Monica, CA 90403, 213-453-2361. Visa,
Mastercard and phone orders welcome.

The Norton Editor™ is a trademark of Peter Norton Computing, Inc. © 1986 Peter Norton Computing.

CIRCLE NO. 150 ON READER SERVICE CARD

GROWING OLD?

...waiting
for C programs to
compile and link?



Use **C-terp**
the **complete** C interpreter
This is the product you've been
waiting (and waiting) for!

Increase your productivity and avoid agonizing waits. Get instant feedback of your C programs for debugging and rapid prototyping. Then use your compiler for what it does best...compiling efficient code ...slowly.

C-terp Features

- Full K&R C (no compromises)
- Complete built-in reconfigurable screen editor -- Editor source available for \$98.
- Fast -- Linking and semi-compilation are breathtakingly fast.
- Convenient -- Compiling and running are only a keystroke or two away. Errors bring you back to the editor at the trouble spot.
- Object Module Support -- Access external functions and data. We support Aztec, Microsoft 3.0, Computer Innovations, Mark Williams, Lattice 2.1x and Lattice 3.0.
- NEW: External functions can call functions being interpreted.
- Complete Multiple Module Support.
- Symbolic Debugging -- Set breakpoints, single-step, and directly execute C expressions.
- NEW: Software Paging to support those BIG jobs.
- Many more features including trace, batch mode and 8087 support.

• Price: \$300.00 (Demo \$45.00) MC, VISA

Price of demo includes documentation & shipping within U.S. PA residents add 6% sales tax. Specify compiler.

- C-terp runs on the IBM PC (or compatible) under DOS 2.x with a suggested minimum of 256Kb of memory. It can use all the memory available.

GIMPEL SOFTWARE

3207 Hogarth Lane • Collegeville, PA 19426
(215) 584-4261

*Trademarks: C86 (Computer Innovations), Lattice (Lattice Inc.) IBM (IBM Corp.), C-terp (Gimpel Software), Microsoft (Microsoft), Aztec (Manx)

PRODUCT WATCH

TABLE 1: Specifications

Version tested	3.02
Supported on other systems	See text
Cross-compiler hosts	See text
Availability of libraries	Fair
Minimum disk space required	330KB
Minimum RAM	256KB
Supports full language	Yes
Full standard library	Yes
PC-specific functions	Yes
Assembly language interface	Yes
COMPATIBILITY	
MASM	—
LINK	—
SOURCE CODE	
Start-up sequence	—
Library functions	—
MEMORY MODELS	
Large	—
Medium	—
Compact	—
Small	Yes
.COM	—
OTHER PROGRAMS INCLUDED	
Librarian	Yes
Assembler	Yes
Linker	Yes
Source-level debugger	Separate
MAKE	—
Other	GREP, PR, Edit., etc.

These specifications can be compared with those for other C compilers in table 1 in "The State of C" (William J. Hunt, January 1986, p. 84).

The Let's C compiler supports the small memory model only. It is not compatible with MASM, and the UNIX-like assembler included with Let's C is not as powerful as MASM.

Documentation for Let's C consists of a single, spiral-bound manual—the same manual included with the C Programming System. The sections applicable only to the larger compiler are indicated with shaded text. Overall, the quality of the documentation is good; it explains clearly the compiler's operation and options. The section dealing with the assembler and linker, however, is weak. See table 3 for an overall rating of the compiler's documentation.

Installation of the Let's C compiler also is clearly explained in the documentation. A separate directory can be used to hold the compiler and linker, the libraries, and the #include files. Operation of the system is convenient. The package includes compilation options that allow the programmer to

Instant-C™ The Fastest Interpreter for C

**Runs your programs 50
to 500 times faster than
any other C language
interpreter.**

Any C interpreter can save you compile and link time when developing your programs. But only **Instant-C** saves your time by running your program at compiled-code speed.

Fastest Development. A program that runs in one second when compiled with an optimizing compiler runs in two or three seconds with **Instant-C**. Other interpreters will run the same program in two minutes. Or even ten minutes. Don't trade slow compiling and linking for slow testing and debugging. *Only Instant-C will let you edit, test, and debug at the fastest possible speeds.*

Fastest Testing. **Instant-C** immediately executes any C expression, statement, or function call, and display the results. Learn C, or test your programs faster than ever before.

Fastest Debugging. **Instant-C** gives you the best source-level debugger for C. Single-step by source statement, or set any number of conditional breakpoints throughout your program. Errors always show the source statements involved. Once you find the problem, test the correction in seconds.

Fastest Programming. **Instant-C** can directly generate executable files, supports full K & R standard C, comes with complete library source, and works under PC-DOS, MS-DOS, or CP/M-86. *Instant-C gives you working, well-tested programs faster than any other programming tool.* Satisfaction guaranteed, or your money back in first 31 days. **Instant-C** is \$495.

Rational Systems, Inc.

P.O. Box 480
Natick, MA 01760
(617) 653-6194

TABLE 2: Compiler Features

COMPILER OPERATION	
Single-step compile command	Yes
Compile and link	Yes
Accepts lists of files	Yes
Accepts wild cards	Yes
Lists preprocessor output	Yes
Lists assembler output	Yes
Line numbers in error messages	Yes
Header file search list	Yes
Flexible disk file layout	Yes
C LANGUAGE EXTENSIONS	
Embedded assembly language	—
Void function returns	Yes
Enumerated types	Yes
Structure assignment, etc.	Yes
Function argument checking	—
LIBRARY EXTENSIONS	
Math functions (sqrt, exp, etc.)	Yes
Unbuffered file I/O	Yes
Keyboard input (low-level)	Yes
PC screen output (cursor control, cursor attributes, scroll)	Some
Execute programs/DOS (exec/fork and system)	Yes
MS-DOS services (date, time, etc.)	Some
PC-specific functions	Some
UNIX-compatible functions	Yes
Error recovery (setjmp(), longjmp())	Yes
FILE I/O	
Redirection	Yes
Full path names	Yes
DOS 1.1 support	—
DOS 3.1 file sharing	—
Record locking	—
ASCII/binary mode	Yes
MEMORY USAGE	
Overlays	Yes
Default stack size	Yes
Stack size settable	Yes
Stack overflow checking	—
8086 FAMILY SUPPORT	
Byte/word alignment	—
80186/80286 support	—
8087/80287 support	—
Automatic sensing	—
ROM support	—

These compiler features can be compared with those for other C compilers in table 2 in "The State of C" (William J. Hunt, January 1986, p. 86).

Let's C is easy to install, and the compiler options are well documented. It is as full featured as many \$500 products.

TABLE 3: Documentation Quality

INSTALLATION	
Packing list	Yes
File inventory	Yes
Key files described	Yes
Quick step-by-step procedure	Yes
Instructions for disk configurations	Yes
List changes from last version	—
SET-UP	
Set-up assumptions described	Good
Notes on RAM/second hard disk	Poor
OPERATIONS EXPLAINED	
Compile options	Good
Compiler error messages	Good
Linking C programs	Fair
Runtime error messages	Good
Runtime options	Good
LANGUAGE/LIBRARY SPECIFICATIONS	
Deviations from Kernighan and Ritchie standard	Good
Data type representation	Good
Memory models and memory layout	Fair
DOS and PC-specific features	Fair
ASSEMBLY LANGUAGE INTERFACE	
Segment, group, and class specification	Fair
Standard prologue, epilogue	Poor
Instruction formats for args, public, extern, struct	Poor
Return value conventions	Fair
Complete examples	Poor
FILE I/O	
Redirection	Fair
Console I/O	Good
Device I/O	Good
Buffered versus unbuffered	Good
ASCII versus binary modes	Good
LIBRARY DOCUMENTATION	
Average lines per function	20
Cross-reference information	Good
Functions in table of contents	Good
Examples of use	Poor
MANUAL ORGANIZATION	
Detailed table of contents	Good
Index with functional entries	Fair
Order of function documentation	Alpha.
OVERALL RATING	
	Good

These notes on the documentation for the Let's C compiler can be compared with those for other compilers in table 3 in "The State of C" (William J. Hunt, January 1986, p. 88).

The documentation supplied with Let's C is the same as that included with the C Developer's System.

check programs rigorously for compliance with the C language as described in Kernighan and Ritchie's *C Programming Language* (Prentice-Hall, 1978). Thus, casual or infrequent C programmers are able to write clean programs with a minimum of trouble. Both the compiler and the linker are reasonably fast when used for development;

overall, the linker is slightly slower than LINK (see table 4 for benchmark times).

Let's C outputs only Mark Williams' proprietary object module format. In addition, output produced by the assembler is readable only by the UNIX-like assembler included with the package, not by MASM. This may not be a problem for users content with rewrit-

ing only a few functions in assembly language to improve program execution speed. For users working with larger projects, however, this restriction can prove a real nuisance. Mark Williams' object format is supported by some (not all) add-on library vendors, including Greenleaf and C Power Packs from Software Horizons, Inc.

TABLE 4: Benchmarks

COMPILE TIMES	
60-line file	20.9
150-line file	37.6
500-line file	60.6
LINK TIMES	
1 object file	35.8
6 object files	41.4
PROGRAM SIZES (bytes)	
Eratosthenes sieve	12,183
Pentathlon	15,480
GENERAL OPERATIONS	
Function calls (Fibonacci)	28.7
Integer arithmetic	36.9
Long arithmetic	199.8
Subscripts (character count)	28.0
Pointer use (string copy)	37.6
With register variables	31.3
Eratosthenes sieve	24.2
With register variables	18.7
FILE I/O	
Read/write	
Floppy disk to floppy disk	19.5
Hard disk to hard disk	5.0
Getc/putc	
Floppy disk to floppy disk	9.1
Hard disk to hard disk	5.3
Floating-point operations	
Add/multiply (dot product)	30.0
Exp/log	34.9
Sin/tan (trig functions)	41.4

Times are shown for the small model only.

Benchmarks were run on an Alpha Micro Workstation, the programs were run from a hard disk. This should be considered when comparing these benchmark times to those in table 4 in "The State of C" (William J. Hunt, January 1986, p. 90), which were reported for a PC/XT.

These benchmark times indicate that Let's C is simply the C Developer's System without the extra memory models and MASM compatibility.

The benchmarks shown in table 4 were run on an Alpha Micro Workstation (a PC/XT clone) equipped with 512KB of memory, a 10MB hard disk, and an STB Chauffeur video board. CONFIG.SYS was present with BUFFERS=20 and FILES=20. The results show that the .EXE files produced by the compiler are smaller than average. In addition, with the exception of the Sieve, execution times were somewhat slower than average, and the result of the long-arithmetic benchmark was much slower than average. Using register variables improves performance slightly. The feature and benchmark tables (see tables 2 and 4, respectively) indicate that Let's C is, in short, the C

Programming System without the memory models or MASM compatibility.

The performance and documentation of the \$75 Let's C compiler rival those of C compilers for the PC currently being sold for \$500. Let's C represents a professional-quality compiler at a bargain price.

In addition, the Let's C compiler, like the full C Programming System, can be used with the Mark Williams csd source debugger. While this debugger suffers from some limitations (for ex-

ample, it is unable to debug assembly language or library functions) and some irritations (especially its habit of proofing input key by key rather than when Return is pressed), it is generally considered adequate for use with small programs. Like Let's C, the debugger is priced at \$75; thus, a complete C programming system that is sufficient for use with small projects can be purchased from Mark Williams for only \$150.

Let's C goes a long way toward bringing the power of C to the average

EditCheck syntax checks C source programs from within its multi-window editor.

EditCheck is a new kind of programmer's tool that provides an integrated C Language source code programming platform. It improves your productivity, and reduces your frustration caused by making multiple cycles between a program editor and a compiler to manually locate and eliminate syntax, semantic, and other errors in your programs.

You can think of EditCheck as a powerful editing and program checking facility that works as a front-end companion to your C compiler.

EditCheck consists of an extensive C language source program checker, a window-oriented full screen editor, a file access facility, and a context-sensitive on-line help facility, all united in a consistent, integrated environment platform that extensively uses a fast windowing system.

All EditCheck commands can be executed through single-key strokes, or thru a fast pop-up menu system, or by a combination of keystrokes and menu choices. All keystroke commands can be user reassigned to any keyboard key.

INTERACTIVE INTRA & INTER-MODULE CHECKING

The heart of EditCheck's contribution is a powerful C language program checker which provides strong type checking from within the editing environment. The "lint-like" checker does a thorough evaluation of your source code and detects common errors and questionable practices, including many that most C compilers will overlook. The checker is based on "K & R" C specs plus Unix extensions and "lint" functions.

The checker runs interactively on part or all of a source program file, or group of program files. It opens a context window on the file where an error is detected and highlights the token which was being parsed when the error was detected. It also opens a message window with a descriptive error message, and presents a menu of options which you can take to correct the error.

The checker allows you to provide a program module list for complete checking or checking of unchecked modules. You can also check the modules in this list in batch mode if you desire.

Everest Solutions Inc.
3350 Scott Blvd., Bldg. 58
Santa Clara, CA 95054
(408) 986-8977

The source program checking capabilities in EditCheck will substantially increase your speed in achieving error-free C programs.

WINDOW-ORIENTED FULL SCREEN EDITOR

EditCheck's editor allows you to edit text in the current window and to copy or move text within or between windows. The editor supports both horizontal and vertical scrolling, and allows you to use marks and zones, move the cursor to specified objects, search and replace (case sensitive or insensitive), change case of the text, control input mode, etc.

The editor uses a file paging scheme which allows you to edit and check modules larger than your available RAM memory. Any ASCII file may be read by the editor. Files may be inserted or appended to the current window file.

The editor is both key-command driven and menu driven, or mixed usage. Key-commands are fully user reassignable.

WINDOWS, FILES AND MORE

The EditCheck environment is window-oriented. You may have as many windows open at the same time as you wish. Windows may overlap or be tiled, at your option. You may switch back and forth between windows, and move or copy information between them.

The windows which you open may display different files or multiple different areas of the same file. You control the location and size of all user windows, and can save the contents of a window, hide it, bury it, close it, or show it.

Windows are also extensively used by the EditCheck system to build commands, display help, show a module list, display messages, show program context while checking, etc.

Access to some of the DOS file-oriented commands is also provided from within EditCheck.

A group of environment commands are available to change the coloring of windows (with a color graphics adapter and display), set the way you are notified of errors, and redefine the meaning of keys on the keyboard.

CONTEXT SENSITIVE HELP

Help is available to you in several ways. You may use a function key to get context sensitive help particular to where you are in the system. You may select the help index, and choose a topic of interest. You may also ask the help subsystem to search for a particular word of interest within the entire system. Display of current key-bindings is also available.

SYSTEM REQUIREMENTS

EditCheck requires an IBM PC/XT/AT or compatible, with 384K RAM, 2 flexible 5.25 inch disk drives or one flexible and one hard disk. DOS 2.0 or later.

HOW TO GET EDITCHECK

You can order today by mailing the coupon, or by phoning our toll free number. Send your check with the coupon, or we can ship COD (US only) or on your purchase order. No Credit Cards at this time. Outside USA please pay in US funds.

EditCheck

Everest Solutions, Inc.
3350 Scott Boulevard, Bldg. 58
Santa Clara, CA 95054

To Order Call:
1-800-621-0854 Ext. 923

or Send Coupon:

Please rush me EditCheck with 30 day money-back guarantee, and without copy-protection.

Price \$90.00 plus applicable charges:
(Please check items below):
___ CA. resid. add Sls. Tax: \$6.30
___ Ground ship add: \$3.00
___ USA Air Ship add: \$5.00
___ Outside USA Air Ship add: \$9.00
___ COD or Purch. Ord. add: \$5.00

Amount Enclosed: _____
or: COD requested (USA only) _____
or P.O. # _____

Co. Name _____

Name _____

Street _____

City _____

State _____ Zip _____

Day Phone _____

CIRCLE NO. 161 ON READER SERVICE CARD

PROTECT YOUR COPIES OF **TECH JOURNAL**

Make your collection of PC TECH JOURNAL a handsome addition to your office or home—and protect and organize your copies for easy reference!

PC TECH JOURNAL Magazine Binders and Cases are made of durable luxury-look leatherette over quality binder board. Custom designed for PC TECH JOURNAL, every order receives FREE transfer foil to mark dates and volume numbers.

FOR FAST SERVICE CALL TOLL-FREE 1-800-972-5858

MAGAZINE BINDERS

Hold your issues on individual snap-on rods. \$8.95 each; 3 for \$25.75; 6 for \$48.75.



OPEN BACK CASES

Store your copies for individual reference. \$7.95 each; 3 for \$22.95; 6 for \$43.95.



TECH JOURNAL

P.O. Box 5120
Philadelphia, PA 19141

Please send ☐ Binders ☐ Cases Quantity _____

Payment enclosed \$_____. * Add \$1 per order for postage & handling. (Outside USA, add \$2.50 per unit ordered, US currency only.)

Charge my:

☐ Amex ☐ Visa ☐ MC (Minimum order \$10.)

Card No. _____ Exp. Date _____

Mr./Mrs./Ms. _____
please print full name

Address _____

City _____

State _____ Zip _____

*PA residents add 6% sales tax.

PRODUCT WATCH

PC programmer at an affordable price. It is not intended for users requiring a large memory model attached to an assembler with the power of MASM. However, this compiler can be highly recommended to users who require an excellent small model implementation with a quick compile-link-run cycle.

—MARTY FRANZ

GENSCREEN

Personal Computer Development Corporation
P.O. Box 8556, Warwick, RI 02888
401/333-8704

PRICE: \$69.99



CIRCLE 354 ON READER SERVICE CARD

GET THE BEST DISK MANAGEMENT SYSTEM, AND STOP PLAYING AROUND.

Hide and seek is a great game, but why play it with your computer? You've been spending too much time chasing after those remote files...mourning your mistaken erasures...trying to hide delicate work-in-progress. Get back to business. Get FILE POWER.

Go ahead, compare it to Norton Utilities and Window DOS. You'll find that FILE POWER is the most powerful and complete disk management system around!

FEATURES	Norton Utilities	Window DOS	FILE POWER
Sort	x	x	x
Encryption			x
Undelete	x		x
Buffer Extender			x
Copy Space Allocation			x
Disk Search	x		x
Path Macros		x	x
Time Display			x
Erase Prompt			x
Change Directory	x	x	x
Directory Display	x	x	x

So get down to work...more efficiently, more accurately, more powerfully...with FILE POWER. It's a great way for you and your computer to get serious.

SPECIAL INTRODUCTORY PRICE:
\$59.95 if you order before
August 31, 1986!

Bruce Newman Company
425 E. 80th St., #2A
New York, NY 10021
Or phone: 212-772-2399



Bulk orders accepted.
All packages are sent UPS.
Add \$5 for UPS blue.
New York State residents
add 8 3/4% sales tax.

CIRCLE NO. 107 ON READER SERVICE CARD

COBOL developers may find a time saver in GENSCREEN, a utility that generates screens for use in applications. Available from Personal Computer Development Corporation, the product is designed for use with programs written in Microsoft COBOL version 2.0 or later and IBM COBOL version 1.0. (According to Personal Computer Development Corporation, GENSCREEN is the only screen generator available for use with Microsoft COBOL that produces compilable source code.)

The program's objective is to reduce the time required to develop and maintain the screen section of a Microsoft COBOL program. To this end, it takes over the tedious task of generating the data statements needed to support screen input and output. GENSCREEN reads an ASCII line sequential file that contains an image of the screen, which can be created with any program editor or word processor capable of outputting a standard ASCII file. In addition to the screen's labels, the screen file also contains delimiters that are used to define the beginning and end of each input or output field.

Unlike some other screen utilities, GENSCREEN does not include a screen painter; the developer must depend on a program editor to create screen images. This can be an advantage when designing a screen because text editors are more powerful and often easier to use than screen painters. On the other hand, if the user's text editor does not support input of non-keyboard characters via the Alt key and numeric keypad, the user will not be able to include graphics characters in screen designs.

After a screen image is created, the user can choose to allow GENSCREEN to generate data names for input fields to create a second file containing a list of custom data names.

GENSCREEN presents a display that allows users to enter parameters for the names of the input and output files, for a fill character for alphanumeric fields, and for the default screen colors. This display is supported by pop-up help windows that almost eliminate the need to refer to the documentation.

GENSCREEN's strength lies in its ease of use. The documentation is short but complete. During testing, the pamphlet was read, the software installed, and a sample screen generated—all in less than 30 minutes. A menu screen with borders and icons was created in an additional 20 minutes.

The penalty for GENSCREEN's ease of use is limited features. GENSCREEN can handle the screen only as a whole—with the exception that it marks the input fields in the screen image. All fields in the GENSCREEN-generated screen section are assigned the same default attributes. As a result, the user cannot take advantage of the complete set of attributes provided by the compilers the product supports. Additional features can be added by editing the copy files produced by GENSCREEN. Any changes to the copy files must be repeated if the screen layout is regenerated.

Two points must be remembered with GENSCREEN. First, the screen image created with the text editor is limited to 80 columns and 25 lines. Second, a space must follow the terminating delimiter of each input or output field.

As a result of the second stipulation, three blank spaces always separate any two fields on the same display line; if borders are used, at least two spaces separate the fields and the screen border. Thus, GENSCREEN cannot convert screens generated in some other COBOL implementations to Microsoft COBOL. However, the product did prove to be a time saver in most cases,

even though some editing was required to produce custom screens.

GENSCREEN is also limited in its handling of screen attributes. Only the foreground and background color of the entire screen can be set within GENSCREEN. To change the color (or any other attribute) of a specific field, the user must manipulate the COBOL code produced by GENSCREEN.

GENSCREEN performed well during testing. The only problem surfaced when an editor was used that embed-

ded Tab characters in the screen image file. GENSCREEN did not process the Tab characters as five spaces. The Personal Computer Development Corporation assures this problem will be corrected.

GENSCREEN is not a screen manager and does not reduce the coding effort necessary for handling screen edits and validations. Nonetheless, the product can save time. It is best suited for programs that will remain fairly static.

—JOHN C. NOLAND




Why debug your Program in Assembly Language when you wrote it in one of these...

Without source level debugging, the programmer must spend time mentally making translations between assembly language and the C or Pascal in which the program was written. These tedious translations burn up valuable time which should be spent making critical product schedules. Lower level debugging tools are superseded by Atron's **SOFTWARE SOURCE PROBE**. This is the debugging tool used by professionals. Why? — Because it has the features they need to solve complex debugging problems.

SOFTWARE SOURCE PROBE has the same command interface as the Atron hardware assisted software debuggers — so you can fill your lab with compatible debugging tools and minimize new learning.

How To Single Step Your Source Code And Keep Critical Data In View

With **SOFTWARE SOURCE PROBE**, you can step your program by source code statements. While stepping, a window which you define can display critical high level data structures in your program. The next several source code statements are also displayed to give you a preview of what the program will do.



Software
Probe Source

How To Display Data In Meaningful Formats

Why look at program data in hex when you defined it to be another data type in your program. **SOFTWARE SOURCE PROBE** provides a formatted print statement to make the display of your variables look like something you would recognize. You can specify data symbolically, too.

Solving The Tough Bugs

When the others fail, **SOFTWARE SOURCE PROBE** keeps on debugging. When you need isolation between the debugger and the program — you get screen switching, dual monitor support, or you can run the debugger from a totally separate CRT. When you need to get out of a program lock up state — you get recovery through the optional crash recovery switch box. When you want to trace a procedure calling sequence — you get a command to unthread stack nesting. When you want conditional sequential breakpoints — you get powerful LOOP, LOOP COUNT and IF/THEN/ELSE debug commands. When you want to build complex command sequences, you get Macro commands. And when you need an affordable debugging tool — you get **SOFTWARE SOURCE PROBE — \$129** **CRASH RECOVERY SWITCH BOX — \$99**. Then when you want to optimize the performance of your program — get Atron's **SOFTWARE PERFORMANCE AND TIMING ANALYZER (also \$129)**. It gives you histograms of your executing program, counts events, and shows you all the execution times of given procedures.

So why waste more time. Call Atron and get one of our **BUGBUSTERS** today...



20665 Fourth Street • Saratoga, CA 95070 • 408/741-5900

CIRCLE NO. 249 ON READER SERVICE CARD

PC ↔ MAINFRAME VIA 9-TRACK TAPE

For Information Interchange - Backup - Archival Storage

IBM format compatible 9-track, 1/2 inch magnetic tape is the universally accepted media for mainframes and minicomputers. Catamount offers *Low Cost, Lightweight* 9-track Tape Subsystems for the IBM-PC/XT/AT computers which allow:

- Reading tapes generated on mainframes and minicomputers.
- Writing tapes to be read on mainframes and minis.
- ASCII, EBCDIC and Binary tapes accommodated.
- 800 bpi NRZI, 1600/3200 bpi PE, and 6250 bpi GCR format systems available.
- Storage capacities up to 270 MB on a single reel.


Systems come complete with comprehensive DOS command syntax oriented software and an Installable Device Driver. For OEM applications, the tape controller is available separately.




CATAMOUNT CORPORATION
2243 Agate Court
Simi Valley, CA 93065-1898
(805) 584-2233

CIRCLE NO. 111 ON READER SERVICE CARD

Our C-language book puts your IBM® PC on the map



COMPLETE C LANGUAGE PROGRAMMING FOR THE IBM® PC by Douglas A. Troy combines the two most popular computing tools on the scene today. Using syntax diagrams—literally the “road maps” of the language—this step-by-step guide will steer you all the way from theory to applications.



Little, Brown and Company
Boston, MA 02108

400 pages \$24.95
ISBN 117943

To order, call
800-343-9204

CIRCLE NO. 173 ON READER SERVICE CARD

Programming

SR. SOFTWARE ENGINEERS


ASHTON-TATE is one of the nation's most dynamic leaders in the microcomputer software industry, publishers of dBASE III Plus®, Framework II® and MultiMate®. We currently have a challenging opportunity for a few qualified Senior Software Engineers in our Product Development Centers.

Selected candidates for these key positions will be senior designers of systems software, database internals, and/or user interfaces; and have a working knowledge of “C” and MS-DOS. Experience with ASHTON-TATE products, database applications and UNIX a plus.

ASHTON-TATE offers a competitive salary and comprehensive benefits package. For immediate consideration, send your resume to: **Mr. Tony Faison, ASHTON-TATE, 20101 Hamilton, Torrance, CA 90502.** Equal Opportunity Employer.

ASHTON-TATE

CIRCLE NO. 134 ON READER SERVICE CARD



ADALAB-PC™ Adds Lab Data Acquisition To Your IBM® PC For \$655

An ideal interface for chromatography, spectrophotometry, process control, etc.


ADALAB-PC includes ① a 13-bit integrating A/D, ② a 12-bit fast A/D (up to 20 kHz, add \$275), ③ a 12-bit D/A voltage output, ④ a second 12-bit D/A (add \$55), ⑤ 32 digital I/O bits, ⑥ four 16-bit timers or counters, and ⑦ a terminator board which has a 4-channel multiplexer and convenient screw terminals (16-channel differential analog multiplexer with programmable gains from 1 to 256, add \$300).

⑧ Versatile ADAPT software and manual (free with ADALAB-PC) works with BASIC, FORTRAN or PASCAL, includes self-test and data acquisition software. Supports fast DMA sampling, extended memory storage, scrolling stripchart display.

⑩ LABTECH NOTEBOOK software \$895.

⑪ IMI is an IBM Value Added Dealer.

COMPLETE ADALAB-PC SYSTEMS at \$3595, including 256K IBM PC, 360KB disk, PC DOS 3.0, green monitor, color/graphics adapter, Epson printer with adapter & cable, ADALAB-PC, ADAPT software, plus IMI's Scientific Plotter-PC (\$95) and Curve Fitter-PC software (\$95) **FREE** with systems!



⑫ Trademark of International Business Machines Corp.

INTERACTIVE MICROWARE, INC.
P.O. Box 139, Dept. 237 Telex: 705250
State College, PA 16804 (814) 238-8294

CIRCLE NO. 209 ON READER SERVICE CARD

An Elegant Scheme

An advanced introduction to the principles of computer science, this text is also an invaluable workbook for the Scheme programmer.

Structure and Interpretation of Computer Programs

Harold Abelson and Gerald Jay Sussman with Julie Sussman (MIT Press/McGraw-Hill, Cambridge, MA 1985)
542 pages, hardcover, \$34.95



Structure and Interpretation of Computer Programs was developed from the course notes for an accelerated introductory computer science course at Massachusetts Institute of Technology (MIT). Written by Professors Harold

Abelson and Gerald Jay Sussman, it covers subjects ranging from procedural abstraction to compiler implementation, from data-directed programming to register machines—all in a style that is universally praised by students.

This book is designed for readers with a working knowledge of the programming language Scheme, a dialect of LISP developed at MIT. As a text, it is not for casual reading and is not an introduction to the language. Rather, it is a complete introduction to the fundamental principles of computer science, and in this it leaves no stone unturned.

Scheme is a lexically scoped, interpreter-based language in which procedures are treated as first class data objects, so that programs may be manipulated as data. Its expressive power and simple syntax make Scheme ideal for illustrating the fundamental concepts of computer science. All the programming exercises and examples in the text are written in Scheme.

The introductory chapter begins with a brief explanation of Scheme which should enable the reader to write simple programs. Features and variations of the language are introduced in later chapters.

Explanations of iterative and recursive computation, orders of growth, and the passing of procedures as parameters and results follow the introductory section on Scheme. The latter capability is one of Scheme's most powerful and makes a whole host of data and control abstraction mechanisms possible.

Chapter 2 explains the use and implementation of data types, using sequences, lists, trees, sets, and real, complex and rational numbers as examples. The text emphasizes simple, functional implementations of data abstractions and provides code for a symbolic differentiator, a Huffman-encoder, and a generic arithmetic package for illustration. Explanations of data-directed programming and message-passing and example programs from earlier in the chapter are rewritten using these techniques.

In chapter 3, the authors provide a fresh perspective on the eternal problem of programming side effects. They deal with issues of local state, including assignment and mutable data objects and the costs and benefits thereof.

This chapter also describes the stream, which is a programming model analogous to the electrical engineer's signal-processing model for circuits. A full implementation of streams, written in Scheme, is presented as a practical means by which to avoid the problems that are usually associated with assignment and mutable data.

The application of computer languages as an abstraction mechanism, including a discussion of elementary language implementation, is covered in chapter 4, "Metalinguistic Abstraction." The authors provide a detailed analysis of the workings of the Scheme interpreter and include code that will implement both the Scheme interpreter and a logic-based database query language. Special attention is paid to binding disciplines (for example, lexical versus dynamic scoping) and the environment model of evaluation.

Abelson and Sussman use a simple register-machine simulator to explain assembly-language programming concepts, including: memory and addressing, registers, flow of control, stack operations, subroutine calls, and tail recursion. After the simulator has been introduced and thoroughly exercised, the authors discuss compilers and their implementation. The text includes a complete compiler, written in Scheme, to convert Scheme expressions to corresponding register-matching code.

Challenging, thought-provoking exercises appear throughout the text. In many, the reader is asked to add or modify code to complete or change the behavior of sample systems. Imaginary characters Ben Bitdiddle and Alyssa P. Hacker pose problems and entertain the reader with their exploits.

All sample code in the text will run without change on Texas Instruments' PC Scheme for the TI Professional and IBM PC. *Structure and Interpretation of Computer Programs* was written with a hands-on learning environment in mind, and PC Scheme complements it well. (See Product of the Month in this issue, p. 29, for more details.)

While it is not light reading, *Structure and Interpretation of Computer Programs* is clear, concise, and frequently amusing. Its emphasis on simple, elegant solutions to problems, and the wide variety of programming tools and techniques it presents, make it a valuable reference book.

—ARTHUR GLECKLER

FREE CATALOG AVAILABLE

The U.S. Government Printing Office offers a free catalog of 1,000 of the government's best sellers. The *US Government BOOKS* catalog includes nearly 20 titles on computer science. It can be ordered by writing to: New Catalog, P.O. Box 37000, Washington, DC 20013.

—WF



New for IBM PC/XT/AT low cost mag tape subsystem

- Fast controller — 40Kbytes/second
- New MAINSTREAMER™ tape drive
- Small size, lightweight

Send for our complete drive and interface manuals so you can evaluate and compare. Only \$25 for both.

Tape systems are also available for all other RS-232-C interfaces. Call or write attn: IBEX Applications Engineer today.

IBEX

Right for the times

IBEX COMPUTER CORPORATION
20741 Marilla St., Chatsworth, CA 91311
(818) 709-8100 TWX: 910-493-2071

CIRCLE NO. 149 ON READER SERVICE CARD

OVERCOME FORTRAN | PASCAL | C LIMITATIONS WITH

\$129

NO
LICENSE
FEE

NO

LIMIT

Ver. 3.0 For:
MS FORTRAN/Pascal/C
IBM Professional
and R-M FORTRAN
SuperSoft FORTRAN

NOW SUPPORTS IBM ENHANCED GRAPHICS AND HERCULES MONOCHROME GRAPHICS

A library of over 90 Assembler routines transform FORTRAN, Pascal and C language compilers into the flexible, responsive, complete languages needed for the microcomputer environment. Hundreds of NO LIMIT owners are creating highly interactive software systems, often utilizing existing mainframe code and saving time and money in the process. Ver. 3.0 features include:

EXTENSIVE GRAPHICS (Get, Put, Paint, Color, Dot, Line, Box, Circle, Ellipse)
FULL SCREEN CONTROL (Windows, Cursor, Read/Write Screen)
STRING MANIPULATION (Match, Compare, Concatenate/Extract, Pack, Justify)
KEYBOARD CONTROL (Read Key During Execution, String Read With Edit)
FILE MANAGEMENT (Exist?, Rename, Delete)
COMMUNICATIONS (Full Interrupt Driven to 9600 Baud, Set Com Line, Send/Receive, Line/Modem Status)
INTERRUPTS DOS Execution, Program Execution
OTHER FEATURES (Command Line Read, DOS 3.1 Directories, Peek, Poke, Random Numbers, System Status, etc.)

And to complement NO LIMIT, the I/O PRO development system allows creation and editing of FORTRAN/Pascal/C callable screens. This word processor type system pays for itself several times over on your first project. \$261.

M | E | F Environmental Inc.

P.O. Box 26537 Austin, Texas 78755

(800) 562-9700 (512) 251-5543 (Texas)

©Trademark of Microsoft Inc., Supersoft Inc., IBM Corporation, Ryan-McFarland and Microsoft Inc., respectively.

CIRCLE NO. 133 ON READER SERVICE CARD



to



the dBx™ translator

- dBx produces quality C direct from dBASE II or III programs.
- Move dBASE programs to UNIX or other machines.
- Improve program speed and reliability.
- Support multi-user/network applications.
- With power guidebook of conversion hints.
- Includes full screen handler and uses your current C database manager.
- May be used to move existing programs or help dBASE programmers learn C easily.
- For MSDOS, PCDOS, UNIX, XENIX, Macintosh, AMIGA. (Uses ANSI.SYS driver on MSDOS, CURSES under UNIX)
- Priced from \$350, also available from distributors.

dBx is a trademark of **Desktop Ai**

1720 Post Road E., Westport, CT 06880 MCIMAIL • DESKTOPAI
Phone • 203-255-3400 Telex • 6502972226MCI

CIRCLE NO. 102 ON READER SERVICE CARD

Does your database program let you...

1. Add and delete fields from existing files without destroying files?
2. Increase or reduce field width without destroying files?
3. Avail the updated data to all user files in the system?
4. Use the existing data instead of re-entering it as original data?
5. Create hierarchy and network databases easily?
6. Keep a true database, not just manage files?

TrueDataBase does! (and much more.)

For further information contact:

Software That Really Works, Inc.

750 E. Colorado Blvd. Ste 4

Pasadena, Ca. 91101

(818) 798-1661

CIRCLE NO. 147 ON READER SERVICE CARD

Taxing Software

A proposed regulation in California would single out software transactions for a special tax.

Two-and-a-half years ago this column noted two approaches being taken to the taxability of the sale of software: some states were treating software encoded on disks the same as music encoded on records and therefore taxing the sale to the user (even in the case of custom programming); others viewed computer programming as a service and therefore not subject to sales tax. (See "Sales Tax and Software: Nothing is Simple," Legal Brief, Max Stul Oppenheimer, January 1984, p. 196.)

The issue is whether a program diskette is \$1.50 worth of tangible property with some very valuable intangible (and therefore nontaxable) property encoded on it, or is it a very valuable piece of tangible property (and therefore taxable at the sales price). The issue could be left to the courts to resolve under general tax statutes, or it could be resolved definitively by specific legislation purposely directed at software transactions.

Taxation is a mixture of logic, fairness, and policy. If the United States Congress wants to reduce the use of gasoline, it can force the price up by adding a tax to the sale of the product. Likewise, if California has decided to kill off its software industry for public policy reasons, it can probably do so.

California's State Board of Equalization (SBE), which is charged with collecting sales tax and therefore with interpreting the sales tax statute, has proposed what seems an illogical method of applying sales tax to software.

The pattern of California's sales tax statute, greatly simplified, is as follows: retail sales of tangible personal property are taxable; sales to a retailer for resale are not; sales by the retailer to the consumer are. On the question of how to deal with computer programs (where intangible data is encoded on tangible media) the California legislature took the middle ground, applying sales tax to "canned" programs (those




ILLUSTRATION • MACIEK ALBRECHT

intended for general or repeated use) but not to "custom computer programs," defined as programs "prepared to the special order of the customer," including "those services represented by separately stated charges for modifications to an existing program which are prepared to the special order of the customer...Modification to an existing program to meet the customer's needs is custom computer programming only to the extent of the modification."

A specific legislative finding and declaration was made that "sales and service of custom computer programs...are service transactions not subject to sales or use taxes under any existing state law. The use of any storage media in the transfer of custom computer programs is only incidental to the true object of the transaction, which is the performance of a service."

The SBE has proposed Draft Regulation #1502, an interpretation of the statute. If the sale of a disk to a user may be taxed, why not tax the sale of the master disk from the author to the publisher? (Several answers are discussed below.) Try to decipher what the SBE is doing with these regulations:

1. The transfer of title of tangible personal property including property on which...information has been recorded...is a sale subject to tax.

2. Charges for modifying consumer-furnished tangible personal property (cards, tapes, disks, etc.), including charges for recording...information on...such tangible personal property are generally subject to tax.
3. Leases of tangible personal property may be taxable under certain conditions. In the case of canned programs the tax applies to license fees.
4. The sale or lease of a prewritten program is not taxable if the program is transferred by telecommunications from the seller's place of business to the purchaser's computer.
5. The tax does not apply to sales of custom computer programs, which include a program prepared to the special order of a customer who will use the program to produce and sell or lease copies of the program.
6. The transfer of a prewritten program on storage media is not a sale for resale when the storage media, or an exact copy, will be used to produce additional copies of the program.

The fifth and sixth provisions seem inconsistent, although they can be reconciled. One interpretation might be that, while the sale of a program to a publisher is not "a sale for resale," it is exempt from sales tax because it is a "special order." The problem with this interpretation is that it makes provision

number 6 nonfunctional unless the SBE intends to draw a distinction between a software author commissioned to write a program (sales tax exempt according to provision 5) and one who writes without a commission, then attempts to sell the program (taxable according to provision 6). This seems an illogical interpretation. Nonetheless, according to the SBE's principal tax auditor, is it precisely the regulation's intention.

The proposed regulation is inadvisable for several reasons. Fairness is the

first. Under the typical sales tax statute in the United States, tax is imposed only on the sale to the end user. When property is sold from a manufacturer to a middleman for resale to the public, the sale to the middleman is tax exempt. Some countries impose a value-added tax on every sale, from the sale by the producer of raw materials to the sale to the end user. This tax applies only to the value added by each process. If \$1 worth of trees are grown and then sold, a tax is paid on \$1; when those trees

are used to produce \$10 worth of paper for sale, the applicable sales tax on the paper is based on \$9; when \$100 worth of books is printed on the paper, the sales tax is based on \$90. The total tax is the tax rate multiplied by \$100 (the end value to the consumer), but it is paid in installments. The proposal by the SBE would result in the total tax being paid on more than 100 percent of the end value to the consumer.

Why is the SBE singling out the software industry for a special tax? The California proposal treats print authors differently than software authors because the print publisher does not make an exact copy of the manuscript, but, according to the SBE, the software publisher does.


Industry opposition to the proposed regulation is gathering momentum. The Software Entrepreneur's Forum and the Software Services Association are fighting the proposal. (Both may be reached through Michael Odawa at P.O. Box 6413, San Jose, California 95150.) If the California SBE persists, and the state legislature does not step in, software authors and publishers in California will have to find ways of dealing with the new regulation. Following are some suggestions discussed in increasing order of cost (and increasing order of the probability of success).

1. Do not allow a publisher to sell an identical copy of your program. For example, supply the program as a print-out, charge a nominal sum for the print-out but a fortune for the right to transfer it to a disk. Alternatively, supply source code and have the publisher compile it—again, charge peanuts for the source code and big bucks for the compile rights. Another method is to add copy protection to the software.
2. Insist that the publisher commission your software.
3. Buy a modem. The SBE acknowledges that sales tax cannot be applied unless an exchange of a tangible medium takes place, and data transmitted by a modem are not tangible media. Why would the SBE propose such an illogical tax and at the same time provide an easy way to circumvent it? Perhaps a strong modem lobby exists in California.
4. Conduct all of your business transactions outside of California—or move to another state.



Max Stul Oppenheimer, PC, is a partner in the law firm of Venable, Baetjer & Howard, located in Baltimore, Maryland.

READY FOR COMMITMENT?



Let DaTapaSS Help You Tie the Knot!

If you're ready to unite your IBM PC's and compatibles to your host system, it's time you thought about DaTapaSS.

DaTapaSS is quick and simple. No fuss, no ceremony: Just a natural union of the features you need most. Features like unattended automatic file transfers. Automatic restart and recovery of interrupted transfers. Error-free uploading and downloading of binary or ASCII files: across public networks, dial-up phone lines, and direct-connect asynchronous lines. Full access to DOS functions. VT100 emulation. Key-selectable signon sequences. Softkeys you can program from DOS or your host system. Outstanding documentation. You can even use it to transfer files between different kinds of host systems.

Best of all, you can use DaTapaSS as is, or you can work with our staff of consultants to build it into your specialized applications.

So. If you're ready to exchange deadlock for wedlock, try DaTapaSS -- and give DTSS a ring!



DTSS Incorporated

A Subsidiary of Metropolitan Life Insurance Company
Buck Road • Box 70 • Hanover, NH • 03755 • 603/643-6600

CIRCLE NO. 103 ON READER SERVICE CARD

NEED IT FAST? WANT TO KNOW MORE? DON'T HAVE TIME TO SHOP AROUND? INTRODUCING...

If you're like most system professionals you're up-to-date about the products in the PC marketplace. You're aware of brand and model differences, are informed about connectivity and compatibility problems, and you shop for competitive prices and fast service.

You're also probably among the many PC TECH JOURNAL readers who purchase by mail. That's why we're starting THE MART—PC TECH JOURNAL'S First Class Mail-Order Section.

Starting this month, and every month hereafter, you'll find the products you're looking for advertised in THE MART—and you'll benefit from the fast service and helpful support that identifies PC TECH JOURNAL advertisers.

If you're ready for First Class service, you're ready for THE MART.

THE MART

FIRST CLASS MAIL ORDER SECTION!

AST ADVANTAGE W/128K \$365
VIDEO 7 VEGA EGA \$425
GENOA SPECTRUM \$295
FORTE PJ \$875

INTERNAL HARD DISKS FOR THE AT*

SEAGATE USED BY IBM

PRIM 40 MB \$1195
PRIM 60 MB \$1395
RODIME 20 MB \$595
RODIME 32 MB \$695
CORE 20 MB "F" \$1195
CORE 30 MB "F" \$1395
CORE 40 MB \$1795
CORE 56 MB \$2595
CORE 72 MB \$3295

SEAGATE
SEAGATE
SEAGATE

LASER
128 AN
PIA AT

Plot's enha
for softwa
compatibles to appear to a m
DEC VT-100/VT-52, a Retrog
O, a Tektronix 4010/4014 or
Tektronix 4027. Over 12,00
currently in use world-wide at
rations, educational facilities,
and independent consulting

more information call toll free

Our High Performance
Drive Subsystem

DRIVE PER
Configuration Sta

Configuration Sta

Configuration Sta

Configuration Sta

Configuration Sta

Configuration Sta

Configuration Sta

Configuration Sta

Configuration Sta

1 MB 1/2 HT. (25 MS)
e reflects quantity purchase

"HOT" NEW PRODUCT

1 MB 1/2 HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

1 MB F. HT. (25 MS)

AMERICA'S LOWEST PRICES ARE EVEN LOWER NOW!!!

IBM XT 256K/1 Dr./20 MB 2250
IBM XT 256K/1 Dr./30 MB 2299
IBM AT 512K/20 MB 3895
IBM AT 512K/30 MB 3995
Compaq Desk Pro-1 128K/1 Dr. 1699
Compaq Portable 256K/2 Dr. 1650
AST 6 PAK w/384 K Advantage 259/369
MCI MSC w/384K 175
Samsung PGS Max 12 109/169
Princeton HX 12/E 435/535
Hercules Color Card/Monochrome graphic 150/299
Hayes 1200B w/SW 349
US Robotics Courier 2400 419

SPECIALS

10 MR Hard Disk 389
Dr./MTR 479
..... 559
..... 895
..... 775
..... 379
..... 360/499
..... 539
16 for AT 575/675
ISA MC AMEX COD PO

Computers, Inc.
es for market
icago, IL locations.
ew of the high-powered
more growth and succe
S MANAGER, West Coast

Computers, Inc.
es for market
icago, IL locations.
ew of the high-powered
more growth and succe
S MANAGER, West Coast

Computers, Inc.
es for market
icago, IL locations.
ew of the high-powered
more growth and succe
S MANAGER, West Coast

Computers, Inc.
es for market
icago, IL locations.
ew of the high-powered
more growth and succe
S MANAGER, West Coast

Computers, Inc.
es for market
icago, IL locations.
ew of the high-powered
more growth and succe
S MANAGER, West Coast

Computers, Inc.
es for market
icago, IL locations.
ew of the high-powered
more growth and succe
S MANAGER, West Coast

Computers, Inc.
es for market
icago, IL locations.
ew of the high-powered
more growth and succe
S MANAGER, West Coast

Computers, Inc.
es for market
icago, IL locations.
ew of the high-powered
more growth and succe
S MANAGER, West Coast

INTRODUCING

4CaST/2™ Complete
Forecasting
System

For marketing, planning, financial
and forecasting professionals:

- Easy to use menus with on-screen help facilities
- Most often used forecasting methods
- Popular spreadsheet interfaces
- Outstanding color graphics
- Fast RAM-based program
- Thoroughly tested and numerically accurate
- Exponential smoothing
- Step-wise and robust capabilities
- Macro language for applications
- Full documentation

Only: \$350 Demo D
4CaST/2X: includes a fa
version of the Census X-
Only: \$595 Demo D

Both versions run on IBM PC AT AT

"Top Sellers Series" UNLOCK DISK "NO. 101"

\$14.95 (Plus \$4 ship/handling
Foreign orders \$9)

LOTUS 1-2-3™
(1.A, 1.A, 2.0)

"Top Seller Series"
UNLOCKS individual
best selling programs
at a special low price!

HIGH PERFORMANCE IBM-AT SPEED

the industry's recognized leader in High Performance Speed
ive performed extensive research and developed unmatched
field. Our products offer the COMPLETE solution.

XCELX™—Switch from five frequencies including the standard
12MHz. Uses reliable frequency synthesis to allow compatibility
with all IBM ATs including the TYPE 2 and Model 239

Mil-Spec Crystals—The famous Ariel crystals. Choose from
16-17-18-19-20-21-22-23-24 MHz

FAST 80286-10—Micro-processor for 20-24 MHz speeds
FAST RAM—For System Board 128K 120 & 100 NS

proteus-286

100% FASTER 100% COMPATIBLE

**TURNKEY SYSTEM
OUR PRICE \$1745**

SYSTEM INCLUDES:

- INTEL 80286 CPU, 6/8/10 MHz (12.5 MHz OPT)
- 1 WAIT STATE (0 WAIT STATE MHz OPT)
- 1024k RAM (MAINBOARD EXPANDABLE TO 4MB!)
- 5 MHz DMA BUS
- 3 SERIAL PORTS - RS 232 & RS 422
- 2 PARALLEL PORTS
- 12MB FLOPPY DRIVE
- HARD DISK/FLOPPY CONTROLLER
- 200 WATTS 110V/220V P/S
- CHOICE OF CGA COLOR GRAPHICS OR
- HERCULES COMPATIBLE GRAPHICS ADAPTR
- ON BOARD BATTERY BACKUP, CLOCK/CALENDAR
- AT KEYBOARD
- FULLY ASSEMBLED, ONE YEAR WARRANTY
- COMPLETE OPERATIONS MANUALS.
- FCC APPROVED!



proteus-turbo-xt
70% FASTER

TURNKEY SYSTEM OUR PRICE \$895

SYSTEM INCLUDES:

- INTEL 8088-2 CPU, 4.77/8MHz
- 640K RAM (MAIN BOARD EXPANDABLE TO 1024K)
- 2 SERIAL PORTS
- 1 PARALLEL PORT
- SASI INTERFACE
- 360K TEAC FLOPPY DRIVE
- FLOPPY CONTROLLER ON BOARD
- CLOCK/CAL WITH BATTERY ON BOARD
- 135W P/S 110V/220V
- MONOCHROME GRAPHICS ADAPTER
- OR CGA COLOR GRAPHICS ADAPTER
- HIGH RESOLUTION MONOCHROME
- MONITOR (OPTIONAL COLOR MONITOR)
- FULLY ASSEMBLED, ONE YEAR WARRANTY.
- COMPLETE MANUALS. FCC APPROVED

DEALERS WELCOME.
CORPORATE & EXPORT
ACCOUNTS WELCOME.

**PHONE 201-288-8629
TELEX: 510 601 0960**

**HARD DISKS
SEAGATE**

20MB INTERNAL HALF HEIGHT	\$350
30MB INTERNAL 30MS	\$670
40MB INTERNAL 30MS	\$CALL
60MB INTERNAL 30MS	\$CALL
120MB MAXTOR 18MS	\$CALL
260MB CORE 18MS	\$CALL



377 ROUTE 17, SUITE 618
HASBROUCK HEIGHTS,
NEW JERSEY 07604

PHONE:201-288-8629

TERMS: COD, VISA/MC, PREPAYMENT, L/C, OR WIRE TRANSFER.
(PRICES & TERMS SUBJECT TO CHANGE WITHOUT NOTICE)

RUNS ALL MAJOR IBM SOFTWARE INCLUDING AUTOCAD, FLIGHT SIMULATOR

MADE IN USA

IMMEDIATE DELIVERY!!

Be 3-6 times more Productive!!! Guaranteed* For \$99⁹⁵

Demo/Prototype/Application Generator

The "Assistant" helps you develop your functional specs (Generates Screen, File, Isam, Variable and Menu Control Documentation) and then allows you to "Quickly" prototype a validation model of your system. (Which can be incorporated as part of your functional specifications.) The Assistant can then generate a super-fast Turbo Pascal Program that features advanced screen input and control, a professional control menu, the database functions of (1) Add/Edit/Delete Records (2) Search Database by any Key (3) Database Recovery programs (4) Screen/Printer Report for each of the keys. Each Key can have up to 6 fields.

Our Users Report

- "Since Fall of 85, I have generated over 300 program modules with it and find it to be just what I needed. Most all of the modules represent 5000 to 8000 lines of Pascal Code." Oner Systems.
- "By being able to produce a 21 screen and menu control demo so quickly helped me obtain the contract."
- "Speeded up my screen development by 6 times" Elexor Associates.
- "Has many of the features of the Super Mini development tools costing \$10,000." Applied Micro Systems.
- "Saved months from having to recode portions of our system." Real Green Inc.
- "We developed 3 Vertical Market Applications in the 6 months we had your system." Absolute Systems.

*** RISK FREE TRIAL** Try the demo package included for 30 days.
If not pleased return for a full refund.

Receive 6 Floppy Disks and a 200+ page manual containing:

1. **Screen Painter/Editor & Generator** • Paint menu screens using keyboard • Has variable dictionary to provide constant edits • Date entry masks • Date & range checks • Field and/or global help screens • Box & line drawing • Error & message handler
2. **Help Screen Maker** - Different help screen for each field.
3. **Menu Editor & Generator** • Allows selection by 4 methods.
4. **Database Program Generator** • Produces "Easy to Read" code that can be easily modified by experienced developers.
5. **Resident Isam Module** - compatible with Turbo Toolbox, but saves 8K of codespace and 10K of dataspace.
6. **Resident Screen Capture Utility** which allows you to capture Text Screens from any running program.

& Much, Much More

**Credit Card & C.O.D. Orders Call: 1-800-821-9503
In Florida 1-800-342-0137**

**NO ROYALTIES
on Generated
Programs**

Btrieve Interface Module

Allows full record locking and Automatic file recovery for the industry's most popular LANs. Works with the industry's leader of professional databases for multi-user LANs.

Requires Btrieve by SoftCraft Inc.

- ☐ Turbo Master Assistant by Hawaiian Village Software \$99.95
- ☐ Btrieve Interface by Innovative Interfaces 99.95
- ☐ Turbo Pascal by Borland International \$69.95

**For Other Inquiries Call:
(305) 892-5686**

Add 7.50 shipping to all U.S. Cities. All foreign orders add 15.00 per product ordered

Btrieve is a trademark of SoftCraft Inc. Turbo Pascal & Turbo Database Toolbox are trademarks of Borland International.

* MICROstar—XT & AT COMPUTER SYSTEMS *

(1 WEEK DELIVERY)

MICROstar—XT

Only \$499

SYSTEM 1:

Includes:


- * 4.77-8 MHZ Turbo
- * 256 K Memory
- * Key Board
- * 360 K Floppy Drive

SYSTEM 2:

Only \$1099

Includes:

- * Turbo Mother Board
- * 256 K Memory
- * 20 MB Hard Disk
- * 360 K Floppy Drive
- * Monochrome TTL Monitor
- * Hi-Res Mono Card
- * Key Board
- * Call For Options



FREE

Fully configured and tested
for your system requirement

* One Year Limited Warranty

* Dealers and Corporate qty.
Discount available

MICROstar—AT

Only \$1399

SYSTEM 1:

Includes:

- * 512 K Memory (1 MB Optional)
- 8 MHZ -80286 CPU
- Phoenix Bios
- 1.2 MB or 360 K Floppy Drive

SYSTEM 2:

\$2099

Includes:

- * 30 MB (40 ns) Hard Disk
- * 1 MB Memory
- * Monochrome Monitor
- * Monochrome Adaptor
- * Same as System 1

* Many Options Available

IBM

IBM-XT w. 640 K, 20 MB...\$2399
IBM-AT w. 512 K, 30 MB...\$3799
IBM-PC w. 256 K, 2 Drvs...\$1299

COMPAQ

Portable 256 K, 2 Drives...\$1649
COMPAQ Port. II from...\$2699
DESKPRO W. 128 K, 1 Drv...\$1649

SPERRY

SPERRY-HT w. 256 K,
2 Drives, Monitor...\$1899
SPERRY—IT w.44 MB
1.2 MB Flp., 1 MB...\$3299

LEADING EDGE..\$ Call AT & T ...\$ Call

* Hard Disk Subsystems *

20 MB Seagate...\$429
30 MB Seagate...\$529
40 MB Complete...\$799
AT HARD DRIVES
20 MB Seagate...\$599
30 MB Seagate...\$699
44 MB Miniscribe...\$1299
60, 80, 120 MB...\$ Call

* Printer For You *

EPSON FX-286...\$549
EPSON FX- 85...\$399
LQ 800, LQ 1000, LX 80...\$ Call
TOSHIBA 321/351...\$549/\$1049
BROTHER M1509...\$429
HP LASERJET =LASER JET=...\$ Call
WE CARRY ALL OTHER
PRINTER BRANDS

* Software *

LOTUS 1-2-3...\$329
DBASE III/FW II...\$ Call

MODEMS

1200 b int. Modem...\$149
* HAYES * PROMETHEUS \$ Call
* MEMORY CARDS *
384 K MFC w. C, S, P, G, ..\$ Call
AST Six Pack 384 K...\$219

EPSON EQUITY..\$ Call

* BEST PRICES * BEST SERVICE * FAST DELIVERY

1-800-MIC-STAR

(312) 968-3323

Mon. — Fri. 9-7

Sat. 10-5

MICROstar




A MEGABYTE FOR DOS!

MicroWay is the world's leading retailer of 8087s and high performance PC upgrades. We stock a complete selection of 8087s that run from 5 to 12 MHz. All of our coprocessors are shipped with a diagnostic disk and the best warranty in the business - one year! We also offer daughterboards for socketless computers (NEC PC) and 287Turbo which increases the clock speed of the 80287 from 4 to 10 MHz. Our NUMBER SMASHER/ECM™ runs at 12 MHz with a megabyte of RAM and achieves a throughput of .1 megaflops with 87BASIC/INLINE, Intel Fortran, or Microsoft Fortran. Software reviewers consistently cite MicroWay software and 8087 expertise as the best in the industry! Our customers frequently write to thank us for recommending the correct software and hardware to meet their specific needs. They also thank us for our same-day shipping! In addition to our own products which support the 8087 and 80287, we stock the largest supply of specialized software available. For more information call us at

617-746-7341

NUMBER SMASHER/ECM™ THE FASTEST ACCELERATOR CARD AVAILABLE

gives you 12 MHz speed in two modes: 704K or one megabyte of "Extended Conventional Memory." MEGASWITCH MMU and MegaDOS software make it possible to run DOS applications with up to 1015K using PC compilers, AutoCAD and Lotus 1-2-3. Does not require EMS software. Totally compatible. Priced from **\$599** with 512K to **\$1199** for complete package. Optional 8087-12 ... **\$295**



**SPEED UP YOUR AT
OR AT COMPATIBLE
WITH 287TURBO™ 10 MHz**

Micro Way® 8087 Support

For the IBM PC, PC XT, PC AT and Compatibles.

A2D-160™ MicroWay's Data Acquisition Board performs 160,000 12 bit Analog to Digital conversions per second! Includes software drivers. The fastest 12 bit A to D board available. For the IBM PC XT and compatibles. **\$1295**

87SFL™ MicroWay's Scientific Function Library contains 170 scientific and engineering functions. Callable from most 8087 compatible compilers ... First Language **\$250**; Additional **\$100**.

MATRIXPAK™ manages a **MEGABYTE!** Written in assembly language, our runtime package accurately manipulates large matrices at very fast speeds. Includes matrix inversion and the solution of simultaneous linear equations. Callable from RM or MS Fortran, MS Assembler, or 87BASIC/INLINE. each **\$99**

87FFT™ Written in assembly language, performs Forward and Inverse FFTs on real and complex arrays which occupy up to 512 Kbytes of RAM. Also does convolutions, auto correlations, hamming, complex vector multiplication, and complex to radial conversions. Callable from most 8087 compatible compilers. **\$200**

87FFT-2™ performs two-dimensional FFTs. Ideal for image processing. Requires 87FFT **\$100**

FASTBREAK™ employs the 8087 to increase the speed of Lotus 1-2-3™ Version 1A or 1A* by up to 36:1 **\$79**

87Verify™ For users who have to be absolutely sure of their results! This background task periodically performs an 8087 accuracy and stress test. **\$49**

Microsoft Fortran V 3.31	\$209
IBM Professional Fortran	\$565
Ryan-McFarland Fortran V 2.0	\$399
NAG Fortran Library	\$300
Grafmatic for Fortran or Pascal	\$125
MultiHalo Graphics (1 language)	\$189
LABTECH NOTEBOOK	\$745
UnkelScope	\$549
INTEL ABOVE BOARD	CALL
JRAM, AST, MAYNARD	CALL

MegaPage™ The only Intel-Lotus EMS board which comes with two megabytes of coo-running, low power drain CMOS RAM installed. Includes RAM disk, print spooler, disk cache, and EMS drivers. For the IBM PC, XT & compatibles. **\$549**

MegaPage AT/ECC™ EMS card for the PC AT and compatibles includes Error Correction Circuitry. With ECC, 11 RAM chips cover 256K so the user never encounters RAM errors. With 1 megabyte CMOS **\$799**; with 3 megabytes CMOS **\$1295**. Optional serial/parallel daughterboard. **\$95**.

DFixer™ Our disk utility which thoroughly checks PC or AT hard disks for bad sectors and updates the MS DOS file allocation table accordingly. Solves the AT hard disk problem! ... **\$149**

Optimizer™ Optimizes the way your hard disk or floppy stores its files. Speeds up accesses by recombining fragmented files. **\$49**

DCache™ Our disk caching software speeds up your I/O by storing repetitively used tracks in memory. The amount of memory used can be selected in 64 Kbyte banks. **\$49**

87MACRO/DEBUG™ Contains all the pieces needed for writing 8087/80287 assembly code & MicroWay's 87DEBUG debugger. **\$199**

OBJ→ASM™ A multipass object module translator and disassembler. Produces assembly language listings which include public symbols, external symbols and labels commented with cross references. Ideal for patching object modules for which source is not available. **\$200**

87BASIC™ includes patches to the IBM BASIC or MS Quick BASIC Compiler for USER TRANS-PARENT 8087 support. Provides super fast performance for all numeric operations including trigonometrics, transcendental, addition, subtraction, multiplication, and division. each **\$150**

87BASIC/INLINE™ converts the output of the IBM BASIC Compiler into optimized 8087 inline code which executes up to seven times faster than 87BASIC. Supports separately compiled inline subroutines which are located in their own segments and can contain up to 64 Kbytes of code. This allows programs greater than 128K! Requires the IBM BASIC Compiler Version 1 and a Macro Assembler. Includes 87BASIC ... **\$200**

MICROWAY UDI runs RTOS or RMX compilers under DOS **\$300**

8087 UPGRADES

All MicroWay 8087s include a one year warranty, complete MicroWay Test Program and accurate installation instructions.

8087 5 MHz..... \$109
For the IBM PC, XT and compatibles.

8087-2 8 MHz..... \$149
For Wang, AT&T, DeskPro, NEC, Leading Edge.

80287-3 5 MHz..... \$179
For the IBM PC AT and 286 compatibles.

80287-6 6 MHz..... \$229
For 8 MHz AT compatibles.

80287-8 8 MHz..... \$295
For the 8 MHz 80286 accelerator cards.

NEC V20, V30..... \$16, \$30

64K RAM Set 150ns..... \$10

256K RAM Set 150ns..... \$29

256K RAM Set 120ns..... \$39

128K RAM Set PC AT..... \$49

287Turbo™ 10 MHz If you own an AT, Deskpro 286 or AT compatible, this is the card you need to get reasonable numeric performance. It plugs into your 80287 socket and includes a specially driven 10 MHz 80287. The card comes in three configurations. The IBM AT version includes a hardware RESET button **\$450**

287Turbo 8 MHz..... \$369

87/88Turbo™ is a stubby card which includes a clock calendar and a speed controller which changes the speed of your motherboard from 4.77 to 7.4 MHz. Its use requires your PC to have a socketed 8284. Typical speed increase is 1.6 to 2.0. The card overcomes slow hardware by slowing up only when such devices are accessed and running at full speed otherwise **\$149**
Optional 8087-2 **\$149**

286TurboCache™ This new MicroWay accelerator uses 8K of cache memory and 80286/80287 processors to provide an average speed increase of 3:1 for most programs. Call for specifications and benchmarks **\$595**

Call for our complete catalog of software which supports the 8087.
In London, please phone 223-7762

**Micro
Way**

P.O. Box 79
Kingston, Mass.
02364 USA
(617) 746-7341

PC BRAND: CAREFULLY CHOSEN PROGRAMMER TOOLS

BRIEF Is Anything But. A Whopper of an Editor

With a name that belies its thoroughness, Brief™ has every feature you've ever contemplated for your editor-in-chief. Text, from keyboard or files, is housed in multiple buffers, and scrolled through one or more windows you open, close, resize. A text buffer may be called to different windows to view two areas at once. A change in one changes both. Text blocks may be marked for printing, writing to files, movement to scrap buffers for cut and paste into other buffers, or deletion, with as many "undo" levels as you want.

Brief has text search abilities rivaling "grep", with wildcards for matching, indifference to intervening characters, acceptance of character ranges.

If you use Lattice, C86™, or Wizard, and have 320k, you can compile your C program without ever leaving Brief. It finds the lines with errors, and marches you through the text for repairs.

Parts of Brief were written with its own Lisp-like macro language which has structure, 32-character variable names, conditional execution, loops, and you can actually read it! Nothing like the hieroglyphs we've seen elsewhere. Bulletin board and public domain disks with macros. "Simply the best text editor you can buy". Dvorak Infoworld. (Needs 192k.)

Ask for: List: PC Brand:
U0590 \$195 Call

HALO GRAPHICS SYSTEM Multi-Board Graphics Library

The premier graphics library that got the ball rolling for PC-based graphics and has grown so omnipotent that it supports over 25 graphics boards — including IBM's EGA and Nr. 9 Revolution's hi-res series — and has a multitude of mouse and printer drivers. All that in each box. Separate C versions for Lattice, M'soft, Aztec, C186. What does Multi-Halo do? A zoom to the last pixel! graphics library plus functions to reset drivers so distributed program can run on anything. Wonderful value for single license. Costly royalties though for redistribution. Specify: S0315 & Language. List: \$300. We: \$219. With Dr. Halo II, a free-standing "paint": List: \$440, Us: \$299.

dBC Lattice Library Maintains dBASE Compatible Files With the Power and Speed of C

dBC™ links C to dBASE. It creates and maintains files and their indexes which exactly replicate dBASE file design. So dBASE can read and update them. And the reverse, dBC can use any files created by dBASE. Now C and dBASE can operate on the same data bases interchangeably.

That opens up the widespread culture of dBASE installations to exploitation by C programmers. Tap that market, avoid the resident dBASE language, and gain the advantages of C with this single product.

dBC's functions parallel all dBASE's file handling commands, many decomposed to give closer control. Each backed by demo source files on disk.

WINDOWS for C/WINDOWS for DATA™ Microsoft Windows™ and TopView™ Compatible

Windows for C™ is a library of over 80 functions to add the pizzazz and practicality of window partitioning to your application. Unlimited windows, each defined in a C structure for easy reference throughout your program, can be made either to pop up or permanently overwrite the screen. Routines will scroll and highlight lists with arrow keys, will read and scroll ASCII files vertically and horizontally in windows, and even write to memory-loaded files off the screen.

Logical treatment of video attributes permits unchanged programs to run on color or monochrome. Colors of windows are set individually.

All functions are in separate modules; only those used are linked. Only buffers holding on-screen or temporarily obscured windows occupy RAM; others released dynamically. Best overall rating and fastest display in Bill Hunt's 7/85 Tech Journal review of five windowing products.

Windows for Data comprises all of Windows for C but takes in data through the windows as well. At the high level a single function lets you specify prompt string, field length, data type, screen location, picture, target variable, then sets lesser functions scurrying to get and process a user's input. There are utilities to get system date and time, mess with strings, create your own masks for fields.

Field options can require entry, prevent entry, permit insert or overwrite, beep on invalid or overflow keystrokes, and attachment of field-specific help messages

and functions you want called to display messages or validate entries. And you decide which keys will clear a field, jump to the next or prior, quit, etc. Options diverse enough that a set of "fields" can be made to behave like a Lotus™ menu.

Specify Compiler: List: PC Brand:
T0100 Windows for C \$195 \$149
T0150 Windows for Data \$295 \$250

C-WORTHY LIBRARY Fits Out Applications with Shipshape Interface

Not of the usual flotilla of functions for small crafting, but a formidable battle wagon for major C engagements.

C-Worthy™ wraps an entire user interface around your application. Its full power can be summoned by only a few high level calls. Proof? A single function call sets up a complete text editor in a screen window!

- High level calls pop menus and scrollable lists to the screen, restoring the background when dismissed, and branching to the chosen activity in your application.
- Windowing facilities open portholes of up to screen size for viewing virtual screens larger than the physical screen.
- Full on-screen context-sensitive help management. Keyboard entry routines look for the help key and interrupt with paged text windows explaining what to do.
- Full error message interface sends error codes to C-Worthy which discusses pro-

30-DAY MONEY-BACK GUARANTEE

We refund the purchase price of any product returned within 30 days in entirely resalable condition. You can even try out programs themselves if product code begins with E, T, or L through N — even if it means breaking the disk seal. Some developers do pose limits, so for product beginning with other letters, opening sealed disks constitutes acceptance. But you can at least review the manual. There's just nothing stopping your buying from PC Brand.

FREE DEMO!

blem with user. Gone is all that error-checking clutter from your core program.

Your application is nested in this powerful environment. C-Worthy's architecture uses C's pointers to functions to drive your application.

C-Worthy includes utilities to maintain text files of help and error messages. Their segregation means applications can readily be translated into foreign languages without program rewriting. Plus display routines resize for text length.

Decomposed low level functions used by the high-level calls are supplied. All machine dependency is housed in interchangeable overlays loaded at run-time. Thus no recompilation needed to run on a mix of PC and MS-DOS machines.

C-Worthy hands you a consistent and intuitive interface and a revolutionary design approach. Novell found it "played a key role and accelerated development" making NetWare™ easier to use. "You owe it to yourselves to take a look."

Specify Compiler: List: PC Brand:
T0500 \$295 \$269
T0550 Network License \$495 \$449

CURSES Unix Style Screen Management

Curses from Lattice™ manages the screen of the PC like Unix™ curses. Library of 84 functions and macros parallels Unix with matching parameter lists. So Unix programs are at home on the PC, and vice versa. Keeps any number of screens in memory, supports color, vast function set to get characters, wrap lines, scroll, blank lines, highlight, etc. Like Unix refreshes screen only on your command. Ask for: L0850, List: \$125. Here: \$99. With Source: L0860, \$250/\$199

C-TREE

B-Tree File Manager, Source Code, No Royalties!

C-tree is sturdy code that has weathered many seasons of prolonged and widespread use. It comes in C source, so you can modify it to fit a special case. No royalties provided you bind it into your binary application.

C-tree's design splits nodes to allow any number of users to access an index file simultaneously even when updates are in progress. So multi-user configurations and adaptation to networks are possible. Record-locking routines are provided for

DOS 3.1/3.2, UNIX and XENIX.

Thanks to source code which does not deviate from the K&R standard, C-tree can travel. Tests in many environments prove that C-tree gives your application a ticket to anywhere.

C-tree permits any number of keys for a data file, supports duplicate keys, alphanumeric or numeric, supports files of variable record length; multiple keys in one index file, and keys of variable length. Both high level ISAM routines which handle details with minimum coding, and decomposed step-by-step functions you can access directly. It's comprehensive.

Ask for: List: PC Brand:
F0660 \$395 \$329

PANEL Feature-Laden Screen Design Tool

Writing your own screenware can blow completion dates and profits. Panel™ works with you interactively to set up foolproof screen displays and data entry forms rapidly. Output is C source code.

Not just single plane: layer your screen designs with up to ten overlapping images: Background pop-up lists, help boxes, and alternate input fields.

Panel builds in a user interface for keystroke movement within and between fields, supplies validation routines for

checking user field entries. Diverse attributes may be selected for any field — size, data type, color, conversion of input to upper case; clearance of existing data when new entry is started; masks for standard formats (eg, dates); phrases which fill in when their first letter is typed; multiple-choice lists from which to choose by cursoring a highlighted bar. Fields may be multi-lined and scrolled if larger than the screen space allotted them. Specify: S0400 & Compiler. List: \$295, Us: \$229

WHY US? Latest versions of all products • Shipped 24 hours or sooner • No surcharge for credit card or COD purchase. **NEED TERMS?** On-the-spot credit to most public companies, government, educational, medical institutions. **LOOKING FOR SOMETHING?** We can get many more products — just ask! **NEED MORE INFO?** Our Catalog and literature cover just about everything.

For Orders, Literature, or Catalogs, Call Us at...

800 PC-BRAND

That's (800) 722-7263. In NY State call (212) 242-3600

PC Brand, 150 5th Ave., New York, N.Y. 10011-4311

Telex: 667962 (SOFT COMM NYK)

1986 PC BRAND

Prices, terms, and specifications subject to change without notice.

SAVE \$5
Just tell us
this code
J8

TODAY'S TOP QUALITY AIDS TO PROGRAMMING PRODUCTIVITY

GREENLEAF *Bountiful Harvest* FUNCTIONS

C source, assembler source, and binary libraries of 225 functions for many compilers. Emphasizes tight functional groupings to minimize loading code which your application may never use. Manual helps select functions, bulletin board, too.

A sampling: *DOS* extensions for file and directory manipulation; *Screen*: to select mode, page, monochrome or color, palette; cursor shape, positioning; clearing and scrolling; pixel get and put; read light pen. *Strings*: Center, justify, etc.; efficient list operations which add, delete, sort string pointers for top speed. *Other*: graphics character primitives, keyboard status, function key assignment, time/date, read registers and memory size, peek and poke. Mature best-seller. Specify: S0770 & Compiler. List: ***185**, Here: ***139**

PFORCE *Phoenix Pfunction Festival*

Lotus® didn't do badly pulling it all together in one place. Phoenix has followed suit with the ultimate integrated C library, offering everything from low level functions for hardware access to complete b-tree database management. Along the way are prerequisites such as string manipulation, time/date, field and screen editing, but also four styles of menus (Lotus included), windowing, background tasking, DOS interfaces, directory management, even interrupt-driven communications. Design emphasizes objects, so characteristics of windows, databases, records and fields can be initiated and changed outside functions.

One large collection in place of bits and pieces means one set of instructions and PforCe™ has tutorials, extensive examples, quick reference, and on-line help.

Everything in source, no royalties, all memory models of Lattice, M'soft. Specify: S0220 & Compiler. List: ***475**, PCB: ***349**

GREENLEAF *Hello World* COMMUNICATIONS

Want your application to communicate with other users or remote data bases by asynchronous communications built right into your C programs! Even if you don't need it now, that's a skill to have at the ready!

120 functions and demo programs in both C and assembler source code set up separate transmit and receive ring buffers for up to 16 simultaneous channels. Interrupt driven so you can halt an incoming record, display it, file it, let the user edit it, then continue. Goodbye separate communications software.

Supports up to 9600 baud, ASCII or binary, any parity or word length, 8250 UARTs, Xon/Xoff and Xmodem, WideTrack receive. Specify: S0750 & Compiler. List: ***185**, Us: ***139**

PRE-C *Pick the Lint from Your Program*

Pre-C is like UNIX's lint. It finds problems your compiler won't. Problems that a debugger will have trouble figuring out. Even problems which will cause trouble with other compilers.

Compilers see one module at a time. Modules only meet at link time. Pre-C looks at all modules at once and reports conflicts in data type declarations; function call parameters which disagree with functions, machine-dependent expressions which inhibit portability. It spots obsolete usage (even C changes), casts with suspect conversions, variables never used, functions never called, unreachable code. Adheres to UNIX System III compile standard to ensure your portability. Ask for: P0590, List: ***395**, Ours: ***279**

DAN BRICKLIN'S DEMO PROGRAM *Storyboard Your Program*

The Legendary One has created Metaphor Two when the rest of us are still on Zero. Dan's first was the original electronic spreadsheet (VisiCalc™). This one is for programmers.

Words don't express program ideas because programs are screens! Dan's Demo creates slide shows. Create a screen — a snapshot of your planned product as it runs. Anything goes: words, borders, box rules, inverse and underlining of monochrome, fore- and background color. Copy this "slide" to an empty screen. Change it a little, to show the next instant of run-time. Do it again. Presto, a whole slide show of your program in action.

All 250 characters and attributes are available from scrollable lists which pop to the screen. All commands are layered in Lotus-style pop-up menus. Frequent choices mapped to function keys as well.

80x25 character mode, not bit-mapped.

Screen areas can be blocked for cut and paste or filled with color or characters, even blink. Slides can overlay on others, can be shuffled, deleted. Slides can proceed at time intervals or branch anywhere in the slide sequence depending on user keyhits.

Invaluable to prototype the program you are about to write, to position the labels, choose the color decor, smoothe out the keystroke interface. Or load the "capture" utility and snapshot the screens of any running program for an instant slide show.

Each copy entitles you to redistribute fifty of the slide projector program that runs demos. Plain manual, no binder keeps price of big product small. "Might... become the essential tool in... user interface prototyping," *Tech Journal*. Ask for: N0100. List: ***75** Us: ***69**

BASTOC *OPTIMIZES!* *Translates BASIC Into C*

For a trifling price, BASTOC™ moves truckloads of BASIC code over to C. It's a translator which takes in Microsoft Extended BASIC and emits pure K&R C for Lattice 3.0. It will optionally convert your program into a single monolithic C function or decompose it into separate functions, one for each GOSUB label.

Version 2's optimization dramatically reduces execution time. Converts to integers those variables in BASIC programs which do not need floating point. Where BASIC uses full assignment statements to increment counters, BASTOC converts to C's compact form. Strings dynamically allocated ridding your application of BASIC's catatonic halts for garbage collection. Creates structure of even convoluted BASIC code. Huge worksaver.

Ask for: List: PC Brand: S0375 ***495** ***399**

Shopping List for the Power Workbench

ASSEMBLERS & DEBUGGERS		LIST	OURS
Advanced Trace-86 Morgan, ASM Interpreter	175	149	
Codesmith-86 Debugger by Visual Age	145	109	
Cdebugger by Micro-Software Developers	165	139	
CSD Debugger C source level by Mark Williams	75	75	
C-Sprite Debugger by Lattice, source level	175	139	
Microsoft Macro Assembler with Utilities	150	109	
Periscope I Debugger Data Base Decisions	295	269	
Periscope II Data Base Decisions	145	129	
Pfix86 by Phoenix, Assembly level debugger	195	149	
Pfix86 Plus by Phoenix, Symbolic Debugger	395	279	
The Profiler DWB Associates, with Source	125	99	
BASIC LANGUAGE			
BetterBASIC Summit Software	195	165	
BetterBASIC Utilities 8087 Math Support	99	85	
Btrieve Interface	99	85	
Run-Time Module	250	225	
Microsoft BASIC Interpreter for XENIX	350	295	
Microsoft QuickBASIC Compiler full BASICA	99	79	
Professional BASIC by Morgan	99	79	
8087 Math Support	50	47	
True BASIC True BASIC Inc	150	119	
Run Time Module	500	420	
True BASIC Libraries Btrieve, Asyn, Sort, etc.	Var	Call	
C COMPILERS			
C-86 Compiler Computer Innovations	395	289	
Lattice C Compiler from Lattice	500	299	
Let's C Compiler by Mark Williams	75	69	
with CSD Source Level Debugger	150	129	
MWC-86: Mark Williams C Development	495	369	
Microsoft C Compiler	395	259	
C INTERPRETERS			
C-Terp by Gimpel Software	300	249	
Instant C by Rational Systems	500	395	
Interactive-C by IMPACC with debugging	249	219	
RUN/C Professional from Lifeboat	250	185	
RUN/C without Loadable Libraries	120	109	
TEXT EDITORS			
Brief from Solution Systems	195	CALL	
CVUE by Lattice	75	69	
with Source	250	195	
Epsilon by Lugaru Software, like EMACS	195	169	
Fast C by Lifeboat	130	105	
FirstTime by Spruce Technology, C syntax	295	229	
Kedit by Mansfield, similar to Kedit	125	115	
LSE, the Lattice Screen Editor Multi Window	125	100	
Pmate by Phoenix, with Macros	225	159	
Text Management Utilities Grep, splat, diff, etc.	120	100	
Vedit by Compview	150	119	
Vedit Plus by Compview	225	180	
FILE MANAGERS			
Btrieve by Softcraft, no royalties	250	195	
Btrieve Network by Softcraft	595	465	
c-tree by FairCom — no royalties, source	395	329	
dbC dBASE file manager from Lattice	250	195	
with source	500	390	
dbVista single user DBMS by Raima	195	159	
with source	495	429	
dbVista multi-user DBMS	495	429	
with source	990	849	
Opt-Tech Sort Can sort Btrieve files	149	119	
SCREEN DESIGN			
Curses by Lattice, UNIX screen designer	125	99	
with Source	250	199	
On-Line Help from Opt-Tech Data	149	119	
Panel by Roundhill, no royalties	295	229	
View Manager for C by Blaise	275	209	
Windows for C Vermont Creative Software	195	149	
Windows for Data includes Windows for C		295	250
ZView Data Management Consultants		245	199
GRAPHICS			
Essential Graphics by Essential, no royalties	250	210	
GSS Graphics Development Toolkit	495	399	
GSS Kernel System by Graphic Software	495	399	
GSS Kernel System for IBM RT	795	676	
GSS Metafile Interpreter	295	249	
GSS Plotting System	495	399	
Halo Graphics Kernel System	300	219	
with Dr. Halo II, by Media Cybernetics	440	299	
COMMUNICATIONS			
Asynch Manager by Blaise, for C or Pascal	175	149	
Greenleaf Communications by Greenleaf	185	139	
Software Horizons Pack 3	149	119	
UTILITY LIBRARIES			
Blaise C Tools 1	125	109	
Blaise C Tools 2 Call about combined price	100	89	
C Food Smorgasbord by Lattice	150	109	
C Utility Library by Essential, 300 functions	185	139	
Greenleaf Functions by Greenleaf Software	185	139	
PforCe by Phoenix, vast library	475	349	
Software Horizons Packages	Var	Call	
TopView Tool Basket by Lattice, source avail	250	199	
Vitamin C by Creative Programming	150	139	
DEVELOPMENT TOOLS			
Code Sifter by David Smith Software, Profiler	119	99	
C-Worthy by Custom Design Software	295	269	
C-Worthy for Network Menu, help, errors	495	449	
Dan Bricklin's Demo Program Prototyper	75	69	
LMK from Lattice by Lattice, "make" like UNIX	195	149	
PC-Lint by Gimpel Software, after UNIX's "lint"	139	125	
PFinish by Phoenix, EXE performance analyzer	395	279	
Plink86 by Phoenix, Overlay Linker	395	279	
Plink86 Plus Utilizes memory for overlays	495	359	
Pmaker by Phoenix, like UNIX "make"	195	149	
Pre-C by Phoenix, UNIX "lint" alike	395	279	
Plantasy Pac six Phoenix products	1295	895	
OTHER TOOLS			
BASTOC by JMI, convert BASIC to C	495	399	
BASIC-C BASIC's functions added to C	175	139	
The HAMMER by OES Systems	195	179	
PASM86 by Phoenix, Macro Assembler	295	219	
Ptel by Phoenix, Binary File Communicator	195	149	
Rtrieve by Softcraft, Btrieve Report Generator	85	75	
Xtrieve by Softcraft, Query Utility for Btrieve	195	175	
FORTRAN COMPILERS & UTILITIES			
ACS Time Series by Alpha Computer Service	495	469	
Forlib-Plus by Alpha Computer Service	70	59	
Microsoft FORTRAN Links with Microsoft C	350	219	
Microsoft FORTRAN for XENIX	495	389	
Pro FORTRAN by Prospero	390	345	
RM/FORTRAN by Ryan-McFarland	595	399	
Scientific Subroutine Library by Peerless	175	149	
Scientific Subroutine Package by Alpha	295	269	
The Statistician by Alpha Computer	295	269	
Strings & Things by Alpha Computer	70	59	
OTHER LANGUAGES & UTILITIES			
Microsoft COBOL Compiler	700	499	
Microsoft COBOL Compiler for XENIX	995	795	
Microsoft COBOL Tools with Source Debugger	350	259	
Microsoft COBOL Tools for XENIX	450	333	
Microsoft Lisp New Common Lisp	250	189	
Microsoft MuMath Includes MuSimp	300	199	
Microsoft Pascal Compiler Links with M'soft C	300	199	
Microsoft Pascal Compiler for XENIX	495	415	
Pro Pascal by Prospero, ISO Validated	390	345	

PRICED TO SAVE YOU MONEY, BEST SHIPPED FAST ANYWHERE. BEST PRICES YET!

INTERACTIVE-C NEW! Compiler-Compatible Interpreter, Editor, Debugger

Earlier C interpreters were miraculous compromises. Interactive-C™ shows how far C interpreters have come. More than an interpreter, Interactive-C is a fully-integrated development environment: a complete K&R interpreter bound tightly to its own editor and debugger.

Slice through programming projects like

RUN/C PROFESSIONAL C Interpreter Links Binary Libraries

Run/C comes in an apprentice and pro version. The professional model dynamically loads and unloads multiple binary function libraries like C-Food Smorgasbord™ and Halo Graphics™ — potentially any library compiled with Lattice's large model. Inside this interpreter your C program can reach for functions in the best of commercial libraries.

This C interpreter behaves like PC BASIC meets WordStar®. Use fullscreen editing to create a program. RUN it. If it stumbles, LIST it, EDIT it, RUN it again, fix it again. Use familiar commands like LOAD, MERGE, SAVE, FILES, even TRON and TRACE.

Ideal for program development. Put up code at high speed, try out things devil-may-care, let RUN/C find your malaprops. Blast away until tight little code segments are undyingly faithful.

Lots more features: system interrupts, a shell command to invoke any operating system command without leaving Run/C, debugging aids ingeniously installed as a Run/C function. Call for debugging conditionally from within your program, a specific function or a menu of aids including immediate mode, single-step tracing, changing of variable values.

Manual shows how to develop the interface to a commercial library, using the Lattice compiler (a must). Link your own function archive the same way. (320k minimum; 512k recommended to fit libraries.)

Ask for: S0950 List: \$250 PCB: \$185

PLINK86 & PLUS Cached Overlays Maximize Memory Use

Along the overlord of overlay linkers, standard Plink86 shoehorns large programs into small machines by sharing memory, swapping program segments in from disk. A 512k program could run in a 128k machine, for example. The Plus version goes beyond: if it finds itself in a larger machine, it moves whatever program overlays that fit into leftover memory.

Overlays now swap at memory speed not disk speed. It also can automatically restore a displaced overlay to which a subsequently called overlay must return, and assign library modules to a program's root segment or its overlay areas.

Plink86-Plus: List: \$495. Us: \$359. Plink86: List: \$395. Us: \$279

a hot knife through butter. Extensive error-checking insures immediate detection of program misbehavior. State of the art debugging tools include breakpoints, watchvalues, several stepping options and interactive viewing and modification of variables. An Interactive-C exclusive lets you interrupt to edit and "continue" from where you left off. Eliminates plodding replays of already debugged code — the ball and chain of other interpreters.

Operate Interactive-C using adjustable edit, command, and status windows. Toggle a second screen showing only your program's output — never any crowded intermixing. Or, boost productivity with twin CRTs. Load object code of functions you have already compiled. Or of commercial libraries. Interactive-C has immediate mode, syntax checking both as you type and run, and cursor positioning precisely pointing at an error, not possible with incremental or pseudo-compilers which leave source code behind.

100% compiler compatible — right down to header files and library calls. Port programs between Interactive-C and your compiler with no modifications whatever — not even tricky areas of dynamic memory allocation and I/O.

Specify: List: PC Brand:
E950 & Compiler \$249 \$219

GSS GRAPHICS SYSTEM Leave the Device Driving to GSS ANSI CGI STANDARD!

GSS™ has reconfigured two components of its comprehensive graphics tools to conform with the ANSI Computer Graphics Interface (CGI) standard.

At the heart of the system is the Development Toolkit which contains all language interfaces and device drivers for keyboards, mice, joysticks, tablets, printers, plotters, cameras, and more. Drivers house management of vector graphics (plotters) and bitmaps used by raster input devices (scanners) to insulate the application program from concern for device idiosyncrasy. No one else has implemented CGI that way. It means your programming remains generic; just switch drivers and the same program will drive a different device.

GSS Kernel™ conforms to level 2b of ANSI's Graphical Kernel System (GKS) and contains all its needed drivers and language bindings. Kernel has macro level tools to draw and color an object, store the sequential instructions, and recreate the object on its own, as well as segment it, transform it, etc. So powerful, a single command may represent several score lower level statements.

Plotting has the equivalent GKS tools for graph and chart generation and their captioning: hand it apples and oranges, say "pie", and it bakes the numbers into a digestible display for screen or plotters.

Kernel and Plotting have tools to convert images they create to ANSI Computer Graphics Metafiles (CGMs), a tokenized standard for storing every form of graphic image as data. The Metafile Interpreter

LATTICE C COMPILER Major Upgrades to the Best Selling C Compiler

Lattice now embraces key UNIX™ enhancements which have entered the language since K&R: void functions returning no value, enumerated data types to assign stepped values to variables, data passing between structures by assignment.

The greatly expanded libraries (325 functions!) enable the file sharing and record locking provisions of DOS 3.1, provide a full complement of transcendental, and a host of utilities to mimic the UNIX and XENIX™ environments.

Lattice 3.0 defaults to the ANSI proposed standard when you need strict adherence, but command line options restore leniency. And it adopts ANSI checking of external function arguments by data type to kill bug swarms when modules join up at link time.

Lattice now delivers smaller .EXE files, boasts very fast link times and a more efficient aliasing algorithm. New options generate code to use 80186 and 80286 features; 8087 of course sensed and utilized. Lattice has enjoyed pre-eminence so long that developers have created far more snap-on tools for Lattice C than any other compiler. William Hunt's PC Tech Journal review of 12 compilers awarded Lattice the only "very good" rating for add-on library availability.

Ask for: List: PC Brand:
S0100 \$500 \$299

BETTER BASIC Convert Microsoft BASIC. Structured, Compilable.

Combines the familiarity of BASIC with the best features of C, Pascal, and Modula 2, yet BetterBASIC is 100% compatible with Microsoft's GW™ BASIC and IBM BASIC including graphics, sound, and assembly language calls. So load your old programs and RUN. SAVE and they are converted automatically to BetterBASIC!

It's big: Needs 192k; programs can go to the PC's full 640k. It's comfy: Behaves like M'soft BASIC at the interactive level, with a full-screen editor, direct statement execution, and always poised to RUN. It's fast: Each statement checked and compiled once, not every time encountered. Sieve runs 6 times faster than with M'soft.

C-like structures house file records so goodbye to FIELD, MKI\$, CVD, LSET, etc. Named "procedures" replace GOSUBs to linenumbers. Lots more features: built-in linker for compiled modules; trace; debugging breakpoints; cross-reference command; 32k strings; DOS and BIOS calls and interrupts; recursion. Run-time module stores object code for redistribution.

Ask for: List: Us:
S1200 BetterBASIC \$195 \$165
S1201 Run-time Module \$250 \$225
S1202 8087 Interface \$99 \$85
S1205 Btrieve Interface \$99 \$85

FOREIGN POLICY
We ship anywhere. Phone or Telex your order. Credit cards: We need card number, expiry date, name and address of card. Or wire funds to PC BRAND, c/o Chemical Bank, 126 East 86th St., NY NY 10028, Account No: 034-016058. We'll ship immediately and confirm by Telex if you provide number.

reads the contents of a CGM and interprets it with full CGI capability for re-creation on various devices.

Quality software? IBM thinks so. They sell the GSS series under their own label.

Unit royalties and annual fees have been instituted for redistribution. Needs 256k.

Ask for: List: PC Brand:
GS010 CGI Dvlpm't Toolkit \$495 \$399
GS020 Kernel System \$495 \$399
GS025 Kernel for IBM RT \$795 \$676
GS030 Plotting System \$495 \$399
GS040 Metafile Interpreter \$295 \$249

BTRIEVE ASK ABOUT XTRIEVE & RTTRIEVE Queen B-tree File Manager Abdicates Royalties

There's no longer a tithe to incorporate Btrieve™ in applications, a welcome proclamation if royalties would ruin your profit margins. Btrieve takes complete charge of all file creation, indexing, reading, writing, insertion, deletion, space recapture, forward and backward searching. It builds function call "commands" right into the language you use: interfaces to C, Pascal, BASIC, and COBOL, with sample programs in all four, come with each copy.

Btrieve has mainframe specifications! Its balanced-tree indexing scheme finds any key in a million in four or less accesses. Files may have up to 24 indexes; fixed record length to 4090 characters; indexes up to 255 characters; files of 4 billion bytes.

Can even extend a file across two drives — even two hard disks!

Version 4.x speeds DOS interaction for large multiply-keyed files; enables variable length records of virtually any length; verifies accuracy (optionally) with read after write, useful in gritty environments; offers password and data encryption.

There's also Xtrieve, for Btrieve file inquiry and data manipulation, and Rtrieve for report writing. All three in versions for any network that supports the MS-DOS 3.1 file sharing function.

Ask for: List: PC Brand:
S0650 \$250 \$195
S0652 Network Version \$595 \$465

TERMS AND CONDITIONS OF SALE

Licenses: Each price is for a license to use a product on a single computer and does not constitute its ownership. We will require for you about site licenses. Except as otherwise indicated or where "x" follows the Product Code, products may be used to create programs for distribution without royalty payments or additional licenses, provided said programs do not substantially replicate the products themselves.

Compatibility: PC BRAND's standard products are designed to operate with the IBM® PC, XT or AT under PC-DOS and require no more than 128k of RAM unless indicated. Non IBM machines using MS-DOS: contact manufacturer about precise differences so we can advise.

Returns: See box page one. Defective parts will be replaced. Please call for authorization to return a product for refund.

Payment: We honor MasterCard, Visa, American Express (no surcharge), checks in advance, or funds wired to PC Brand, c/o Chemical Bank, 126 East 86 St., New York, Account 034-016058. COD (U.S. only) for cash, money order, certified check (no fee). NY State, add sales tax. Purchase orders accepted from larger corporations and institutions at our discretion if you agree to net 30 days plus 2% a month late penalty thereafter.

Shipping & Handling: U.S.: UPS Surface: 1st product \$6, each addl \$3. UPS 2nd Day Air: 1st product \$10, each addl \$4.50. UPS Next Day Air or Federal Express 1-2 Day Air: 1st product \$18, each addl \$6. FedEx Next Day 10 AM: 1st product \$28, each addl \$7. International: Charges vary by destination and carrier. \$10 per shipping container for export forms. Air parcel post at your risk beyond collected insurable amount.

For Orders, Literature, or Catalogs, Call Us at...

800 PC-BRAND

That's (800) 722-7263. In NY State call (212) 242-3600

PC Brand, 150 5th Ave., New York, N.Y. 10011-4311

Telex: 667962 (SOFT COMM NYK)

© 1986 PC BRAND

Prices, terms, and specifications subject to change without notice.

SAVE \$5
Just tell us
this code
JB

COMPUTING POWER

FROM FLOPPY DISK SERVICES




PRICES AND SPECS SUBJECT TO CHANGE WITHOUT NOTICE.

Floppy Disk Services has been supplying storage systems to the hobby and professional computer community for 7 years now. You can buy with confidence from a supplier that is in for the long haul. Whether you need advice or technical help, our staff is here to serve you.

The 'Service' in Floppy Disk Services stands for the confidence you'll have in dealing with us. We do not make you wait when a problem comes up. We will be there to help, and more importantly support and guide you. In the unlikely event we cannot answer your questions, a staff member will return a call to you in a timely and professional manner with the answer.

Warranty is a term that sometimes is taken for granted. At Floppy Disk Services, we support one of the strongest warranty policies in the business. Our policy is to replace any equipment found to be defective in any way during the warranty period. It's as simple as that! No waiting for the merchandise to be sent back to the factory. If we find a problem, (other than abuse), we simply ship a new unit back to you.

The XT-clone system pictured above is our Super System VII XT clone. It contains a turbo processor, a 20mb hard disk formatted RLL to 31mb, 640K RAM, two 360K floppies, 1 AT 1.2 mb drive, mono amber monitor, par port, ser port, clock and AT type keyboard! You might expect to pay thousands for this system, but Floppy Disk Services, Inc. will supply it ready to run with a 1 year warranty. Call for latest quotes on your custom system needs...



Complete line of drive enclosures

800-223-0306

CALL FOR FREE CATALOG

Dealer Inquiries Invited



39 Everett Dr., Bldg. D Lawrenceville, NJ 08648
(609) 799-4440




Subscribe to PC Magazine and save 65%

You'll receive in-depth and comprehensive product evaluations and comparative hardware and software evaluations from PC Labs, the publishing industry's *only* testing laboratory.

You'll receive new applications, power tips and special reports designed to add more power and flexibility to your IBM/MS DOS-standard system.

And you'll network with other users and discover routines and techniques that can save you time and money.

Subscribe to *PC Magazine* today! Send the coupon to: *PC Magazine* • Box 2443 • Boulder, Colorado 80322 or call Toll-Free, 1-800-852-5200 now!



Yes, send me PC Magazine for:

☐ 22 issues (one year) for \$24.97. Save 62%!

☐ 44 issues for only \$44.97. Save 65%!

Savings based on annual single-copy price of \$64.90.

MR./MRS./MS.

PLEASE PRINT FULL NAME

COMPANY

ADDRESS

CITY

STATE

ZIP

Add \$15 per year for postage outside USA, US currency only. Please allow up to 60 days for delivery of first issue. Basic annual subscription price is \$34.97.

8ZD66

ACCELERATED XT & AT

MOTHERBOARD

\$129

8/4.7 MHz

SYSTEM

\$799

XT-88 Turbo: 8088-2 CPU: BIOS and 8 I/O slots standard, 640K or 256K RAM optional.

\$249

8 MHz

\$919

\$319

10 MHz

\$989

XT-186: 80186 CPU: BIOS 1.0 standard, BIOS 2.0 optional, 8 I/O slots: 6 XT type and 2 AT type, 640K or 256K RAM optional.

\$629

8 MHz

\$1549

XAT 286: 80286 CPU: Phoenix BIOS 6 I/O slots: 3 AT type and 3 XT type. 512 K optional. XT size.

\$629

8 MHz

\$1649

AT-286: 80286 CPU, Phoenix BIOS, 8 I/O slots: 6 AT type and 2 XT type, 640K or 1M RAM optional. AT size.

Above systems include motherboard plus:

RAM (256K on XT, 512K on XAT, 640K on AT) keyboard & enclosure, floppy drives & controller (dual 360KB on XT, 1.2 MB with hard disk/floppy controller on AT & XAT), monochrome graphic/prINTER card, power supply. Interface and peripherals optional.

Challenger

CHALLENGER COMPUTER, INC.

122 South Rd., Bedford, MA 01730 TEL: 617-275-3517

NEW DEALER SPECIAL

XT—COMPUTER	QTY 2
640K MOTHER BOARD W/OK	89
256K RAM	27
135 WATT POWER SUPPLY	53
FLOPPY DISK CONTROLLER	27
FLIP TOP BOX	38
XT/AT KEYBOARD	59
MONO/GRAPHICS/PRN (HERC)	54
TTL MONITOR W/SWIVEL	96
(1) 360K FLOPPY	92

PARTS	\$535
ASSEMBLY & TEST	64
	\$599

20 MEG HARD DISK W/CONTROLLER	425
-------------------------------	-----

AT COMPUTER	QTY 2
-------------	----------

80286 MOTHER BOARD	595
W 512K RAM	
200 W POWER SUPPLY	98
AT BOX W/KEY LOCK	79
SERIAL & PARALLEL CARD	65
AD KEYBOARD	59
1.2 M FLOPPY	129
FDD & HDD CONTROLLER CARD	225

PARTS	\$1,250
ASSEMBLY & TEST	150
	\$1,400

30 MEG 40 MSEC HARD DRIVE	615
---------------------------	-----

EGA CARD	295
EGA MONITOR	449

XT PORTABLE	\$995
-------------	-------

640K MOTHER BOARD	
640K RAM	
MULTI I/O CARD	
CLOCK, CALENDAR,	
SERIAL,	
PARALLEL	
TWO 360K	
FLOPPY DRIVES	
MONO/GRAPHICS/PRN (HERC)	
DETACHED KEYBOARD	
135 W POWER SUPPLY	
PORTABLE CASE	
9" MONITOR, GREEN or AMBER	



ADD ON BOARDS — PARTIAL LIST

XT-640K TURBO 4.77/8 MHZ W/OK	99
LOCAL AREA NET CARD W/SOFTWARE	249
384K MULTI-FUNCTION (AST 6 COMP) OK	69
MODEM CARD 300/1200 (HAYES COMP)	149
DISK I/O 2FD CTRL, PRN, SER, CLOCK,	70
CAL, GAME	
AB SWITCH BOX W/64K BUFFER (1:2 or 2:1)	94
AB SWITCH BOX (1:2 or 2:1)	29
COLOR/GRAPHICS/PRINTER CARD RGB	58

ACS IMPORTERS

5311 DERRY AVE., UNIT A
AGOURA HILLS, CA 91301
HOURS 9 AM - 6 PM PST
(818) 889-1092
TELEX: 299353 POST UR

READER SERVICE NUMBER	ADVERTISER	PAGE
* ACS Importers		195
190 Advanced Development Technologies		68
116 Advanced Logic Research		Cover 3
199 Advanced Logic Research		136
101 Alpha Computer Service		108
247 Alps America		44-45
218 American Small Business Computers		170
198 Ansa Software		19
136 Arity Corporation		169
134 Ashton-Tate		182
140 AST Research, Inc.		122-123
203 Atron		8
249 Atron		181
105 Barrington Systems, Inc.		56
104 Blaise Computing, Inc.		105
114 Blaise Computing, Inc.		107
254 Borland International		Cover 2-1
107 Bruce Newman		180
111 Catamount Corp.		182
213 Central Point Software		145
* Challenger Computer, Inc.		195
189 Coefficient Systems		163
117 Cordata		167
* Creative Programming Consultants		127
118 Data Access Corp.		124
215 Data Base Decisions		5
102 Desktop A.i.		184
106 Dialectic Systems		21
* Digital Equipment Corp.		109
103 DTSS, Inc.		186
131 Ecosoft		162
170 Ellis Computing		165
161 Everest Solutions, Inc.		179
169 Everex Systems, Inc.		112
139 Everex Systems, Inc.		114
119 FairCom		22
153 Flagstaff Engineering		90
251 Flexus International Corp.		161
* Floppy Disk Services, Inc.		194
138 Foresight Resources		150
* Gimpel Software		177

READER SERVICE NUMBER	ADVERTISER	PAGE
113 HavenTree Software Limited		18
* Hawaiian Village Computer Software		188
149 IBEX Computer Corp.		184
* IBM		33-36
202 I-Bus Systems		128
108 Innovative Data Technology		164
216 Intel Corp.		78-79
209 Interactive Microware		182
148 Kurtzberg Computer Systems		22
128 Lahey Computer Systems, Inc.		166
160 Lattice, Inc.		138
144 Lifeboat Associates		155
173 Little, Brown & Company		182
* LOGITECH, Inc.		23
229 LOGITECH, Inc.		25
109 Macmillan Software Co.		121
205 Mark Williams Company		17
250 Mathsoft		128
133 MEF Environmental		184
211 Micro Data Base Systems, Inc.		147
110 MicroHelp, Inc.		131
* Microsoft Corp.		28
* Microsoft Corp.		42-43
* Micro Star		189
167 Microstuf, Inc.		Cover 4
* MicroWay		190
112 Novell Data Systems		26-27
222 Opt-Tech Data Processing		4
142 Orchid Technology		88
185 Overland Data, Inc.		141
137 Paradise Systems Inc.		6-7
230 Paradise Systems Inc.		41
* PC Brand		191-193
145 PC's Limited		117-119
172 Peripherals Design		157
150 Peter Norton		176
175 Programmer's Connection		49-51
220 Programmer's Shop		46
162 Programmer's Shop		76

READER SERVICE NUMBER	ADVERTISER	PAGE
151 Programmer's Shop		77
252 ProLog Corporation		20
171 Quadram Corp.		139
166 Raima Corp.		100
181 Rational Systems, Inc.		177
143 Relational Database Systems, Inc.		143
174 Ryan-McFarland		137
141 RYBS Electronics		171
121 Santa Cruz Operation, Inc.		135
125 Seattle Telecom & Data, Inc.		70
122 Simware		140
164 SofCap, Inc.		133
201 SoftCraft, Inc.		2
192 Software Bottling Co. of NY		149
245 Software Directions		158
123 Software Garden		74
196 Software Link		48
168 Software Masters		130
147 Software That Really Works		184
130 Solution Systems		14
126 Solution Systems		24
129 Solution Systems		24
195 Summit Software Technology, Inc.		160
152 Sunny Hill Software		168
158 Sunny Hill Software		168
231 Systems & Software		134
197 Tall Tree Systems		39
206 Tangent Technologies		129
233 Tech PC		92-93
182 TeleVideo		106
* Texas Instruments		142
246 Tiara Computer System, Inc.		72
184 TORUS Systems, Inc.		103
115 Vermont Creative Software		16
212 Vu Data		133
124 Wells American		101
* Wintech		188
219 Zanthé Information, Inc.		144

TECH MART

ATTENTION SOFTWARE DEVELOPERS!

More Users For Less Money!
Digitrol's software solution
to multi-user.



pcSHARE MULTI-USER O/S

pcSHARE allows your IBM-XT/AT or compatible to support up to 5 users running your vertical market programs and 1-2-3, dBASE, WordStar, and more on inexpensive serial CRTs. pcSHARE efficiently runs compiled Basic, dBASE, Pascal & C programs with full DOS 3.0 compatible record locking.

DIGITROL COMPUTERS INC.

440 Phillip Street,
Waterloo Ontario, CAN N2L 5R9
(519) 884-4541

IBM XT/AT, Lotus 1-2-3, dBASE, and WordStar are trademarks of IBM Corp.
Lotus Development Corp., Aston-Tate and MicroPro International respectively.

CIRCLE 375 ON READER SERVICE CARD

Protect Your Private Parts.

Whether you're a software developer or an end user, whether you work alone on a PC or you're part of a 24-person project team, keeping new software or sensitive data from prying eyes is serious business.

Short of complicated, wizard-like protection schemes, or James Bond, you haven't had too many realistic alternatives. Until now.

Because Rainbow Technologies has developed simple, easy-to-use systems called Sentinels that say no to prying eyes. No matter how hard they look.

The key to Sentinel is just

that—a smart piece of plastic smaller than a best-selling cassette that plugs into the parallel port of your IBM PC/XT/AT or compatible.

There are two ways to go. The Software Sentinel™, that prevents anyone from using your licensed software program unless you give them a key. And the Data Sentinel™, Rainbow Technologies' newest prying eye-

stopper, that automatically protects sensitive personal or project data as you enter it. The Sentinel Security Systems from Rainbow Technologies. The only hard part is the key.



**RAINBOW
TECHNOLOGIES INC.**

17971 Skypark Circle, Suite E, Irvine, CA 92714
Phone (714) 261-0228 Telex: 386078

CIRCLE 378 ON READER SERVICE CARD

64K ■ 128K ■ 256K

DRAMS

80287-8 ■ 80287-3

8087-3 ■ 8087-2

8087-1

BITTNER



899 SOUTH COAST HIGHWAY
LAGUNA BEACH, CA 92651
(714) 497-6200

CALL NOW FOR **FREE CATALOG**

CIRCLE 376 ON READER SERVICE CARD

PERFECT COPIES GUARANTEED

Why risk duplicating your important programs on your computer, when our equipment is designed solely to duplicate disks and verify their perfection 100%?

Over 600 formats. 3 1/2", 5 1/4" and 8". Plus serialization, copy protection, labeling, packaging, shrink-wrapping and fast, personalized service.



**Western
Transdata Inc.**
DISK DUPLICATION

1701 E. Edinger Ave.
Building A4
Santa Ana, California 92705
(714) 547-3383 (Collect)

CIRCLE 379 ON READER SERVICE CARD

FANSI- CONSOLE™

The Integrated Console Utility™
All the little things IBM forgot!
for IBM—PC, XT, AT & clones.

- 1.2 to 3.0 times faster DOS & BIOS screen writing
- more escape sequences than ANSI.SYS
- usable in any language
- scroll recall facility
- compatibility w/PC & AT software
- full EGA support
- 255 character typeahead buffer
- increase key repeat rate
- no scroll blink for some adaptors
- VT 100/52 emulation
- auto dual screen disable
- keyboard induced breakpoints
- window support
- support for 50 line display
- many many more little features

400p Manual (w/slip case) & disk \$75, or just Shareware disk \$25. As described in *PC-World* February 86, pg. 282 and in *Lotus* June 85, pg. 8.

HERSEY MICRO CONSULTING, INC.
Box 8276E, Ann Arbor, MI 48107
(313) 994-3259 x363 VISA/MC

CIRCLE 383 ON READER SERVICE CARD



IBM PC, XT and AT programmers:

Don't give away results of your effort!
Don't waste your money buying costly fingerprinted diskettes!

You can have your programs automatically protected against piracy!

- No special training needed!
- No confusing instructions!
- No discouraging procedures!

No Sales Tax on orders outside N.Y. State

\$ 180



YETIWARE CORP.
P.O. BOX 21152
MID TOWN STATION
NEW YORK N.Y. 10129

DEALER INQUIRIES INVITED

CIRCLE 377 ON READER SERVICE CARD

Sort RM/COBOL Files • • • QISORTC • • •

Finally, a sort utility for RM/COBOL. Using efficient algorithms in assembly language making it the fastest sort on the MS-DOS market. Qisortc supports:


- RM/COBOL Version 1.5x & 2.xx files
- Single / Dual File Indexed
- Relative and Sequential
- ASCII, COMP-1, & COMP-3 fields
- 32 sort control fields
- ascending / descending
- 32 record selection fields
- EQ, NE, GE, LE, LT, GT field: constant
- implied AND, OR may be specified
- 32 output fields or total record
- CALL from RM/COBOL, when provided subroutine is linked with runtime
- Use pathnames and return codes
- Keyboard or Parameter file
- Requires MS-DOS ver 2.xx or above
- Only \$95.00 - COD, VISA, or MC.

Quantum Information Systems, Inc.

145 N.W. 85th St., Suite 103
Seattle, Washington 98117
(206) 789-2888 Telex 4941041

CIRCLE 380 ON READER SERVICE CARD

RS-422 Communications Board



- For IBM-PC/AT/XT and compatibles
- Dual RS-422 serial interface
- Programmable to 56k baud
- Differential drivers to 4000 ft.

\$345.00

QUA TECH, INC.

478 E. Exchange St. Akron OH 44304
(216) 434-3154 TLX: 5101012726

CIRCLE 382 ON READER SERVICE CARD

NEW EPROM PROGRAMMER



**EPROM 1
\$495**

- * Programs all 28-Pin, 5-Volt EPROMs and EEPROMs.
- * Perfect for engineering workstations, field service and small production runs.
- * Simple keyboard and display for stand alone duplication.
- * Interface to your computer via an RS232C port.
- * PC control software included at no extra charge.

TO ORDER PHONE:

800-325-6028 Outside California

916-885-7262 Inside California

VISA AND MASTERCARD ACCEPTED



**INTERNATIONAL
MICROSYSTEMS
INCORPORATED**

11554 C Avenue, Auburn, CA 95603

CIRCLE 384 ON READER SERVICE CARD

TECH MART

FREE DISK SPACE

THE FILE STORAGE METHOD USED BY PCTECHLINE.

The ARC file archive utility can save 50% or more on disk storage, and modern transfer time.

- Not copy protected
- Program Sources Included

Only \$50

"A sophisticated and eminently useful product."

—PC Week

SYSTEM ENHANCEMENT ASSOCIATES
21 New Street, Wayne, NJ 07470
(201) 473-5153

CIRCLE 386 ON READER SERVICE CARD

MYSTIC PASCAL

Fastest Compiler on Earth

NOW ONLY \$16!!!

- 640K code, data and stack
- incremental compiler runs in background while you are editing
- effective compiler speed greater than 100,000 lines/min
- immediate execution of Pascal statements
- true multi-tasking for up to 100 Pascal procedures
- full screen editor
- complete Help windows

disk with condensed manual to print out \$16—printed manual \$16—both \$32—for IBM PC 256K Visa/MC/COD—add \$2 shipping, COD \$5, overseas \$10

Mystic Canyon Software
P.O.B. 1010

Pecos, NM 87552 505/757-6344

CIRCLE 387 ON READER SERVICE CARD

the HD test

Professional Test/Format Program For Hard Drives in PC/XT/AT

- Setup interleave, step rate, etc.
- Surface analysis to flag bad tracks
- Load/save setup and bad track files
- Now supports AUTOCONFIG!
- Menu driven, with help windows
- Free PARK program included!
- Order HDTEST today for only \$99!

Proto PC inc.
612-644-4660

2424 Territorial Rd., St. Paul, MN 55114
Telex 910-380-7623

CIRCLE 388 ON READER SERVICE CARD



Real-Time Multitasking Executive

- No royalties
- Source code included
- Fault free operation
- Ideal for process control
- Timing control provided
- Low interrupt overhead
- Inter-task messages

Options:


- Resource Manager
- Buffer Manager
- Integer Math Library

Language Interfaces:

- C
- Pascal
- PL/M
- Fortran

DOS File Access:

- CP/M-80
- IBM PC DOS



AMX is TM of KADAK Products Ltd.
CP/M-80 is TM of Digital Research Corp.
IBM PC DOS is TM of IBM Corp.

KADAK Products Ltd. (604) 734-2796
206-1847 W. Broadway, Vancouver, B.C., Canada V6J 1Y5
Telex: 04-55670

CIRCLE 389 ON READER SERVICE CARD

ASMLIB

ASSEMBLY PROGRAMMING LIBRARY

- NO ROYALTIES REQUIRED
- Graphics - Color, Herc, Monochrome, EGA
- Floating Point Trigonometry and Arithmetics
- 8087 Supported but not required
- ASCII to Numeric conversions
- Formatted Output (PRINT USING)
- Console I/O with Windowing
- DOS Shells
- Sound Generation
- Plus much, much more

ASMLIB has over 170 functions for the IBM PC/XT/AT or compatible under DOS 2.00 or newer. Supplied in MS Assembly language source code on 3 DOS Diskettes with 215+ page reference manual.

All for only... \$149.00 ppd

BC ASSOCIATES
13073 Springdale Street, Suite 134
Westminster, California 92683
(714) 741-3015

CIRCLE 390 ON READER SERVICE CARD

TECH JOURNAL

TECH MART TECH BOOK

THE CLASSIFIED ADVERTISER'S FORMULA FOR SUCCESS IN SELLING TO TECHNICAL EXPERTS IN THE IBM MARKETPLACE.

FOR RATES & INFO
CALL: (212) 503-5115

PROTECT YOUR COPIES OF TECH JOURNAL

Make your collection of PC TECH JOURNAL a handsome addition to your office or home—and protect and organize them for easy reference!

PC TECH JOURNAL Magazine Binders and cases are made of durable luxury-look leatherette over quality binder board. Custom designed for PC TECH JOURNAL, every order receives FREE transfer foil to mark dates and volume numbers.

FOR FAST SERVICE CALL TOLL-FREE 1-800-972-5858

MAGAZINE BINDERS

Hold your issues on individual snap-on rods.

\$8.95 each; 3 for \$25.75; 6 for \$48.75.



OPEN BACK CASES

Store your copies for individual reference. \$7.95 each; 3 for \$22.95; 6 for \$43.95.



P.O. Box 5120
Philadelphia, PA 19141

Please send ☐ Binders ☐ Cases Quantity _____
Payment enclosed \$ _____. * Add \$1 per order for postage & handling. (Outside USA, add \$2.50 per unit ordered, US currency only.)

Charge my: ☐ Amex ☐ Visa ☐ MC (Minimum order \$10.)

Card No. _____ Exp. Date _____

Mr./Mrs./Ms. _____
please print full name

Address _____

City _____

State _____ Zip _____

*PA residents add 6% sales tax.

TECH BOOK

ACCESSORIES/SUPPLIES

•• SOFTWARE PUBLISHING ••

GDS offers a wide variety of services that will help get your software to the market. Address your needs with GDS.

- IBM style cloth/vinyl 3-ring binders/slips
- Labels, sleeves, disk pages...
- Disk duplication with 100% verification
- Bulk diskettes
- Shrink wrapping and assembly
- Quick turnaround

A well-packaged product can make the difference in making a sale. Call us NOW. VISA/MC Glenco Development Systems
3920 North Ridge Avenue
Arlington Heights, IL 60004
(312) 392-2492

BAR CODING

BAR CODE READERS

- IBM PC/XT, AT, AT&T 6300 & 6300 PLUS key-board models or RS-232 interface
- NO programming. Reads dot matrix
- Auto-recognition and single code decoding
- Reads Code 39, UPC A/E, Codabar & 12 of 5
- \$635 list, units in stock, 2 year warranty
- Bar code printing software, call for info:



PERCON, Inc.
2190 W. 11th
Eugene, OR 97402
(503) 344-1189

BAR CODE LABEL PRINTING

PrintBar II is a unique memory resident program that prints code 39 and UPC bar codes on Epson, IBM graphics and LaserJet printers. Print directly from almost any program, without copying data to special print files. 30 day money back guarantee. \$295 plus \$12 S/H second day air.
BEAR ROCK SOFTWARE CO.
P.O. Box 212
Placerville, CA 95667
(916) 622-4640

BUSINESS OPPORTUNITIES

INCORPORATE!

- *Save Taxes!
- *Protect Your assets!
- *Free Booklet!
- *Free Forms!
- *Save \$— Do It Yourself!
- *No Legal Fees!

WRITE OR CALL TOLL-FREE TODAY!
HARVARD BUSINESS SERVICES, INC.
3151 Summerset Rd.
Wilmington, DE 19810
800-345-CORP

Personal Computer Owners
CAN EARN \$1,000 TO \$5,000
monthly selling simple services performed by their computer. Work at home—in spare time. Get free list of 100 best services to offer. Write:
C.I.L.B.Q.
PO Box 60369
San Diego, CA 92106-8369

HARDWARE/ADD-ON BOARDS

ACQUIRE DATA WITH YOUR PC

- *16 to 64 differential A-D, up to 8 D-A
 - *24 to 48 digital I/O, 24 event counters
 - *Processor and 8 to 40K RAM on board
 - *Floating-pt processing, Battery backup
 - *Linearization, 4 selectable gain ranges
 - *Menu-driven software. Programmable.
 - *Systems start at \$895, 1 year guarantee
- WESTERN TELECOMPUTING
202 E. Kagy Bozeman, MT 59715
(406) 586-1511. Or touch-tone, toll-free:
1-800-423-0587, then 328 222.

Z80 Co-processors

For PC and PC/AT. From \$199.50. Clock speeds to 9 Mhz. Run CP/M-80 software fast. Develop microprocessor software with our remote debugger kernel. Also run Intel ISIS software tools. We have Z80 processors for VAX and PDP-11 too.
Decmatron
2065 Martin Ave #110
Santa Clara, CA 95050
(408) 980-1678

SPEECH SYNTHESIS

SynPhonix: TRUE Unlimited Speech Synthesizer for IBM-PC/XT/AT/jr & compatibles. This low power short card includes an SSi263 speech chip, amplifier and speaker. Software includes Text-to-Speech, Phonetic Editor, Talking Clock & demos. Can be programmed with BASIC and other languages. Prices start below \$200.

SynPhonix

Electronic Speech Articulator

Artic Technologies
1311 N. Main St.
Clawson, MI 48017
(313) 435-4222

RS-232/RS-422 Communications

Versatile communications and I/O boards.

- Four port RS-232 with DOS drivers \$349
- RS-422/485-serial interface \$149
- RS-232/422 with 24 parallel I/O \$199
- RS-422 synchronous with DMA \$299
- Delivery from stock
- Custom designs available

adams

Adams Incorporated
P.O. Box 17525
Greenville, SC 29606
(803) 297-9630

FIXED DISK BIOS/BOOT

FIXT boots from most popular Hard Disks—DA-VONG, TECMAR, IOMEGA, GT LAKES, etc. Adds XT-like BIOS interface to your disk for PC. Security, multiple volumes, removable media support optional. No-slot plug-in installation. Specify controller and computer with order. \$80-\$95. Add \$3 shpg., CA tax.



GOLDEN BOW SYSTEMS
2870 Fifth Avenue
Suite 201
San Diego, CA 92103
(619) 298-9349

PC-PROMPAC ROM Expansion for PC!

Alidia systems introduces PC-PROMPAC, a "half-sized" PROM/ROM expansion board for IBM and IBM compatible PCs. PC-PROMPAC will support up to six 28-pin JEDEC compatible devices (ex: 2764, 27128, 27256, 27512, 6264, etc.) with individually selectable address ranges. Prices start at \$125 for single units. Quantity discounts and OEM arrangements available. MC/VISA.
ALDIA SYSTEMS, Inc.
P.O. Box 37634
Phoenix, AZ 85069
(602) 886-1786

HARDWARE/DISK DRIVES

8 INCH DISKETTE SYSTEM

Read, write and format diskettes from IBM mainframes, minicomputers, data entry equipment, etc. Complete easy to use software handles EBCDIC conversion. Can read and write CP/M 8-inch diskettes (many formats). You also can use 8-inch drives for PC DOS files; 1200 KB per diskette! \$1295 complete.

MicroTech Exports
223 Forest Avenue
Palo Alto, CA 94301
(415) 324-9114

HARDWARE/PERIPHERALS

TURBO START YOUR PC!!!

FOR IBM PC's ONLY!! The PC-INMA a Firmware ROM Module for the IBM-PC!!! Features: BOOT within 10 SECONDS!!! BREAK the 640K BARRIER!! Access up to 704K of RAM!!! (Lotus, DOS, etc.) SCREEN RELIEF—protects your monitor, and MORE!! Easily PLUGS IN-NO SLOT! Only \$49.95 + \$3 S/H. Dlr. inquiries accepted CK/MO/VISA/MC.
JS&J Software
1281 S. King St. Suite 6A
Honolulu, HI 96814
24 hr Orders Only: (800) 821-5226 ext. 435

IBM PC/XT/AT SPEEDUP

*OVERTRUSTER: Boots the performance of PC and XT by 280%! 100% software compatible, is switchable between 4.77 and 7.38Mhz. \$195.
*SPEEDSWITCHER: This is an economical 6 speed switch (4-11Mhz) for AT's. \$89
*XCELEX: Automatic 5 speed switch (6-12Mhz) This unit will switch on the fly and works with ALL IBM AT's including the new Models with speed limiting Rom Bios. \$149.
DATA MANAGEMENT SYSTEMS, INC.
1525 Hickory St.
Salina, KS 67401
ORDER HOTLINE (913) 823-6440

RATES AND INFORMATION

Standard listings consist of a bold lead line (25 characters maximum); 7 lines of body copy (45 characters per line); 4 lines for company name, address and telephone number. \$140 per insertion—3 issue minimum. Additional charge for extra lines and company logos. Prepayment and frequency discounts available. American Express, MasterCard, Visa accepted. Copy subject to publishers approval. Send typewritten or printed copy, reproducible logo art (if applicable) and remittance to Kathryn Cumberlander, Classified Sales Manager, Ziff-Davis Publishing Company, One Park Avenue, New York, NY 10016. For additional information, assistance, or to place an order by phone, call collect (212) 503-5115.

TECH BOOK

SOFTWARE/BUSINESS

The Andsor Collection™

Unique concepts: creates complete, self-contained, window-based data management environment in one DOS file. Simplifies everything. Combine functions to create your own solutions in any application: calculations, database management, modeling, text processing, charts, data analysis, statistics, reports, labels, forms, presentations, mail-merge, etc. Simple enough for a PCjr, sophisticated enough for a PC AT. Superb, 400 page hard-cover manual, with many examples. From simple calculations, files, inquiries, to complex models, data structures, reports: when your favorite data manager/spreadsheet/word processor/integrated system cannot provide the solution you need, remember The Andsor Collection. 60 day money-back guarantee. US\$95 + \$5 s&h. Visa/MC/AmEx/Chk/MO/COD. Call or write now to order, or for info. IBM/PC/XT/AT/PCjr, 128K+, one drive or hard disk, monochrome and/or color monitor, DOS 2.0+. Not copy-protected.



Andsor Research Inc.
181 University Avenue, Suite 1202
Toronto, Ontario, Canada M5H 3M7
(416) 364-8423

THE DGI ORGANIZATION—PRINTERS SUPPORTED

Lets you easily manage your organization charts. It is menu-driven for easy use. You can create, save, update and print or plot your organization charts. You can input up to 58 individuals with four lines of text each, two title lines and a footnote. For use with the IBM PC or compatible computer and most printers or HP plotters. \$95. DECISION GRAPHICS, INC.
P.O. Box 2776-PCTJ
Littleton, CO 80161
(303) 796-0341

SOFTWARE/COMMUNICATIONS

PC SERIAL DATA ANALYZER

Use your IBM PC or compatible to analyze data streams between two serial devices (up to 9600 BAUD). Two windows display each devices transmission in ASCII or HEX. PC can also act as a terminal for either device. Invaluable tool for debugging serial interfaces. Disk & manual \$150. Triple C Software
2897 SW 13th St.
Fort Lauderdale, FL 33312
(305) 583-0687

SOFTWARE/DEVELOPMENT TOOLS

ROMable CODE on PC!

PCLOCATE allows PC users to develop ROM-based software from MS-DOS "Exe" files. The user specifies the physical location of all segments. Output files are compatible with most PROM programmers. PCLOCATE supports the 8086, 8088, 80186, 80188, and 80286 processors. MC/VISA.
ALDIA SYSTEMS INCORPORATED
P.O. Box 37634
Phoenix, AZ 85069
(602) 866-1786

REALIA COBOL SITES

REALFORM is the Screen Handler you have been looking for. It features interactive screen design, an on-line forms editor, relief of cursor control, expedites screen generation, supports numerous data field types, is easy to use and offers powerful data entry functionality. \$395. US.
CHARANDON COMPUTER SYSTEMS INC.
1600 Laperriere Avenue
Ottawa, Ontario, Canada K1Z 8P5
(613) 729-3003

FIRMWARE PRODUCTION ON PC

LINK&LOCATE enables PC users to produce ROM-based firmware for 8086/87/186 from object files generated by C, PL/M compilers & MASM. Provides full control of segments placement anywhere in memory. Supports output of INTEL hex file for PROM programmer, absolute object file for symbolic debugger & ICE, and MS-DOS EXE file. Includes an INTEL compatible linker, locator, librarian and hex formatters. \$350.



Systems & Software, Inc.
3303 Harbor Blvd., C11
Costa Mesa, CA 92626
(714) 241-8650

C-INDEX

C-INDEX is a state-of-the-art data management library for C. Designed for serious product development. No Royalties. B+ Tree, variable length records, multiple keys, and transportable source code. Call for our free info packet.


C-INDEX/PRO \$195 Partial Source
C-INDEX/PLUS \$395 Full Source
TRIO SYSTEMS
2210 Wilshire Blvd. Suite 289
Santa Monica, CA 90403
213-394-0796

GENSCREEN FOR MS-COBOL

Cobol Source Code Generator for generating the screen section and data division cobol source code for Microsoft and IBM PC cobol. Screen Image Text files are run through GENSCREEN to produce all of the source code for your screen in less than a minute. Super fast programmer productivity tool \$69.99.
Personal Computer Development Corporation
P.O. Box 8556
Warwick, R.I. 02888-8556
(401) 333-8704

FLOWCHARTS BY PROFLO

The fast, friendly, flowchart drawing program for the software professional. PROFLO speeds software development and reduces documentation costs. Lets you create, edit, and print clear, precise flowcharts, quickly and easily. Requires IBM PC (or clone) with DOS, 128K, graphics monitor & graphics printer. Program & Documentation \$49.95. Demo Disk \$10.00.



Star Systems
28 Topstone Drive
Bethel, CT 06801
(203) 744-0546

TURBO PASCAL GENERATOR

GTP APPLICATION DEVELOPMENT SYSTEM, version 2. Builds complete, working application systems. You give it spec's, it writes error-free code.

Indexed Data Bases	Multiple Screens
Context Sensitive	Memory-mapped
Help	Video
Global/Phonetic	Full Keyboard Supt
Search	

Easy to Use Price \$150.00 Visa/MC, ck, MO AEF
P.O. Box 928
Katy, TX 77492
(713) 391-8570

SCREENWARE UTILITIES

FAST ELEGANT SCREEN CREATIONS FOR PC ASSEMBLY ROUTINES. Make new or edit existing screens, even those CAPTURED in OTHER pgms BY OUR PGM! Supports ALL color/char/att & monitors. Pop-up menus, help & file management. Creates binary & assembler-ready ASCII source files. Easy to link to main pgm & invokes w/little code. KBD template, charts, 50pg Man, PC/AT-128K, ONLY \$27!
Crosswinds Software
8621 Windjammer Drive, Suite M-56
Raleigh, NC 27609
(919) 847-1812

ADVANCED MODULA-2 TOOLS

REPERTOIRE: \$64. includes 360K of Logitech or ITC Modula-2 source code: screen compiler and fast display system with input checking, help, windows, menus, colors; auto-adapts to hardware. Integrated multiwindow editor; natural-language analyzer. DOS & BIOS tools. FREE documentation & demo disk. MC/VISA
PMI
4536 SE 50th
Portland, OR 97206 (503) 293-7706
MCI Mail: PMI; Compuserve: 74706,262

WORK HORSE BY USERSOFT

The BASIC code generator that provides:
1) screen painting 2) help screens
3) structured programs 4) maintainable code
5) outs programming time 6) INKEY\$ routine
7) merging 8) printing 9) cross-references
10) runs interpretively or can be compiled.
All this and more for just \$59.00.
USERSOFT, Inc.
P.O. Box 517
Manteo, NC 27954
(919) 473-1970

THE PL/M CONNECTION

- Develop PC software with your PL/M compiler.
- Complete Interface to PC-DOS and PC-BIOS
- Fast Graphics Routines example programs
- All source files are included
- 200 page Technical Reference Manual
- \$295.00 No Royalties.

CompuFirm Corporation
7841 Balboa Ave #108
San Diego, CA 92111
(619) 571-0228

BASIC PROGRAMMERS

ADD MORE HORSEPOWER TO YOUR PROGRAMS!! Use THE BASIC ENGINE™ to build YOUR programs in FAST compiled BASIC. Add your modules to a working core of assembly routines, menus, data screens, pop-up help, sort, more; over 60 subroutines. Complete source for two working programs, full instructions, \$79.95. Requires DOS 2+, MS-QuickBASIC compiler.
Praxis Software Engineering Associates
370 Andrews St.
Green River, WY 82935-4846
(307) 875-9626

PRODUCTIVITY TOOLS

SRMS™ Software Revision Management System stores all versions of source code in a single library. Allows retrieval of any version of source and application of changes while recording when, why, and where changes were made with no duplication of common code. DOS pathname, directory, and environment variable support, typeset manual, much more.
New version (2.0)..... \$125.00.
QMAKE™ is an intelligent system builder patterned after the UNIX make utility. Only compiles those routines that have changed since last build. Support for macros, multiple entry points, command line parameters. Integrates fully with SRMS..... \$99.00.
MS/PC-DOS 2.0 (MN plus 6%) MC/VISA
QUILT™ COMPUTING
7048 Stratford Rd.
Woodbury, Minnesota 55125
(612) 739-4560

Better BASIC Programmers

BetterTOOLS 2.00 SPEEDS BetterBASIC 1.1/2.0 development. Includes: 190+ useful tools in 17 modules, manual, and source code. No royalties. Quicksort, screen builder, extended math, disk directories, display and printer routines, powerful input, data encryption, on-line error descriptions, much more. Only \$89. VISA, MC, COD.
SOFTWARE ASSOCIATES
6220 W. Airport Blvd.
Houston, TX 77035
(713) 726-0706

PC CROSS-ASSEMBLERS

Up to 10,000 lines per minute! Fast X-ref and Linker plus Macros and Librarian. Generates HEX, TEKHEK, S-records, and .OBJ output records. Over 40 micros and XENIX, MS DOS, CPM 80 and ISIS versions. Accepts MOTOROLA and INTEL directives and Mnemonics.
RELMS™
P.O. Box 6719
San Jose, CA 95150
(408) 265-5411

TECH BOOK

SUPERTECH "PREP" \$19.95

Powerful, exceptionally flexible, language-independent pre-processor. Use it, for example, to write register, opcode and operator synonyms, nested macros, line-length identifiers, etc. with assemblers without such features built-in. OK to share. Phone 24 hrs. (Please add \$3 s/h, WA res. add 7.9% tax)

SUPERTECH
11410 NE 124 St. Suite 6143
Kirkland, WA 98034-4399
(206) 488-9253

SOURCE CODE LIBRARIAN

TLIB™ stores ALL versions of your source in ONE compact library file, even with hundreds of revisions. Updates (deltas), 5-7 times faster than Unix SCCS. Date & comments for each version, easy retrieval. LAN-shared libraries. "Free public domain MAKE (with source) by Landon Dyer." DOS 2.x/3.x \$99.95 \$3 s/h VISA/MC.

Burton Systems Software
P.O. Box 4156
Cary, NC 27511-4156
(919) 469-3068

LAZY ASSEMBLE

Batch program assembles/links multiple ASM's. Specify which error-free .LST files you want printed. Delete form feeds from .LSTs if desired. Link only if all assemblies ok. Other utilities: link map re-arranger and case sens/insens high speed string search across editable file list. \$49.95 (CK/M.O.)
Goldbrick Software
1376 Deerport Ave. #22
Fullerton, CA 92631
(714) 524-6604

Fortran Addenda '86

Libraries for graphics and friendly/interactive programs. ASMUTIL2: Total PC control; printers (3), CRTs (2), disks, FULL keyboard, strings, high-speed gets/puts, line/box, fills, tile-painting, EGA graphics modes. BUTILE2: Input word-processing/editing, non-overflowing formats, window management, ... 100 easy to program, "smart" routines + defaults/toggles. 170 pg. manual & annotated samples. \$95 alone; both \$165. Specify compiler and version.
IMPULSE Engineering, B.R. Strong, Jr.
P.O. Box 3540
San Francisco, CA 94119-3540
(415) 788-4611

The SCREEN GENERATOR

SAVE TIME! Powerful Screen Designer and Memory Resident Screen Manager eliminates tedious screen management tasks from your program. Handles all screen display & data entry. Easy access to Screen Manager from your program. Not a Code Generator! NO Royalties, Not Copy Protected. Easy conversion from other systems. Use with BASIC, TURBO (\$59), FORTRAN, C, Realia COBOL, BetterBASIC, PL/M-86, or Assembler. Call if not listed. Price \$125.
THE WEST CHESTER GROUP
P.O. Box 1304
West Chester, PA 19380
(215) 644-4206

TREES END DIAGRAM LAYOUT DRUDGERY \$29.95!

Decision trees; composition of data flows and date stores; Functional decomposition; Family trees; Process descriptions and structure diagram; Structured English; Warner-Orr data structure, process structure, and data flow. TREES frees you from positioning symbols!

- Fits brackets as your text grows/shrinks.
 - Line wraps and scrolls each text element.
 - Diagram stores as machine-readable tree.
 - 1000 elements + 32760 characters/diagram.
 - Requires MS-DOS, hard disk, 512K.
- Ver. 2.0 \$29.95 VISA/MC orders: 618-242-4161



Trees

Box 687
Mt. Vernon, IL
62864

StruBAS- the BEST BASIC!

Adds structure, full-screen handling, indexed files and menus to BASIC. Translates structured BASIC to Microsoft BASIC. Provides interactive screen definition and creates runtime code and tables. Includes subroutine library and sample application. Not copy protected. \$150 + \$5 s/h.
Demo \$5. VISA/MC
LANEY SYSTEMS, INC.
3 Office Park Dr. Suite 100
Little Rock, AR 72211
501-225-7755

Documentation Generator

Customizing Documentation Generator offers:
FLEXIBILITY—define your documentation
SIMPLICITY—follow DOS tree structure
CREATIVITY—run all commands and programs
COMMAND ABILITY—repeat an expanded command
I/O ABILITY—run special I/O redirection check \$39, MO, VISA/MC.
U-NEED & SEE COMPUTER SYSTEMS
P.O. Box 7363
Thousand Oaks, CA 91359
(805) 495-8441/(818) 889-3324

METRICS FOR MANAGEMENT

ANALYZE reads your code and produces metrics on VOLUME, COMPLEXITY, PRODUCTIVITY & more! Management, QA/QC & Engineers gain valuable insight into scheduling, problem areas, testing, maintenance & compliance to standards. For IBM PC. Process FORTRAN & "C" \$495.00 + S/H. Add Ada for only \$200.00 more!
MC/VISA
AUTOMETRIC INC.
891 Elkridge Landing RD., Suite 350
Linthicum, MD 21090 (301) 859-4111

SOFTWARE/ENGINEERING

METAL FABRICATORS

PC/Cutlist takes input from your bill of material—Detail drawing and calculates the best cutting combination for any length stock and prints a shop ready cutting list and scrap report. Also an optimization feature finds best mult length for mill orders. Price \$300. Demo Disk \$25.00
THE JOSEPH ALBERT CO.
P.O. Box 611
Blue Island, Illinois 60406
(312) 349-9032

CREATE PCB's EASILY

Easily create double-sided printed circuit board artwork of up to 21" square using PC-Layout on an IBM-PC. The artwork is created using a color artwork editor. The final artwork, solder mask and silk-screen (text) is produced using either a printer or a plotter. Price \$745. Demo disk/manual \$45. Demo disk credited to final purchase.

Draco Technology
7210 Jordan Ave., Suite D50
Canoga Park, CA 91303
(800) 235-6646 ext. 646 (outside CA)
(800) 235-6647 ext. 646 (CA only)

PC/8087 VECTOR PROCESSING

The VECTOR87 library is written in assembler, includes 60 routines to turbocharge your math & scientific programs. FFT, vector operations, convolution, etc. 1K real FFT takes only 1.2 second. Versions for Fortran (MS, R/M, Lahey), C (MS, Lattice). \$120 each version with source, no royalties. Write for technical information.
VECTORPLEX Data Systems Ltd.
P.O. Box 138, Station M
Calgary, Alberta, Canada T2P 2H6
(403) 248-1250

SOFTWARE/FILE MANAGEMENT

Wilkes Database

For IBM-PC and compatibles. Paint screens to create/view/update/delete/sort/search/print/reformat/arithmeticly manipulate new or extant files. ASCII, 16/32 bit integer and 32/64 bit floating point storage. Powerful key sort and report formatting. \$325. Demo \$40.
Wilkes Software
5231 Longwood Drive
Memphis, TN 38134
(901) 386-4712

SOFTWARE/FINANCIAL

FINANCIAL CALCULATOR

Memory resident software for PC/XT/AT or compatible computers. Non-resident version also available. Loan amortization, internal rate of return, IRA, real estate, savings, depreciation, and much more!!! FREE shipping in the U.S. 30 day money back guarantee.
NOT COPY PROTECTED. \$49.
OPUS Engineering
5825 Vargas Ct.
San Jose, CA 95120
(408) 997-1503

SOFTWARE/GENERAL

PUBLIC DOMAIN SOFTWARE IN C

Over 60 volumes of public domain software in CP/M & MS-DOS formats.
• editors & compilers
• text formatters
• communications packages
• many UNIX-like tools
Write or call for more details.



THE C USERS' GROUP
P.O. Box 97
McPherson, KS 67460
(316) 241-1065

SOFTWARE/GRAPHICS

TEKTRONIX 4010 EMULATION

High resolution screen/printer graphics for the IBM PC. Full interactive capabilities with file transfer and cross-hair control. Utilizes PLOT 10, protocols. OFF-line review of graphics output. Supports IBM color/graphic or Hercules cards. Easy to use 4010 emulation at an affordable price. \$80.00. Demo disk \$5.
Technological Systems Group
5044 Haley Court
Lilburn, GA 30247
(404) 923-4980

SCIENTIFIC DATA PLOTTING

SCI-GRAF creates graphs up to 1680 x 1712 dots (over 3 million pixels!) on Epson or IBM graphics printers. Supports log scaling, overlays, point-labeling, legend creation, batch mode, wide-carriage printers, and color graphs on a JX-80. Requires DOS 2 or 3, 256K. No credit cards. \$99.95
Microcomputer Systems Consultants (MSC)
27-P Forest Avenue
Port Jefferson Station, NY 11776
(516) 928-7493

TECH BOOK

FORTRAN GRAPHICS LIBRARY

MicroGlyph's SciPlot provides MicroSoft or IBM Professional FORTRAN graphics library on IBM PC/XT/AT under PC DOS. Features high resolution plots from printers (IBM/EPSON/Apple LaserWriter), or graphics displays (IBM Color/HERCULES-Monochrome/TECMAR-GM). Price: \$69.95 + \$3 shipping + 5% MASS tax. MicroGlyph Systems
P.O. Box 1066
East Arlington, MA 02174-9998

COMPUTER AIDED GRAPHICS

Free form 2D full screen graphics editor for the IBM-PC and compatibles. Use it to create charts such as: Organization, Gantt, Flow and Pie. Also produces Graphs, Work area plans, Electronic schematics and more. Drives HP or compatible plotters. Only \$49.95 a price of a game. For more details send a long SASE to:
WorkWare
P.O. Box 661295
Sacramento, CA 95866-1295
(916) 922-5819

MetaWINDOW™/TurboWINDOW™

Advanced graphics toolkit provides Xerox Star/Apple Macintosh style graphics on your IBM PC. Supports most popular graphics cards. Allows you to create pop-up menus, windows & icons; use proportionally spaced fonts; rubberband & drag lines, text or bitmap images; supports mouse-cursor tracking. Tightly optimized for use with Turbo Pascal, IBM Pascal, C, Fortran. METAGRAPHICS SOFTWARE CORP.
4575 Scotts Valley Drive
Scotts Valley, CA 95066
(408) 438-1550

FORTRAN GRAPHICS LIBRARY

GRAFATIC (screen graphics): 75 MS FORTRAN/Pascal, R-M/Profrot, Lahey FORTRAN callable subroutines. Fully documented, prof. graphics capabilities, inc. general utility, 2-D interactive, total 2-D plots, 3-D plots and solid models. \$135. H-P or H-I plotter? get PLOTMATIC, complete plotter graphics library. Interfaces w/GRAFATIC. \$135. Both \$240. MICROCOMPATIBLES, INC.
301 Prelude Drive Dept. J
Silver Spring, MD 20901
(301) 593-0683

SOFTWARE/LANGUAGES

EASY WAY TO MASTER DOS!

New handbook shows how, why, and when to use all 44 PC & MS DOS commands quickly and easily! Lively hands-on tutorial makes learning fun, for a change. Covers basic thru advanced topics. All versions up to 3.1. Lots of practical examples. 221 pages only \$15.95 at bookstores, or send check + \$1.00 S&H to:
LITTLE, BROWN & COMPANY PUBLISHERS
200 West Street, Code T-368121
Waltham, MA 02254
1-800-343-9204 (credit cards)

SOFTWARE/ NETWORKING

LAN SOFTWARE

LAN software for your PC, XT or AT, allows you to connect to your VAX and other systems. Provides file transfer and terminal services at hundreds of kilobits/sec. TCP/IP or XNS protocols available; MS-DOS, XENIX, VENIX and PC/IX supported, many additional options, basic PC package only \$350.



NETWORK RESEARCH CORP.
2380 North Rose Avenue
Oxnard, CA 93030
(805) 485-2700, TLX 297579

SOFTWARE/ONE OF A KIND

INTRODUCING-JORJ

JORJ-The first and only phonetic dictionary! 50K words/15K definitions. Finds words super fast for both good/poor spellers. JOSE a fun word-game is included in initial release as a bonus. Requires IBM-PC DOS2 & Hard disk. Copy protected. Price \$100. JORJ demo disk \$10. Check/ M.O. Mich. residents add 4% sales tax.
JORJ SOFTWARE CO.
4354 Fletcher Rd.
Manchester, MI 48158
(313) 428-8010

SOFTWARE/OPERATING SYSTEMS

UN/EMULATOR BY WAWA

Run CPM on your PC or clone at MACHINE SPEED. UN/EMULATOR runs native 8080 code and increases DOS performance by 10%. We include disk conversion software, terminal emulators, and serial transfer utility. Available in 5 MHz and 8 MHz. Starting at \$99.95 plus \$5 S&H. Dealer inquiries welcome. Call or write:
WEITZMAN AND WOOD ASSOCIATES
580 N.W. 99th Way
Pembroke Pines, FL 33024
(305) 432-8025

SOFTWARE/PUBLIC DOMAIN

TURBO PASCAL™ SOFTWARE \$6

Write or call for information about:

- Systems & applications development tools
- Programs for home and business
- Communication tools & applications
- Games in specialized applications
- Scientific/engineering programs & routines
- Graphics including animation tools

TURBO S.I.X.
P.O. Box 8373
Waco, TX 76714
(817) 753-2182

THE BEST OF THE BEST!

Public Domain & User Supported Software for IBM PC & Compatibles! Wordprocessing, Accounting, Spreadsheets, Database, Modem, Games, Languages, etc., etc. 50 disks crammed Full-\$205.00! or rent for 2wks. \$75.00. Info. and Super Sampler Disk \$6.50. Deluxe Word Processor \$6.50. Both \$12.00. MC/VISA.
BLUE CIRCLE GROUP, Inc.
P.O. Box 23502; Dept. TJ
Minneapolis, MN 55423
(612) 823-4111

SOFTWARE/SCIENTIFIC

SPARSE/DENSE MATRIX

MATRIX: Does to matrix what TK! solver did for numbers. Solves lin/nonlin/diff eqns. Programmable Matrix functions. \$59.95
SPARSEPACK: Turbo Pascal source code for user-transparent Sparse Matrix handling. Overcome 64K barrier and more. \$49.95. VISA/MC call 1-800-835-2246 ext. 80.
SoftTech Inc.
18505 W. 8 mile.
Detroit, MI 48219
1-313-544-8544

SCI/ENG GRAPHICS

OMNILOT [S] (screen graphics) & OMNILOT [P] (plotter driver) provide integrated engineering/scientific 2-D & 3-D graphics with NO PROGRAMMING! Menu-driven, flexible, professional. Choice of formats: tabular/line, contour, bar, pie, 3-D wire frame & much more! OMNILOT [S] \$195. Add OMNILOT [P], both \$295.
MICROCOMPATIBLES, INC.
301 Prelude Dr. Dept. J
Silver Spring, MD 20901
(301) 593-0683

SOFTWARE/SECURITY

"NEW" BIT-LOCK® SECURITY

Piracy SURVIVAL 4 YEARS proves effectiveness of powerful multilayered security. Uses rapid decryption algorithms and small reliable port for transparent security device. NOW AVAILABLE for PARALLEL or SERIAL port. NEW KEY-LOK™ security device available at HALF-PRICE.
MICROCOMPUTER APPLICATIONS
7805 S. Windermere Circle
Littleton, CO 80120
(303) 798-7683 or 922-6410

SECURE AT/XT/PC

Control system access, data access! FiXT/S. Control system boot for most popular XT/PC hard disk controllers. Feature for AT-and-XT-compatible HD controllers segments hard disk by volumes, controls access with passwords, supports hard disk expansion. \$80 \$120 + \$3 shpg. plus CA tax.



Golden Bow Systems
2870 Fifth Ave. Suite 201
San Diego, CA 92103
(619) 298-9349

SMART COPY PROTECTION

In the past, Copy-Protecting your programs meant inconvenience to the end-user, limited or no hard disk support, and a lot of added expense per product copy. Our new software based EVERLOCK System solves these problems. For IBM and compatibles, call for info.



Az-Tech Software Inc.
423 Grandview
Richmond, MO 64085
(816) 776-8153

SOFTWARE/SERVICES

TAPE/DISK CONVERSIONS

Conversion services to or from over 500 computer systems:
• Magtapes
• Micro Computers
• Mini Computers
• Word Processors
• Typesetters
Our conversion capabilities surpass most in the industry.
Pivar Computing Services, Inc.
165 Arlington Hgts. Rd. #T
Buffalo Grove, IL 60089
(312) 459-6010

RENT POPULAR SOFTWARE

Finally, you can rent popular software for your IBM or compatible. See how good that game really is. Try that business package before dishing out huge amounts of money. Not public domain. No membership fee. Where else can you get \$75.00 programs for \$5.00? Send \$1.00 for complete catalog.
R.S.D.
Dept. TJ
P.O. Box 272
Bronxville, NY 10708

TECH BOOK

SOFTWARE/STATISTICS

RATS!

RATS is the ultimate econometric software package. It is powerful, fast, accurate, and inexpensive. RATS performs regression analysis, time-series forecasting (including Box-Jenkins) and cross-section (including logit and probit). RATS supports a variety of data formats, including Lotus WKS files. RATS also offers a programming language that provides maximum flexibility and power. Spectral analysis and graphics are available as options. Base program \$200. Demo including 300 page manual \$40. MC/VISA. VAR Econometrics P.O. Box 19334 Minneapolis, MN 55419 (612) 822-9690

SW/STATISTICS

TWG/ARIMA—a univariate Box-Jenkins forecasting package, designed for statisticians. EASI/ARIMA—same as above, for the non-statistician. \$450. each. ELF—The Statistical Package—a general purpose statistical package. \$350. Call or write for more information. THE WINCHENDON GROUP, INC. P.O. Box 10339 Alexandria, VA 22310 (703) 960-2587

SOFTWARE/TERMINAL EMULATION

Color VT 102 & 4010

PC102 turns an IBM PC/XT/AT/jr to a VT 102/52 terminal with printer/ASCII & KERMIT file transfer support. Optional: 132 col. 4010 graphics support. Guaranteed compatibility with all VT 100 applications including EDT, WORD11, All-In-One, & UNIX. Easy to use. From \$89. Call for free package! General Micro Systems P.O. Box 5330, Dept. TJ Hopkins, MN 55343 (612) 944-0593

SIDETERM

Pop-up VT200/100/52 emulation package accessible from inside any program. Window can be moved and sized at any time. Data can be cut/pasted between terminal and application. Virtual 132 col. screen. Supports EDT, UNIX, and scrolling regions. Not copy protected. \$59.99. CK/MO. Demo \$10. MO res. add 6.225% tax. SOFTWARE INNOVATIONS P.O. Box 32466 Kansas City, MO 64111 (816) 756-2745

SOFTWARE/UTILITIES

AT/XT/PC HARD DISK EXPANSION

"Replace hard disk with a bigger one, or add a second drive! Vteature BREAKS THE 33 MBYTE BARRIER on standard AT, XT, and compatible hard disk controllers. Includes multiple volumes, security features, selectable clusters, keyboard lock. \$80-\$120 + \$3 shipping + CA Tax"



Golden Bow Systems
2870 Fifth Avenue, Suite 201
San Diego, CA 92103
(619) 298-9349

DISK MECHANIC

THE ULTIMATE Floppy Disk Backup & Repair Utility. Can back up ALL software protected disks written on the IBM PC. Works manually or automatically. Files or sectors can be restored, searched, examined & changed. Checks disk drive speed, req. IBM PC, XT, AT, DOS 1, 2, 3, 192K + 64K if only 1 floppy drive. \$73 ppd. USA MLI MICROSYSTEMS PO BOX 825, Dept TB2 Framingham, MA 01701 USA (617) 926-2055 for info MC/VISA

CHARACTER CUSTOMIZATION

CHARGENI 2.1 works with the IBM EGA to let you modify the character set, allowing many word processors to display technical material, equations or other special characters. Also works on the Color/Graphics Adapter in graphics modes. Requires DOS 2.x or 3.x, IBM Standard or Enhanced Graphics Adapter. \$35 + \$2 s/h (MN add 6%). DK Micro Consultants P.O. Box 6714 Minneapolis, MN 55406 (612) 722-0931

TallScreen—DOS POWER

Natural extension of DOS. Scroll back through screen output, edit text on full screen, mark blocks to printer or file, recall commands & directories, enter multiple commands, capture screens from application programs, create user profiles. Solid tech support. A real bargain at \$49.95 VISA/MC.



Qualitas, Inc.
8314 Thoreau Drive
Bethesda, MD 20817
(301) 469-8848

Directory eXtended™

BE IN COMMAND! New version of very popular command-oriented file manager! POWERFUL batch file generation—perform any task! FLEXIBLE file matching and sorting! CONTROL file attributes! TEST file integrity! MONITOR disk params; 2-col display! MUCH MORE! Send \$35+\$5 p&h (in TX, add tax); money back guarantee!

DIRECTORY EXTENDED™

ECONO-SOFT Dept. T66
9200 North Plaza # 1906
Austin, TX 78753

HELL uva SHELL

Most DOS interfaces are designed for IDIOTS! Get the BEST full-screen interactive directory around ... DOS command recall ... command aliasing ... multiple commands at DOS prompt ... find files anywhere on disk ... find complex text patterns in files ... browse files ... copy files based on time stamp & MORE. Only \$39! DOS 2.0+, uses 96K memory. NCP! Dwarf Nebula Software 666-SHELL P.O. Box 46, Dept. TJ Sugarland, TX 77487

EASYINDEXE PLUS™

Cross reference all source code by file name. Create index by page number. Unlimited number of indexes and accessed files. Word or phrase indexes up to 59 characters. Table of contents generation, typesetting, and print formatting. Supports over 100 printers. \$39.95 \$3 shipping (CA. RES. ADD \$2.60 Tax) Foreman Software 977 Clayton St. D4 San Francisco, CA 94117 (415) 665-6414

TurboRef 4.0

Pascal programmers get organized with TurboRef! TurboRef will cross reference a source program and create a program listing. TurboRef can process a list of files, will read "include" files, identifies line number for each reference. New release now avail. IBM PC and jr., XT, AT or compatible, only \$49.95; VISA/MC, or check.

GRACON SERVICES, INC.

GRACON Services Inc.
4632 Okemos Rd.
Okemos, MI 48864
(517) 349-4900

TURBO PACKAGE for Turbo Pascal

*Crash the 64K barrier. Forget MODULA2.
*1000 times faster than chains or overlays.
*Precompiler turns short calls into long calls. Run 500K of memory resident code.
*32 bit integer math toolbox, ASM.
*Mix Turbo, TurboBCD, and Turbo-87.
*Free information.
*Turbo Package plus tools, \$39.95.
CONVERSATIONAL COMPUTER SYSTEMS
5371 Verbena Road
San Antonio, TX 78240
(512) 692-0353

LIST-IT

Make your IBM BASICA and IBM compiled Basic program readable with a pretty print. Cross references for statements and variables are included. While-wend, FOR-NEXT and IF-THEN-ELSE structures recognized. \$29.95. Calif. residents add 6%. CHECK/MO/VISA/MC PCS 50 Cornell #9 Irvine, CA 92715 (714) 854-1282

SAVE THAT SCREEN!

Do you immediately reach for the PrtSc key to save screen info? What a waste of time and paper! Now, SCREENSNAP™ lets you save and recall up to 9 screens at the touch of a key. Friendly with other resident programs but unlike some it is compact; will run in as little as 5K. Also includes useful utilities to save and recall from files, programmer's interface and sample code. Build your own help screens with your text editor, then save and recall them with SCREENSNAP. \$39. Aldridge Real-Time Software Inc. Call 800-443-4160; NJ (201) 846-7242

REPEAT PERFORMANCE™

OUTSMARTS IBM PC KEYBOARD LIMITATIONS! Smoothly ACCELERATES CURSOR MOVEMENT, speeds up editing. High speed scrolling. You set ADJUSTABLE REPEAT SPEED and DELAY. SKID SQUELCH™ feature auto-adjusts to match performance of word-processors/text editors/spreadsheets. Cursor & scrolling STOP INSTANTLY when key is released. EXPANDS TYPE-AHEAD BUFFER-type DOS commands while your programs compile. Less than 2K resident. WARNING: ADDICTIVE! IBM/PC/XT/AT compatibles. \$back guar. \$39.95 +\$5 p&h. VISA/MC/AMEX/CK. Site licensing from second copy!



Popular Demand Inc.
62 South 1025 East
Linden, UT 84062
(801) 785-0101

FILE PRINT MANAGER

GLISTER™
★ Use DOS wildcards to build a list of up to 100 files to print
★ Save/restore file lists
★ Restart a file on any page after a printer jam
★ Print multiple copies
★ Control: margins, line/page length, spacing, user-formatted header/footer lines and more
★ Prints files as fast as printer is capable \$49 Aldridge Real-Time Software Inc. Call 800-443-4160; NJ (201) 846-7242

TECH BOOK

AUTOMENU™ VERSION 4.0

Create one menu system to run all your programs, batch files and DOS commands. "Insulates" novices; many options for power users. On-screen help, password protection, user-defined prompts. Written in assembler. 16K size. Over 7,000 satisfied users. Money back guarantee. \$46 + \$4 s/h. Chk/Visa/MC.



MAGEE ENTERPRISES

Magee Enterprises
6577 Peachtree Industrial Blvd., Dept. T8
Norcross, GA 30092-3796/USA
(404) 446-6611

DISK UPGRADE BIOS for ATs

DUB-14 overrides AT Drives Table to allow any compatible drive to be attached and fully used on the standard AT controller. Two ROMs plug into empty sockets on system board. Includes complete Set-Up routine and low-level format facility. Works with UNIX, XENIX, other OS and networks. \$95 + \$3 shpg. CA tax.



GOLDEN BOW SYSTEMS
2870 Fifth Avenue, Suite 201
San Diego, CA 92103
(619) 298-9349

HARD DISK EXPANSION!

Disk Manager allows the installation of any ST506 hard disk on PC, XT, AT and compatibles. Volumes up to 256mb! Menu driven/auto install, compatible w/ all vers of MS/PC DOS (does not modify DOS), up to 16 volumes, easy to use! \$125+ ship. Ask about Novell product! Dealer inquiries invited.



Ontrack Computer Systems, Inc.
7460 Washington Ave. S.
Eden Prairie, MN 55344
(612) 941-4504

VCACHE GETS YOUR DISK MOVING!

Hard disk accelerator increases speed of cartridge and fixed disk operations using memory caching to eliminate repetitive disk access. Allocate up to 15Mb of extended or expanded memory, or .5Mb of standard memory for caching disk data. Includes diskette and screen accelerator modules. Automatic and transparent after installation. \$65+ \$3 shpg, CA tax.



GOLDEN BOW SYSTEMS
2870 Fifth Avenue, Suite 201
San Diego, CA 92103
(619) 298-9349

SOFTWARE/WORD PROCESSING

FORMATH™ TEXT-FORMATTER

For technical texts. Sizes & places equations, matrices, ratios, integrals, big symbols, footnotes. Macros; multiple fonts, 158 Greek/math symbols. Automatic hyphenation, section/equation/reference numbering, indexes, table of contents. Dot-matrix, daisywheel, laser printers, plain/graphics monitors. \$400. \$50 for demo.

$$\lim_{n \rightarrow \infty} \sum_{i=1}^n \left[\frac{1}{i(i+1)} - \frac{1}{2^i} \right] = \frac{1}{2} \left[\int_0^1 \frac{\log(1-x)}{-x} dx - 1 \right]$$

SHANTHA SOFTWARE, INC.
50 West 97th St. Room 11N
New York City 10025
212-222-7647
Touch-tone Toll-free: 950-1088-wait-FORMATH


Subscribe to PC Magazine and save 65%

You'll receive in-depth and comprehensive product evaluations and comparative hardware and software evaluations from PC Labs, the publishing industry's *only* testing laboratory.

You'll receive new applications, power tips and special reports designed to add more power and flexibility to your IBM/MS DOS-standard system.

And you'll network with other users and discover routines and techniques that can save you time and money.

Subscribe to *PC Magazine* today! Send the coupon to: *PC Magazine* • P.O. Box 2443 • Boulder, Colorado 80322 or call Toll-Free; 1-800-852-5200 now!



Yes, send me PC Magazine for:

- ☐ 22 issues (one year) for \$24.97. Save 62%!
☐ 44 issues for only \$44.97. Save 65%!

Savings based on annual single-copy price of \$64.90.

Mr./Mrs./Ms. _____ please print full name

Company _____

Address _____


City _____ State _____ Zip _____

Add \$15 per year for postage outside USA, US currency only.

Please allow up to 60 days for delivery of first issue. Basic annual subscription price is \$34.97.

8ZD74

RS#	PRODUCT	ADVERTISER	PAGE	RS#	PRODUCT	ADVERTISER	PAGE
IBM COMPUTERS AND COMPATIBLE UNITS				249	Software SOURCE PROBE	Atron	181
116	PC 2/286	Advanced Logic Research	Cover 3	104	Turbo Power Tools Plus	Blaise Computing, Inc.	105
199	DART	Advanced Logic Research	136	114	Programming Tools	Blaise Computing, Inc.	107
	Business Hardware	IBM	33-36	*	"Vitamin C"	Creative Programming Cons.	127
252	MS DOS 3.1/STO BUS	ProLog Corp.	20	215	Periscope	Data Base Decisions	5
233	Portable/Desktop 286	Tech-Personal Computers	92-93	102	dBX Translator	Desktop Ai	184
182	AT Compatible	Tele-Video Systems, Inc.	106	106	SoftScreen HELP	Dialectic Systems	21
124	A Star	Wells American	101	*	A to Z Software	Digital Equipment Corp.	109
ACCESSORY CARDS				161	EditCheck	Everest Solutions, Inc.	179
247	Alps Graphics Board	Alps America	44-45	119	C-Tree	FairCom	22
140	RAMPAGE! AT	AST Research Inc.	122-123	251	Screenplay	Flexus International Corp.	161
139	EGA Card	Everex	112	148	C-Tree Query	Kurtzberg Computer Systems	22
202	CPU Boards	I-Bus-Systems	128	144	Lattice C	Lifeboat Associates	155
216	Above-Board	Intel Corp.	78-79		Utilities, Editors, Functions, Graphics	Lifeboat Associates	155
230	High Resolution Graphics Card	Paradise Systems, Inc.	41	110	Peeks-N-Pokes	MicroHelp Inc.	131
137	EGA Card	Paradise Systems, Inc.	6-7	222	Opt-Tech Scroll	Opt-Tech Data Processing	4
171	EMS	Quadram Corp.	139	222	Opt-Tech Sort	Opt-Tech Data Processing	4
141	Hi Card Memory Board	RYBS Electronics	171	150	Norton Editor	Peter Norton Utilities	176
125	Accessory Card	Seattle Telecom & Data	70	123	Dan Bricklan's Demo Program	Software Garden	74
197	RT Board	Tall Tree Systems	39	168	The Visible Computer	Software Masters	130
MASS STORAGE HARDWARE				130	BRIEF	Solution Systems	14
182	9 Track Tape Systems	Catamount Corp.	111	152	Turbo Professional	Sunny Hill Software	168
149	Mag Tape Subsystem	IBEX Computer Corp.	184	206	Turbo-Task	Tangent Technologies	129
108	LEO	Innovative Data Technology	164	192	Flashcode, Screen Sculptor, Flash-up Windows	The Software Bottling Co. of NY	149
185	TC-50 and TC-PC	Overland Data, Inc.	141	115	Windows for C	Vermont Creative Software	16
231	Perstor	Systems & Software	134	SOFTWARE UTILITIES			
PRINTERS-PLOTTERS				254	Sidekick	Borland International	Cover 2-1
117	Desktop Printshop	Cordata, Inc.	167	254	Traveling Sidekick	Borland International	Cover 2-1
245	Print Q	Software Directions	158	254	Superkey	Borland International	Cover 2-1
ALTERNATE INPUT DEVICES				254	Turbo Lightening	Borland International	Cover 2-1
201	B-Trieve	SoftCraft, Inc.	2	254	Lightening Word Wizard	Borland International	Cover 2-1
DATA ACQUISITION				107	File-Power	Bruce Newman & Co.	180
209	ADALAB-PC	Interactive Microware	182	164	HD Tune-Up	SoftCap Inc.	133
INTEGRATED CIRCUITS				158	Taskview	Sunny Hill Software	168
213	Copy II PC	Central Point Software	145	GRAPHIC SOFTWARE			
133	No Limit	MEF Environmental Inc.	184	218	Pro Design II	American Small Business Comp.	170
COMMUNICATIONS HARDWARE				138	Drafix I	Foresight Resources Corp.	150
169	Evercom Modem	Everex	114	113	Flowchart	Haven Tree Software Limited	164
196	Multilink Advanced	The Software Link	48	DATA BASE MANAGEMENT SOFTWARE			
COMMUNICATIONS				198	Paradox	Ansa Software	19
189	V-Term	Coefficient Systems	163	254	Reflex, The Analyst	Borland International	Cover 2-1
103	DaTapaSS	DTSS, Inc.	186	254	Reflex Workshop	Borland International	Cover 2-1
160	SideTalk	Lattice, Inc.	138	118	Dataflex	Data Access Corp.	124
167	Remote	Microstuf	Cover 4	211	MDBS III	Micro Data Base Systems Inc.	147
112	"SFT NetWare System"	Novell Inc.	26-27	166	db VISTA	Raima Corp.	100
122	SIM 3278 PC	Sinware	140	143	INFORMIX-SQL	Relational Data Base Systems	143
129	ZAP	Solution Systems	24	147	True Data Base	Software That Really Works	184
SOFTWARE FOR PROFESSIONALS				219	ZIM	Zanth Information, Inc.	144
109	ASYST	Macmillan Software	1	ARTIFICIAL INTELLIGENCE			
ENGINEERING SOFTWARE				*	Personal Consultant	Texas Instruments	142
25	Mass CAD	MathSoft	128	CONVERSION SYSTEMS			
LANGUAGES				153	Conversion Systems	Flagstaff Engineering	90
136	Prolog Compiler	Arity Corporation	169	MICROPROCESSORS			
105	Clarion	Barrington Systems Inc.	56	142	PC Turbo 286E	Orchid Technology	88
254	Turbo Pascal	Borland International	Cover 2-1	NETWORKING PRODUCTS			
254	Turbo Database Toolbox	Borland International	Cover 2-1	246	Tiara Link	Tiara Computer Systems, Inc.	72
254	Turbo Gameworks	Borland International	Cover 2-1	184	Tapestry	TORUS Systems, Inc.	103
254	Turbo Prolog	Borland International	Cover 2-1	CAREER OPPORTUNITIES			
254	Turbo Tutor	Borland International	Cover 2-1	134	Senior Software Engineer	Ashton-Tate	182
254	Turbo Editor Toolbox	Borland International	Cover 2-1	HARDWARE DIAGNOSTIC TOOLS			
254	Turbo Graphics Toolbox	Borland International	Cover 2-1	212	Model AID/88	Vu-Data	133
131	'EcoSoft C'	EcoSoft, Inc.	162	LITERATURE			
170	Utah Software	Ellis Computing	165	173	C Programmers Book Newsletter	Little, Brown & Co.	182
*	C-terp	Gimpel Software	177	*		Microsoft Corp.	28
128	F77/Lahey Fortran	Lahey Computer Systems	166	OTHER SERVICES			
229	Modula 2/86	LOGITECH, Inc.	23, 25	172		Peripherals Design	157
*	C Compiler	Microsoft Corp.	42-43	MAIL ORDER			
181	Instant C	Rational Systems, Inc.	177	*	Mail Order	ACS Importers	195
174	Fortran	Ryan McFarland	137	*	Mail Order	Challenger Computer Inc.	195
129	LISP-86	Solution Systems	24	*	Mail Order	Floppy Disk Services, Inc.	194
195	Better BASIC	Summit Software Tech., Inc.	160	*	Mail Order	Micro Star	189
205	Let's C	The Mark Williams Company	17	*	8087 Boards 2020	MicroWay	000
121	XENIX	The Santa Cruz Operation, Inc.	135	*	Mail Order	PC Brand	191-193
PROGRAMMER'S TOOLS				145	Mail Order	PC's Limited	117-119
190	The CREATOR	Advanced Development Tech.	68	175	Mail Order	Programmers Connection	49-51
101	Fortran Support	Alpha Computer Service	108	220	Mail Order	The Programmer's Shop	46
101	EGA Graphics Support	Alpha Computer Service	108	162	Mail Order	The Programmer's Shop	76
101	Hercules Graphics Support	Alpha Computer Service	108	151	Mail Order	The Programmer's Shop	77
203	PC PROBE	Atron	8	*	Mail Order	Wintech Data Products Corp.	188



AUGUST

August 4-6 LISP and Functional Programming Cambridge, MA

Sponsor: ACM
Contact: Richard P. Gabriel,
Lucid, Inc., 707 Laurel Street,
Menlo Park, CA 94025

August 5-7 ACM SIGCOMM Futures in Communications Conference Stowe, VT

Contact: Walter Kosinsky,
Norwich University,
Northfield, VT 05663;
802/485-5011, ext. 237

August 11-13 Symposium on Principles of Distributed Computing Calgary, Alberta, Canada

Sponsor: ACM SIGACT-
SIGOPS
Contact: ACM, 11 W. 42nd
Street, New York, NY 10036

August 18-22 Annual Conference on Computer Graphics and Interactive Techniques Dallas, TX

Sponsor: SIGGRAPH '86
Contact: Smith, Bucklin, and
Andy Associates, 111 E.
Wacker Drive, Suite 600,
Chicago, IL 60601;
312/644-6610

SEPTEMBER

September 1-5 World Computer Conference Dublin, Ireland

Sponsor: International
Federation for Information
Processing
Contact: IFIP Congress '86,
1899 Preston White Drive,
Reston, VA 22091;
703/620-8900

September 8-10 NCC-Telecommunications Conference Philadelphia, PA

Sponsor: AFIPS, ACM, DPMA,
IEEE, SCS
Contact: Mike Sherman,
AFIPS, 1899 Preston White
Drive, Reston, VA 22091;
703/620-8935

September 8-10 1986 ACM Conference on Research and Develop- ment in Information Retrieval Systems Pisa, Italy

Sponsor: ACM SIGIR and
AICA-GLIR
Contact: L. Rossi Bernardi,
C.N.R. Piazza A. Moro 7,
Roma, Italy

September 8-11 National Database and 4th Generation Language Symposium Hong Kong

Sponsor: Digital Consulting
Associates, Inc.
Contact: Digital Consulting
Associates, Inc., 6 Windsor
Street, Andover, MA 01810;
617/470-3870

September 15-18 Euromicro '86: Sympo- sium on Microprocessing and Microprogramming Venice, Italy

Contact: Mrs. Chiquita
Snippe-Marlisa, p/a TH

Twente, Department INF,
Room A227, P.O. Box 217,
7500 AE Enschede, The
Netherlands; +31/53/338799

September 30-October 2 Northcon '86 Seattle, WA

Sponsor: IEEE
Contact: Northcon '86 Pro-
fessional Program Commit-
tee, Dale Litherland, Director
of Education, 8110 Airport
Blvd., Los Angeles, CA 90045;
800/421-6816; in California,
800/262-4208

OCTOBER

October 5-10 Compsac '86 Chicago, IL Contact: Compsac '86, 1730 Massachusetts Avenue NW, Washington, DC 20036- 1903; 202/371-0101

October 5-10 International Conference on Computer Design Atlantic City, NJ Contact: ICCD '86, 1730 Massachusetts Avenue NW, Washington, DC 20036- 1903; 202/371-0101

October 7-9 Introduction to Data Communications Atlanta, GA

Contact: Deidre Mercer, De-
partment of Continuing Edu-
cation, Georgia Institute of
Technology, Atlanta, GA
30332-0385; 404/894-2547

October 15-17 Scan-Tech '86 San Francisco, CA

Sponsor: Automatic Identifi-
cation Manufacturers, Inc.
Contact: Automatic Identifi-
cation Manufacturers, Inc.,
1326 Freeport Road, Pitts-
burgh, PA 15238;
412/963-8588

October 16 Communications Network Procurement Atlanta, GA

Sponsor: Georgia Institute of
Technology
Contact: Deidre Mercer, De-
partment of Continuing Edu-
cation, Georgia Institute of
Technology, Atlanta, GA
30332-0385; 404/894-2547

October 20-24 Using Computer Graphics to Enhance Productivity and Management Effectiveness Atlanta, GA

Contact: CGA '86 Conference
Director, 2033 M Street NW,
Suite 333, Washington, DC
20036; 202/775-9556

CALLS FOR PAPERS

August 31, 1986 Computers and Applications Peking, China

(June 24-26)
Sponsor: IEEE-CS and
Chinese Computer
Federation
Submit papers to: Oscar
N. Garcia, Department of
EE and CS, Room T-637,
The George Washington
University, 801 22nd
Street NW, Washington,
DC 20052; 202/676-7175

Use these reader service cards to get FREE INFORMATION about the products and services in this issue of TECH JOURNAL

Learning more about a product that's advertised or mentioned in an article in this month's issue is as simple as 1-2-3. And absolutely free.

1 Print or type your name and address on the attached card.
Use only one card per person.

2 Circle the numbers on the card that correspond to the numbers at the bottom of the advertisements or articles for which you want more information.

3 Simply mail the card, and the literature will be mailed to you free of charge by the manufacturer.

(Key numbers for advertised products also appear in the Advertisers' index.)

TECH JOURNAL

Are you personally involved in the selection of microcomputers and related products for:

- 1** Your company or organization?
☐ Yes ☐ No
- 2** Your client companies or organizations?
☐ Yes ☐ No
- 3** Are you planning to purchase in the next 6 months:
☐ PC Hardware?
☐ PC Software?
☐ PC Peripherals?

101	116	131	146	161	176	191	206	221	236	251	266	281	296	311	326	341	356	371	386
102	117	132	147	162	177	192	207	222	237	252	267	282	297	312	327	342	357	372	387
103	118	133	148	163	178	193	208	223	238	253	268	283	298	313	328	343	358	373	388
104	119	134	149	164	179	194	209	224	239	254	269	284	299	314	329	344	359	374	389
105	120	135	150	165	180	195	210	225	240	255	270	285	300	315	330	345	360	375	390
106	121	136	151	166	181	196	211	226	241	256	271	286	301	316	331	346	361	376	391
107	122	137	152	167	182	197	212	227	242	257	272	287	302	317	332	347	362	377	392
108	123	138	153	168	183	198	213	228	243	258	273	288	303	318	333	348	363	378	393
109	124	139	154	169	184	199	214	229	244	259	274	289	304	319	334	349	364	379	394
110	125	140	155	170	185	200	215	230	245	260	275	290	305	320	335	350	365	380	395
111	126	141	156	171	186	201	216	231	246	261	276	291	306	321	336	351	366	381	396
112	127	142	157	172	187	202	217	232	247	262	277	292	307	322	337	352	367	382	397
113	128	143	158	173	188	203	218	233	248	263	278	293	308	323	338	353	368	383	398
114	129	144	159	174	189	204	219	234	249	264	279	294	309	324	339	354	369	384	399
115	130	145	160	175	190	205	220	235	250	265	280	295	310	325	340	355	370	385	400

Please print clearly—Use only one card per person.

Void after November 30, 1986

Name _____ Phone (____) _____

Title _____

Company _____

Address _____ Apt. _____

City _____ State _____ Zip _____

(Zip code must be included to insure delivery.)

☐ Please send me 1 year (12 issues) of *PC Tech Journal* for \$23.70 and bill me. I'll save 50% off the single copy price!

TJ8862

TECH JOURNAL

Are you personally involved in the selection of microcomputers and related products for:

- 1** Your company or organization?
☐ Yes ☐ No
- 2** Your client companies or organizations?
☐ Yes ☐ No
- 3** Are you planning to purchase in the next 6 months:
☐ PC Hardware?
☐ PC Software?
☐ PC Peripherals?

101	116	131	146	161	176	191	206	221	236	251	266	281	296	311	326	341	356	371	386
102	117	132	147	162	177	192	207	222	237	252	267	282	297	312	327	342	357	372	387
103	118	133	148	163	178	193	208	223	238	253	268	283	298	313	328	343	358	373	388
104	119	134	149	164	179	194	209	224	239	254	269	284	299	314	329	344	359	374	389
105	120	135	150	165	180	195	210	225	240	255	270	285	300	315	330	345	360	375	390
106	121	136	151	166	181	196	211	226	241	256	271	286	301	316	331	346	361	376	391
107	122	137	152	167	182	197	212	227	242	257	272	287	302	317	332	347	362	377	392
108	123	138	153	168	183	198	213	228	243	258	273	288	303	318	333	348	363	378	393
109	124	139	154	169	184	199	214	229	244	259	274	289	304	319	334	349	364	379	394
110	125	140	155	170	185	200	215	230	245	260	275	290	305	320	335	350	365	380	395
111	126	141	156	171	186	201	216	231	246	261	276	291	306	321	336	351	366	381	396
112	127	142	157	172	187	202	217	232	247	262	277	292	307	322	337	352	367	382	397
113	128	143	158	173	188	203	218	233	248	263	278	293	308	323	338	353	368	383	398
114	129	144	159	174	189	204	219	234	249	264	279	294	309	324	339	354	369	384	399
115	130	145	160	175	190	205	220	235	250	265	280	295	310	325	340	355	370	385	400

Please print clearly—Use only one card per person.

Void after November 30, 1986

Name _____

Title _____ Phone (____) _____

Company _____

Address _____ Apt. _____

City _____ State _____ Zip _____

(Zip code must be included to insure delivery.)

☐ Please send me 1 year (12 issues) of *PC Tech Journal* for \$23.70 and bill me. I'll save 50% off the single copy price!

TJ8861

FREE INFORMATION

Follow the instructions
on the reverse side of
this card to
receive advertisers'
product information.
FREE.

SUBSCRIBE NOW!

Now's an ideal time to
consider having us start
you as a PC Tech Jour-
nal subscriber.

12 issues cost you
only \$23.70...a savings
of 50% off the single
copy price. Just check
the box at the bottom
of the reply card.



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 27346 PHILADELPHIA, PA

Postage will be paid by addressee

**TECH
JOURNAL**

P.O. Box 40086
Philadelphia, PA 19106-9931



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 27346 PHILADELPHIA, PA

Postage will be paid by addressee

**TECH
JOURNAL**

P.O. Box 40086
Philadelphia, PA 19106-9931



Sometimes Waiting For Large Corporations To Introduce New Technology Is Like Watching Apes Evolve

pc2
286

PC2/286
\$1545
PC/XT Size
Shown with
Optional
ALR EGA
Graphics



MOST OF US NEED SOLUTIONS NOW . . . IN THIS MILLENNIUM!

Our engineers got tired of waiting for a product that could succeed the legendary PC. So with our experience in designing and manufacturing some of the most powerful PC/XT and AT compatibles, we've engineered a PC with today's technology to provide solutions for tomorrow's challenges.

Introducing the ALR PC2/286. The next generation.

A computer with processing power equal to the 8MHz IBM AT computer (introduced April 1986), so you can solve problems 500 times faster than with the original PC.

A computer with more storage capacity. The PC2/286 integrates modern floppy technology allowing you to store 3 times more information than you could before.

Evolutionary Winchester hard disk technology further enhances the power of the PC2/286.

The PC2/286 incorporates all the best hardware developments of yesterday while maintaining the vital link of total software compatibility through Phoenix Bios.


The economy of modern technology allows the PC2/286 to be priced lower than the original PC and most other primitive PC compatibles.

The Result is a \$1545 Complete System.

If you are tired of waiting for a maybe product, or you don't want to buy yesterday's technology, then treat yourself to the performance and features of the PC2/286.

Call and talk to our dealers or sales engineers for the product that says tomorrow.

ENGINEERING ADVANCED COMPUTERS



ADD UP TO 2 HALF-HEIGHT FLOPPIES
2 HALF-HEIGHT OR 1 FULL HEIGHT HARD DISK

ALR IN CANADA 416-229-6477

DEALER INFORMATION CONTACT: MR. KIRKEY or MR. ANEIL

Advanced Logic Research, Inc.

10 Chrysler, Irvine, California 92718 - (714) 581-6770
FAX: (714) 581-9240 - TELEX: 5106014525, Answerback Advanced Logic

CIRCLE NO. 116 ON READER SERVICE CARD





How Does One Air Express Office Send Another Air Express Office a List of What's Coming?

Next time you have a lengthy message to send cross country, load it into your computer instead of a plane. It's a lot faster.

Our Crosstalk software and a modem can make it possible for your PC to communicate almost instantly with almost any other computer in the world, over ordinary phone lines.

In minutes, you could send or receive a 10-page report, an inventory list, or anything else you'd like to have in someone else's hands right now. You can speed the way you do business, no matter where you do business.

Crosstalk facilitates communication among different

computer brands, operating systems, and modems. It even makes it possible for your PC to become a smart remote terminal to almost any dial-up computer — your company mainframe, for example, or an information utility such as CompuServe.

Because Crosstalk is so easy for beginners to use and so versatile for experts, it's become the most popular microcomputer communications

program available. Ask your dealer, or send for our brochure.

CROSSTALK

XVI

MICROSTUF

1000 Holcomb Woods Parkway / Roswell, Georgia 30076
CROSSTALK is a registered trademark of Microstuf, Inc.
CompuServe is a Servicemark of HGR Black

CIRCLE NO. 167 ON READER SERVICE CARD